

This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.


We also ask that you:

- + Make non-commercial use of the files We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + Refrain from automated querying Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + Maintain attribution The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + Keep it legal Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at http://books.google.com/











	,		
		•	
•	•		
		•	
•			

·	•				
	•				
					•
			•		
•					
		•			
			•		
				•	
				•	





		-		
•				
		•		
	•			

Hatfield 3-VEE



" are 1877

THEORY

OF

TRANSVERSE STRAINS

AND ITS APPLICATION

IN THE

CONSTRUCTION OF BUILDINGS.

INCLUDING A FULL DISCUSSION OF THE THEORY AND CONSTRUCTION OF FLOOR BEAMS, GIRDERS, HEADERS, CARRIAGE BEAMS, BRIDGING, ROLLED-IRON BEAMS, TUBULAR IRON GIRDERS, CAST-IRON GIRDERS, FRAMED GIRDERS, AND ROOF TRUSSES; WITH

TABLES,


Calculated and prepared expressly for this Work,

OF THE DIMENSIONS OF FLOOR BEAMS, HEADERS AND ROLLED-IRON BEAMS; AND TABLE'S SHOWING RESULTS OF ORIGINAL EXPERIMENTS ON THE TENSILE, TRANS-VERSE, AND COMPRESSIVE STRENGTHS OF AMERICAN WOODS.

R. G. HATFIELD, ARCHITECT.


FELLOW AM. INST. OF ARCHITECTS; MEM. AM. SOC. OF CIVIL ENGINEERS; AUTHOR OF "AMERICAN HOUSE CARPENTER."

NEW YORK:
JOHN WILEY & SONS, 15 ASTOR PLACE.



COPYRIGHT, 1877.

JOHN WILEY & SONS.



PREFACE.

This work is intended for architects and students of architecture.

Within the last ten years, many books have been written upon the mathematics of construction. Among them are several of particular excellence. Few, however, are of a character adapted to the specific wants of the architect. The subject is treated, by some, in the abstract, and in a manner so diffuse and general as to be useful only to instructors. In other works, where a practical application is made, the wants of the civil engineer rather than of the architect are consulted. Writers of scientific books, as well as the public at large, have failed to appreciate the wants of the architect. Indeed, many architects are content to forego a knowledge of construction; following precedent as far as precedent will lead, and, for the rest, trusting to the chances of mere guess-work. For such, all scientific works are alike useless; but there is a class of architects who, through a faulty system of education, have failed to obtain, while students, the knowledge they need; and who now have little time and less inclination to apply themselves to abstract or inappropriate works, although feeling keenly the need of some knowledge which will help them in their daily duties.

For this class, and for students in architecture, this book is written. In fitting it for its purpose, the course adopted has been to present an idea at first in concrete form, and then to lead the mind gradually to the abstract truth or first principles upon which the idea is based. This method, or the manner in which it is executed, may not meet the approval of all. Nevertheless, it is hoped that those for whom the work is written may, by its help, acquire the knowledge they need, and be enabled to solve readily the problems arising in their professional practice.

4 PREFACE.

To adapt the work to the attainments of younger students, the attempt has been made to present the ideas, especially in the first chapters, in a simple manner, elaborating them to a greater extent than is usual.

The graphical method of illustration has been employed largely, and by its help some of the more abstruse parts of the science of construction, it is thought, have been made plain. Results obtained by this method have been analyzed and shown to accord with the analytical formulas heretofore employed. In a discussion of the relation between strength and stiffness, a method has been developed for determining the factor of safety in the rules for strength. Rules for carriage beams with two and three headers are given. The subject of bridging has been discussed, and the value of this system of stiffening floors defined.

Especial attention has been given to the chapters on tubular iron girders, rolled-iron beams, framed girders and roofs; and these chapters, it is hoped, will be particularly acceptable to architects.

The rules for the various timbers of floors, trussed girders, and roof trusses, are all accompanied by practical examples worked out in detail. Tables are given containing the dimensions of floor beams and headers for all floors. These tables are in two classes; one for dwellings and assembly rooms, the other for first-class stores; and give dimensions for beams of Georgia pine, spruce, white pine and hemlock, and for rolled-iron beams.

Immediately following the tables will be found a directory, or digest, by which the more important formulas are so classified that the proper one for any particular use may be discerned at a glance.

The occurrence recently of conflagrations, resulting in serious loss of life, has shown the necessity of using every expedient calculated to render at least our public buildings less liable to destruction by fire. To this end it is proposed to construct timber floors solid, laying the beams in contact, so as to close the usual spaces between the beams, and thus prevent the passage of air, and thereby retard the flames. The strength of these solid floors has been discussed in Article 702, and a rule been obtained for the depth of beam or thickness of floor. By this rule the depths for floors of various spans have been computed, and the results recorded in table XXI.

5

Tables XXIII. to XLVI. contain a record of experiments made, expressly for this work, upon six of our American woods. In these experiments and in computations, the author has been assisted by his son, Mr. R. F. Hatfield.

In the preparation of the work, he has had recourse to the works of numerous writers on the strength of materials, to whom he is under obligation, and here makes his acknowledgments. The following are the works which were more particularly consulted:—

Baker on Beams, Columns, and Arches.

Barlow on Materials and on Construction.

Bow on Bracing.

Bow's Economics of Construction.

Campin on Iron Roofs.

Cargill's Strains upon Bridge Girders and Roof Trusses.

Clark on the Britannia and Conway Tubular Bridges.

Emerson's Principles of Mechanics.

Fairbairn on Cast and Wrought Iron.

Fenwick on the Mechanics of Construction.

Francis on the Strength of Cast-Iron Pillars.

Haswell's Engineers' and Mechanics' Pocket-Book.

Haupt on Bridge Construction.

Hodgkinson's Tredgold on the Strength of Cast-Iron.

Humber on Strains in Girders.

Hurst's Tredgold on Carpentry.

Kirkaldy's Experiments on Wrought-Iron and Steel.

Mahan's Civil Engineering.

Mahan's Moseley's Engineering and Architecture.

Moseley's Engineering and Architecture.

Poisson's Traité de Mécanique.

Ranken on Strains in Trusses.

Rankine's Applied Mechanics.

Robison's Mechanical Philosophy.

Rondelet sur le Dôme du Panthéon Français.

Sheilds' Strains on Structures of Ironwork.

Styffe on Iron and Steel.

Tarn on the Science of Building.

Tate on the Strength of Materials.

Tredgold's Carpentry.

Unwin on Iron Bridges and Roofs.

Weisbach's Mechanics and Engineering.

Wood on the Resistance of Materials.

GENERAL CONTENTS.

INTRODUCTION.

CHAPTER I.

THE LAW OF RESISTANCE.

CHAPTER II.

APPLICATION OF THE LEVER PRINCIPLE.

CHAPTER III.

DESTRUCTIVE ENERGY AND RESISTANCE.

CHAPTER IV.

EFFECT OF WEIGHT AS REGARDS ITS POSITION.

CHAPTER V.

COMPARISON OF CONDITIONS—SAFE LOAD.

CHAPTER VI.

APPLICATION OF RULES—FLOORS.

CHAPTER VII.
GIRDERS, HEADERS AND CARRIAGE BEAMS.

CHAPTER VIII.

GRAPHICAL REPRESENTATIONS.

CHAPTER IX.

STRAINS REPRESENTED GRAPHICALLY.

CHAPTER X.

STRAINS FROM UNIFORMLY DISTRIBUTED LOADS.

CHAPTER XI.
STRAINS IN LEVERS, GRAPHICALLY EXPRESSED.

CHAPTER XII.

COMPOUND STRAINS IN BEAMS, GRAPHICALLY EXPRESSED.

CHAPTER XIII.

DEFLECTING ENERGY.

CHAPTER XIV.

RESISTANCE TO FLEXURE.

CHAPTER XV.

RESISTANCE TO FLEXURE—LIMIT OF ELASTICITY.

CHAPTER XVI.

RESISTANCE TO FLEXURE—RULES.

CHAPTER XVII.

RESISTANCE TO FLEXURE—FLOOR BEAMS.

CHAPTER XVIII.

BRIDGING FLOOR BEAMS.

CHAPTER XIX.
ROLLED-IRON BEAMS.

CHAPTER XX.

TUBULAR IRON GIRDERS.

CHAPTER XXI.

CAST-IRON GIRDERS.

CHAPTER XXII. FRAMED GIRDERS.

CHAPTER XXIII. ROOF TRUSSES.

CHAPTER XXIV.

DIGEST OR DIRECTORY.

INDEX.

ANSWERS TO QUESTIONS.

CONTENTS.

INTRODUCTION.

ART.

- 1.—Construction Defined.
- 2.—Stability Indispensable.
- 3.—Laws Governing the Force of Gravity.
- 4.—Science of Construction, for Architect rather than Builder.
- 5.—Parts of Buildings requiring Special Attention.
- 6.—This Work Limited to the Transverse Strain.
- 7.—In Construction Safety Indispensable.
- 8.—Some Floors are Deficient in Strength.
- 9.—Precedents not always Accessible.
- 10.—An Experimental Floor, an Expensive Test.
- 11.—Requisite Knowledge through Specimen Tests.
- 12.—Unit of Material—Its Dimensions.
- 13.—Value of the Unit for Seven Kinds of Material.

CHAPTER I.

THE LAW OF RESISTANCE.

- 14.—Relation between Size and Strength.
- 15.—Strength not always in Proportion to Area of Cross-section.
- 16.—Resistance in Proportion to Area of Cross-section.
- 17.—Units may be Taken of any Given Dimensions.
- 18.—Experience Shows a Beam Stronger when Set on Edge.
- 19.—Strength Directly in Proportion to Breadth.
- 20.—By Experiment Strength Increases more Rapidly than the Depth.
- 21.—Comparison of a Solid Beam with a Laminated one.
- 22.—Strength due to Resistance of Fibres to Extension and Compression.
- 23.—Power Extending Fibres in Proportion to Depth of Beam.

CHAPTER II.

APPLICATION OF THE LEVER PRINCIPLE.

- 24.—The Law of the Lever.
- 25.—Equilibrium—Direction of Pressures.

- 26.—Conditions of Pressure in a Loaded Beam.
- 27.—The Principle of the Lever.
- 28.—A Loaded Beam Supported at Each End.
- 29.—A Bent Lever.
- 30.—Horizontal Strains Illustrated by the Bent Lever.
- 31.—Resistance of Fibres in Proportion to the Depth of Beam.

CHAPTER III.

DESTRUCTIVE ENERGY AND RESISTANCE.

- 32.—Resistance to Compression—Neutral Line.
- 33.—Elements of Resistance to Rupture.
- 34.—Destructive Energies.
- 35.—Rule for Transverse Strength of Beams.
- 36.—Formulas Derived from this Rule.
- 37 to 51.—Questions for Practice.

CHAPTER IV.

THE EFFECT OF WEIGHT AS REGARDS ITS POSITION.

- 52.—Relation between Destructive Energy and Resistance.
- 53.—Dimensions and Weights to be of Like Denominations with those of the Unit Adopted.
 - 54.—Position of the Weight upon the Beam.
 - 55.—Formula Modified to Apply to a Lever.
 - 56.—Effect of a Load at Any Point in a Beam.
 - 57.—Rule for a Beam Loaded at Any Point.
 - 58.—Effect of an Equally Distributed Load.
 - 59.—Effect at Middle from an Equally Distributed Load.
 - 60.—Example of Effect of an Equally Distributed Load.
 - 61.—Result also Obtained by the Lever Principle.
 - 62 to 65.—Questions for Practice.

CHAPTER V.

COMPARISON OF CONDITIONS—SAFE LOAD.

- 66.—Relation between Lengths, Weights and Effects.
- 67.—Equal Effects.

- 68.—Comparison of Lengths and Weights Producing Equal Effects.
- 69.—The Effects from Equal Weights and Lengths.
- 70.—Rules for Cases in which the Weights and Lengths are Equal.
- 71.—Breaking and Safe Loads.
- 72.—The above Rules Useful Only in Experiments.
- 73.—Value of a, the Symbol of Safety.
- 74.—Value of 'a, the Symbol of Safety.
- 75.—Rules for Safe Loads.
- 76.—Applications of the Rules.
- 77—Example of Load at End of Lever.
- 78.—Arithmetical Exemplification of the Rule.
- 79.—Caution in Regard to a, the Symbol of Safety.
- 80.—Various Methods of Solving a Problem.
- 81.—Example of Uniformly Distributed Load on Lever.
- 82.—Load Concentrated at Middle of Beam.
- 83.—Load Uniformly Distributed on Beam Supported at Both Ends.
- 84 to 87—Questions for Practice.

CHAPTER VI.

APPLICATION OF RULES-FLOORS.

- 88.—Application of Rules to Construction of Floors.
- 89.—Proper Rule for Floors.
- 90.—The Load on Ordinary Floors, Equally Distributed.
- 91.—Floors of Warehouses, Factories and Mills.
- 92.—Rule for Load upon a Floor Beam.
- 93.—Nature of the Load upon a Floor Beam.
- 94.—Weight of Wooden Beams.
- 95.—Weight in Stores, Factories and Mills to be Estimated.
- 96.—Weight of Floor Plank.
- 97.—Weight of Plastering.
- 98.—Weight of Beams in Dwellings.
- 99.—Weight of Floors in Dwellings.
- 100-Superimposed Load.
- 101.—Greatest Load upon a Floor.
- 102.—Tredgold's Estimate of Weight on a Floor.
- 103.—Tredgold's Estimate not Substantiated by Proof.
- 104.—Weight of People—Sundry Authorities.
- 105.—Estimated Weight of People per Square Foot of Floor.
- 106-Weight of People, Estimated as a Live Load.
- 107.—Weight of Military.
- 108-Actual Weights of Men at Jackson's and at Hoes' Foundries.
- 109.—Actual Measure of Live Load.
- 110.-More Space Required for Live Load.
- 111,-No Addition to Strain by Live Load.

- 112-Margin of Safety Ample for Momentary Extra Strain in Extreme Cases.
- 113.—Weight Reduced by Furniture Reducing Standing Room.
- 114.—The Greatest Load to be provided for is 70 Pounds per Superficial Foot.
 - 115.—Rule for Floors of Dwellings.
 - 116.—Distinguishing Between Known and Unknown Quantities.
 - 117-Practical Example.
 - 118.—Eliminating Unknown Quantities.
 - 119.—Isolating the Required Unknown Quantity.
 - 120.—Distance from Centres at Given Breadth and Depth.
 - 121.—Distance from Centres at Another Breadth and Depth.
 - 122.—Distance from Centres at a Third Breadth and Depth.
 - 123.—Breadth, the Depth and Distance from Centres being Given.
 - 124.—Depth, the Breadth and Distance from Centres being Given.
 - 125.—General Rules for Strength of Beams.
 - 126 to 135.—Questions for Practice.

CHAPTER VII.

GIRDERS, HEADERS AND CARRIAGE BEAMS.

- 136.—A Girder Defined.
- 137.—Rule for Girders.
- 138.—Distance between Centres of Girders.
- 139.—Example of Distance from Centres.
- 140.—Size of Girder Required in above Example.
- 141.—Framing for Fireplaces, Stairs and Light-wells.
- 142.—Definition of Carriage Beams, Headers and Tail Beams.
- 143.—Formula for Headers—General Considerations.
- 144.—Allowance for Damage by Mortising.
- 145.—Rule for Headers.
- 146.—Example.
- 147.—Carriage Beams and Bridle Irons.
- 148.—Rule for Bridle Irons.
- 149.—Example.
- 150.—Rule for Carriage Beam with One Header.
- 151.—Example.
- 152.—Carriage Beam with Two Headers.
- 153.—Effect of Two Weights at the Location of One of Them.
- 154.—Example.
- 155.—Rule for Carriage Beam with Two Headers and Two Sets of Tail Beams.
- 156.—Example.
- 157.—Rule for Carriage Beam with Two Headers and One Set of Tail Beams.
- 158,—Example.
- 159 to 166.—Questions for Practice.

CHAPTER VIII.

GRAPHICAL REPRESENTATIONS.

- 167.—Advantages of Graphical Representations.
- 168.—Strains in a Lever Measured by Scale.
- 169.—Example—Rule for Dimensions.
- 170.—Graphical Strains in a Double Lever.
- 171.—Graphical Strains in a Beam.
- 172.—Nature of the Shearing Strain.
- 173.—Transverse and Shearing Strains Compared.
- 174.—Rule for Shearing Strain at Ends of Beams.
- 175.—Resistance to Side Pressure.
- 176.—Bearing Surface of Beams upon Walls.
- 177.—Example to Find Bearing Surface.
- 178.—Shape of Side of Beam, Graphically Expressed.
- 179 to 187.—Questions for Practice.

CHAPTER IX.

STRAINS REPRESENTED GRAPHICALLY.

- 188.—Graphic Method Extended to Other Cases.
- 189.—Application to Double Lever with Unequal Arms.
- 190.—Application to Beam with Weight at Any Point.
- 191.—Example.
- 192.—Graphical Strains by Two Weights.
- 193.—Demonstration.
- 194.—Demonstration—Rule for the Varying Depths.
- 195.—Graphical Strains by Three Weights.
- 196.—Graphical Strains by Three Equal Weights Equably Disposed.
- 197.—Graphical Strains by Four Equal Weights Equably Disposed.
- 198.—Graphical Strains by Five Equal Weights Equably Disposed.
- 199.—General Results from Equal Weights Equably Disposed.
- 200.—General Expression for Full Strain at First Weight.
- 201.—General Expression for Full Strain at Second Weight.
- 202.—General Expression for Full Strain at Any Weight.
- 203.—Example.
- 204 to 209.—Questions for Practice.

CHAPTER X.

STRAINS FROM UNIFORMLY DISTRIBUTED LOADS.

- 210.—Distinction Between a Series of Concentrated Weights and a Thoroughly Distributed Load.
 - 211.—Demonstration.
 - 212.—Demonstration by the Calculus.
 - 213.—Distinction Shown by Scales of Strains.
 - 214.—Effect at Any Point by an Equally Distributed Load.
 - 215.—Shape of Side of Beam for an Equably Distributed Load.
 - 216.—The Form of Side of Beam a Semi-ellipse.
 - 217 to 220—Questions for Practice.

CHAPTER XI.

STRAINS IN LEVERS, GRAPHICALLY EXPRESSED.

- 221.—Scale of Strains for Promiscuously Loaded Lever.
- 222—Strains and Sizes of Lever Uniformly Loaded.
- 223.—The Form of Side of Lever a Triangle.
- 224.—Combinations of Conditions.
- 225.—Strains and Dimensions for Compound Load.
- 226.—Scale of Strains for Compound Loads.
- 227.—Scale of Strains for Promiscuous Load.
- 228 to 233.—Questions for Practice.

CHAPTER XII.

COMPOUND STRAINS IN BEAMS, GRAPHICALLY EXPRESSED.

- 234.—Equably Distributed and Concentrated Loads on a Beam.
- 235.—Greatest Strain Graphically Represented.
- 236.—Location of Greatest Strain Analytically Defined.
- 237.—Location of Greatest Strain Differentially Defined.
- 238.—Greatest Strain Analytically Defined.
- 239.—Example.
- 240—Dimensions of Beam for Distributed and Concentrated Loads.
- 241.—Comparison of Formulas, Here and in Art. 150.
- 242.—Location of Greatest Strain Differentially Defined.
- 243.—Greatest Strain and Dimensions.
- 244—Assigning the Symbols.
- 245.—Example—Strain and Size at a Given Point.
- 246.—Example—Greatest Strain.
- 247—Example—Dimensions.

- 248.—Dimensions for Greatest Strain when h Equals n.
- 249—Dimensions for Greatest Strain when 'h is Greater than n.
- 250.—Rule for Carriage Beams with Two Headers and Two Sets of Tail Beams.
 - 251.—Example.
 - 252.—Carriage Beam with Three Headers.
 - 253.—Three Headers—Strains of the First Class.
 - 254.—Graphical Representation.
 - 255.—Greatest Strain.
 - 256.—General Rule for Equably Distributed and Three Concentrated Loads.
 - 257.—Example.
- 258.—Rule for Carriage Beams with Three Headers and Two Sets of Tail Beams.
 - 259.—Example.
 - 260.—Three Headers—Strains of the Second Class.
 - 261.—Greatest Strain.
 - 262.—General Rule for Equally Distributed and Three Concentrated Loads.
 - 263.—Example.
 - 264.—Assigning the Symbols.
 - 265.—Reassigning the Symbols.
 - 266.—Example.
- 267.—Rule for Carriage Beam with Three Headers and Two Sets of Tail Beams.
 - 268.—Example.
 - 269 and 270.—Questions for Practice.

CHAPTER XIII.

DEFLECTING ENERGY.

- 271.—Previously Given Rules are for Rupture.
- 272.—Beam not only to Be Safe, but to Appear Safe.
- 273.—All Materials Possess Elasticity.
- 274.—Limits of Elasticity Defined.
- 275.—A Knowledge of the Limits of Elasticity Requisite.
- 276.—Extension Directly as the Force.
- 277.—Extension Directly as the Length.
- 278.—Amount of Deflection.
- 279.—The First Step.
- 280.—Deflection to be Obtained from the Extension.
- 281.—Deflection Directly as the Extension.
- 282.—Deflection Directly as the Force, and as the Length.
- 283.—Deflection Directly as the Length.
- 284.—Deflection Directly as the Length.
- 285.—Total Deflection Directly as the Cube of the Length.
- 286.—Deflecting Energy Directly as the Weight and Cube of the Length.
- 287 to 291.—Questions for Practice.

CHAPTER XIV.

RESISTANCE TO FLEXURE.

- 292.—Resistance to Rupture, Directly as the Square of the Depth.
- 293.—Resistance to Extension Graphically Shown.
- 294.—Resistance to Extension in Proportion to the Number of Fibres and their Distance from Neutral Line.
 - 295.—Illustration.
 - 296.—Summing up the Resistances of the Fibres.
 - 297.—True Value to which these Results Approximate.
 - 298.—True Value Defined by the Calculus.
 - 299.—Sum of the Two Resistances, to Extension and to Compression.
 - 300.—Formula for Deflection in Levers.
 - 301.—Formula for Deflection in Beams.
 - **302.**—Value of F, the Symbol for Resistance to Flexure.
 - 303.—Comparison of F with E, the Modulus of Elasticity.
 - 304.—Relative Value of F and E.
 - **305.**—Comparison of F with E common, and with the E of Barlow.
 - 306-Example under the Rule for Flexure.
 - 307 to 310.—Questions for Practice.

CHAPTER XV.

RESISTANCE TO FLEXURE—LIMIT OF ELASTICITY.

- 311.—Rules for Rupture and for Flexure Compared.
- 312.—The Value of a, the Symbol for Safe Weight.
- 313.—Rate of Deflection per Foot Length of Beam.
- 314.—Rate of Deflection in Floors.
- 315 to 319.—Questions for Practice.

CHAPTER XVI.

RESISTANCE TO FLEXURE—RULES.

- 320.—Deflection of a Beam, with Example.
- 321.—Precautions as to Values of Constants F and ϵ .
- 322.—Values of Constants F and e to be Derived from Actual Experiment in Certain Cases.

- 323.—Deflection of a Lever.
- 324.—Example.
- 325.—Test by Rule for Elastic Limit in a Lever.
- 326.—Load Producing a Given Deflection in a Beam.
- 327.—Example.
- .328.—Load at the Limit of Elasticity in a Beam.
- 329.—Load Producing a Given Deflection in a Lever—Example.
- 330.—Deflection in a Lever at the Limit of Elasticity.
- 331.—Load on Lever at the Limit of Elasticity.
- **332.**—Values of W, l, b, d and δ in a Beam.
- 333.—Example—Value of / in a Beam.
- **334.**—Example—Value of b in a Beam.
- 335.—Example—Value of d in a Beam.
- **336.**—Values of P, n, b, d and δ in a Lever.
- 337.—Example—Value of n in a Lever.
- 338.—Example—Value of b in a Lever.
- **339.**—Example—Value of d in a Lever.
- 340.—Deflection—Uniformly Distributed Load on a Beam.
- **341.**—Values of U, l, b, d and δ in a Beam.
- **342.**—Example—Value of U, the Weight, in a Beam.
- 343.—Example—Value of I, the Length, in a Beam.
- **344.**—Example—Value of b, the Breadth, in a Beam.
- 345.—Example—Value of d, the Depth, in a Beam.
- **346.**—Example—Value of δ , the Deflection, in a Beam.
- 347.—Deflection—Uniformly Distributed Load on a Lever.
- **348.**—Values of U, n, b, d and δ in a Lever.
- **349.**—Example—Value of U, the Weight, in a Lever.
- 350.—Example—Value of n, the Length, in a Lever.
- **351.**—Example—Value of b, the Breadth, in a Lever.
- **352.**—Example—Value of d, the Depth, in a Lever.
- **353.**—Example—Value of δ , the Deflection, in a Lever.
- 354 to 357.—Questions for Practice.

CHAPTER XVII.

RESISTANCE TO FLEXURE—FLOOR BEAMS.

- 358.—Stiffness a Requisite in Floor Beams.
- 359.—General Rule for Floor Beams.
- 360.—The Rule Modified.
- 361.—Rule for Dwellings and Assembly Rooms.
- **362.**—Rules giving the Values of c, l, b and d.
- 363.—Example—Distance from Centres.
- 364.—Example—Length.
- 365.—Example—Breadth.
- 366.—Example—Depth.

- 367.—Floor Beams for Stores.
- 368.—Floor Beams of First class Stores.
- 369.—Rule for Beams of First-class Stores.
- 370.—Values of c, l, b and d.
- 371.—Example—Distance from Centres.
- 372.—Example—Length.
- 373.—Example—Breadth.
- 374.—Example—Depth.
- 375.—Headers and Trimmers.
- 376.—Strength and Stiffness—Relation of Formulas.
- 377.—Strength and Stiffness—Value of a, in Terms of B and F.
- 378.—Example.
- 379.—Test of the Rule.
- 380.—Rules for Strength and Stiffness Resolvable.
- 381.—Rule for the Breadth of a Header.
- 382.—Example of a Header for a Dwelling.
- 383.—Example of a Header in a First-class Store.
- 384.—Carriage Beam with One Header.
- 385.—Carriage Beam with One Header, for Dwellings.
- 386.—Example.
- 387.—Carriage Beam with One Header, for First-class Stores.
- 388.—Example.
- 389.—Carriage Beam with One Header, for Dwellings—More Precise Rule.
- 390.—Example.
- 391.—Carriage Beam with One Header, for First-class Stores—More Preise Rule.
 - 392.—Example.
- 393.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for)wellings, etc.
 - 394.—Example.
- 395.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for irst-class Stores.
 - 396.—Example.
 - 397.—Carriage Beam with Two Headers and One Set of Tail Beams.
- 398,—Carriage Beam with Two Headers and One Set of Tail Beams, for wellings.
 - 399.—Example.
- 400.—Carriage Beam with Two Headers and One Set of Tail Beams, for irst-class Stores.
 - 401.—Example.
- 402.—Carriage Beam with Two Headers and Two Sets of Tail Beams—lore Precise Rules.
 - 403.—Example— h less than n.
 - 404.—Example— h greater than n.
- 405.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for wellings—More Precise Rule.
 - 406.—Example.
- 407.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for irst-class Stores—More Precise Rule.

- 408.—Example.
- 409.—Carriage Beam with Two Headers and One Set of Tail Beams—More Precise Rule.
 - 410.—Example.
- 411.—Carriage Beam with Two Headers and One Set of Tail Beams, for Dwellings—More Precise Rule.
 - 412.—Example.
- 413.—Carriage Beam with Two Headers and One Set of Tail Beams, for First-class Stores—More Precise Rule.
 - 414.—Example.
- 415.—Carriage Beam with Two Headers, Equidistant from Centre, and Two Sets of Tail Beams—Precise Rule.
 - 416.—Example.
- 417.—Carriage Beams with Two Headers, Equidistant from Centre, and Two sets of Tail Beams, for Dwellings and for First-class Stores—Precise Rules.
 - 418.—Examples.
- 419.—Carriage Beam with Two Headers, Equidistant from Centre, and One Set of Tail Beams—Precise Rule.
 - 420.—Example.
- 421.—Carriage Beams with Two Headers, Equidistant from Centre, and One Set of Tail Beams, for Dwellings and for First-class Stores—Precise Rules.
 - 422.—Example.
- 423.—Beam with Uniformly Distributed and Three Concentrated Loads, the Greatest Strain being Outside.
 - 424.—Example.
- 425.—Carriage Beam with Three Headers, the Greatest Strain being at Outside Header.
 - 426.—Example.
- 427.—Carriage Beam with Three Headers, the Greatest Strain being at Outside Header, for Dwellings.
- 428.—Carriage Beam with Three Headers, the Greatest Strain being at Outside Header, for First-class Stores.
 - 429.—Examples.
- 430.—Beams with Uniformly Distributed and Three Concentrated Loads, the Greatest Strain being at Middle Load.
 - 431.—Example.
- 432.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header.
 - 433.—Example.
- 434.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for Dwellings.
- 435.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for First-class Stores.
 - 436.—Example.
 - 437 to 442.—Questions for Practice.

CHAPTER XVIII.

BRIDGING FLOOR BEAMS.

- 443.—Bridging Defined.
- 444.—Experimental Test.
- 445.—Bridging—Principles of Resistance.
- 446.—Resistance of a Bridged Beam
- 447.—Summing the Resistances.
- 448.—Example.
- 449.—Assistance Derived from Cross-bridging.
- 450.—Number of Beams Affording Assistance.
- 451.—Bridging Useful in Sustaining Concentrated Weights.
- 452.—Increased Resistance Due to Bridging.

CHAPTER XIX.

ROLLED-IRON BEAMS.

- 453.—Iron a Substitute for Wood.
- 454.—Iron Beam—Its Progressive Development.
- 455.—Rolled-Iron Beam—Its Introduction.
- 456.—Proportions between Flanges and Web.
- 457.—The Moment of Inertia Arithmetically Considered.
- 458—Example A.
- 459.—Example B.
- 460,—-Example C.
- 461.—Comparison of Results.
- 462.—Moment of Inertia, by the Calculus—Preliminary Statement.
- 463.—Moment of Inertia, by the Calculus.
- 464—Application and Comparison.
- 465.—Moment of Inertia Graphically Represented.
- 466.—Parabolic Curve—Area of Figure.
- 467.—Example.
- 468.—Moment of Inertia—General Rule.
- 469.—Application.
- 470.—Rolled-Iron Beam—Moment of Inertia—Top Flange.
- 471.—Rolled-Iron Beam—Moment of Inertia—Web.
- 472.—Rolled-Iron Beam—Moment of Inertia—Flange and Web.
- 473-Rolled-Iron Beam-Moment of Inertia-Whole Section.
- 474.—Rolled-Iron Beam—Moment of Inertia—Comparison with other Formulas.
 - 475.—Rolled-Iron Beam—Moment of Inertia—Comparison of Results.
 - 476.—Rolled-Iron Beam—Moment of Inertia—Remarks.
 - 477.—Reduction of Formula—Load at Middle.

478.—Rules—Values of W, l, δ and I.

479—Example—Weight.

480.—Example—Length.

481.—Example—Deflection.

482.—Example—Moment of Inertia.

483.—Load at Any Point—General Rule.

484.—Load at Any Point on Rolled-Iron Beams.

485.—Load at Any Point on Rolled-Iron Beams of Table XVII.

486.—Example.

487.—Load at End of Rolled-Iron Lever.

488.—Example.

489.—Uniformly Distributed Load on Rolled-Iron Beam.

490.—Example.

491.—Uniformly Distributed Load on Rolled-Iron Lever.

492.—Example.

493.—Components of Load on Floor.

494.—The Superincumbent Load.

495.—The Materials of Construction—Their Weight.

496.—The Rolled-Iron Beam—Its Weight.

497.—Total Load on Floors.

498.—Floor Beams—Distance from Centres.

499.—Example.

500:—Floor Beams—Distance from Centres—Dwellings, etc.

501.—Example.

502.—Floor Beams—Distance from Centres.

503.—Example.

504.—Floor Beams—Distance from Centres—First-class Stores.

505.—Example.

506.—Floor Arches—General Considerations.

507.—Floor Arches—Tie-Rods.

508.—Example.

509.—Headers.

510.—Headers for Dwellings, etc.

511.—Example.

512.—Headers for First-class Stores.

513.—Carriage Beam with One Header.

514.—Carriage Beam with One Header, for Dwellings, etc.

515.—Example.

516.—Carriage Beam with One Header, for First-class Stores.

517.—Example.

518.—Carriage Beam with Two Headers and Two Sets of Tail Beams.

519.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for Dwellings, etc

520.—Example.

521.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for First-class Stores.

522.—Example.

523.—Carriage Beam with Two Headers, Equidistant from Centre, and Two Sets of Tail Beams, for Dwellings, etc.

524.—Example.

525.—Carriage Beam with Two Headers, Equidistant from Centre, and Two Sets of Tail Beams, for First-class Stores.

526.—Example.

527.—Carriage Beam with Two Headers and One Set of Tail Beams, for Dwellings, etc.

528.—Example.

529.—Carriage Beam with Two Headers and One Set of Tail Beams, for First-class Stores.

530.—Example.

531.—Carriage Beam with Three Headers, the Greatest Strain being at Outside Header, for Dwellings, etc.

532.—Example.

533.—Carriage Beam with Three Headers, the Greatest Strain being at Outside Header, for First-class Stores.

534.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for Dwellings, etc.

535.—Example.

536.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for First-class Stores.

537 to 545.—Questions for Practice.

CHAPTER XX.

TUBULAR IRON GIRDERS.

546.—Introduction of the Tubular Girder.

547.—Load at Middle—Rule Essentially the Same as that for Rolled-Iron Beams.

548.—Load at Any Point-Load Uniformly Distributed.

549.—Load at Middle—Common Rule.

550.—Capacity by the Principle of Moments.

551.—Load at Middle—Moments.

552.—Example.

553.—Load at Any Point.

554.—Example.

555.—Load Uniformly Distributed.

556.—Example.

557.—Thickness of Flanges.

558.—Construction of Flanges.

559.—Shearing Strain.

560.—Thickness of Web.

561.—Example.

562.—Construction of Web.

563.—Floor Girder—Area of Flange.

564—Weight of the Girder.

565.-Weight of Girder per Foot Superficial of Floor.

566 .- Example.

567.—Total Weight of Floor per Foot Superficial, including Girder.

568.—Girders for Floors of Dwellings, etc.

569.—Example.

570.-Girders for Floors of First class Stores.

571.-Ratio of Depth to Length, in Iron Girders.

572.-Economical Depth.

573.-Example.

574 to 579.—Questions for Practice.

CHAPTER XXI.

CAST-IRON GIRDERS.

580.—Cast-Iron Superseded by Wrought-Iron.

581-Flanges-Their Relative Proportion.

582.-Flanges and Web-Relative Proportion.

583, -Load at Middle.

584,-Example.

585.-Load Uniformly Distributed.

586 .- Load at Any Point-Rupture.

587-Safe Load at Any Point.

588.-Example.

589.—Safe Load Uniformly Distributed—Effect at Any Point.

590 .- Form of Web.

591 Two Concentrated Weights-Safe Load.

592.-Examples,

593 .- Arched Girder.

594.-Tie-Rod of Arched Girder.

595,-Example.

596.—Substitute for Arched Girder.

597 to 602.-Questions for Practice.

CHAPTER XXII.

FRAMED GIRDERS.

603,-Transverse Strains in Framed Girders.

604.—Device for Increasing the Strength of a Beam,

605.-Horizontal Thrust.

606.—Parallelogram of Forces.—Triangle of Forces.

607,-Lines and Forces in Proportion.

- 608.—Horizontal Strain Measured Graphically.
- 609.—Measure of Any Number of Forces in Equilibrium.
- 610.—Strains in an Equilibrated Truss.
- 611.—From Given Weights to Construct a Scale of Strains.
- 612.—Example.
- 613.—Horizontal Strain Measured Arithmetically.
- 614.—Vertical Pressure upon the Two Points of Support.
- 615.—Strains Measured Arithmetically.
- 616.—Curve of Equilibrium—Stable and Unstable.
- 617.—Trussing a Frame.
- 618.—Forces in a Truss Graphically Measured.
- 619.—Example.
- 620.—Another Example.
- 621.—Diagram of Forces.
- 622.—Diagram of Forces—Order of Development.
- 623.—Reciprocal Figures.
- 624.—Proportions in a Framed Girder.
- 625.—Example.
- 626.—Trussing, in a Framed Girder.
- 627.—Planning a Framed Girder.
- 628.—Example.
- 629.—Example.
- 630.—Number of Bays in a Framed Girder.
- 631.—Forces in a Framed Girder.
- 632.—Diagram for the above Framed Girder.
- 633.—Gradation of Strains in Chords and Diagonals.
- 634.—Framed Girder with Loads on Each Chord.
- 635.—Gradation of Strains in Chords and Diagonals.
- 636.—Strains Measured Arithmetically.
- 637.—Strains in the Diagonals.
- 638.—Example.
- 639.—Strains in the Lower Chord.
- 640.—Strains in the Upper Chord.
- 641.—Example.
- 642.—Resistance to Tension.
- 643.—Resistance to Compression.
- 644.—Top Chord and Diagonals—Dimensions.
- 645.—Example.
- 646.—Derangement from Shrinkage of Timbers.
- 647.—Framed Girder with Unequal Loads, Irregularly Placed.
- 648.—Load upon Each Support—Graphical Representation.
- 649.—Girder Irregularly Loaded—Force Diagram.
- 650.—Load upon Each Support, Arithmetically Obtained.
- 651 to 656.—Questions for Practice.

CHAPTER XXIII.

ROOF TRUSSES.

- 637. King Trusses considered as Framed Girders.
- 638. Comparison of Roof Trusses.
- 639. Force Diagram—Load upon Each Support.
- 660.—Force Diagram for Truss in Fig. 98.
- 661. Force Diagram for Truss in Fig. 99.
- 662. Force Diagram for Truss in Fig. 100-
- 663.—Force Diagram for Truss in Fig. 101.
- 664. Force Diagram for Truss in Fig. 102.
- 665.—Force Diagram for Truss in Fig. 103.
- 666.—Force Diagram for Truss in Fig. 104.
- 667.—Force Diagram for Truss in Fig. 105.
- 668.—Force Diagram for Truss in Fig. 106.
- 669.—Strains in Horizontal and Inclined Ties Compared.
- 670.—Vertical Strain in Truss with Inclined Tie.
- 671.—Illustrations.
- 672.—Planning a Roof.
- 673.—Load upon Roof Truss.
- 674.—Load on Roof per Foot Horizontal.
- 675.—Load upon Tie-Beam.
- 676.—Selection of Design for Roof Truss.
- 677.—Load on Each Supported Point in Truss.
- 678.—Load on Each Supported Point in Tie-Beam.
- 679.—Constructing the Force Diagram.
- 680.—Measuring the Force Diagram.
- 681.—Strains Computed Arithmetically.
- 682.—Dimensions of Parts Subject to Tension.
- 683.—Dimensions of Parts Subject to Compression.
- 684.—Dimensions of Mid-Rafter.
- **685.**—Dimensions of Upper Rafter.
- 686.—Dimensions of Brace.
- 687—Dimensions of Straining-Beam.
- 688 to 692.—Questions for Practice.

CHAPTER XXIV.

TABLES.

- 693.—Tables I. to XXI.—Their Utility.
- 694.—Floor Beams of Wood and Iron (I. to XIX.).
- 695.—Floor Beams of Wood (I. to VIII.).
- 696.—Headers of Wood (IX. to XVI.).
- 697.—Elements of Rolled-Iron Beams (XVII.).
- 698.—Rolled-Iron Beams for Office Buildings, etc. (XVIII.).

- 699.—Rolled-Iron Beams for First-class Stores (XIX.).
- **700.**—Example.
- 701.—Constants for Use in the Rules (XX.).
- 702.—Solid Timber Floors (XXI.).
- 703.—Weights of Building Materials (XXII.).
- 704.—Experiments on American Woods (XXIII. to XLVI.).
- 705.—Experiments by Transverse Strain (XXIII. to XXXV., XLII. and XLIII.).
- 706.—Experiments by Tensile and Sliding Strains (XXXVI. to XXXIX., XLIV. and XLV.).
 - 707.—Experiments by Crushing Strain (XL., XLI. and XLVI.).

TABLES.

I.—Hemlock	Floor I	Beams	for I	Dwellir	ngs. Off	ice Buil	ldings	etc.			
II.—White Pin			44	44	-6-,	16	"	11			
III.—Spruce	44		46	44		• •	"	46			
IV.—Georgia P	ine "		46	• 6		16	"				
V.—Hemlock Floor beams for First-class Stores.											
VI.—White Pin			44	66		44					
VII.—Spruce	4.4		••	4 6		44					
VIII.—Georgia P	ine "		60	4.6		66					
IX.—Hemlock Headers for Dwellings, Office Buildings, etc.											
X.—White Pin		• •		"	44	"	66	-			
XI.—Spruce	44	4.4		• •	"	46	6.6				
XII.—Georgia P	ine "	"		• •	44	46	46				
XIII.—Hemlock Headers for First-class Stores.											
XIV.—White Pin		• •		**	"	•					
XV.—Spruce	44	46		46							
XVI.—Georgia P	ine "	44	1	44	44						
XVII.—Elements of Rolled-Iron Beams.											
XVIII.—Rolled Iron Beams for Dwellings, Office Buildings, etc.											
XIX.— "	44	64		•	Stores.		•				
XX.—Values of Constants Used in the Rules.											
XXI.—Solid Timber Floors—Thickness.											
XXII.—Weights of Materials of Construction and Loading.											
XXIII.—Transverse Strains in Georgia Pine.											
XXIV.— "	66	" I	ocus	t.							
XXV.— "	44	" 1	W hite	Oak.							
XXVI.— "	64	" 5	pruce	€.							
XXVII.— "	44	4.6	4.6								
XXVIII.— "	46	44	44								
XXIX.— "	45	"]	White	Pine.							
XXX.— "	44	44	4.6	"							
XXXI.— "	44	66	4.6	4.6							
XXXII.— "	64	44	"	64							

T— JIIZZZ	ransverse	Strains in	Hemlock	K.	
XXXIV.—	4	4 "	46		
XXXV.—	• •	4 "	46		
T—.IVXXX	ensile Str	ains in Ge	orgia Pin	e, Locust an	d White Oak.
XXXVII.—	• •	" " Spi	ruce, Whi	te Pine and	Hemlock.
XXXVIII.—S	liding Str	ains in Ge	orgia Pin	e, Locust an	d White Oak.
-XIXXX	4.6	" " Spr	uce, Whi	te Pine and	Hemlock.
XL.—C	rushing S	Strains in G	eorgia P	ine, Locust	and White Oak.
XLI.—	• •	" " S	pruce, W	hite Pine ar	d Hemlock.
XLII.—R	upture by	Transvers	se Strain-	-Values of	B.
XLIII.—R	esistance	to Deflecti	ion—Valu	ues of F.	
XLIV.—R	•			alues of T.	
XLV.—	44 44	Sliding	4	" G.	
XLVI.—	4 4	Compress	sive Strain	n—Values o	f <i>C</i> .

DIGEST OR DIRECTORY.

INDEX.

ANSWERS TO QUESTIONS.

INTRODUCTION.

- ART. I.—The science of Construction, as the term is used in architecture, comprehends a knowledge of the forces tending to destroy the materials constituting a building, and of the capacities of resistance of the materials to these forces.
- 2.—One of the requisites of good architecture is Stability. Without this the beautiful designs of the architect can have no lasting existence beyond the paper upon which they are delineated.
- 3.—The force of Gravity is inherent not only in the contents of a building, but also in the materials of which the building itself is constructed; and unless these materials have an adequate power of resistance to this force, the safety of the building is endangered. Hence the necessity of a knowledge of the laws governing the force of gravity in its action upon the several parts of a building, and of the expedients to be resorted to in order to resist its action effectually.
- 4.—It may be objected by some that this knowledge pertains rather to building than to architecture, and that the architect is required merely to indicate the outlines of his plans, leaving to the builder the work of determining the arrangement and dimensions of the materials. This objection is not well founded. Between the duties c

the architect and those of the builder there is a well-defined line. This may be shown by a consideration of the operation of building as it is usually conducted. The builder is selected generally from among those who compete for the work. Each builder competing fixes the amount for which he is willing to erect the building, after an examination of the plans and specifications and an estimate of the cost of the work. To arrive at this cost the arrangement and dimensions of the materials must be fixed; and if not fixed by the plans and specifications, in what way shall they be determined? Shall it be by the builder? The builder has not yet been selected. Shall each builder estimating be permitted to assign such dimensions as his caprice or cupidity shall dictate? The evil effect of such a course is apparent. The only proper method is to have the arrangement and dimensions of the materials all definitely settled by the architect in his plans and specifications.

Moreover, the necessity for a knowledge of this subject by the architect is manifest in this, that he is constantly liable, without this knowledge, to include in his plans such features as the action of gravity would render impossible of production in solid material, or which, if executed, would not possess the requisite degree of stability.

- 5.—In considering the requisites for stability in a building, the various parts need to be taken in detail: such as Walls, Piers, Columns, Buttresses, Foundations, Arches, Lintels, Floors, Partitions, Posts, Girders and Roofs.
- 6.—It is the purpose of the present work to treat principally of those parts which are subjected to transverse strains.
- 7.—In the construction of a floor, the safety of those who are to trust themselves upon it is the first consideration.

- 8.—Floors are not always made sufficiently strong. Scarcely a year passes without its record of deaths consequent upon the failure of floors upon which people should have assembled with safety. Many floors now existing, and not a few of those annually constructed, are deficient in material, or have an improper arrangement of it.
- 9.—The strength of a floor consists in the strength of its timbers.

The dimensions of the timbers for any given floor may be ascertained, practically, by an examination of other similar floors which have been tried and found sufficiently strong. But if no similar floor is found, how is the problem to be solved?

- by constructing one or more experimental floors, and testing them with proper weights; but this would be attended with great expense, and probably with the loss of more time than could be spared for the purpose.
- 11.—There is a simple method, which is quite as certain and less expensive. The chemist, from a small specimen, makes an analysis sufficient to determine the character of whole mines of ore or quarries of rock. So we, by proper tests of a small piece of any building material, may determine the characteristics of all material of that kind.
- 12.—To obtain, then, the requisite knowledge of the strength of floor timbers, let us adopt a piece of convenient size as the unit of material. Let it be a piece one inch square and one foot long in the clear between the bearings. This we will submit to a transverse force, applied at the middle of its length, sufficient to break it crosswise, and learn from the result the power of resistance it possesses.

Numerous experiments of this nature have been made

upon all the ordinary kinds of timber, stone and iron, and the average results collected in tabular form. (See Table XX.) A few results are here given.

13.—The unit of material, when of

Hemlock, breaks with 450 pounds:
White Pine, " 500 "
Spruce, " 550 "
White Oak, " 650 "
Georgia Pine, " 850 "
Locust, " 1200 "
Cast-Iron " 2100 "

These figures give the average unit of strength for these several kinds of material, when exposed to a transverse strain at the middle of their length.

CHAPTER I.

THE LAW OF RESISTANCE.

ART. 14.—Relation between Size and Strength.—Having ascertained, by careful experiment, the power of resistance in a unit of any given material, the next question is: What is the existing relation between size and strength? Is the increase of one proportionate to that of the other?

In two square beams of equal length, but of different sectional area, the larger one will bear more than the smaller. From this it appears that the resistance is, to a certain degree at least, in proportion to the quantity of material, or to the area of cross-section. There is an element of strength, however, other than this, and one which modifies the proportion very materially.

15.—Strength not always in Proportion to Area of Cross-section.—That the strength of any two pieces of equal length is not always in proportion to the area of cross-section, is shown by attempts to break two given pieces. For example, take two beams of equal length, but of differing area of cross-section; the one being 3 × 8, and the other 5 × 6 inches. The former has 24 and the latter 30 inches of sectional area. If the strength be in proportion to the sectional area, the weights required to break these two pieces will be in the proportion of 24 to 30—their relative areas of cross-section; but they will be found (the pieces being placed upon edge) to be in the proportion of 24 to $22\frac{1}{2}$; the smaller piece being actually stronger than the larger!

16.—Resistance in Proportion to Area of Cross-section.

—Preliminary to seeking the cause of this apparent want of proportion, it will be well to show first that, under certain conditions, the resistance of beams is directly proportional to their area of cross-section.

Let there be twenty pieces of smooth white pine, each one inch square, and one foot long in the clear between the bearings. The resistance of any one of these pieces is limited to 500 pounds. This has been ascertained by experiment as before stated in Art. 13.

Let four of these pieces be placed side by side upon the bearings. The resistance of the four is evidently just four times the resistance of one piece; or $4 \times 500 = 2000$ pounds.

Let four more pieces be placed upon the first four: the strength of the eight amounts to $2 \times 2000 = 4000$ pounds.

Add four more, and the combined resistance of the twelve pieces will be $3 \times 2000 = 6000$ pounds.

The resistance of four tiers of four each, or of sixteen pieces, will be $16 \times 500 = 8000$ pounds.

The total strength of the twenty pieces, piled up five tiers high, will be $20 \times 500 = 10,000$ pounds.

Thus we see that the resistance is exactly in proportion to the amount of material used.*

17.—Units may be Taken of any Given Dimensions.— In this trial we have taken as the unit of material a bar one inch square. We might have taken this unit of any other dimension, as a half, a quarter, or even a tenth of an inch square, and, after finding by trial the strength of one of

^{*} The truth of this proposition depends upon obtaining, in the experiment, pieces of wood so smooth that, in being deflected by the weight, they will move upon each other without friction: a condition not quite possible in practice to obtain. This friction restrains free action, and, as a consequence, the weight required to effect the suprate will be somewhat greater than is stated.

these units, could have as readily known the strength of the whole pile by merely multiplying the number of units by the strength of one of them.

We will now consider the relation between breadth and depth.

- Edge.—One of the first lessons of experience with timber of greater breadth than thickness, is the fact of its possessing greater strength when placed on edge than when laid on the flat. As an example: a beam of white pine, 3×8 inches, and 10 feet long between bearings, will require 9600 pounds to break it when set on edge; while three eighths of this amount, or 3600 pounds, will break it if it be laid upon the flat. Here again, as in Art. 15, we have a fact seemingly at variance with the one but just previously established—namely, that of the resistance being in proportion to the area of cross-section. We will now investigate the apparent anomaly.
- 19.—Strength Directly in Proportion to Breadth.—First, as to the breadth of a beam. If two beams of like size are placed side by side, the two will resist just twice that which one of them alone would. Three beams will resist three times as much as one beam would. So of any number of beams, the resistance will be in proportion directly as the breadth.


This is found by trial to be true, whether the beams are separate or together, solid; for a 6×8 inch beam will bear as much, and only as much, as three beams 2×8 inches set side by side, and, in both cases, on the edge. In other words, when the depths and lengths are equal, a beam of six

inches breadth will bear just three times as much as a beam of two inches breadth, or twice as much as one of three inches breadth.

So this fact appears established, that the resistance of beams is directly in proportion to their breadth.

20.—By Experiment Strength Increases more Rapidly than the Depth.—In regarding the depth of beams, another law of proportion is found. Having two beams of the same breadth and length, but differing in depth, we find the strength greater than in proportion to the depth. If it were in this proportion, a beam nine inches high would bear just three times as much as one three inches high, whereas experiment shows it to bear much more than this.

21.—Comparison of a Solid Beam with a Laminated one.—To test this, let there be two beams of equal length, breadth and depth, one of them being in one solid piece



(Fig. 2), while the other is made up of horizontal layers or veneers, laid together loosely (Fig. 1). Placing weights upon these two beams, it is seen that, although they contain a like quantity of material in cross-section, and are of equal height, the solid beam will sustain much more weight than the laminated one. Let the several parts of the latter beam be connected together by glue, or other cementing material,

and again applying weights, it will be found that it has become nearly, if not quite, as strong as the beam naturally solid.

From these results we infer that the increased strength is due to the union of the fibres at each juncture of the horizontal layers. But why does this result follow? If the simple knitting together of the fibres is the cause, then why, in considering the breadth, is a solid beam no stronger than two beams, each of half the breadth, as has been shown?

and Compression.—An examination of the action of the beams under pressure in Figs. 1 and 2 may explain this. The weights bending the beams make them concave on top. In Fig. 1 the ends of the veneers or layers remain in vertical planes, while, in the other case, the end of the solid beam is inclined, and normal to the curve. It is also seen that the upper surface in Fig. 2 is shorter than the lower one, although the two surfaces were of the same length before bending. This change in length has occurred during the process of bending, and could only happen through a change in length of the fibres constituting the beam.

In the operation of bending, one of two things must of necessity take place: either the fibres must slide upon each other, as in Fig. 1, or else the length of the fibres must be changed, as in Fig. 2; and since in practice it is found that the fibres are so firmly knit as effectually to prevent sliding, we have only to consider the effects of a change in the length of the fibres. The resistance to this change is an element of strength other than that due to quantity of material, and its nature will now be examined.

23.—Power Extending Fibres in Proportion to Depth of Beam.—If a beam be made of four equal pieces, as in Fig. 3, and be held together by an elastic strap firmly



Fig. 3.

attached to the under side of the beam, and by two cross pieces let into the horizontal joint and closely fitted; and if upon this beam a weight be laid at the

middle sufficient to elongate the strap and open the vertical joint at the bottom a given distance—say an eighth of an inch; then, if the weight and the two upper quarters of the beam be removed, and a weight laid on at the middle sufficient to open the joint to the like distance as before, it will be found that this weight is just one half of that before used. In this experiment, the strap may be taken to represent the fibres at the lower edge of the beam.

We here find a relation between the weight and the height of the beam. The greater the height, the greater must be the weight to produce a like effect upon the fibres of the lower edge. Double the height requires double the weight. Three times the height requires three times the weight. Therefore we decide that, in elongating the fibres at the bottom, the weight and the height are directly in proportion.

It must be observed that Fig. 3 and its explanation are not to be taken as a representation of the full effect of a transverse strain upon a beam. The scope of the experiment is limited to the action of the fibres at the lower edge. The other fibres, all contributing more or less to the resistance, are, for the moment, neglected, in order to show this one feature of the strain—namely, the manner in which fibres at any point contribute to the general resistance.

Galileo, of Italy, who, two hundred and fifty years since,

was the first to show the connection of the theory of transverse strains with mathematics, not recognizing in his theory the compressibility of the fibres at the concave side of the beam, supposed that in a rupture by cross strain all the fibres were separated by pulling apart; as might be shown in Fig. 3, in case the rubber were extended up each side to the top, instead of being confined to the lower edge. We are greatly indebted to Galileo for his studies in this direction; but Hooke, Mariotte, and Leibnitz, about 1680, found the theory of Galileo to be defective, and showed that the fibres were elastic; that only those fibres at the convex side of the beam suffer extension; that those at the concave side suffer compression and are shortened; and that, at the line separating the fibres which are extended from those which are compressed, they are neither lengthened nor shortened, but remain at their natural length. This line is denominated the neutral line or surface.

It will here be observed that the *amount* of extension or compression in any fibre is proportional to its distance from the neutral line.

CHAPTER II.

APPLICATION OF THE LEVER PRINCIPLE.

ART. 24.—The Law of the Lever.—The deduction drawn from the experiment named in Art. 23 depends for its truth upon what is known as the law of the lever. This law, in so far as it applies to transverse strains, will now be considered.

25.—Equilibrium—Direction of Pressures.—When equal weights, suspended from the ends of a beam supported upon a fulcrum, as at W in Fig. 4, are in equilibrium, it is found that the point of support is just midway between the two weights, provided that the beam be of equal size and weight throughout its length.

It will be observed that the directions of the strains upon the beam are vertical, those at the ends being down-




Fig. 4.

ward, while that at the middle is upward; also that the strains are evidently equal, the upward pressure at the middle being just equal to the sum of the two weights at the ends; for if unequal, there

would be no equilibrium, but a movement in the direction of the greater power.

We decide, then, that the pressure upon the fulcrum is equal to the sum of the two weights.*

^{*} In ascertaining the pressure at the fulcrum, the weight of the beam itself should be added to the sum of the two weights, but to simplify the question, the beam, or lever, is supposed to be without weight.

26.—Conditions of Pressure in a Loaded Beam.—In Fig. 5 we have a beam supported at each end, and a weight Wlaid upon the middle of its length.

Comparing this with Fig. 4
we see that the strains here
are also vertical but in reversed order, the one at the
middle being downwards,




Fig. 5.

while those at the ends are upwards. In other respects we have here the same conditions as in Fig. 4.

The downward pressure at the middle is equal to the upward pressures or reactions at the ends; and, since the weight is placed midway between the points of support, the reactions at these points are equal, and each is equal to one half the weight at the middle.

27.—The Principle of the Lever.—In Fig. 6 is shown a lever resting upon a fulcrum W, and carrying at its ends the weights R and P.

· m ·

Here, the fulcrum W is not at the middle as in Fig. 4, but at a point which divides the lever into two unequal parts, m and n.

In accordance with the prin- F_{IG} . 6. ciple of the lever, the two parts m and n, when there is an equilibrium, are in proportion to the two weights P and R; or, the shorter arm is to the longer as the lesser weight is to the greater;* or,

m:n::P:R

^{*} For a demonstration of the lever principle see an article, by the author, in the *Mathematical Monthly*, published at Cambridge, U. S., vol. 1, 1858, page 77.

from which we have

$$Rm = Pn$$

$$R = P\frac{n}{m} \tag{1.}$$

and

$$P = R \frac{m}{n} \tag{2.}$$

As an example: suppose the lever to be 12 feet long, and so placed upon the fulcrum as to make the two arms, m and n, 4 and 8 feet respectively. Then, if the shorter arm have suspended from its end a weight, R, of 500 pounds, what weight, P, will be required at the end of the longer arm to produce equilibrium?

Formula (2.) is appropriate to this case. Therefore $P = R\frac{m}{n} = 500 \times \frac{4}{8} = 250$ pounds; equals the weight required on the longer arm.

From Art. 25 it is evident that the sum of the weights R and P is equal to the upward force or reaction at W.

Therefore, we have,

$$W = R + P$$
$$W - R = P$$

and

Substituting this value for P in formula (2.), we have

$$W - R = R \frac{m}{n}$$

$$W = R + R \frac{m}{n}$$

$$W = R \left(1 + \frac{m}{n}\right)$$

$$\frac{W}{1 + \frac{m}{n}} = R \quad \text{and, multiplying by } n,$$

$$\frac{W n}{n + m} = R$$

and, since n + m is equal to the whole length of the beam, or to l, therefore

$$R = W \frac{n}{I} \tag{3.}$$

In a similar manner, it is found that

$$P = W \frac{m}{l} \tag{4.}$$

28.—A Loaded Beam Supported at Each End.—In Fig. 7 a weight W, is carried by a beam resting at its ends

upon two supports. Here we have, with the pressures in reversed order, similar conditions with those shown in Fig. 6. Here, also, it will be observed that the weight W is equal to the sum of the




Fig. 7.

upward resistances R and P (Arts. 25 and 26)—neglecting for the present the weight of the beam itself—and that the upward resistance at R may be found by formula (3.); while that at P is found by formula (4.).

For example: suppose the weight W, Fig. 7, to be 800 pounds; and that it be located five feet from one end of the beam and eight feet from the other end.

Here W = 800, m = 5, n = 8 and l = 13.

To find the pressure at R, we have, by formula (3.),

$$R = W \frac{n}{l} = 800 \times \frac{8}{13} = 492\frac{4}{13}$$
 pounds.

To find the pressure at P, we have, by formula (4.),

$$P = W \frac{m}{l} = 800 \times \frac{5}{13} = 307 \frac{9}{13}$$
 pounds.

To verify the rule, we find that

$$492\frac{4}{13} + 307\frac{9}{13} = 800 \text{ pounds} = W.$$

Either one of these upward pressures, or reactions, being found, the other may be determined by subtracting the first from W.

From the above, we see that the portion of a weight borne by one support is equal to the product of the weight into its distance from the other support, divided by the length between the two supports.

29.—A Bent Lever.—In Fig. 8 let PCG be a rigid bar,





Fig. 8.

shaped to a right angle at C, and free to revolve on C as a centre. Let R and H be two weights attached by cords to the points P and G, the cords passing over the pulleys D and E. Let the weights be so proportioned as to produce an equilibrium.

Here P C G is what is termed a bent lever, and the arms a and b are in proportion to the weights R and H; or,

$$a:b::R:H$$
 and $H=R\frac{b}{a}$

30.—Horizontal Strains Illustrated by the Bent Lever.— To apply the principle of the bent lever let a beam RE (Fig. 9) be laid upon two points of support, R and E, and



F1G. 9.

be loaded at the middle with the weight W. The action of this weight upon the beam is similar in its effect to that taking place in the bent lever of Fig. 8, producing horizontal strains, which compress

the fibres at the top of the beam and extend those at the bottom. (Art. 23).

Let the line PC represent the line of division between the compressed, and the extended fibres. Then PCG may be taken to represent the bent lever of Fig. 8; for the upward pressure or reaction at R, moving the arm of lever PC, which turns on the point C, as a centre, acts upon the point G, through the arm of lever CG, moving the point G horizontally from E, and thus extending the fibres in the line GE.

Now, if H represents this horizontal strain along the bottom of the beam, and R the vertical strain at P—both being due to the action of the weight W; if the arm P C be called b, and C G called a, then, as before,

$$a:b::R:H$$
 from which $H=R\frac{b}{a}$

For an application: let b in a given case equal 10 feet, a equal 6 inches, or 0.5 of a foot, and R equal 1200 pounds; what will be the horizontal strain in the fibres at the lower edge of the beam?

From the above formula,

$$H = R \frac{b}{a} = 1200 \times \frac{10}{0.5} = 1200 \times 20 = 24,000$$

or the horizontal strain equals 24,000 pounds.

31.—Resistance of Fibres in Proportion to the Depth of Beam.—From the proportion in the last article,

$$a:b::R:H$$
 we have $Ha = Rb$ and dividing by ab we have $\frac{H}{b} = \frac{R}{a}$

For any given material, the power of the fibres to resist tension is limited, and, since this power is represented by H,

therefore H is limited. In any given length of beam, b, which is dependent upon the length, is also given; hence $\frac{H}{b}$ becomes a fixed quantity; and since $\frac{H}{b} = \frac{R}{a}$, therefore $\frac{R}{a}$ is a fixed quantity. But R and a may vary individually, provided that the quotient of R divided by a be not changed. So, then, if R be increased, a must also be increased, and in a like proportion; if R be doubled, a must be doubled; if one be trebled, the other must be trebled; or, in whatever proportion one is increased or diminished, the other must be increased or diminished in like proportion. Therefore R and a are in direct proportion.

Take a as equal to one half of the depth of the beam, or $\frac{d}{2}$, and R as equal to one half the weight at the middle of the beam, or $\frac{W}{2}$.

Then, since a is in proportion to R, d is in proportion to W, or the depth of the beam must be in proportion to the weight.

This result is the same as that arrived at in Art. 23; that the power of the fibres at the bottom to resist extension is in proportion to the depth of the beam.

CHAPTER III.

DESTRUCTIVE ENERGY AND RESISTANCE.

ART. 32.—Resistance to Compression—Neutral Line.—We have shown the manner in which the fibres at the convex side of a beam contribute to its strength by their resistance to extension. It may now be observed that the resistance to compression of the fibres at the concave side is but a counterpart of the resistance to extension of the fibres at the convex side.

Whatever resistance may be given out in one way at one side of the beam, a like amount of resistance will be called up in the other way at the other side. The one balances the other, like two weights at the ends of a lever (Figs. 4 and 6). If the powers of resistance to compression and extension be equal, as is the case in some kinds of wood, then one half of the fibres will be compressed while the other half are extended; and, should the beam be of rectangular section, the neutral line will occur at the middle of the height of the beam, and the condition of equilibrium will be as shown in Fig. 4.

If the capability to resist compression exceeds the resistance to extension, as in cast-iron, then the greater portion of the fibres will be employed in resisting tension, and the neutral line will be nearer to the concave side; an equilibrium represented by Fig. 6, in which the shorter arm of the lever may represent the portion of the fibres subjected to compression, and the longer arm those suffering tension, and where R, the heavier weight, may represent the power of any given number of fibres to resist compression, while P, the lesser

weight, represents the power of an equal number of fibres to resist tension.

In Art. 31 the power of the fibres at the convex side of a beam to resist extension was shown to be in proportion to the depth of the beam. This result was obtained by taking the position of the neutral line at the middle of the depth. The like result will be obtained even when the neutral line occurs at a point other than the middle. For, whatever be the proportionate distance of this line from the lower edge, that distance, for the same material, will always bear the same proportion to the depth of the beam.

33.—Elements of Resistance to Rupture.—Having now sufficient data for the purpose, the several elements of strength which have been developed may be brought together, and their sum taken as the total resistance to rupture.

First.—We have the rate of strength, or the weight in pounds required to break a unit of the given material one inch square and one foot long, when supported at each end (Arts. 12 and 13). Let B represent this weight.

Second.—We have the strength in proportion to the area of cross-section, or to the product of the breadth into the depth (Arts. 16 and 17). If b be put to represent the breadth, and d the depth, both in inches, then this element of strength may be represented by $b \times d$ or bd.

Third—and last, we have the strength due to the resistance of the fibres to a change in length, which has been shown to be in proportion to the depth (Arts. 22, 23 and 31), and may therefore be represented by d.

Putting these three elements of strength together, and representing by R the total resistance, we have,

$$R = B \times bd \times d$$
 or $R = Bbd^2$ (5.)*

and this is the total power of resistance to a cross strain.

34.—Destructive Energies.—It is requisite now to consider the destructive energies. It has been shown (Art. 27) that the power of a weight, acting at the end of a lever, is in proportion to the length of the lever. This is seen in Fig. 6, where a small weight acting at the end of the longer arm produces as great an effect as the larger weight upon the shorter arm. This principle may be stated thus: The moment of a weight is equal to the product of the weight into the length of the arm of leverage at which it acts.

If n (Fig. 6) be the arm of leverage, and P the weight acting at its end, then the moment of P is equal to the weight P multiplied by the length of the lever n; or,

Moment = Pn.

Let S represent the weight which it is found on trial is required to break a lever or rod of given material, one inch square, and projecting one foot from a wall into which it is firmly imbedded; the weight being suspended from the free end of the lever. Then, since the moment equals the weight into its arm of leverage, as above stated, which arm in this case equals unity, we have

$$S \times I = Pn$$

^{*}Strictly speaking, the whole power of a beam to resist rupture is due to the resistance of the fibres to compression and extension,—as will be shown in speaking of the resistance to bending—and it is usual to obtain the amount of this power by a more direct method; arriving at the total resistance by one operation, and this based upon a consideration of the resistance offered by each fibre to a change of length, and taking the sum of these resistances; but it is thought that the method here pursued is better adapted to securing the object had in view in writing this work.

or the power of resistance of such a rod equals S, the weight required to break it.

Having this index of strength, S, and knowing (Art. 33) that the resistance to breaking is in proportion to the breadth and the square of the depth, then for levers larger than one inch square, and longer than one foot, when the destructive energy equals the resistance, we have

$$Pn = Sbd^{2} \tag{6.}$$

that is, for the moment, or destructive energy, we have P, the weight in pounds, multiplied by n, the length in feet; and for the resistance, we have S, the index of strength for the sectional area of one inch square, multiplied by the breadth of the lever, and by the square of its depth; the breadth and depth both being in inches.

35.—Rule for Transverse Strength of Beams.—This formula, (6.), gives a rule for the transverse strength of levers. From it we may derive a rule for the transverse strength of beams supported at both ends.

We know, for example, from Arts. 25 and 26, that the strains in a lever are the same as in a beam which is twice the length of, and loaded at the middle with twice the weight supported at the end of the lever. Therefore, when P is equal to the half of IV, the weight at the middle of a beam (Fig. 5), and n is equal to the half of l, the length of the beam, we have

$$Pn = \frac{IV}{2} \times \frac{l}{2} = \frac{III}{4}$$
 and since, (form. 6),
 $Pn = Sbd^2$ by substitution we have
 $\frac{IVI}{4} = Sbd^2$ (7.) or
 $IVI = 4Sbd^4$ (8.)

in which 117 equals the moment or destructive energy of a weight at the middle of a beam, and 45bd' equals the resist-

ance of the beam. But this resistance was found (Art. 33) to be equal to Bbd^2 ; therefore,

$$4Sbd^2 = Bbd^2$$
hence
$$Wl = Bbd^2 \qquad (9.)$$

This is the required rule for the strength of beams supported at each end. In it W equals the pounds laid on at the middle of the beam, l the length of the beam in feet, b and d the breadth and depth respectively of the beam in inches, and B the weight in pounds at the middle required to break a unit of material (Art. 12) of like kind with that in the beam, when strained in a similar manner.

It may be observed here that from

$$Bbd^2 = 4Sbd^2$$
 as above, we have $B = 4S$

or, the weight at the middle required to break a unit of material, when supported at each end, is equal to four times the weight required to break it when fixed at one end only, and the weight suspended from the other.*

To compare the two, let M be put for the S of Prof. Moseley. Then his expression (Art. 414, p. 528) for rectangular beams,

$$P = \frac{1}{6} S \frac{bc^2}{a}$$
 becomes
$$P = M \frac{bc^2}{6a}$$
 in which

P is the weight at one end of a beam, which is fixed at the other end, and c is the depth and a the length, both in inches. If for c we put d and for a we put n, representing feet instead of inches, so that a = 12 n, then

^{*} Professor Moseley, in his "Engineering and Architecture," puts S to represent the index of strength, but his definition of this index shows it to be not the same as that for which S is put in this work. While, with us, S represents the resistance to rupture of a unit of material (one inch square and one foot long), fixed at one end and loaded at the other; in his work (Art. 408, p. 521, Mahan's Moseley, New York, 1856), S is placed to represent the "resistance in pounds opposed to the rupture of each square inch at the surface exposed to a tensile strain."

36.—Formulas Derived from this Rule.—From the general formula, (9.), of Art. 35, any one of the five quantities named may be found, the other four being given.

$$P = M \frac{bd^2}{72n}$$
 and
$$72 Pn = Mbd^2$$

Now we have found (form. 6), that

$$Pn = Sbd^2$$

Multiplying this by 72 gives

$$72 Pn = 72 Sbd^2$$

Comparing this value of 72 Pn with that from Prof. Moseley, as above, we have

 $Mbd^2 = 72 Sbd^2$

from which

$$M = 72S$$

or M, the S of Prof. Moseley, is equal to 72 times the S of this work.

We also find that Prof. Rankine (Applied Mechanics, Arts. 294 and 296) similarly designates the index of strength; or, as he and Prof. M. both term it, "the modulus of rupture." Prof. R. defines it the same as Prof. M.; except, that instead of limiting it to the tensile strain, he applies it equally to that element, tension or compression, which first overcomes the strength of the beam.

Prof. Rankine further defines it (p. 634) to be "eighteen times the load which is required to break a bar of one inch square, supported at two points one foot apart, and loaded in the middle between the points of support." Now the bar here described is identical with the unit of material adopted in this work (Arts. 12 and 13); to designate the strength of which we have used the symbol B. To compare the two, we have, as above found,

and also, (Art. 35) M = 72SB = 4S

Multiplying the latter equation by 18, we have

$$18B = 72S or$$

$$18B = M or$$

as defined by Prof. Rankine, M, the S of Prof. Moseley, is equal to 18 times the value of B, the index of strength as used in this work. Hence the values of S, as given for various materials by Profs. Moseley and Rankine, are 18 times the values of B in this work for the same materials. Owing, however, to a considerable variation in materials of the same name, this relation will be found only approximate.

For example,

$$B = \frac{Wl}{bd^2} \tag{10.}$$

$$b = \frac{Wl}{Bd^3} \tag{11.}$$

$$d = \sqrt{\frac{Wl}{Bb}} \tag{12.}$$

$$W = \frac{Bbd^2}{I} \tag{13.}$$

$$l = \frac{Bbd^2}{W} \tag{14.}$$

In these formulas B is the *breaking* weight in pounds applied at the *middle*. The value of B (Arts. 33 and 35) is given for the *length* in *feet*, and the *breadth* and *depth* in *inches*.

QUESTIONS FOR PRACTICE.

- 37.—What kind of strain is a floor beam subjected to?
- 38.—In a beam subjected to a transverse strain, how does the breadth contribute to its strength?
 - 39.—How does the depth contribute to its strength?
- 40.—What are the elements of resistance, and what is the expression for this resistance?
- 41.—When a beam supported at each end carries a load at its middle, what is the amount of pressure sustained by the two points of support, taken together?

- 42.—What portion of the load is upheld by each support?
- 43.—If the load be not at the middle, what is the sum of the pressures upon the two points of support?
- 44.—In the latter case, what proportions do the parts borne at the two points of support bear to each other?
- 45.—What expression represents that borne by the *near* support.
- 46.—What expression represents the pressure upon the remote support?
- 47.—If a beam, 12 feet long between bearings, carries a load of 15,000 pounds, at a point 4 feet from one bearing, what portion of this load is borne by the near support?

And what is the pressure upon the remote support?

- 48.—When a beam is subjected to transverse strain at its middle, what constitutes the destructive energy tending to rupture?
- 49.—When the destructive energy and the resistance are in equilibrium, what expression represents the conditions of the case?
- 50.—What is the breaking load of a Georgia pine beam, 15 feet long between the bearings; the breadth being 4 inches, the depth 10, and the load at the middle?
- 51.—How many times as strong as when laid on the flat is a beam when set on edge?

CHAPTER IV

THE EFFECT OF WEIGHT AS REGARDS ITS POSITION.

ART. 52.—Relation between Destructive Energy and Resistance.—In a beam, laid upon two bearings, and sustaining a load at the middle, we have discovered certain relations between the load and the beam.

The load has a tendency to destroy the beam, while the beam has certain elements of resistance to this destructive power.

The destructive energy exerted by the load is equal to the product of half the load multiplied by half the length of the beam. The power of resistance of the beam is equal to the product of the area of cross-section of the beam, multiplied by its depth and by the strength of the unit of material. At the moment of rupture, the destructive energy and the power of resistance are equal; or, as modified in Art. 35,

Wl = Bbdd or, as in formula (9.), $Wl = Bbd^*$

53.—Dimensions and Weights to be of Like Denominations with Those of the Unit Adopted.—In applying the above formula it is to be observed, that the length, breadth and depth, in any given case, are to be taken in like denominations with those of the unit of material adopted (Art. 33). For example: if the unit of material be that of this work, then, in the application of the formula, the breadth and depth are to be taken in inches, and the length between bearings in feet.

54 EFFECT OF WEIGHT AS REGARDS ITS POSITION. CHAP. IV.

It is also requisite that the weight be taken in like denomination with that by which the resistance of the unit of material was ascertained. If the one is in ounces, the other is also to be in ounces; if one is in pounds, the other must be in pounds; or, if in tons, then in tons.

The strength of the unit of material adopted for this work is given in pounds; therefore, in applying the rule, the weight given, or to be found, must necessarily be in pounds.

54.—Position of the Weight upon the Beam.—The location of the weight upon the beam now requires consideration.

Upon our unit of material, which is supported at each end, the load is understood to have been located at the middle of the length; so, in using formula (9.), the weight given, or sought, must be located at the middle of the length of the given beam.

55.—Formula Modified to Apply to a Lever. — By proper modifications this formula may also be applied to the case of a weight suspended from one end of a lever or projecting beam. To show the application, we proceed as follows:

In Fig. 10 one half of the load W is borne on each one of the supports A and B.




Fig. 10.

In Fig. 11 we have a beam of the same length, and subjected to the same forces, but in reversed order (Art. 26).

Fig. 11.

While Fig. 10 represents a beam supported at both ends and loaded in the middle, one half of Fig. 11 may be taken to represent a lever projecting from a wall and loaded at the free end.

In these two cases the moment or destructive energy tending to break the beam is the same in each, and yet it is produced in Fig. 11 with only one half the weight, acting at the end of a lever only one half the length of the beam. We have, therefore,

$$\frac{1}{2}W \times \frac{1}{2}l = \frac{1}{4}Wl$$

or, in a lever, it requires but a quarter of the weight to produce a given destructive energy, that is required in a beam of equal length, laid upon two supports—that is to say, if two beams of like material, and of the same cross-section, be subjected to transverse strains, in like positions as to breadth and depth, one beam being supported at both ends and loaded in the middle, and the other one firmly fixed in a wall at one end and loaded at the other; and if the distance between the wall and the weight in this latter beam be equal to the distance between the bearings in the former; then but one quarter of the weight requisite to break the beam supported at both ends will be required to break the projecting one.

If the former requires 10,000 pounds to break it, then the latter will be broken by 2500 pounds.

The proportion between the weights is as 4 to 1. But suppose the weights upon the two beams are equal. In this case the lever will have to be made stronger, and its sectional area enlarged sufficiently to carry 4 times the weight. Hence we have, for beams fixed at one end and loaded at the other,

$$4Wl = Bbd^{s}$$

in which W is the weight suspended from the end of the lever, and l is the length of the lever; or, to correspond with

56 EFFECT OF WEIGHT AS REGARDS ITS POSITION. CHAP. IV.

the symbols used in Art. 34, where P equals the weight and n equals the length of the lever, we have

$$4Pn = Bbd^{s} \tag{15.}$$

56.—Effect of a Load at Any Point in a Beam.—The next case for consideration is that of the effect of a weight located at any point in the length of a beam, the beam being supported at both ends.

In Arts. 27 and 28 it was shown, in cases of this kind, that R, the portion of the whole weight borne at the nearer end, is (form. 3.) equal to $W\frac{n}{l}$; and that P, the portion resting upon the more remote end, is (form. 4.) equal to $W\frac{m}{l}$; where W equals the weight on the beam, R the portion of the weight carried to the near support, P the portion carried to the remote support, P the length of the beam, P the distance from the weight to the near support, and P the distance to the remote support.

As shown in Art. 34, the effective power or moment of a weight is equal to the product of the weight into the arm of the lever, at the end of which it acts. In Fig. 6 the weight R may be taken to represent the reaction of the point of support R in Fig. 7; and the destructive effect at the point of the fulcrum W in Fig. 6, taken to be the same as that at the location of the weight W in Fig. 7, as the strains in the two pieces are equal; and hence, the moment of R, Fig. 6, is equal to the product of R into its arm of lever m, or equal to Rm.

Taking the value of R in formula (3.), and multiplying it by its arm of lever, m, we have

$$Rm = W \frac{n}{l} m = W \frac{mn}{l}$$

Again, taking the value of P in formula (4.), and multiplying it by its arm of lever, n, we have

$$Pn = W \frac{m}{l} n = W \frac{mn}{l}$$

The two results agree, as they should.

57.—Rule for a Beam Loaded at Any Point.—These formulas may be tested by taking the two extreme conditions, the load at the middle and at the end.

First: When the load is at the middle

$$m=n=\frac{1}{2}l$$

the destructive energy, as above, will be

$$D = W \frac{mn}{l} = W \frac{\frac{1}{2}l \times \frac{1}{2}l}{l} = W \frac{\frac{1}{4}l^{2}}{l} = W \frac{1}{4}l = \frac{1}{4}Wl$$

the same value as obtained in Art. 35.

Second: When the weight is moved towards the nearer end, *m* becomes gradually shorter, and when the weight in its movement reaches the point of support, *m* becomes zero, and *n* equals *l*. The destructive energy will then be

$$D = W \frac{mn}{l} = W \frac{o \times l}{l} = W o = o$$

as it ought to be, for the weight no longer exerts any cross strain upon the beam.

The destructive energy therefore of a weight, W, when laid at any point upon a beam, is

$$D = W \frac{mn}{I}$$

When laid at the middle, it is as above shown,

$$W\frac{mn}{l} = \frac{1}{4}Wl$$

58 EFFECT OF WEIGHT AS REGARDS ITS POSITION. CHAP. IV.

In formula (7.) we have

$$\frac{1}{2}Wl = Sbd^2$$

therefore, by substitution,

$$W\frac{mn}{l} = Sbd^*$$

Multiplying by 4, we have

$$4W\frac{mn}{l} = 4Sbd^2$$

and since, by Art. 35,

$$4S = B$$

we have

$$4W\frac{mn}{l} = Bbd^2 \tag{16.}$$

a rule for the resistance of a beam when the weight is located at any point in its length.

58.—Effect, of an Equally Distributed Load.—Let the effect of an equally distributed weight now be considered.

Formula (16.) gives the effect of a weight at any point of a beam—that is, the effect of the weight at the point where it is located; but what effect at the middle of the beam is produced by a weight out of the middle?

When a weight is hung at the end of a projecting lever, its effective energy, at any given point of the length of the lever, is equal to the product of the weight multiplied into the distance of that point from the weight (Art. 34).

In Arts. 27 and 28 we have the effect of the weight W upon its points of support. For the remote end, in Fig. 7, this is $P = W \frac{m}{l}$. This is the reaction, or power acting upward

at the point of support P. We have, Arts. 56 and 57, the moment or destructive energy due to this reaction equal to

$$Pn = W \frac{m}{l} n = W \frac{mn}{l}$$

but if, instead of the whole distance n, we take only a part of it, or say to the middle of the beam, or $\frac{1}{2}l$, we have, instead of Pn,

$$P \times \frac{1}{2}l = W \frac{m}{l} \times \frac{1}{2}l = \frac{1}{2}W \frac{ml}{l} = \frac{1}{2}Wm$$

or, we have, for M, the effect at the middle due to a weight placed at any point,

$$M = \frac{1}{2}Wm$$

This result may be tested as in Art. 57; for let $m = \frac{1}{2}l$, then $M = \frac{1}{2}Wm$ becomes

$$M = \frac{1}{2}W \times \frac{1}{2}l = \frac{1}{2}Wl$$

which is a quarter of the weight at the middle into the whole length, as shown in Art. 55.

Again, taking the other extreme; when m becomes zero, then $M = \frac{1}{2}Wm$ becomes

$$M = \frac{1}{2}W \times 0 = 0$$

which is evidently correct, for when the weight is moved from over the clear bearing on to the point of support it cases to exert any cross strain whatever upon any point of the beam.

From the above, we conclude that the effect produced at the middle of a beam, by a weight located at any point of its length, is equal to the product of half the weight into its distance from its nearest point of support.

This result would be true of a second weight, and a third, and of any number of weights. If the weights R, P, Q, etc. (Fig. 12), be located on a beam, at distances from their near-

60 EFFECT OF WEIGHT AS REGARDS ITS POSITION. CHAP. IV. est point of support equal to m, r, s, etc., their joint effect at the middle of the beam will be


$$\frac{1}{2}Rm + \frac{1}{2}Pr + \frac{1}{2}Qs + \text{etc.}$$

 $\frac{1}{2}(Rm + Pr + Qs + \text{etc.})$

OL

59.—Effect at Middle from an Equally Distributed Lond.—We may now ascertain the effect produced at the middle of a beam by an equally distributed load.

Let a beam, AB (Fig. 12), of homologous material, and of equal sectional area throughout its length, be divided into



The weight of any one of these parts will equal that of any other part, and therefore we have in this beam a case of an equally distributed load. Now, suppose the weight of

each of these parts to be concentrated at its centre of gravity, and represented by a ball, as R, P, or Q, suspended from that centre of gravity. Let t equal the length of each of the parts into which the beam is divided, then $m = \frac{1}{2}t$, $r = \frac{3}{2}t$ and $s = \frac{5}{2}t$, and, since $M = \frac{1}{2}Wm$, we have for the effect of the weight R, at the middle of the beam, $M = \frac{1}{2}R\frac{1}{2}t$; for the effect of P, $M = \frac{1}{2}P\frac{3}{2}t$; and for the effect of Q, $M = \frac{1}{2}Q\frac{5}{2}t$; etc., for all the weights on one half of the beam.

If these results be doubled (for the effects of the weights on the other half would equal these), we shall have the total effect at the middle of the beam of all the weights. When

as in this case, the beam is divided into six parts, we have for the total effect at the middle,

$$M = \frac{1}{2} tR + \frac{3}{2} tP + \frac{5}{2} tQ$$

Now if we put the symbol U to represent a uniformly distributed load, we have

$$R = P = Q = \frac{U}{6}$$
 therefore
$$M = \frac{I}{2} t \frac{U}{6} + \frac{3}{2} t \frac{U}{6} + \frac{5}{2} t \frac{U}{6}$$
$$M = \frac{Ut}{6} \left(\frac{I}{2} + \frac{3}{2} + \frac{5}{2} \right) = \frac{Ut}{6} \times \frac{9}{2} = \frac{3}{4} Ut$$

In this case t equals $\frac{l}{6}$, therefore

$$M = \frac{3}{4} U \frac{l}{6} = \frac{1}{8} U l$$

in which U equals the whole weight uniformly distributed over the beam.

We have seen (Art. 35) that $\frac{1}{4}Wl$ is the destructive energy of a weight concentrated at the centre of the beam. We now see, as above, that this same effect is produced by $\frac{1}{8}Ul$. We therefore have

$$\frac{1}{8}Ul = \frac{1}{4}Wl$$
 or, multiplying by 4, $\frac{1}{4}U = W$

or, when the effects of the two loads upon a beam are equal, one half of U, the distributed load, will equal the load W, concentrated at the middle.

60.—Example of Effect of an Equally Distributed Load.—Let R, P, Q, etc., each equal 20 pounds; or the whole load U equal $6 \times 20 = 120$ pounds. Let the whole length, 12 feet, be divided into six equal parts, and the equal loads be suspended from the centre of each of these parts. Then from the nearer point of support, A, the distance m to R is one foot; the distance r to P is three feet; and the distance s to

62 EFFECT OF WEIGHT AS REGARDS ITS POSITION. CHAP. IV.

Q is five feet; and, since R, P, and Q are each equal to zo, and (Art. 58)

$$M = \frac{1}{3}Wm$$
 therefore
 $M = \frac{1}{2}Rm + \frac{1}{2}Pr + \frac{1}{2}Qs$
 $M = \frac{1}{2} \times 20 (m+r+s)$
 $M = 10 (1+3+5) = 10 \times 9 = 90$

The like effect, 90 pounds, is had from the three weights upon the other half of the beam. Adding these, we have 180 pounds. This is the destructive energy exerted at the middle of the beam by the six weights, or by U, the 120 pounds equally distributed along the beam. As a test of this, let it now be shown what weight concentrated at the middle of the beam would produce the like effect. In Art. 35 we have for the destructive energy, $D = \frac{1}{4}Wl$, from which $W = \frac{D}{\frac{1}{4}l}$, and since, as above, D = 180 and l = 12, we have $W = \frac{180}{3} = 60$ pounds. This is the weight concentrated at the middle. Above, we had U, the equally distributed weight, equal to 120 pounds, or twice 60. Therefore 2W = U. Thus, as before, it is seen that an equally distributed weight produces an effect at the middle equal to that produced by one half the weight if concentrated at the middle.

61.—Result also Obtained by the Lever Principle.—This result may also be obtained by an application of the lever




Fig. 13.

Q one foot; therefore,

principle. In Fig. 13 a double lever is loaded with weights, producing strains similar to those in a beam such as Fig. 12. Here the arm of lever at which R acts is five feet, that of P three feet, and

$$R \times 5 = 20 \times 5 = 100$$

 $P \times 3 = 20 \times 3 = 60$
 $Q \times I = 20 \times I = 20$
180 pounds.

This is the whole energy, because the weights on the other side of the fulcrum do not add to the strain at W; they only balance the weights R, P, and Q.

The full effect, therefore, at the middle of the beam is 180 pounds, as before shown, and this effect is produced by $3 \times 20 = 60$ pounds equally distributed.

Now, what concentrated weight at the end of the lever would produce an equal effect?

Since the weight P, at the end of a lever, multiplied by n, the length of the lever, is the moment or destructive energy of the weight, therefore

$$Pn = 180$$
 the moment as above, or
$$P = \frac{180}{n} = \frac{180}{6} = 30.$$

and this is one half of 60, the distributed weight which produced a like effect.

Hence we find that a given load, if concentrated at the middle of a beam, will have a destructive energy there equal to that of twice said load equally distributed over the length of the beam; or, in other words, an equally distributed load will need to be double the weight of a concentrated load to produce like effects upon any given beam.

In formula (9.) W represents the concentrated weight at the middle. If for W we substitute its equivalent $\frac{1}{2}U$, we have

$$\frac{1}{2}Ul = Bbd^2 \tag{17.}$$

QUESTIONS FOR PRACTICE.


- **62.**—A white pine beam, 6×9 inches, supported at each end, and set upon edge, is 12 feet long. What weight laid at 4 feet from one end would break it?
- 63.—What weight equally distributed over the length of the above beam would break it?
- 64.—What weight concentrated at the middle of the length of the same beam would break it?
- 65.—What weight would break this beam if suspended from one end of it, the other end being fixed in a wall?

CHAPTER V.

COMPARISON OF CONDITIONS—SAFE LOAD.

ART. 66.—Relation between Lengths, Weights and Effects.—In the consideration of the effect of weights upon beams, we have deduced certain formulas applicable under various conditions. These rules will now be presented in such manner as to show by comparison: first, what relation the lengths and weights bear to each other when the effects are equal; and, second, the resulting effects when the lengths and weights are equal.

67.—Equal Effects.—Take the four Figs., 14, 15, 16 and 17.



The lengths of the beams and the amounts of the weights with which they are loaded, are such as to produce equal

effects. For example, the dimensions are such that in all of the figures, l=2n and $s=\frac{n}{8}=\frac{l}{16}$; and the weights are so proportioned that W=2 P=4 R. By comparison, we find that in Fig. 14 the destructive energy is

$$Pn = \frac{1}{2}W \times \frac{1}{2}l = \frac{1}{4}Wl$$

In Fig. 15 the destructive energy is equal to the sum of the products of the several weights R, into their respective distances from the point of support; or,

$$Rs + R 3 s + R 5 s + R 7 s =$$

 $Rs (1 + 3 + 5 + 7) = 16 Rs = 16 \times \frac{1}{4} W \times \frac{1}{16} l = \frac{1}{4} W l$

In Fig. 16 the destructive energy is

$$\frac{1}{2}W \times \frac{1}{2}l = \frac{1}{2}Wl$$

In Fig. 17 the destructive energy equals the sum of the products of the several weights R, into one half their respective distances from the nearest point of support (Art. 58),

or,
$$2(\frac{1}{2}Rs + \frac{1}{2}R 3 s + \frac{1}{2}R 5 s + \frac{1}{2}R 7 s) =$$

$$2[\frac{1}{2}Rs (1 + 3 + 5 + 7)] =$$

$$2(\frac{1}{2}Rs 16) = 16Rs = 16 \times \frac{1}{2}W \times \frac{1}{16}l = \frac{1}{2}Wl$$

When the load is at any point upon the beam, the destructive energy is $W \frac{mn}{I}$.

This case is a modification of Fig. 16, for, when

$$m=n=\frac{1}{2}l$$
 we have,
$$W\frac{\frac{1}{2}l\times\frac{1}{2}l}{l}=W\frac{\frac{1}{4}l^2}{l}=\frac{1}{4}Wl$$


68.—Comparison of Lengths and Weights Producing Equal Effects.—We now see that, in order to produce equal effects, we must have the length and weight in Fig. 16 twice

those in Fig. 14; and the length and weights of Fig. 17 twice those of Fig. 15.

Again, we see that, while the lengths of Figs. 14 and 15 are the same, the weights of the latter are equal in amount to twice that of the former; and that the same proportions exist in Figs. 16 and 17.

69.—The Effects from Equal Weights and Lengths.—In regard to the second relation, as expressed in Art. 66.

We have, in Figs. 18, 19, 20, and 21, examples showing the



difference of effect when the load upon each beam is equal to the load upon either of the other beams, and the lengths of the beams are equal.

The destructive energy is

in Fig. 18,
$$D = Pn$$

" 19, $D = \frac{1}{2}Un$

" 20, $D = \frac{1}{2}W \times \frac{1}{2}l = \frac{1}{4}Wl$

" 21, $D = \frac{1}{2} \times \frac{1}{2}U \times \frac{1}{2}l = \frac{1}{3}Ul$

70.—Rules for Cases in which the Weights and Lengths are Equal.—Putting these equal to the resistance for levers, we have (Art. 35) for the case shown

in Fig. 18,
$$Pn = Sbd^{2}$$

" i9, $\frac{1}{2}Un = Sbd^{2}$

" 20, $\frac{1}{4}Wl = Sbd^{2}$

21, $\frac{1}{8}Ul = Sbd^{2}$

and, since (Art. 35) 4S = B, $S = \frac{1}{4}B$. If in the above we substitute this value for S, we shall have the following rules:

For case 1,
$$4Pn = Bbd^2$$
 (15.)
" " 2, $2Un = Bbd^2$ (18.)
" " 3, $Wl = Bbd^2$ (9.)
" " 4, $\frac{1}{2}Ul = Bbd^2$ (17.)
and in case 5, $4W\frac{mn}{l} = Bbd^2$ (16.)

this last being that of a load located at any point in the length of a beam (Art. 57).

71.—Breaking and Safe Loads.—These rules show the relation of the load to the resistance. Before showing their applications, the proportion which exists between the breaking load and what is called the safe load will be considered.

72.—The above Rules Useful Only in Experiments.—The rules thus far shown have all been based upon the condition of equilibrium between the destructive power of the load and the resistance of the material; or, in other words, an equilibrium at the point of rupture. Hence they are chiefly useful in testing materials to their breaking point.

73.—Value of a, the Symbol of Safety. — To make the rules useful to the architect, it is requisite to know what portion of the breaking load should be trusted upon a beam. It is evident that the permanent load should not be so great as to injure the fibres of the beam.

The proportion between the safe and the breaking weights differs in different materials. The breaking load on a unit of material being represented by B, as before, let T represent the safe load, and a the proportion between the two; or, $T:B:: I: a = \frac{B}{T}$ then $T = \frac{B}{a}$. The values of a, for several kinds of building materials, have been found and retorded in Table XX., an examination of which will show that a, for many kinds of materials, is nearly equal to 3, a number which is in general use.*

74.—Value of a, the Symbol of Safety.—In the rules a may be taken as high as we please above the value given for a in the table; but never lower than the value there given. If a be taken at 4, then, as above, $T = \frac{B}{a} = \frac{1}{4}B$ equals the safe power of the unit of material, and we have $Wl = \frac{1}{4}Bbd^2$; or, $4Wl = Bbd^2$, as the proper rule for a beam supported at each end and loaded at the centre. In order, however, to

^{*} This is the value as fixed by taking the average of the results of the tests of several specimens of the same kind of material, or material of the same name.

Owing to the large range in the results in any one material, it is not safe, in a general use of this symbol, to take it at the average given in the table. It should for ordinary use be taken higher.

When the kind of material in any special and important work is known, and tests can be made of several fair specimens of it, and from the results computations made of the values of a, then an average of these would be safe to use. For the ordinary woods in general rules, it is prudent to take the value of a at not less than 4.

make the rules general, we shall not adopt any definite number, as 4, but use the symbol a, the value of which is to be taken from the table in accordance with the kind of material employed, increasing its value at discretion. (See note, Art. 73.)

75.—Rules for Safe Loads.—The rules, with this factor a introduced, will then be as follows:

Rule 1,
$$4Pan = Bbd^{2}$$
 (19.)
" 2, $2Uan = Bbd^{2}$ (20.)
" 3, $Wal = Bbd^{2}$ (21.)
" 4, $\frac{1}{2}Ual = Bbd^{2}$ (22.)
" 5, $4Wa\frac{mn}{I} = Bbd^{2}$ (23.)

76.—Applications of the Rules.—In this form the rules are ready for use—applying them as below.

Rule I is applicable to all cases where a load is suspended from the end of a lever (Fig. 18), said lever being fixed at the other end in a horizontal position.

Kule 2 applies to cases where a load is equally distributed upon a lever fixed at one end (Fig. 19).

Kule 3 is applicable to a load concentrated at the middle of a beam supported at both ends (Fig. 20).

Kule 4 is applicable to equally distributed loads upon learns supported at both ends (Fig. 21).

ipon a beam supported at both ends (Fig. 7).

77. Example of Load at End of Lever.—To show the matteral working of these rules, take, first, an example many under rule 1, formula (19.),

$$4Pan = Bbd^{2}$$

Let it be required to find the requisite breadth and depth of a piece of Georgia pine timber, fixed at one end in a wall, and sustaining safely, at five feet from the wall, a weight of 1200 pounds; the ratio between the safe and breaking weights being taken as 1 to 4, and the value of B for Georgia pine being 850 (Art. 13).

78.—Arithmetical Exemplification of the Rule.—The first thing, in applying a rule, is to distinguish between the known and the unknown factors of an equation, by so transposing them that those which are known shall stand upon one side, and the unknown upon the other side of the equation. In rule 1, formula (19.), as above, the known factors are 4, P, a, n and B; therefore we transpose, so that

$$\frac{4Pan}{B} = bd^*$$

Substituting the known quantities for the symbols of the first member, we have

$$\frac{4 \times 1200 \times 4 \times 5}{850} = bd^{2}$$

79.—Caution in Regard to a, the symbol of Safety.—The working of this problem is interrupted to remark that students are liable to err in estimating the value of a, making it a fraction instead of a whole number. Thus, if the proportion between the safe and the breaking weights be as I to 4, they, starting with the idea that the safe weight is to be one fourth of the breaking weight, make a equal to $\frac{1}{2}$, instead of 4. This is a serious error, as the result would be a destructive energy of only one sixteenth (for $\frac{1}{2}:4::1:16$) of the true amount, and consequently the resultant resistance of the timber would be but one sixteenth of what it should

be, and in practice it would be found that the beam would break down with only one fourth of the amount considered the safe weight.

To farther explain the value of a, let W equal the breaking weight, and T the safe weight; the proportion being as 4 to 1. Then $T = \frac{1}{4}W$, or 4T = W. Now, in formula (9.) $(Wl = Bbd^2)$, in order to preserve equality, it is requisite, in removing the symbol W denoting the breaking weight, that we substitute its equal, or 4T. So when, in the new formula for safe weight, W is understood to represent not the breaking but the safe weight, 4T becomes 4W, and we have $4Wl = Bbd^2$; therefore the symbol a is to be not a fraction but a whole number.

Returning from this digression to the expression at the end of Art. 78, and reducing it, we have

$$bd^2 = \frac{96000}{850} = 112.94$$

Here we have the value of the breadth multiplied by the square of the depth, but neither the one nor the other is as yet determined.

80.—Various Methods of Solving a Problem.—There are at least three ways of procedure by which to determine the value of each of these factors. The breadth and depth may be required to be equal; the breadth may be required to bear a certain proportion to the depth; or, one of the factors may be fixed arbitrarily.

First. If the timber is to be square, then b will equal d,

$$bd^{2} = d^{2}$$
, and $d = \sqrt[8]{112.94} = 4.83$

that is, the dimensions required are 4.83, or, say 5 inches square.

Second. Let the breadth be to the depth in the proportion of 6 to 10, then

$$b:d::6:10$$
 or $10b = 6d$ or $b = 0.6d$ Then $112.94 = bd^2 = 0.6d \times d^2 = 0.6d^2$ $\frac{112.94}{0.6} = d^3 = 188.23 = \overline{5.73}^3$ that is $d = 5.73$, and $b = 5.73 \times 0.6 = 3.44$

The timber should be therefore 3.44 inches broad, and 5.73 inches deep; or, $3\frac{1}{2} \times 5\frac{3}{4}$ inches.

Third. The breadth or depth may be determined arbitrarily, or be controlled by circumstances. Let the breadth be fixed, say at 3 inches, then

$$112.94 = bd^{2} = 3d^{2}$$

$$\frac{112.94}{3} = d^{2} = 37.65$$

$$d = 6.14$$

The dimensions should be 3×6.14 , or, say, $3 \times 6\frac{1}{4}$ inches. Again, let the depth be fixed, say at 6 inches, then

$$112.94 = bd^2 = b \times 6^2$$

$$\frac{112.94}{36} = b = 3.14$$

thus giving as the dimensions of the beam 3.14×6 , or, say $3\frac{1}{4} \times 6$ inches.

We have now these four answers to the question of Art. 77, namely:

If the beam be square, the side of the square must be 5 inches.

If the breadth and depth be in the proportion of 6 to 10, the breadth must be 3½ and the depth 5½ inches.

If the breadth be fixed at 3 inches, then the depth must be 61 inches.

If the depth be fixed at 6 inches, then the breadth must be 3½ inches.

81.—Example of Uniformly Distributed Load on Lever.

—Take an example coming under rule 2, formula (20.),

$$2 Uan = Bbd^{2}$$

Let the conditions be similar to those given in Art. 77, except that the weight is to be equally distributed, instead of being concentrated at the end. What are the required dimensions of breadth and depth?

The formula transposed becomes,

$$\frac{2Uan}{B} = bd^2$$

As the known factors are all the same as in the last example, except the numerical co-efficient, which here is only one half of its former value, it follows that bd' in this case must be equal to one half of bd' in the previous case; or,

$$\frac{112.94}{2} = 56.47 = bd^2$$

Now to apply this result:

First. If the timber be square,

$$56.47 = d^3 = \overline{3.84}^3$$

Second. If the breadth and depth are to be as 6 to 10,

$$56.47 = 0.6 d^{3}$$

$$\frac{56.47}{0.6} = d^{3} = 94.12 = \frac{4.55}{4.55}^{3}$$

$$b = 4.55 \times 0.6 = 2.73$$

and

Third. If the breadth be fixed at 2 inches, then

$$56.47 = bd^3 = 2d^3$$

$$\frac{56.47}{2} = d^3 = 28.24$$

$$d = 5.31$$

Fourth. If the depth be fixed at 5 inches, then

$$56.47 = bd^2 = b \times 5^2$$

$$b = \frac{56.47}{25} = 2.26$$

The four answers are, therefore, $3\frac{7}{8}$ square— $2\frac{9}{4} \times 4\frac{5}{8}$ — $2 \times 5\frac{7}{8}$ and $2\frac{1}{4} \times 5$; and the beam may be made of the dimensions named in either of these four cases and be equally strong.

- 82.—Load Concentrated at Middle of Beam.—In an example under rule 3, the value of bd in the formula Wal = Bbd, would be just one quarter of that required by rule 1.
- 83.—Load Uniformly Distributed on Beam Supported at Both Ends.—In cases under rule 4, the values of bd^2 would be only one eighth of those under rule 1; and, in general, the five rules given are so related that when the result of computations under any one of them has been obtained, the result in any other one may be found by proportion, in comparing the two rules applicable.

QUESTIONS FOR PRACTICE.

- 84.—What breadth and depth are required for a white pine beam, of sufficient strength to carry safely 3000 pounds equally distributed over its length, the beam being 12 feet long and supported at each end? The breadth is to be one half of the depth, and the factor of safety a equals 4.
 - 85.—What would be the size if square?
- 86.—What would be the depth if the breadth be fixed at 3 inches?
- 87.—What would be the breadth if the depth were fixed at 6 inches?

CHAPTER VI.

APPLICATION OF RULES—FLOORS.

ART. 88.—Application of Rules to Construction of Pieers.—Having completed the investigation of the strength of beams to resist rupture so far as to obtain formulas or rules applicable to the five principal cases of strain, we will now show the application of these rules to the solution of such problems as occur in the construction of floors. As these rules, however, are founded simply upon the resistance to rupture, the size of a beam determined by them will be found to be much less than by rules hereafter given; and the beam, although perfectly safe, will yet be found so small as to be decidedly objectionable on account of its excessive deflection. Owing to this, floor beams in all cases should be computed by the rules founded upon the resistance to flexure, as in Chapter XVII.

89.—Proper Rule for Floors.—Floor beams are usually subjected to equally distributed loads. For this, formula (22.) is appropriate, as it "is applicable to equally distributed loads upon beams supported at both ends." It is

$$\frac{1}{2}Ual = Bbd^2$$

90.—The Load on Ordinary Floors, Equally Distributed.— The load upon ordinary floors may be considered as being equally distributed; at least when put to the severest test—a densely crowded assemblage of people. For this load all floors should be prepared.

- 91.—Floors of Warehouses, Factories and Mills.—The floors of stores and warehouses, factories and mills, are required to sustain even greater loads than this, but in all the load may be treated as one equally distributed.
- 92.—Rule for Load upon a Floor Beam.—Each beam in a floor is subjected to the strain arising from the load upon so much of the floor as extends on each side half way to the next adjoining beam; or, that portion of the floor which is measured by the length of the beam and by the distance apart from centres at which the beams are laid. Denote the distance apart, in feet, at which the beams are placed (measuring from the centres of the beams) by c. Then cl will equal the surface of the floor carried by one of the beams.

If the load in pounds upon each superficial foot of the floor be expressed by f, then the total load upon a floor beam will be cfl. This is an equivalent for U, the load.

By substituting for U its value cfl in the formula

$$\frac{1}{2}Ual = Bbd^2$$
 we have

$$\frac{1}{2}acfl^2 = Bbd^2 \tag{24.}$$

which is a rule for the load upon a floor beam.

93.—Nature of the Load upon a Floor Beam.—Before this formula can be used, the value of f must be determined.

This symbol represents a compound weight, comprising the weight of the materials of construction and that of the superimposed load.

The weight of the materials of construction is also in itself a compound load. A part of this load—the floor plank and ceiling (the latter being either of boards or plastering)—will be a constant quantity in all floors; but the floor beam

will vary in weight as the area of its cross-section. In all cases of wooden beams, however, the weight of the beam is so small, in proportion to the general load, that a sufficiently near approximation to its weight may be assigned in each case before the exact size of the beam be ascertained.

- 94.—Weight of Wooden Beams.—For example, in floors for dwellings, the beams will vary from 3×8 to 3×12 , according to the length of the beam. If the timber be white pine (the weight of which is about 30 pounds per cubic foot, or $2\frac{1}{2}$ pounds per superficial foot, inch thick), the 3×8 beam will weigh 5 pounds, and the 3×12 beam $7\frac{1}{2}$ pounds; or, as an average, say $6\frac{1}{2}$ pounds per *lineal* foot for all white pine beams for dwellings. For spruce, the average weight is about the same. Hemlock, which is a little heavier, may be taken at 7 pounds; and Georgia pine (seldom used in dwellings) should be put at about 9 pounds per *lineal* foot.
- 95.—Weight in Stores, Factories and Mills to be Estimated.—For stores, factories and mills the weight is greater, and is to be estimated.
- 96.—Weight of Floor Plank.—The weight of the floor plank, if of white pine or spruce, is about 3 pounds; or, if of Georgia pine, about 4½ pounds per superficial foot.
- 97.—Weight of Plastering.—The weight of plastering varies from 7 to 11 pounds, and is, on the average, about 9 pounds, including the lathing and furring, per superficial foot.
- 98.—Weight of Beams in Dwellings.—The weights of beams, given in Art. 94, are for the lineal foot, but it is requisite that this be reduced so as to show the weight per square foot superficial of the floor. When the distance from

centres at which the floor beams are placed is known, the weight per lineal foot divided by the distance between centres in feet will give the desired result.

Thus, let the distance from centres of white pine floor beams be 16 inches, or $1\frac{1}{8}$ feet. Then $6\frac{1}{4} \div 1\frac{1}{8} = 4\frac{7}{8}$ pounds.

As the average distance from centres in dwellings differs little from 16 inches, the weight of beams may be safely taken at 5 pounds per superficial foot for white pine and spruce.

- 99.—Weight of Floors in Dwellings.—In summing up we have, for the weight of the floor plank, 3 pounds; for the plastering, 9 pounds, and for the beams, 5 pounds; and the sum of these items, 17, or, in round numbers, say 20 pounds is the total weight of the materials of construction upon each superficial foot of the floor of ordinary dwellings; and this is large enough to cover the weight per superficial foot, even when a heavier kind of timber, such as Georgia pine, is used.
- 100.—Superimposed Load.—We have now to consider the superimposed weight, or the load to be carried upon the floor.
- 101.—Greatest Load upon a Floor.*—Mr. Tredgold, in speaking of bridges, says (Treatise on Carpentry, Art. 273): "The greatest load that is likely to rest upon a bridge at one time would be that produced by its being covered with people." Again he says: "It is easily proved that it is about the greatest load a bridge can possibly have to sustain, as well as that which creates the most appalling horror in the case of failure." The floors of churches, theatres, and other

^{*} The substance of the following discussion of the load per foot upon a floor was read by the author before the American Institute of Architects, and published in the Architects' and Mechanics' Journal, New York, in April, 1860.

assembly rooms, and also those of dwellings, are all liable to be covered with people at some time (although not usually), to the same compactness as a bridge. Therefore, to find the greatest strain to which floor timbers of assembly rooms and dwellings are subjected, it will be requisite, simply, to weigh the people; or, to find an answer to the question in the experiments of those who have weighed them.

102.—Tredgold's Estimate of Weight on a Floor.—Mr. Tredgold, in the article quoted, says: "Such a load is about 120 lbs. per foot;" and again, at page 283 of his Treatise on the Strength of Iron, he says: "The weight of a superficial foot of a floor is about 40 lbs. when there is a ceiling, counterfloor, and iron girders. When a floor is covered with people, the load upon a superficial foot may be calculated at 120 lbs. Therefore 120+40 = 160 lbs. on a superficial foot is the least stress that ought to be taken in estimating the strength for the parts of a floor of a room."

Mr. Tredgold's most excellent works on construction have deservedly become popular among civil engineers and architects. With very few exceptions, the whole of the valuable information advanced by him has stood the test of the experience of the last fifty years; and notwithstanding that many other works, valuable to these professions, have since appeared, his works still remain as standards. Statements made by him, therefore, should not be dissented from except upon the clearest proof of their inaccuracy; and only after obtaining ample proof is the statement here ventured that Mr. Tredgold was in error when he fixed upon 120 pounds per foot as the weight of a crowd of people.

In the writings of Mr. Tredgold; his positions are generally sustained by extensive quotations and references; but

in this case, so important, he gives neither reference, data from which he derives the result, nor proof of the correctness of his statement. This proof must be sought elsewhere.

104.—Weight of People—Sundry Authorities.—In the year 1848, an article appeared in the Civil Engineer and Architects' Fournal, containing information upon this subject. From this article we learn that upon the fall of the bridge at Yarmouth, in May 1845, Mr. James Walker, who was employed by government to investigate the matter, stated in evidence before the coroner, that his estimate of the load upon the bridge was based upon taking the weight of people at an average of 7 stone (98 pounds) each; and admitted that this was a large estimate, rather higher, perhaps, than it ought to be; yet he did so because it was customary to estimate them at this weight; and further, that he calculated that six people would require a square yard for standing room. At this rate there would be two persons in every three feet, and the weight would be 65 pounds per foot.

Herr Von Mitis, who built a steel suspension bridge over the Danube, at Vienna, estimated 15 men, each weighing 115 Vienna pounds, to a square fathom of Vienna. This, in English measurement and weight, would be equal to 39 men in every hundred square feet, and nearly 55 pounds per foot.

Drury, in his work on suspension bridges, lays down an arbitrary standard of two square feet per man of 10 stone weight. This equals 70 pounds per superficial foot.

In testing new bridges in France, it is usual for government to require that 200 kilogrammes per square metre of platform shall be laid on the bridge for 24 hours. This is equal to 41 pounds per foot.

The result of combining the above four instances is an average of 57% pounds per foot.

But we have a more accurate estimate, founded upon trustworthy data. Quetelet, in his *Treatise on Man*, gives the average weight of males and females of various ages as follows:—

```
Average weight of males at 5, 10 and 15 years,
                                                     61.53
                                         25
                                  20
                                                     135.59
   "
                                         50
                              30, 40
                                                     140.21
Average weight of females at 5, 10 and 15 years,
                                                     57.50
                                         25
                                                    116-33
                                  20
   "
                              30, 40
                                         50
                                                     121.80
                                                 6 | 632.96
```

Total average weight in lbs. = 105.5

105.—Estimated Weight of People per Square Foot of People.—The weight of men, women and children, therefore, is 105.5 pounds each, on the average. This may be taken as quite reliable as to the weight of people. Now as to the space occupied by them.

It is known among military men that a body of infantry closely packed will occupy, on the average, a space measuring $15 \times 20 = 300$ square inches each. At this rate, 48 men would occupy 100 square feet, and if a promiscuous assembly should require the same space each, then there would be a load of 5064 pounds upon each square foot. In military ranks, however, the men would weigh more. Taking the weight of males from 20 to 50 years, in the above table—this being the probable range of the ages of soldiers—the average is found to be 1379; a weight of 66 pounds upon each superficial foot of floor; and this weight may be taken as the greatest which can arise from a crowd of people.

But this is simply the weight, no allowance being made for any increase of strain by reason of the movement of the people upon the floor. We will now consider the increase made in consequence of the agitation of the weight through walking and other movements.

In walking, the body rises and falls, producing in its fall a strain additional to that due to its weight when quiet.

The moving force of a falling body is known to be equal to the square root of 64½ times the space fallen through in feet, multiplied by the weight of the body in pounds. By this rule, knowing the weight and the height of fall, we may compute the force.

The weight in the present case, 66 pounds, is known, but the height of fall is to be ascertained. This height is not that of the rise and fall of the foot, but of the body; the latter being less than the former. The elevation of body varies considerably in different persons, as may be seen by observing the motions of pedestrians. Some rise and fall as much as half an inch at each step, while others deviate from a right line but slightly. If, in the absence of accurate observation, the rise be assumed at a quarter of an inch, as a fair average, then the moving force of the 66 pounds, computed by the above rule, would be 76.4 pounds. This would be the moving force at the moment of contact, and the effect produced would be equal to this, provided that the falling body and the floor were both quite inelastic; but owing to the presence of an elastic substance on the soles of the feet, and at the joints of the limbs, acting as so many cushions, the force of the blow upon the floor is much diminished. The elasticity of the floor also diminishes the effect of the force to a small degree. Hence the increase of over ten pounds, as found above, would be much diminished, probably one half, or, say to six pounds.

107.—Weight of Military.—This six pounds would be the increase per foot superficial. To make this effect general over the whole surface of the floor, it is requisite that the weight over the whole surface fall at the same instant; or, that the persons covering the floor should all step at once, or with regular military step. It will be found that this is the severest test to which a floor of a dwelling or place of assembly can be subjected. In promiscuous stepping the strain would be much less, scarcely more than the quiet weight of the people.

108.—Actual Weights of Men at Jackson's and at Hoes' Foundries.—The above results, it must be admitted, are derived from data—with reference to the height of fall, and to the lessening effect of the elastic intervening substances,—which are in a measure assumed, and hence are not quite conclusive. They need the corroboration of experiment.

To test them, I experimented, in April, 1860, at the foundry of Mr. James L. Jackson in this city. He kindly placed at my service his workmen and his large scale. The scale had a platform of $8\frac{1}{2} \times 14$ feet. It was of the best construction, and very accurate in its action. Eleven men, taken indiscriminately from among the workmen of the foundry, stood upon the platform. Their combined weight while standing quietly was 1535 pounds, being an average of 139.55 pounds per man. This is but a pound and a half more than was derived from the tables of Quetelet. It is quite satisfactory in substantiating the conclusion there drawn.*

In May, 1876, since the above was written, by the courtesy of Messrs. R. Hoe & Co., of this city, who placed at my disposal their platform scale and men, I was enabled, by a second experiment, to ascertain the weight of men and the space they occupy. Selecting twenty-six stalwart men from their smith shop, they were found to weigh 3955 pounds, and to occupy upon the platform a space $7 \times 7\frac{1}{2} = 52\frac{1}{2}$ square feet, or $75\frac{1}{2}$ pounds per superficial foot. This is a

109.—Actual Measure of Live Load.—After ascertaining the quiet weight of the men, they commenced walking about the platform, stepping without order, and indiscriminately. The effect of this movement upon the scale was such as to make it register 1545 pounds; an increase of only ten pounds, or less than one per cent. They were then formed in a circle and marched around the platform, stepping simultaneously or in military order. The effect upon the scale produced by this movement was equal to 1694 pounds, an increase of 159 pounds, or over ten per cent. This corroborated the results of the computation before made most satisfactorily; ten per cent of the weight per foot, 66 pounds, being 6-6 pounds.

As a final trial, the men were directed to use their utmost exertion in jumping, and were urged on in their movements by loud shouting. The greatest consequent effect produced was 2330 pounds, an increase of 795 pounds, or about 52 per cent.

a much more severe strain than the former, but we must consider that men engaged in the violent movements necessary to produce this increase of over 50 per cent need more standing room. Packed closely, occupying only 15 × 20 inches (the space allowed per man in computing the weight per foot to be 66 pounds), it would not be possible to move the limbs sufficiently for jumping. To do this, at least twice as much space would be required. But, to keep within the limits of safety, let only one half more space be allowed. In this case the 66 pounds would be the weight on a foot

larger average than found at Mr. Jackson's, or than any previous weight on record, and is accounted for by the fact that these were muscular men, weighing about 12½ pounds each more than the heaviest hereinbefore noticed, and much heavier than it were reasonable to expect in assemblages generally.

and a half, or there would be but 44 pounds on each foot of surface.

Add to this the 50 per cent for the effects of jumping, or 22 pounds, and the sum, 66 pounds, is the total effect of the most violent movements on each foot of the floor; the same as for the weight of men standing quietly, but packed so much more closely.

III.—No Addition to Strain by Live Load.—The greatest effect, then, that it appears possible to produce by an assembly on a floor, is from the regular marching of a body of men, closely packed; and amounts to 66 + 6.6 = 72.6 pounds per superficial foot.

This result would show the necessity of providing for ten per cent additional to the weight of the people. This in general is not needed, for the conditions of the case generally preclude the possibility of obtaining this additional strain upon the floor. The strain of 66 pounds is only obtained by crowding the people closely together in the whole room. To obtain the ten per cent additional strain, they must be set to marching; but there is no space in which to march, unless they march out of the room, and in doing this the strain is not increased, for the weight of those who pass out is fully equal to the stress caused by the act of marching.

Were both ends of the room quite open, or were it a long hall, as a bridge, through which the people could march solid, the throng being sufficiently numerous to keep the floor constantly full, then the ten per cent would need to be added, but not in ordinary cases of floors of rooms.

112.—Margin of Safety Ample for Momentary Extra Strain in Extreme Cases.—It may be argued still, that, although the room be full and marching can only be effected by some of the people leaving the floor, yet this additional strain will be

obtained in consequence of the exertion made in the act of taking the very first step, before any have left the room. To this we reply that the strain thus produced would not endanger the safety of the floor, because this strain, when compared with the ultimate strength of the beams sustaining it, would be quite small, and its existence be but momentary. Beams made so strong as not to break with less than from three to five times the permanent load would certainly not be endangered by the addition for a moment of only ten per cent of that load.

Room.—Hence, for all ordinary cases, no increase of strength need be made for the effects of motion in a crowd of people upon a floor, and therefore the amount before ascertained, 66 pounds, or, in round numbers, say 70 pounds, may be used in the computations as the full strain to which the beams may be subjected. Indeed, the cases are rare where the strain will even be as much as this. When we consider the space occupied in dwellings by furniture, and in assembly rooms by seats, the presence of these articles reducing the standing room, the average weight per foot superficial will be found to be very much less.

114.—The Greatest Load to be provided for is 70 Pounds per Superficial Poot. As a conclusion, therefore, floor beams computed to safely sustain 70 pounds per superficial foot, or to break with not less than three or four times this, will be quite able to bear the greatest strain to which they may be subjected in the floors of assembly rooms or dwellings; and especially so when the precaution of attaching them to each other by bridging* is thoroughly performed, thereby ena-

^{*} The subjects of Floor Beams and of Bridging are farther treated in Chapters XVII, and XVIII.

bling the connected series of beams to sustain the concentrated weight of a few heavier persons or of some heavy article of furniture.

115.—Rule for Floors of Dwellings.—We now have, by including the weight of the materials of construction as shown in Art. 99, the total weight per superficial foot, as follows:—

$$f = 70 + 20 = 90$$

for the floors of dwellings. With this value of f, formula (24.),

$$\frac{1}{2} acfl^2 = Bbd^2$$
 becomes
$$\frac{1}{2} ac 90 l^2 = Bbd^2$$
 or, when $a = 4$

$$180 cl^2 = Bbd^2$$
 (25.)

116.—Distinguishing Between Known and Unknown Quantities.—This formula may now be applied in determining problems of floor construction in dwellings, in which the safe strength is taken at one fourth of the breaking strength.

In distinguishing between known and unknown quantities, we will find generally that B and I are known, while c, b and d are unknown.

From formula (25.) therefore, we have, by grouping these quantities,

$$\frac{180 l^2}{B} = \frac{bd^2}{c} \tag{26.}$$

117.—Practical Example.—Formula (26.) is a general rule for the strength of floor beams of dwellings.

As an example under this rule, let it be required to find the sectional dimensions and the distance from centres of the beams of a floor of a dwelling; the span or length between bearings being 20 feet, and the material, spruce. Here B = 550 and l = 20; and from formula (26.) $\frac{180 \times 20^{2}}{550} = \frac{bd^{2}}{6} = 130.9$

 $\frac{100 \text{ M}}{550} = \frac{1}{c} = 130.9$

118.—Eliminating Unknown Quantities.—We have here the numerical value of a quotient, arising from a division of the product of the breadth and square of the depth, by the distance from centres at which the beams are to be placed.

Two of the three unknown quantities are now to be assigned a value, before the third can be determined. Circumstances will indicate which two may be thus eliminated. In some cases the breadth and depth of the timber are fixed, and the distance from centres is the unknown quantity; in others, the distance from centres and the depth may be the fixed quantities, and the breadth be the factor to be found; or, the distance and the breadth be fixed upon, and the depth be the quantity sought for. Generally, the breadth and depth are assigned according to the requirements of the case, or simply as a trial to ascertain the scope of the question, and the distance from centres is the dimension left to be determined by the formula.

119.—Isolating the Required Unknown Quantity.—In the solving of a question of either kind, the formula must first be transposed so as to remove all of the factors, except the one sought for, to the same side of the equation; thus,

$$\frac{bd^{2}}{c} = 130.9$$
 becomes either
$$b = \frac{130.9 c}{d^{2}}$$
 or
$$d^{2} = \frac{130.9 c}{b}$$
 or
$$c = \frac{bd^{2}}{130.9}$$

Assuming the value of any two of the factors, we select the proper formula and proceed with the test for the third factor.

120.—Distance from Centres at Given Breadth and Depth.

For example, fix the breadth and depth at 3 and 9 inches. Then to find c, the above expression,

$$c = \frac{bd^2}{130.9}$$
 becomes
$$c = \frac{3 \times 9^2}{130.9} = \frac{243}{130.9} = 1.86$$

The value of c being in feet, this gives about 1 foot 10 inches, or 22 inches.

121.—Distance from Centres at Another Breadth and Depth.—The above result may be considered too great, and beams of less size and nearer together be more desirable. If so, assume a less size, say 3×8 ; we then have

$$c = \frac{3 \times 8^2}{130 \cdot 9} = \frac{192}{130 \cdot 9} = 1.47$$

This gives c equal to about $17\frac{1}{2}$ inches.

122.—Distance from Centres at a Third Breadth and Depth.—With the object in view of economy of material, let another trial be had, fixing the size at $2\frac{1}{2} \times 9$. In this case

$$c = \frac{2\frac{1}{2} \times 9^2}{130 \cdot 9} = \frac{202 \cdot 5}{130 \cdot 9} = 1.55$$

This gives for c about 18 $\frac{1}{2}$ inches. The answers then to this problem are,

for
$$3 \times 9$$
 inches, 22 inches from centres,
" 3×8 " $17\frac{1}{2}$ " " and " $2\frac{1}{2} \times 9$ " $18\frac{1}{2}$ " "

These trials may be extended to any other proportions thought desirable, fixing first the breadth and depth, and then determining the corresponding value of c. (See precaution, Art. 88.)

123.—Breadth, the Depth and Distance from Centres being Given.—Again, it may be desirable to assume a value for c, and then to ascertain the proper corresponding breadth and depth. In this case, one of the two unknown factors, b and d, must also be assumed. Let us fix upon c = 1.5 and d = 8, then the formula in Art. 119,

$$b = \frac{130.9 c}{d^2}$$
 becomes $b = \frac{130.9 \times 1.5}{64} = 3.07$

or, say 3 inches for the breadth.

124.—Depth, the Breadth and Distance from Centres being Given.—If the breadth be assumed, say at $2\frac{1}{2}$, then, with c = 1.5, to find the depth we have (Art. 119),

$$d^{2} = \frac{130.9 c}{b} = \frac{130.9 \times 1.5}{2.5} = 78.54$$

$$d = 8.86 = 8\frac{7}{8} \text{ inches.}$$

Thus, when placed at 18 inches from centres, we have, in the one case 3×8 inches, and in the other $2\frac{1}{8} \times 8\frac{7}{8}$ inches.

125.—General Rules for Strength of Beams.—Any other case of wooden beams for dwellings may be treated in a similar manner, using formula (25.),

$$180 cl^2 = Bbd^2$$

Beams of any material for any building may be determined by the general formula (24.),

$$\frac{1}{2}acfl^2 = Bbd^2$$

in all cases regarding the caution given in Art. 88.

QUESTIONS FOR PRACTICE.

- 126.—In the floor of a dwelling, composed of 3×9 inch beams 16 feet long, how far from centres should spruce beams be placed?
 - 127.—How far if of hemlock?
 - 128.—How far if of white pine?
- 129.—In the floor of a dwelling, composed of $2\frac{1}{2} \times 10$ inch beams 19 feet long, how far from centres should spruce beams be placed?
 - 130.—How far if of hemlock?
 - 131.—How far if of white pine?
- 132.—In a floor of 4×12 inch beams 23 feet long, and required to carry 150 pounds per superficial foot (including material of construction), how far from centres should spruce beams be placed, the factor of safety being 4?
 - 133.—How far if of hemlock?
 - 134.—How far if of white pine?
 - 135.—How far if of Georgia pine?

CHAPTER VII.

GIRDERS, HEADERS AND CARRIAGE BEAMS.

- ART. 136.—A Girder Defined.—By the term girder is meant a heavy timber set on posts or other supports, and serving, as a substitute for a wall, to carry a floor.
- 137.—Rule for Girders.—A girder sustaining a tier of floor beams carries an equally distributed load; the same per superficial foot as that which is carried by the floor beams. In determining the size of the girder formula (24.) is applicable, namely,

$$\frac{1}{2}acfl^2 = Bbd^2$$

138.—Distance between Centres of Girders.—In applying this formula to girders, it is to be observed that c represents the distance between centres of girders, where there are two or more, set parallel; or, the distance from centre of girder to one of the walls of the building, if the girder be located midway between the two walls; or, an average of the two distances, if not midway. As an example of the latter case,—in a building 30 feet wide, the centre of a girder is 12 feet from one wall and 18 feet from the other. Here

$$c = \frac{12 + 18}{2} = 15$$

- 139.—Example of Distance from Centres.—What is the required size of a Georgia pine girder placed upon posts set 15 feet apart, the centre of the girder being 12 feet from one wall and 18 feet from the other; the load per foot superficial of floor, including the weight of the materials of construction, being 100 pounds, and the value of a being taken at 4?
- 140.—Size of Girder Required in above Example.—By transposing formula (24.) we have

$$\frac{\frac{1}{2}acfl^2}{B} = bd^2$$

and if the breadth be to the depth in the proportion of, say 7 to 10, then (Art. 80)

$$\frac{\frac{1}{2}acfl^{s}}{B} = 0.7d^{s}$$

$$\frac{0.5 \times 4 \times 15 \times 100 \times 15^{2}}{0.7 \times 850} = d^{s} = 1134.45$$

$$d = \sqrt[3]{1134.45} = 10.43$$

and $b = 0.7 \times 10.43 = 7.30$.

Therefore the girder should be 7.3×10.43 ; or, to avoid fractions, say 8×11 inches.

- 141.—Framing for Fireplaces, Stairs and Light-weils.—We will now consider the subject of framing around openings in floors, for fireplaces, stairs and light-wells.
- 142.—Definition of Carriage Beams, Headers and Tail Beams.—Fig. 22 may be taken for a representation of a stairway opening in a floor; AB and CD being the walls of the




Fig. 22.

building, AC and BD the carriage beams or trimmers, EF the header, and the beams which reach from the header to the wall CD, such as GH, the tail beams.

143.—Formula for Headers—General Considerations.—First, the *headers*.

The load upon the header EF is equally distributed, therefore formula (22.) is applicable.

$$\frac{1}{2}Ual = Bbd^{*}$$

The header carries half the load upon the tail beams, or the load upon a space equal to the length of the header by half the length of the tail beams. Let g represent the length of the header, n the length of the tail beams, and f the load per foot superficial; then U, the load upon the header, equals

$$g\frac{n}{2}f = \frac{1}{2}fng = U$$

and, as g here represents l, the length, therefore,

$$Ul = \frac{1}{2} fng^2$$

and formula (22.) becomes

$$\frac{1}{2}a\frac{1}{2}fng^2 = Bbd^2$$

$$\frac{1}{2}afng^2 = Bbd^2$$

144.—Allowance for Damage by Mortising. — This last formula should be modified so as to allow for the damage done to the header by the mortising for the tenons of the tail beams. This cutting of the header ought to be confined as nearly as possible to the middle of its height, so that the injury to the wood may be at the place where the material is subject to the least strain.

If this is properly attended to, it will be a sufficient modification to make the depth of the header one inch more than that required by the formula. Thus, when the depth by the formula is required to be 9 inches, make the actual depth 10; or, for d^2 substitute $(d-1)^2$, d being the actual depth. The rule, thus modified, will determine a header of the requisite strength with a depth one inch less than the actual depth. This will compensate for the damage caused by mortising.

The expression in the last article then becomes

$$\frac{1}{4}afng^2 = Bb(d-1)^2$$

145.—Rule for Headers.—Generally, the depth of a beader is equal to the depth of the floor in which it occurs. Hence, when the depth of the floor beams has been determined, that of the header is fixed. There remains then only the breadth to be found.

We have, for the breadth of a header (from Art. 144)

$$b = \frac{afng^2}{4B(d-1)^2}$$
 (27.)

(See precaution in Art. 88.)

146.—Example.—In a tier of nine inch beams, what is the required breadth of a white pine header at the stairway of a dwelling, the header being 12 feet long, and carrying tail beams 16 feet long; the factor of safety being 4?

In formula (27.), making a=4, f=90, n=16, g=12, B=500 and d=9, the formula becomes

$$b = \frac{4 \times 90 \times 16 \times 12^{3}}{4 \times 500 \times 8^{3}} = 6.48$$

The breadth of the header should be $6\frac{1}{3}$, or say 7 inches, and its size 7×9 inches.

147.—Carriage Beams and Bridie Irons.—A carriage beam, or trimmer, in addition to the load of an ordinary beam, is required to carry half the load of the header which




Fig. 23.

hangs upon it for support. As this is a concentrated load at the point of connection, all mortising at this point to receive the header should be carefully

avoided, and the requisite support given with a bridle iron, as in Fig. 23.

148.—Rule for Bridle Irons.—In considering the strain upon a bridle iron, we find that it has to bear half the load upon the header, and, as the iron has two straps, one on each side of the header, each strap has to bear only a quarter of the load upon the header.

We have seen (Art. 143) that the load upon the header equals $\frac{1}{2}fng$, where g represents the length of the header, n the length of the tail beams, both in feet, and f the load per

superficial foot. The load upon each strap of the bridle iron will, therefore, be equal to

$$\frac{1}{4} \times \frac{1}{2} fng = \frac{1}{8} fng$$

Good refined iron will carry safely from 9000 to 15,000 pounds to the square inch of cross-section. Owing, however, to the contingencies in material and workmanship, it is prudent to rate its carrying power, for use in bridle irons, at not over 9000 pounds.

If the rate be taken at this, and r be put to represent the number of inches in the cross-section of one strap of the bridle iron, then 9000r equals the pounds weight which the strap will safely bear; and when there is an equilibrium between the weight to be carried and the effectual resistance, we shall have

$$\frac{1}{8} fng = 9000r$$

from which

$$r = \frac{fng}{72000} \tag{28.}$$

149.—Example.—For an example, let f = 100, n = 16, and g = 12; then

$$r = \frac{100 \times 16 \times 12}{72000} = 0.266$$

If the bridle iron were made of $\frac{1}{4}$ by $1\frac{1}{2}$ inch iron $(\frac{1}{4} \times 1\frac{1}{4} = 0.375)$ the size would be ample. For such a header they are usually made heavier than this, yet this is all that is needed. It is well to have the bridle iron as broad as possible, in order to give a broad bearing to the wood, so that it shall not be crushed.

150.—Rule for Carriage Beam with One Header.—To return to the carriage beam, or trimmer. The weight to be carried upon a carriage beam is compounded of two loads; one the ordinary or distributed load upon a floor beam, as

shown in formula (24.); the other a concentrated load from the header. Of the former a carriage beam is required to carry one half as much as an ordinary beam; or, the load which comes upon the space from its centre half way to the adjacent common beam. This is the half of that shown in formula (24.), or

 $\frac{1}{2}acfl^2 = Bbd^2$

The symbol W in formula (23.) represents the load from the header, and is equal (Art. 143) to $\frac{1}{2}$ fng. The carriage beam carries half this load, or $\frac{1}{2}$ fng; hence

$$\frac{1}{4}fng = W$$
 or, by formula (23.),
$$4Wa \frac{mn}{l} = 4a\frac{1}{4}fng \frac{mn}{l} = afg \frac{mn^2}{l}$$

Combining this with the formula for the diffused load, we have

$$\frac{1}{4}acfl^2 + afg\frac{mn^2}{l} = Bbd^2$$
 or

$$af\left(\frac{1}{4}cl^2 + gn^2\frac{m}{l}\right) = Bbd^2 \qquad (29.)$$

This is a rule for the resistance to rupture in carriage beams having one header. (See Art. 241, and caution in Art. 88.)

151.—Example.—As an example, let it be required to show the breadth of a white pine carriage beam 20 feet long, carrying a header 10 feet long, with tail beams 16 feet long, in a floor of 10-inch beams, which are placed 15 inches from centres; and where the load per superficial foot is 100 pounds, and the factor of safety is 4.

Transposing formula (29.) we have

$$b = af \frac{\left(\frac{1}{4}cl^2 + gn^2 \frac{m}{l}\right)}{Bd^2}$$

in which a = 4, f = 100, c = 15 inches = 1 $\frac{1}{4}$ feet, l = 20, g = 10, n = 16, m = l - n = 20 - 16 = 4, B = 500 and d = 10. Therefore,

$$b = 4 \times 100 \times \frac{\left(\frac{1}{2} \times 1\frac{1}{2} \times 20^{2} + \frac{10 \times 16^{2} \times \frac{4}{20}}{500 \times 10^{2}}\right)}{500 \times 10^{2}}$$

$$b = 400 \times \left(\frac{125 + 512}{50000}\right) = 5.096$$

The breadth required is 5.096, or say 5 inches. The trimmer should be 5 × 10 inches.

152.—Carriage Beam with Two Headers.—For those cases in which the opening in the floor (Fig. 25) occurs at or near the middle (instead of being at one side, as in Fig. 22), two headers are required; consequently the carriage beam, in addition to the load upon an ordinary beam, has to carry two concentrated loads.

To obtain a rule for this case the effect produced upon a beam by two concentrated loads will first be considered.

153.—Effect of Two Weights at the Location of One of Them.—The moment of one weight upon a beam is (Art. 56) $W\frac{mn}{l}$. This is the effect at the point of location of the weight. A second weight, at another point, will produce a strain at the location of the first weight. To find this strain, let two weights, W and V (Fig. 24) be located upon a beam resting upon two supports, A and B. Let the distance from W to

the support which may be reached without passing the other

weight, be represented by m, and the distance to the other

support by n. From V let the distances to the supports


be designated respectively by s and r; s and n being

distances from the same support.

The letters W and V, representing the respective weights, are to be carefully assigned as follows:—Multiply

one of the weights by its distance from one support, and the product by the distance from the other. Treat the other weight in the same manner; and that weight which, when so multiplied, shall produce the greater product is to be called W.

For example, in Fig. 24 let the two weights equal 8000 and



6000, l=20, the distances from the 8000 weight to the supports equal 4 and 16, and those from the 6000 weight

equal 5 and 15.

Then $8000 \times 4 \times 16 = 512000$ and $6000 \times 5 \times 15 = 450000$

The former result being the greater, the former weight, 8000, is to be called W, and the latter V.

The moment or effect of the weight W at its location is equal, as before stated, to $W\frac{mn}{l}$. The effect of the weight V at the point W will (Art. 27) be equal to the portion of V borne at A, multiplied by the arm of lever m (Arts. 34 and 57). The portion of V sustained by A is (Arts. 27 and 28), $V\frac{s}{l}$; hence the effect of V at W will be $V\frac{s}{l} \times m = V\frac{ms}{l}$. Adding the two effects, we have

$$W\frac{mn}{l} + V\frac{ms}{l} = \frac{m}{l}(Wn + Vs)$$

This is the total effect produced at W by the two weights.

In like manner it may be shown that the total effect at V is

$$V\frac{rs}{l} + W\frac{ms}{l} = \frac{s}{l}(Vr + Wm)$$

These are the moments or total effects at the two points of location. The first, when modified by the factor of safety a, gives

$$a\frac{m}{l}(Wn+Vs)=Sbd^{s}=\frac{B}{4}bd^{s}$$

(see Art. 35) from which we have

$$4a\frac{m}{l}(Wn + Vs) = Bbd^{2} \qquad (30.)$$

for the dimensions at W. Then, also,

$$4a \frac{s}{l} (Vr + Wm) = Bbd^{2} \qquad (31.)$$

for the dimensions at V.

(See caution in Art. 88.)

154.—Example.—When the beam is to be of equal cross-section throughout its length, as is usually the case, then formula (30.), giving the larger of the two results, is to be used.

For example, let a weight of 8000 pounds be placed at 3 feet from one end of a beam 12 feet long between bearings, and another weight of 3000 pounds at 5 feet from the other end.

Then, as directed in Art. 153,

$$8000 \times 3 \times 9 = 216000$$

 $3000 \times 5 \times 7 = 105000$

The weight of 8000 pounds having given the larger product, it is to be designated by W, and the other weight by V.

104 GIRDERS, HEADERS AND CARRIAGE BEAMS. CHAP. VII.

Making a = 4, we have for the greater effect (form. 30.),

$$4a\frac{m}{l}(Wn + Vs) = Bbd^{s}$$

$$4 \times 4 \times \frac{3}{12} \times (\overline{8000 \times 9} + \overline{3000 \times 5}) = Bbd^2 = 348000$$

and with B=500, and b=0.7d, we have

$$B \times 0.7d \times d^{2} = 348000$$

$$d^{3} = \frac{348000}{500 \times 0.7} = 994.29$$

$$d = 9.98$$

$$b = 0.7 \times 9.98 = 6.99$$

or the beam should be 6.99×9.98 , or $7 \times 10^{\circ}$ inches.

155.—Rule for Carriage Beam with Two Headers and Two Sets of Tail Beams.—Let the rules of Art. 153 be applied to the case of a carriage beam with two concentrated loads, as in Fig. 25.




Fig. 25.

When the opening in the floor is midway between the walls, the two sets of tail beams are of equal length; or, m=s; and n=r; therefore mn=sr. The weights are also equal; therefore Wmn=Vrs; or, the strains at the headers

are equal. By moving the opening from the middle, the weight at the header carrying the longer tail beams is increased; so also the product of the distances to the supports is increased; therefore the letter W is to be put at that header which carries the longer tail beams, for then the product Wmn will exceed the product Vrs.

The weight at W is equal to the load upon one end of the header which is lodged there for support. This is equal to (Arts. 143 and 150) $\frac{1}{2}fgm$ (m being the length of the tail beams sustained by this header), or $W = \frac{1}{2}fgm$.

In like manner it may be shown that $V = \frac{1}{2}fgs$.

By substituting these values of W and V in formula (30.) we have

$$\frac{4am}{l}(\frac{1}{l}fgmn + \frac{1}{l}fgs^{s}) = Bbd^{s}$$

$$\frac{afgm}{l}(mn + s^{s}) = Bbd^{s}$$

In addition to this load, the carriage beam is required to carry half the load upon a common beam, or half that shown at formula (24.), or $\frac{1}{4}acfl^2$. The expression for the full effect at W therefore is

$$Bbd^{2} = \frac{afgm}{l}(mn + s^{2}) + \frac{1}{4}acfl^{2}$$

$$Bbd^{2} = af\left[m(mn + s^{2})\frac{g}{l} + \frac{1}{4}cl^{2}\right] \qquad (32.)$$

In like manner we find for the full effect at V,

$$Bbd^{s} = af\left[s\left(rs + m^{s}\right)\frac{g}{l} + \frac{1}{4}cl^{s}\right] \qquad (33.)$$

(See caution in Art. 88.)

These two formulas (32. and 33.) give the sizes of the carriage beam at W and V respectively, but when the beam is made equal in size throughout its length, as is usual, the larger expression (form. 32.) is to be used.

156.—Example.—What is the required breadth of a Georgia pine carriage beam 25 feet long, carrying two headers 12 feet long, so placed as to provide an opening between them 5 feet wide; the tail beams being 15 feet long on one side of the opening and 5 feet long on the other; the floor beams being 14 inches deep and placed 18 inches from centres; the load per superficial foot being 150 pounds, and the factor of safety being 4?

Taking m to represent the longer tail beams, we have a=4, f=150, m=15, n=10, s=5, g=12, l=25, c=18 inches = $1\frac{1}{2}$ feet, B=850 and d=14.


Formula (32.) now becomes

$$850 \times b \times 14^{2} = 4 \times 150 \left[15(\overline{15 \times 10} + 5^{2}) \frac{12}{25} + \overline{4 \times 1\frac{1}{2} \times 25^{2}} \right]$$

$$b = \frac{4 \times 150}{850 \times 196} \left[15(\overline{15 \times 10} + 25) \frac{12}{25} + \overline{4 \times 1\frac{1}{2} \times 625} \right] = 5.38$$

showing that the breadth should be 5.38. The beam may be made $5\frac{1}{4} \times 14$ inches.

One Set of Tail Beams.—The preceding discussion, and the rules derived therefrom, are applicable to cases in which the two headers include an opening between them. When the headers include a series of tail beams between them, leaving an opening at each wall (Fig. 26), then the loads at W and V are equal; for the total load is that which is upon the one series of tail beams, and is carried in equal portions at the ends of the two headers—a quarter of the whole load at each



end of each header. If by j we represent the length of the tail beams, we have $W = V = \frac{1}{2}jfg$, and from formula (30.) we have, for the effect at W,

$$\frac{4aWm}{l}(n+s) = \frac{ajfgm}{l}(n+s)$$

Add to this half the load upon a common beam, $\frac{1}{4}acfl^2$ (Art. 92), and we have, as the full effect at W,

$$\frac{ajfgm}{l}(n+s) + \frac{1}{4}acfl^{2} = af\left[\frac{jg}{l}m(n+s) + \frac{1}{4}cl^{2}\right]$$

and, for the size of the beam at W,

$$af\left[\frac{jg}{l}m(n+s)+\frac{1}{4}cl^2\right]=Bbd^2 \qquad (34.)$$

Similarly, we find for the size of the beam at V,

$$af\left[\frac{jg}{l}s(r+m)+\frac{1}{4}cl^{2}\right]=Bbd^{2} \qquad (35.)$$

These are identical, except that s(r+m) in (35.) occupies the place of m(n+s) in (34.). (See caution in Art. 88.)

As in Art. 153, care must be taken to designate by the proper symbols the weights and their distances. In that article the proper designation was found by putting the letter W to that weight which when multiplied into its distances m and n would give the greater product. Here, as the weights are equal, the comparison may be made simply between the two rectangles mn and rs. Of these, that will give the greater product which appertains to the weight located nearer the middle of the beam; this weight, therefore, is to be designated by W, and will be found at that header which is at the side of the wider opening. distances m and n appertain to the weight The symbols being thus carefully arranged, formula (34.) gives the larger result, and is to be used when the beam is to be of equal sectional area throughout.

158.—Example.—To show the application of this rule, let it be required to find the size of a carriage beam in a tier of beams 12 inches deep and 16 inches from centres, with a weight per superficial foot of 100 pounds. In this case what should be the breadth of a white pine carriage beam 20 feet long between bearings, carrying two headers 12 feet long each, with one series of tail beams 10 feet long between them, so located as to leave an opening 6 feet wide at one wall and 4 feet at the other; the factor of safety being 4? Here we have the two distances m and s equal to 6 and 4, and putting m for the larger we have s = 4, s = 100, s = 10, s = 12, s = 20, s = 14, s = 4, s = 1 $\frac{1}{8}$, s = 500 and s = 12.

Transposing formula (34.) to find b, we obtain

$$b = \frac{af}{Bd^2} \left[\frac{jg}{l} m(n+s) + \frac{1}{4} cl^2 \right]$$

$$b = \frac{4 \times 100}{500 \times 12^{3}} \times \left[\frac{10 \times 12}{20} \times 6(14 + 4) + \frac{1}{4} \times 1\frac{1}{3} \times 20^{3} \right] = 4.34$$

The breadth is required to be 4.34 inches, and the size of carriage beam, say $4\frac{1}{2} \times 12$ inches. (See caution, Art. 88.)

QUESTIONS FOR PRACTICE.

159.—A building, 26 feet wide between the walls, has a tier of floor beams 12 inches deep and 14 inches from centres, supported at 16 feet from one of the walls by a girder resting upon posts set 15 feet apart. Upon that side of the building where the girder is 16 feet distant from the wall a stair opening occurs, extending 14 feet along the wall, and 6 feet wide. The floor is required to carry 150 pounds per foot superficial, including the weights of the materials of construction, with a factor of safety of 4. The girder, trimmers and header all to be of Georgia pine.

Note.—The resulting answers to the following questions will be smaller than if obtained under rules in Chapter XVII. (See Art. 88.)

- 160.—What must be the breadth and depth of the girder, the breadth being equal to 55 hundredths of the depth?
 - 161.—What should be the breadth of the carriage beams?
 - 162.—What should be the breadth of the header?
- 163.—What should be the area of cross-section of the bridle iron?

- 164.—Another opening 6 feet wide in the same tier of beams, has headers 10 feet long, with tail beams on one side 6 feet long and on the other side 4 feet long. What should be the breadth of the carriage beams?
- 165.—What ought the breadth of the floor beams of the aforesaid floor to be on the 16 feet side of the girder, if of white pine?
- 166.—In the same tier of beams there is still another pair of carriage beams. These carry two headers 16 feet long, and the two headers carry between them one series of tail beams 8 feet long, thus forming two openings, one at the girder 3 feet wide and the other at the wall 5 feet wide. What should be the breadth of these carriage beams?

CHAPTER VIII.

GRAPHICAL REPRESENTATIONS.

ART. 167.—Advantages of Graphical Representations.—In the discussion of the subject of rupture by cross-strains, rules have been given by which the effect in certain cases has been ascertained; for example, that at the middle of a beam which rests upon two supports; that at the wall in the case of a lever inserted in the wall; and that at any given point in the length of a beam or lever.

These rules are perhaps sufficiently manifest; but when it becomes desirable to know the effect of the load in a new location, or under other change of conditions, an entirely new computation is needed.

To obviate the necessity for this labor, and to fix more strongly upon the mind the rules already given, the method of representing strains graphically, or by diagrams, is useful, and will now be presented.

168.—Strains in a Lever Measured by Scale.—In Fig. 27

we have a lever AB, or half beam, in which the destructive energy or moment of the weight P, suspended from the free end B, is equal to the product of the weight into the arm of leverage at the end of which it acts (Art. 34); or $D = \frac{1}{2}P$.




Fig. 27.

From A drop the vertical line AC = c, make it by any convenient scale equal to $\frac{1}{2}lP$, and join C and B. The tri-

angle ABC forms a scale upon which the strain produced at any point in AB may be obtained, simply by measurement; for, at any point, D, the ordinate DE (= y), drawn parallel with the line AC, is equal (measured by the same scale) to the strain at the point D. In the two homologous triangles ABC and DBE, we have this proportion:

$$\frac{1}{2}l : c :: x : y = \frac{cx}{\frac{1}{2}l}$$

By construction $c = \frac{1}{2}lP$, therefore

$$y = \frac{\frac{1}{2}lPx}{\frac{1}{2}l} = Px$$

equals the weight into the arm of lever at the end of which it acts; or Px = y is the destructive energy or moment of the weight P at the point D.

In this equation (Px = y) since P is constant, the value of y is dependent upon that of x, for however x may be varied, y will vary in like manner. If x be doubled, y will be doubled; if x be multiplied or divided by any number, y will require to be multiplied or divided by the same number.

We conclude then that we may assign any value to \boldsymbol{z} desirable, or select any point in AB for the location of D, from D draw an ordinate DE, parallel with the line AC, and measuring the ordinate by the same scale by which \boldsymbol{c} was projected, find the strain or destructive energy exerted upon the beam at the selected point D.

169.—Example—Rule for Dimensions.—For example, let P = 100 and l = 20, then $AB = \frac{1}{2}l = 10$, and $\frac{1}{2}lP = 10 \times 100 = 1000$

Now from a scale of equal parts (say tenths of an inch, or any other convenient dimensions), lay off c equal to ten of the divisions of the scale; then each division represents 100.

pounds and $c = 1000 = \frac{1}{2}lP$. Draw the line CB, and from any point D draw the ordinate y. Suppose that y, measured by the same scale, is found to equal $7\frac{1}{4}$; then the strain at D equals $7\frac{1}{4} \times 100 = 725$ pounds.

If y=6, then the strain at D equals 6∞ pounds; and so of any other ordinate, its measure will indicate the strain in the beam at the end of that ordinate.

We have, therefore [as in Art. 34, formula (6.)]

$$Px = Sbd^{*}$$

and, with a the factor of safety, and putting for S its equivalent $\frac{1}{2}B$ (Art. 35),

Pax =
$$\frac{1}{4}Bbd^{2}$$

or, $4Pax = Bbd^{3}$ (36.)

It is to be observed that the b and d of this formula are those required at D, the location of the ordinate y.

When x equals the length of the lever AB, equals $\frac{1}{2}l$, we have

$$4Pa\frac{1}{2}l = Bbd^{2}$$
$$2Pal = Bbd^{2}$$

and if P be taken as $\frac{1}{2}W$, W being the load at the centre of a whole beam, we have

$$2 \times \frac{1}{2} Wal = Bbd^{2}$$

$$Wal = Bbd^{2}$$

the same as formula (21.).

, 170.—Graphical Strains in a Double Lever.—In Fig. 28.

we have a beam AB resting upon a point at the middle C, and carrying the two equal loads R and P suspended from the ends.

The half of this beam, or CB, under the same conditions of





Fig. 28.

strain as the beam AB in Fig. 27, and since the weights R and

P are equal, and C is at the middle of AB, the one half of the beam, or AC, is strained alike with the other half CB. Therefore a strain at any point in the length of the beam is measured by an ordinate from that point to the line AWB, and formula (36.) is applicable to this case also, conditioned that x does not exceed $\frac{1}{2}l$.

171.—Graphical Strains in a Beam.—In Fig. 29 we have a beam AB, resting upon two supports A and B, and loaded



at middle with the weight W, one half of which, R, is borne upon A, and the other half, P, is supported by B.

This beam has the same strains as that of Fig. 28, therefore (see Art. 26) the same

formula (36.) is applicable, namely:

$$4Pax = Bbd^{*}$$

 $P = \frac{1}{2}W$, and by substitution.

$$4 \times \frac{1}{2} Wax = Bbd^{2}$$

$$2 Wax = Bbd^{2}$$
(37.)

a rule applicable to this case, conditioned that x shall not exceed $\frac{1}{2}l$.

When $x = \frac{1}{2}l$ then we have

$$2 Wa \frac{1}{2}l = Bbd^{2}$$

$$Wal = Bbd^{2}$$

the same as given in formula (21.).

Again, if x be diminished until it shall reach zero, then

$$2Wax = 0$$

or the strain is nothing. This is evidently correct, as the effect of the weight, in producing cross-strain, disappears at

the edge of the bearing. We are not to be permitted, however, in shaping the beam to its exact requirements, to remove all material at and upon the bearing wall, for there is another strain, known as the *shearing strain*, for which provision is to be made at the end of the beam.

This strain we will now consider.

172.—Nature of the Shearing Strain.—The nature of the shearing strain, as well as of the cross-strain, is very clearly shown in Fig. 30, a diagram suggested by a similar one

in "Unwin's Wrought-Iron Bridges and

Roofs, London, 1869."

In this figure a semi-beam, AB, fixed in a wall at A, is cut through at CD, and the severed piece, CB, is held in place by means of a strut at D and a link at C, which resist the compression and tension due to the cross-strain arising from the weight P; and by the weight R equal to P) suspended over a pulley E,




Fig. 30.

which prevents the severed beam from sinking, or resists the shearing strain.

As the link C and strut D are both acting in a horizontal direction, they can have no effect in resisting a vertical strain, consequently the weight P must be entirely sustained by the counter-weight R, and as the action of the latter is frectly opposite to that of the former, it must be equal to it amount.

In the above arrangement we may see that were the trut D removed, the beam CB, under the action of the neight P, would revolve upon C as a centre, closing the gap at the bottom; hence the strut D is compressed.

In like manner, if the link at C were removed, the

weight P would cause the beam to revolve on D, making wider the opening at the top, and showing that the link C is in tension. If the tension at C be represented by t, the compression at D by c, and the depth CD by d, then

$$td = cd = P \times CB$$

Disregarding the weight of the beam, the shearing strain at CD equals the weight P. As this strain is wholly independent of the distance between C and B, the beam may be cut at any point in its length with a like result as to the amount of the shearing strain. At every point we shall have R = P, or the shearing strain equal to the weight.

If the weight of the beam be included in the consideration, the shearing strain at any point will equal the weight P plus the weight of so much of the beam as extends beyond the point at which the shearing strain is considered.

Let CD be the cross-section at which it is required to find the shearing strain; let x equal the distance from this cross-section to B, in feet; and let e represent the weight per foot lineal of the beam; then the weight of the piece CB will equal ex, and the shearing strain at CD will equal P + ex, or the destructive energy is

$$D = P + \epsilon x$$

173.—Transverse and Shearing Strains Compared.—Before this formula can be available, it is needed to know the resistance of the different materials to this kind of force. Experiments have been made upon wrought-iron which show that its shearing resistance is about seventy-five per cent of its resistance to tension. If, in the absence of the experiments necessary to establish the resistance to shearing in materials generally, it be assumed that they bear the

same proportion to their tensile resistance as is found in wrought-iron, this shearing strength may be put equal to

$$R = \frac{3}{4}Tbd$$

in which T equals the absolute resistance to tension per square inch of cross-section.

The resistance of certain woods to tension may be found in Table XX.

When D = R we have

$$P + ex = \frac{3}{4}Tbd$$

This gives bd, or the area of cross-section, equal only to the destructive energy. In this case rupture would ensue. We therefore introduce the factor of safety, a, and have

$$a(P + \epsilon x) = \frac{3}{4} Tbd \quad . \tag{38.}$$

The portion of T considered safe is from one sixth to one ninth. We then have a = 6 to a = 9.

As an example: Suppose a semi-beam (as AB, Fig. 30) of white pine to be 10 feet long, and loaded at the end with P=10,000 pounds; what would be the required area of cross-section at the wall?

Here the weight of the beam is so small in comparison with the load P that it may be neglected in the computation. Throwing it out of the formula, we have

$$Pa = \frac{3}{4} Tbd \tag{39.}$$

Let a=9 and T=12000; then

$$10000 \times 9 = \frac{3}{4} \times 12000 \times bd$$

$$\frac{10000 \times 9}{\frac{8}{4} \times 12000} = bd = 10$$

To compare this requirement with that for the cross-strain, we make use of the formula for this strain, (19.),

$$4Pan = Bbd^{2}$$

and, making a = 4, have

$$4 \times 10000 \times 4 \times 10 = 500 \times bd^{2}$$

$$\frac{4 \times 10000 \times 4 \times 10}{500} = bd^2 = 3200$$

and, making d = 16, have

$$b \times 16^{\circ} = 3200$$

$$b = \frac{3200}{16^2} = 12.5$$

therefore the area will be $12\frac{1}{2} \times 16 = 200^{\circ}$ square inches.

This is the area required at the wall, but at the end B, the point of attachment of the weight, we have seen (Fig. 27) that the destructive energy in cross-strain is zero. Were this the only effect produced by the weight P, the beam might be tapered here to a point. Owing, however, to the shearing effect of the weight, we find, as above, a requirement of material equal to 10 inches in area, or the beam 12½ inches wide would require to be eight tenths of an inch thick; and the rope supporting the weight should be so attached as to have a bearing across the whole width of the piece.

174.—Rule for Shearing Strain at Ends of Beams.—
The shearing strains at the two supports upon which a beam is laid are together equal to the weight of the beam and the load laid upon it. If the beam be of equal cross-section throughout its length, and the load upon the beam be located at the middle, or symmetrically about the middle, then the

weight of the beam and its load will be sustained half upon each support. In this case, the shearing strain at the two supports will be equal, and each equal to half the total load. Putting W for the load upon the beam, and el for the weight of the beam, then for the shearing strain at each end of the beam we have

$$\frac{1}{2}W + \frac{1}{2}el = D$$

Putting this equal to the safe resistance [see formula (38.), Art. 173] we shall have

$$a\left(\frac{1}{2}W + \frac{1}{2}cI\right) = \frac{1}{4}Tbd$$

$$\frac{1}{2}a\left(W + cI\right) = \frac{3}{4}Tbd$$

$$\frac{2a}{3T}(W + \epsilon I) = bd$$
(40.)

When the load is not at the middle nor symmetrically disposed about the middle, the portion borne upon each support may be found by formulas (3.) and (4.), Art. 27. The shearing strain at each support is equal to the reaction of the support or to the load it bears.

175.—Resistance to Side Pressure.—Beyond the foregoing considerations, there is still another of some importance. Care should be taken that the surfaces of contact of the wall and the beam are of sufficient area to be unyielding. Usually the wall composed of brick or stone is so firm that there need be no apprehension of its failure, and yet it is well to know that it is safe. It should, therefore, be carefully considered, to see that the given surface is sufficiently large for the given material to carry safely the weight proposed to be distributed over it. In calculations for heavy roof trusses this precaution is particularly necessary.

The upper surface of the joint, or under side of the beam,

requires especial attention. This is usually of timber, and parallel with the fibres of the material. The pressure upon the surface tends to compress these fibres more compactly together by closing the cells or pores which occur between the fibres. When pressed in this way, timber is much more easily crushed, as may readily be supposed, than when the pressure is applied at the ends of the fibres in a line parallel with their direction.

The resistance to side pressure approaches the resistance to end pressure in proportion to the hardness of the material.

By experiments made by the author some years since, to test the side resistance, results of which are recorded in the American House Carpenter, page 179, it appears that the hardest woods, such as lignum-vitæ and live oak, will resist about 1½ times the pressure endwise that they will sidewise; ash, 1½ times; St. Domingo mahogany, twice; Baywood mahogany, oak, maple and hickory, about 3 times; locust, black walnut, cherry and white oak, about 3½ times; Georgia pine, Ohio pine and whitewood, about 4 times; chestnut, 5 times; spruce and white pine, 8 times; and hemlock, 9 times. Their resistance to side pressure is in proportion to the solidity of the material, or inversely in proportion to the size of the pores of the wood.

In the above classification, the comparison is not that of the absolute resistance of the several kinds of wood to side pressure. It is only a comparison of the results of the two pressures on the same wood. Whitewood, classed above with Georgia pine, resists sidewise only as much, absolutely, as white pine. Its power of resistance to end pressure is the lowest of any of the woods, being but one half that of white pine.

The average effectual resistance to side pressure per square inch of surface, p, for

Spruce = 250 pounds.

White pine $\stackrel{.}{=} 300$ "

Hemlock = 300 "

Whitewood = 300 "

Georgia pine = 850 "

Oak = 950 "

Under these pressures only a slight impression is made, and the woods may be safely trusted with these respective amounts.

176.—Bearing Surface of Beams upon Walls.—The surface of the beam in contact with the wall must be sufficient in extent to insure that it shall not be exposed to more pressure than is above shown to be safe. If b equal the breadth of the beam, h the length of the bearing surface, and p the resistance per inch, as above, then the total resistance equals

$$R = bhp$$

The destructive energy for one end of the beam is, as before (Art. 174),

$$D = \frac{1}{2}W + \frac{1}{2}cl$$

When there is equilibrium, then R = D, or

$$\frac{1}{2}(W+cl) = bhp \tag{41.}$$

Owing to the deflection of the beam by the load upon it, its extreme ends may be slightly raised from off the bearing surface, and in consequence the pressure be concentrated at the edge of the wall. No serious effect will ensue from this, for if the pressure be greater than the timber can resist at the edge, the fibres will be crushed there, but only sufficiently so to allow the surface of contact to extend towards

the end of the beam, until it is so enlarged as to effectually resist any further crushing.

Beams which are likely to be depressed considerably should have their ends formed so that their under surface will coincide throughout with the wall surface when the greatest load shall have been put upon them.

177.—Example to Find Bearing Surface.—Let a white pine carriage beam 6 inches wide, 24 feet long between bearings, and weighing 15 pounds per lineal foot, be loaded with 12,000 pounds, equally distributed over its length. What should be the length of the bearing upon each wall?

By transposition, formula (41.) becomes

$$\frac{W+el}{2bp}=h$$

In this case, W = 12,000, e = 15, l = 24, b = 6, and p = 300; then

$$\frac{12000 + 15 \times 24}{2 \times 6 \times 300} = h = 3.43$$

or the end of the beam must extend upon the wall, say 3\frac{1}{2} inches. The usual bearing for floor beams, which is 4 inches, would in this case be amply sufficient.

Where the concentrated weight is so large in comparison with the weight of the beam, the latter weight may be neglected without any serious result; for had we considered the 12,000 pounds only, in the above example, the value of k would have been 3.33, only a tenth of an inch shorter than the former result.

As will be observed, we have digressed from the principal subject. This became necessary in order to explain the apparently anomalous result of leaving the beam without any

support at the ends. For it was seen that in an application of the formula for cross-strains the requirement of material gradually lessened towards the ends of the beam, until at the very edge of the bearings it entirely disappeared.

To prevent the beam, with its load, from falling as a dead weight between the bearings; or, to provide against the shearing strain, as well as against the crushing of the material upon its bearings, we have turned aside so far as seemed to be needed. And before returning to the main subject, it may be well here to show that the line CB in Figs. 27 and 29, limiting the ordinates of cross-strain in the lever and beam, does not show, as might be supposed, the shape of the depth of a lever or beam having a cross-section of equal strength throughout its length. A short consideration of the relation between the strains at given points in the length will show the true shape.

By construction, c, Fig. 27, is equal to $\frac{1}{2}lP$, and from this we have shown (Art. 168) that

$$y = Px$$

and when the destructive energy and the resistance are equal.

$$\frac{1}{2}lP = Sbd^2 \qquad \text{and}$$

$$Px = Sbd^2, \qquad \text{from which}$$

$$c: y:: Sbd^2: Sbd^2, \qquad \text{and when}$$

S and b are constant

$$c:y::d^2:d^2$$

or, the ordinates are in proportion to the squares of the depths, and not directly as the depths themselves.

From these ordinates, however, the shape of the side of the lever may be directly found by taking their square roots. For let AB in Fig. 3¹ be the upper edge of the lever, and

CB the line limiting the ordinates of cross strain. Then, if




Fig. 31.

AD be made equal to the square root of AC, and, correspondingly, d_{ij} , d_{ij} , d_{ij} , d_{ij} , etc., be each made respectively equal to the square root of the ordinate upon which it lies, and if a line be drawn through the ends of d_{ij} , d_{ijj} , d_{ijj} , etc., this line, DEB, will limit the shape of the lever.

This curve line is a semi-parabola, with its vertex at B and its base vertical at AD. By con-

struction, each ordinate y is in proportion to x, its distance from B, or (since y equals d') d' is in proportion to x, a property of the parabola. Hence to obtain the shape of the lower edge of the lever, any method of describing a parabola may be used, making AD, its base, equal to (form. 19.)

$$d = \sqrt{\frac{4Pan}{Rh}}$$




Fig. 32,

As a whole beam is in like condition with two semi-beams, as to the cross strains, therefore the shape of a whole beam of equal strength throughout its length is that given by two semi-parabolas placed base to base, as in Fig. 32.

QUESTIONS FOR PRACTICE.

- 179.—In a semi-beam, or lever, 10 feet long, fixed in a wall, and loaded at the free end with 3672 pounds, what is the destructive energy at the wall?
- 180.—Make a graphic representation of the above by a horizontal scale of one foot to the inch, and a vertical scale of 1000 foot-pounds to the inch. What is the height CA of the triangle of cross-strains, in terms of the scale selected?
- 181.—Measuring horizontal distances from the free end, what are the lengths, by the scale, of the respective ordinates at the several distances of 5, 6, 7, 8 and 9 feet; and what the amount of cross-strain corresponding thereto at these several points in the beam?
- 182.—What will be the required depth at the wall, and at 9 and 8 feet respectively from the free end; the lever being of Georgia pine, 6 inches broad, and the factor of safety 4?
- 183.—In a white pine beam, 4 inches broad, 16 feet long between bearings, and loaded at the middle with 3250 pounds, what should be the respective depths at the several distances of 3, 5, 7 and 8 feet from one end, the factor of safety being 4?
- 184.—A white pine semi-beam, 12 feet long and 4 inches broad, is loaded with 693 pounds at the free end, including the effect of the weight of the beam itself. The factor of safety is 4, the beam is of constant breadth and depth

throughout its length, and its weight is 30' pounds per cubic foot.

What is its required depth at the wall?

What is the weight suspended from the end of the beam?

What is the shearing strain at the wall?

What is the shearing strain at 5 feet from the wall?

- 185.—A beam of Georgia pine, 4 inches broad and 20 feet long, is loaded at the middle with 9644% pounds. The beam is 17 inches high at the middle, and tapered in parabolic curves to each end. The material of the beam is estimated at 48 pounds per cubic foot. What is the weight of the beam?
 - 186.—What is the shearing strain at each wall?

With a factor of safety of 9, how high is the beam required to be at the ends to resist the shearing strain safely?

187.—How far upon each wall is the beam required to extend, in order to prevent crushing of the material?

CHAPTER IX.


STRAINS REPRESENTED GRAPHICALLY.

ART. 188.—Graphic Method Extended to Other Cases.—In Figs. 27, 28 and 29, with a given maximum strain upon a semi-beam, or upon a full beam, we have a ready method of finding the strain at any given point in the length.

This simple method of ascertaining the strain at any point, graphically, is based upon a principle which is applicable to strained beams under conditions other than those given, as will now be shown.

189.—Application to Double Lever with Unequal Arms.—In Figs. 28 and 29 the load upon the beam is at the middle. But it may be shown that the triangle of strains is applicable in cases where the load is not at the middle.

Let R and P, Fig. 33, represent two unequal weights,



suspended from the ends of a balanced lever AB. From the law of the lever, we have (Art. 27)

Rm = Pn


If CD, called g, be made of a length to represent Pn, then will it also represent Rm; for Rm = Pn. Hence, since the triangle BCD is the triangle of strains, in which an ordinate, y, showing the strain at any given point in DB, may be drawn, therefore the triangle ACD will give ordinates, y', measuring the strains at the points in AD, from which they may be drawn; or, since

Pn:
$$g:: Px: y$$

$$y = \frac{g}{n}x \qquad (42.)$$
so also
$$Rm: g:: Rx': y'$$

$$y' = \frac{g}{m}x' \qquad (43.)$$

190.—Application to Beam with Weight at Any Point.— In Fig. 34, AB represents a beam supported at each end, carrying a load W at a point nearer to A than to B. This



beam is strained in all respects like that in Fig. 33, except that the strains are in reversed order. Therefore an ordinate, y, drawn across the triangle BCW, will indicate the strain at the point of its location. So an ordinate, y', across the triangle ACW, will indicate the strain at its point of

location. Or, generally, the two triangles ACW and BCW limit the ordinates which measure the strains at any point in the length of the beam. Thus when

$$g = Pn = Rm$$
 we have $y = Px$ and $y' = Rx'$ and since $P = W \frac{m}{l}$ and $R = W \frac{n}{l}$ (Art. 27) we have $y = W \frac{m}{l}x$ (44.)

Now, since Rm = Pn = g, equals the destructive energy of the weight at its location, therefore any ordinate across the triangles ACW and BCW equals, when measured by the same scale, the destructive energy at the location of that ordinate, and when the resistance is equal to the destructive energy we have for the strain at any point to the right of the weight

$$W\frac{m}{l}x = Sbd^2$$

Putting for S its equivalent $\frac{1}{2}B$ (Arts. 35 and 57) to agree with the unit of dimensions, we have, for the safe weight,

$$4Wa\frac{m}{L}x = Bbd^2 \tag{46.}$$

which, with x at its maximum equal to n, is identical with formula (23.).

For the safe weight at any point to the left of the weight we have

$$4Wa\frac{n}{l}x' = Bbd^{2} \tag{47.}$$

191.—Example.—As an example in the application of these expressions, let it be required to find the strains at

various points in the length of a white pine beam, the maximum strain being given.

Let the beam be 10 feet long and loaded with 2000 pounds at a point three feet from the left-hand end.


What is the strain at the location of the weight? What are the several strains at 2, 4 and 6 feet from the right-hand end and at 2 feet from the left-hand end?

Take first the strains to the right.

Here, by formula (44.), $y = W \frac{m}{l} x$, and with x at its maximum we have

$$y = 2000 \times \frac{3}{10} \times 7 = 4200$$

In Fig. 35, make the length between the bearings A and B by any scale, equal to 10 feet, and CW, or g, equal to 42 units of any other scale. Then each of these units will



represent 100 pounds of strain. The number of units in the length of the ordinates, y, at the several distances, x equal to 2, 4 and 6 feet, and of x' = 2 feet, will give, when multiplied by 100, the strains at these several points. Thus it will be found that,

at 2 feet from B,
$$y = 12$$
, and $12 \times 100 = 1200$;
" 4 " " B, $y = 24$, " $24 \times 100 = 2400$;
" 6 " " B, $y = 36$, " $36 \times 100 = 3600$;
and " 2 " " A, $y' = 28$, " $28 \times 100 = 2800$.

Now, if it be required to find the proper depth of the beam at these several points, we take, for the right-hand end, formula (46.),

$$4Wa\frac{m}{l}x = Bbd^2$$

in which W represents 2000 pounds, the weight upon the beam, and in which $W\frac{m}{l}x$ will give the strain at each ordinate; and by transposition have

$$d^{2} = \frac{4Wam}{Bbl} x \tag{48.}$$

and if a = 4, $B = 5\infty$ and b = 3, we have

$$d^{2} = \frac{4 \times 2000 \times 4 \times 3}{500 \times 3 \times 10} x = 6.4 x$$

and therefore

when
$$x = 2$$
 then $d^2 = 6 \cdot 4 \times 2 = 12 \cdot 8$ and $d = 3 \cdot 58$
" $x = 4$ " $d^2 = 6 \cdot 4 \times 4 = 25 \cdot 6$ " $d = 5 \cdot 06$
" $x = 6$ " $d^2 = 6 \cdot 4 \times 6 = 38 \cdot 4$ " $d = 6 \cdot 20$
" $x = n = 7$ " $d^2 = 6 \cdot 4 \times 7 = 44 \cdot 8$ " $d = 6 \cdot 69$

For the left-hand end we use formula (47.)

$$4Wa \frac{n}{l}x' = Bbd^{*}$$

$$d^{*} = \frac{4Wan}{Bbl}x' \qquad (49.)$$

$$d^{2} = \frac{4 \times 2000 \times 4 \times 7}{500 \times 3 \times 10} x' = 14.93 x'$$

and hence,

when
$$x' = 2$$
 then $d' = 14.93 \times 2 = 29.9$ and $d = 5.47$
" $x' = m = 3$ " $d' = 14.93 \times 3 = 44.8$ " $d = 6.69$

This last result agrees with the last from the right-hand end, as it should, for they are both for the same location. The above results are all obtained by computations, but the value of d^2 , at as many points as may be desired, can be obtained by scale, in a similar way with the ordinates for the destructive energy; but this scale, for the purpose of obtaining the depths, must be made with the principal ordinate, g, equal to the requirement


$$d^2 = \frac{4Wamn}{Bhl} \tag{50.}$$

(see form. 23.), and then the square root of each ordinate drawn across the scale will be the required depth at its location.

For example: Make g, by any convenient scale, equal to 44.8 as above required; then the several values of d at 2, 4 and 6 feet may be found by measuring the ordinates drawn at these several distances from B.

The square root of each ordinate will equal the depth of the beam there. The results obtained by measurements, although not exact to the last decimal, are yet sufficiently exact for all practical purposes. If it be required to find the exact dimension, this may be done by computation, as shown, and the diagram will then serve the very useful purpose of checking the result against any serious error in the calculation. 192.—Graphical Strains by Two Weights.—The value of graphic representations is manifest where two or more weights are carried at as many points upon a beam.

In Fig. 36 we have a beam carrying two weights A' and B'.



The destructive energy of the weight A', at its location, is equal to (Art. 56)

$$D' = A' \frac{mn}{l}$$

and the destructive energy of the weight B', at its location, is equal to

$$D'' = B' \frac{rs}{I}$$

Make AE equal to $A'\frac{mn}{l}$ by any convenient scale. By the same scale make BF equal to $B'\frac{rs}{l}$. Draw the lines CE and DE, CF and DF.


Now, while AE represents the effect of the weight A' at the point A, so also AG measures (Art. 190) the effect, at the same point, of the weight B'; therefore make $E\mathcal{F}$ equal to AG, then $A\mathcal{F}$ is the total effect at A of both weights.

In like manner (FK being made equal to BH), BK measures the total effect at B. Draw the line CFKD, and by dropping a vertical ordinate from any point in the beam CD to this line, we have the total strain in the beam at that point.

193.—Demonstration.—The above may be proved, as follows:

First. Let the ordinate occur between the two weights as LM, Fig. 37.

Extend the lines CF, DE and $\mathcal{F}K$, till they meet at R and S, and draw CR and DS.



Now the effect of B' at B, is measured by BF, and at L by LP (Art. 189). Also the effect of A' at A, is measured by AE, and at L by LN. The joint effect of A' and B' at L, is thus LP + LN, and if it can be shown that PM equals LN, then

$$LP+LN=LP+PM=LM$$

equals the joint effect of the two weights A' and B', at L.

In two triangles of equal base and altitude, two lines drawn parallel to the respective bases, and at equal altitudes, are equal; from which, conversely, if two triangles of equal base have equal lines drawn parallel to the base, and

at equal altitudes, then the altitudes of the two triangles are equal. In the present case we have $AE = G\mathcal{F}$; for $AG = E\mathcal{F}$ by construction; and if, to each of these equals we add the common quantity GE, the sums will be equal, or

$$AG+GE = GE+E\mathcal{F}$$
$$AE = G\mathcal{F}$$

The two triangles ADE and GSF are therefore standing upon equal bases, AE and GF.

Moreover, at equal distances, AB, from the line of bases $A\mathcal{F}$, and parallel with it, we have the two lines BH and FK, made equal by construction. Consequently, the two triangles have equal altitudes. Hence all lines drawn across them, parallel with and at equal distances from the base, are equal, and therefore LN and PM, having these properties, are equal, and LM = LP + LN equals the true measure of the strain induced at L by the weights A' and B'; or, in general, any vertical ordinate drawn across $A\mathcal{F}KB$ will measure the total strain caused by the two weights at the location of the ordinate.

194.—Demonstration—Rule for the Varying Depths.—Second. Let the ordinate occur at one end, between B and D, as OQ, Fig. 37.

Here we have OT for the strain caused by A', and OV for the strain caused by B'; or the total strain equals OT + OV.

Now if VQ can be proved equal to OT, we shall have

$$OT + OV = VQ + OV = OQ$$

equal to the total strain at O.

We have the two triangles BDH and FDK, with bases




Fig. 37.

BH and FK, made equal by construction, and with equal altitudes BD, and we have the two lines OT and VQ drawn parallel with, and at equal altitudes (BO) from the base; consequently OT and VQ are equal, and OQ measures the total strain of the two weights at O; or, in general, any vertical ordinate drawn across BDK will measure the total strain at the location of the ordinate.

Since it may be shown in like manner that any vertical ordinate drawn across $AC\mathcal{F}$ will measure the total strain at its location, therefore we conclude that a vertical ordinate from any point in the beam CD to the line $C\mathcal{F}KD$ will show the total strain in the beam at that point.

In practice, the scale of strains CFKD may be constructed as just shown, in detail, but more directly by obtaining the points F and K in the following manner:

We have for the joint effect of the two weights at the location of one of them, A, (see Art. 153)

$$D = \frac{m}{l}(Wn + Vs)$$

which becomes, on changing W and V into A' and B',

$$D = \frac{m}{l}(A'n + B's) \tag{51.}$$

equals the length of the ordinate AJ.

In like manner we have

$$D' = \frac{s}{l}(B'r + A'm) \qquad (52.)$$

for the length of the line BK.

The points \mathcal{F} and K are to be obtained by these expressions. The scale is then completed by connecting these points and the ends of the beam by the line $C\mathcal{F}KD$. The strain at any point in the beam may then be readily measured, sufficiently near for all practical purposes.

If, however, the exact strain is desired, this may be obtained as follows:

Putting g for $A\mathcal{F}$, p for BK, and h for AB, we have for the several ordinates

s:p::x:y

$$y = \frac{p}{s}x$$

$$m : g :: x' : y'$$

$$y' = \frac{g}{m}x'$$

$$h : p-g :: x'' : y''-g$$

$$h(y''-g) = x''(p-g)$$

$$hy''-hg = x''(p-g)$$

$$hy'' = x''(p-g) + hg$$
(53.)

(55.)

If it be required to know the depth of the beam at every point, to accord with the strain there, then, instead of making the two principal ordinates as above shown, find their lengths thus:

 $y'' = \frac{p - g}{h} x'' + g$

By formulas (30.) and (51.) make $A\mathcal{F}$ equal to


$$d^{s} = \frac{4a\frac{m}{l}(A'n + B's)}{Bb}$$
 (56.)

and by formulas (31.) and (52.) make BK equal to

$$d^{s} = \frac{4a_{\overline{I}}^{s}(B'r + A'm)}{Bb} \tag{57.}$$

Draw the line CJKD, and then an ordinate drawn across this scale at any point will give the square of the depth at that point. The square root of this length will be the required depth there.

195.—Graphical Strains by Three Weights.—In Fig. 38 we have a graphical representation of the strains resulting from three weights.



This figure is constructed by making $A\mathcal{F}$ equal to the moment of A' at A, BK equal to the moment of B' at B, and CL equal to the moment of C' at C, all by the same

scale. Connect \mathcal{F} , K and L each with the ends of the beam E and D. Make $\mathcal{F}F$ equal to AM + AN, KG equal to BO + BP, and LH equal to CQ + CR.

Join E, F, G, H and D, and this line will be the boundary of any vertical ordinate from any point in ED, which, by the same scale as used for $A\mathcal{F}$, etc., will measure the strain at the location of the ordinate.

In this diagram, the points F, G and H may be found directly, as follows:

To find F, we have (Art. 153) $A'\frac{mn}{l}$ for the effect of A', $B''\frac{ms}{l}$ for B', and so, in like manner, we may have $C'\frac{mv}{l}$ for that of C'. Added together, these will equal

$$AF = \frac{m}{I}(A'n + B's + C'v) \qquad (58.)$$


To find G, we have $A'\frac{ms}{l}$ for A', $B'\frac{rs}{l}$ for B', and $C'\frac{rv}{l}$ for C'; which together give

$$BG = \frac{A'ms + B'rs + C'rv}{l} \qquad (59.)$$

To find H, we have $A'\frac{mv}{l}$ for A', $B'\frac{rv}{l}$ for B', and $C'\frac{tv}{l}$ for C; which added, will equal

$$CH = \frac{v}{l}(A'm + B'r + C't) \tag{60.}$$

If it be desirable, the strains may, as in the last figure, be computed; for putting g for AF, p for BG, k for CH, k for AB, and q for BC, we have, for an ordinate between C and D,



$$v: k:: x: y$$

$$y = \frac{k}{n}x \tag{61}$$

For an ordinate between E and A we have

$$m : g :: x' : y'$$

$$y' = \frac{g}{m}x'. \tag{62.}$$

For an ordinate between A and B we have, as in Fig. 37,

$$y'' = \frac{p - g}{h} x'' + g \qquad (68)$$

and for ordinates occurring between B and C we have

$$y''' = \frac{p-k}{a}x''' + k \tag{64.}$$

These expressions give the strains at any point, due to the three weights.

In like manner, we may find the strain at any point in a beam, arising from any number of weights.

To obtain the squares of the depths at various points by scale, make AF equal to

THREE EQUAL WEIGHTS SYMMETRICALLY DISPOSED. 141

$$d^{2} = \frac{4a\frac{m}{l}(A'n + B's + C'v)}{Bb}$$
 (65.)

Make BG equal to

$$d^{2} = \frac{4a\frac{A'ms + B'rs + C'rv}{l}}{Bb}$$
 (66.)

Make CH equal to

$$d^{2} = \frac{4a^{2'}(A'm + B'r + C't)}{Bb}$$
 (67.)

The square roots of ordinates upon this scale will give the depths required at their several locations.

196.—Graphical Strains by Three Equal Weights Equaby Disposed.—Let us now consider the effect of equal weights, equably disposed.

In Fig. 39 we have three equal weights, L, placed at equal distances apart upon a beam, ED, the distance from either wall to its nearest weight being one half that between any two of the weights; or,

$$EA = CD = \frac{1}{2}AB = \frac{1}{2}BC = \frac{1}{6}l$$

The line EFGHD is obtained as directed for Fig. 38. It may also be obtained analytically, thus:

First. The line AF, or the effect at A of the three weights, equals the sum of the three lines $A\mathcal{F}$, AO and AN.




Fig. 39.

Let EA = CD = t, and AD = h, then t + h = l, and (Art. 56)

$$A\mathcal{F} = L\frac{t \times h}{l} = \frac{1}{6}L\frac{th}{l}$$

as per Art. 195.

$$AO = L\frac{BD \times EA}{l} = L\frac{\frac{3}{8}h \times t}{l} = \frac{3}{8}L\frac{th}{l}$$

$$AN = L\frac{CD \times EA}{l} = L\frac{\frac{1}{8}h \times t}{l} = \frac{1}{8}L\frac{th}{l}$$
or
$$A\mathcal{F} + AO + AN = (\frac{1}{8} + \frac{3}{8} + \frac{1}{8})L\frac{th}{l} = \frac{3}{8}L\frac{th}{l} = AF$$

Second. The line BG, or the effect at B of the three weights, is equal to the sum of the line BK and twice the line BQ.

Let
$$EB = t$$
, $BD = h$, and $t + h = l$; then
$$BK = L\frac{t \times h}{l}$$

$$BQ = L\frac{EA \times BD}{l} = L\frac{\frac{1}{8}t \times h}{l} = \frac{1}{8}L\frac{th}{l}$$
and
$$BK + 2BQ = L\frac{th}{l} + 2 \times \frac{1}{8}L\frac{th}{l} = \frac{1}{8}L\frac{th}{l} = BG$$

FOUR EQUAL WEIGHTS SYMMETRICALLY DISPOSED. 143

Third. The effect at C produced by the three weights is equal to that at A.


We have, then,

for the total effect at
$$A$$
, $AF = \frac{1}{4}L\frac{th}{l}$

" " B , $BG = \frac{1}{4}L\frac{th}{l}$

" " C , $CH = \frac{1}{4}L\frac{th}{l}$

197.—Graphical Strains by Four Equal Weights Equably Msposed.—When there are four equal weights, as in Fig. 40, imilarly disposed as in Fig. 39, the effect at A is,



or the total effect at A, of the four weights, is

$$(7+5+3+1)L\frac{ht}{l} = +L\frac{ht}{l} = AF$$

The effect at B is,

from load at
$$A$$
,
$$L \frac{\frac{1}{8}t \times h}{l} = \frac{1}{8}L \frac{ht}{l}$$
" B ,
$$L \frac{t \times h}{l} = \frac{1}{8}L \frac{ht}{l}$$
" C ,
$$L \frac{\frac{3}{8}h \times t}{l} = \frac{1}{8}L \frac{ht}{l}$$
" D ,
$$L \frac{\frac{1}{8}h \times t}{l} = \frac{1}{8}L \frac{ht}{l}$$

or the total effect at B, of the four weights, is

$$(\frac{1}{8} + \frac{5}{6} + \frac{3}{6} + \frac{1}{6})L\frac{ht}{l} = \frac{32}{16}L\frac{ht}{l} = BG$$

The effect at C is equal to that at B, and the effect at D is equal to that at A.

198.—Graphical Strains by Five Equal Weights Equably Disposed.—When there are five equal weights, as in Fig. 41, similarly disposed as those in Fig. 39, the effect at A is,

from load at
$$A$$
,
$$L\frac{h \times t}{l} = \frac{1}{6}L\frac{ht}{l}$$

$$" B,
$$\frac{1}{6}h \times t\frac{L}{l} = \frac{1}{6}L\frac{ht}{l}$$

$$" C,
$$\frac{1}{6}h \times t\frac{L}{l} = \frac{1}{6}L\frac{ht}{l}$$

$$" D,
$$\frac{3}{6}h \times t\frac{L}{l} = \frac{3}{6}L\frac{ht}{l}$$

$$" M,
$$\frac{1}{6}h \times t\frac{L}{l} = \frac{1}{6}L\frac{ht}{l}$$$$$$$$$$

Fig. 41.

or the total effect at A, of all the weights, is

$$(\frac{1}{3} + \frac{7}{3} + \frac{6}{3} + \frac{3}{3} + \frac{1}{3})L\frac{ht}{l} = \frac{3}{3}L\frac{ht}{l} = AF$$

The total effect at B is,

from load at A, $\frac{1}{3}t \times h\frac{L}{l} = \frac{1}{3}L\frac{ht}{l}$ " B, $h \times t\frac{L}{l} = \frac{1}{4}L\frac{ht}{l}$ " C, $\frac{1}{4}h \times t\frac{L}{l} = \frac{1}{4}L\frac{ht}{l}$ " D, $\frac{1}{4}h \times t\frac{L}{l} = \frac{1}{4}L\frac{ht}{l}$ " M, $\frac{1}{4}h \times t\frac{L}{l} = \frac{1}{4}L\frac{ht}{l}$

or the total effect at B, of all the weights, is

$$(\frac{1}{8} + \frac{7}{4} + \frac{9}{4} + \frac{9}{4} + \frac{1}{4})L\frac{ht}{l} = \frac{11}{8}L\frac{ht}{l} = BG$$

The total effect at C is,

from load at
$$A$$
,
$$\frac{1}{8}t \times h \frac{L}{l} = \frac{1}{8}L \frac{ht}{l}$$
" B ,
$$\frac{1}{8}t \times h \frac{L}{l} = \frac{1}{8}L \frac{ht}{l}$$
" C ,
$$h \times t \frac{L}{l} = \frac{1}{8}L \frac{ht}{l}$$
" D ,
$$\frac{1}{8}h \times t \frac{L}{l} = \frac{1}{8}L \frac{ht}{l}$$
" M ,
$$\frac{1}{8}h \times t \frac{L}{l} = \frac{1}{8}L \frac{ht}{l}$$

or the total effect at C, of all the weights, is

$$(\frac{1}{8} + \frac{3}{8} + \frac{5}{8} + \frac{3}{8} + \frac{1}{8})L\frac{ht}{l} = \frac{13}{8}L\frac{ht}{l} = CH$$

The effects produced at D and M are, respectively, like those at B and A.

199.—General Results from Equal Weights Equably Disposed.—In looking over the results here obtained, it will be seen that in each case the effect is equal to $gL\frac{ht}{l}$, in which g is put for the numerical coefficient, L for any one of the equal weights with which the beam is loaded, t and h the respective distances from the point at which the strain is being measured to the ends of the beam, and l for the length of the beam. All of these are simple quantities except the coefficient g, and this it will be shown is subject to a certain law and may be stated in general terms.

200.—General Expression for Full Strain at First Weight.

—The coefficient g is a fraction, having its numerator and denominator both dependent upon the number of weights upon the beam.

Let us first consider the value of the *numerator* in measuring the effect of the weights at A, the location of the first weight from the left.

With three weights, g, the coefficient, was $\frac{1}{5} + \frac{3}{5} + \frac{5}{5} = \frac{9}{5}$, the numerators being 1 + 3 + 5 = 9.

With four weights, g was equal to $\frac{1+3+5+7}{7} = \frac{16}{7}$, the numerators being 1+3+5+7=16.

With five weights, g was equal to $\frac{1+3+5+7+9}{9} = \frac{25}{9}$, and the numerators 1+3+5+7+9=25.

In general, we shall find that the numerator of the fraction g, is in all cases equal to the sum of an arithmetical progression comprising the odd numbers 1, 3, 5, etc., to n terms; n being put to represent the number of weights upon the beam, the first term being unity, and the last being 2n-1.

To find the sum of this progression, we have

$$S = \frac{(a+l)n}{2}$$

in which S = the sum, a = the first term, l = the last term, and n = the number of terms; or

$$S = \frac{\overline{1 + (2n - 1)n}}{2} = \frac{n + 2n^{2} - n}{2} = n^{2}$$

Hence, the numerator of the coefficient of the expression showing the effect of any number of weights at the location, A, of the first weight, is equal to the square of the number of weights; thus, when there are

2 weights,
$$n = 2$$
, and the numerator $= 2^{2} = 4$
3 " $n = 3$, " $= 3^{2} = 9$
4 " $n = 4$, " $= 4^{2} = 16$
5 " $n = 5$, " $= 5^{2} = 25$
6 " $n = 6$, " $= 6^{2} = 36$

and so for any number of weights.

In considering the value of the *denominator* of g it will be observed that it is derived by taking the value of h in each case in terms of t. With three weights, h = 5t; with four weights, h = 7t; and with five weights, h = 9t; so that in general, h = (2n-1)t. The denominator of the fraction generally, therefore, is 2n-1.

The value of the coefficient is, consequently, $\frac{n^2}{2n-1}$, and the full effect at A of any number of equal weights equably disposed upon a beam is $\frac{n^2}{2n-1}L\frac{ht}{l}$.

201.—General Expression for Full Strain at Second Weight.—For the effect at the location B we have the expression $pL\frac{ht}{l}$; in which the same quantities occur as before, except in the case of the coefficient p.

This coefficient is composed of two classes of fractions. The first of these is based upon the relation between the distances EA and EB, and since EA is in all cases equal to $\frac{1}{3}$ of EB, therefore this part of the coefficient p will be equal to $\frac{1}{3}$.

In the second fraction of the coefficient, the numerator is, as in the case at A, equal to the sum of an arithmetical progression, but extending one less in the number of the terms, so that in place of n^2 we put $(n-1)^2$.

The denominator is found by taking n-1 for n, or 2(n-1)-1, equal to 2n-3, for 2n-1. The value of

this fraction is therefore $\frac{(n-1)^2}{2n-3}$. To this, adding the first fraction, we have

$$p = \frac{1}{8} + \frac{(n-1)^2}{2n-3}$$

and for the full effect at B, of all the weights,

$$\left(\frac{1}{8} + \frac{(n-1)^2}{2n-3}\right) L \frac{ht}{l}$$

From the above, the value of the coefficient p is as follows:

with 2 weights,
$$p = \frac{1}{8} + \frac{(2-1)^3}{(2\times 2) - 3} = \frac{1}{8} + \frac{1}{1} = \frac{4}{8}$$
" 3 "
$$p = \frac{1}{8} + \frac{(3-1)^2}{(2\times 3) - 3} = \frac{1}{8} + \frac{4}{8} = \frac{15}{15}$$
" 4 "
$$p = \frac{1}{8} + \frac{(4-1)^3}{(2\times 4) - 3} = \frac{1}{8} + \frac{9}{6} = \frac{39}{15}$$
" 5 "
$$p = \frac{1}{8} + \frac{(5-1)^3}{(2\times 5) - 3} = \frac{1}{8} + \frac{16}{7} = \frac{55}{21}$$
" 6 "
$$p = \frac{1}{8} + \frac{(6-1)^2}{(2\times 6) - 3} = \frac{1}{8} + \frac{25}{9} = \frac{84}{27}$$

The numerators of these results are in the order of 2n, 5m, 8m, 11m and 14n; the numerals differing by 3. The denominators are the products of 1, 3, 5, 7 and 9, each by 3. We may continue therefore the values to any number of weights by following these laws, thus

for 7 weights,
$$p = \frac{17 \times 7}{11 \times 3} = \frac{119}{33}$$

for 8 weights, $p = \frac{20 \times 8}{13 \times 3} = \frac{160}{39}$

or, in general, the effect at B for any number of weights may be had directly from the previous expression.

202.—General Expression for Full Strain at Any Weight.—For the sum of effects at C, it is seen that we have $kL\frac{ht}{l}$, and it can be shown that the coefficient k is the sum of two fractions—namely, $\frac{1}{2}$ and $\frac{(n-2)^2}{2n-5}$ or

$$k = \frac{4}{8} + \frac{(n-2)^2}{2n-5}$$

For the effect at D we have

$$u = \frac{9}{7} + \frac{(n-3)^2}{2n-7}$$

For the effect at E we have

$$q = \frac{16}{9} + \frac{(n-4)^2}{2n-9}$$

or, putting them in sequence, we have

at
$$A$$
 the effect $g = \frac{9}{1} + \frac{(n-0)^2}{2n-1}$
" B " " $p = \frac{1}{8} + \frac{(n-1)^2}{2n-3}$
" C " " $k = \frac{4}{8} + \frac{(n-2)^2}{2n-5}$
" D " " $u = \frac{9}{7} + \frac{(n-3)^2}{2n-7}$
" E " " $q = \frac{16}{9} + \frac{(n-4)^2}{2n-9}$
" F " " $v = \frac{25}{11} + \frac{(n-5)^2}{2n-11}$

GENERAL EXPRESSION-TOTAL STRAIN AT ANY WEIGHT. 151

and so for any number of weights upon one end of the beam.

An examination of this series shows that in the first of the two fractions the numerator is equal to the square of the number of weights preceding the one under consideration; for instance, at A, where there are no weights preceding, we have the numerator o; at B there is one weight preceding, and hence the numerator is 1' equals 1; at C there are two weights preceding, hence the numerator equals 2' equals 4: at D there are three weights, hence the numerator equals 3' equals 9; etc. For the denominator of the first fraction we have, for the several cases in consecutive order, the values 1, 3, 5, 7, etc.; an arithmetical series of the odd numbers.

In the second fraction we have a numerator equal to the square of the difference between n and the number of weights preceding the one at which the strain is being measured; and a denominator of 2n minus the denominator of the first fraction.

Let r represent in any case the number of weights preceding the one at the location of which we wish to know the strain. Then we shall have, as the coefficient of the effect at that point,

$$x = \frac{r^{s}}{2r+1} + \frac{(n-r)^{s}}{2n - (2r+1)}$$

and for the full effect, or the destructive energy,

$$D = L_{\tilde{I}}^{ht} \left(\frac{r^*}{2r+1} + \frac{(n-r)^*}{2n - (2r+1)} \right)$$
 (68.)

which L represents one of the equal weights with which the beam is loaded; h the distance from the weight at which the strain in the beam is being measured to the right-hand and of the beam; t the distance from the same point to the left-hand end; t = h + t the length of the beam between sup-

ports; n the number of equal weights equally disposed upon the beam, as in Fig. 41; and r the number of weights between the point where the strain is measured and the left-hand end of the beam, not including the one at the point where the strain is measured.

203.—Example.—What is the strain at the fifth weight from the left-hand end of a beam 22 feet long, loaded with 11 weights of 100 pounds each; the weights placed at equal distances from centres, and the distance from each end of the beam to the centre of the nearest weight being equal to half the distance between the centres of any two adjoining weights? Here the distance between centres of weights will be 2 feet, t will equal 9 feet, and h will equal 13 feet, L = 100, n = 11, and r = 4.

From these the strain at the fifth weight will be (form. 68.)

$$D = 100 \times \frac{13 \times 9}{22} \left(\frac{4^2}{8+1} + \frac{(11-4)^2}{22-(8+1)} \right) = 2950$$

QUESTIONS FOR PRACTICE.

- 204.—A beam 12 feet long is loaded at 4 feet from the left-hand end with 4000 pounds. What is the strain at that point?
- 205.—What are the strains, respectively, at 2, 4, and 6 feet from the right-hand end?
- **206.**—A beam 14 feet long is loaded with two weights; one, A', weighing 3000 pounds, is located at 4 feet from the left-hand end; the other, B', weighing 5000 pounds, is at 6 feet from the right-hand end.

What strain is caused by these two weights at the point A?

What strain is caused at B?

207.—In the above beam what strain is caused by the two weights at a point 2 feet from the left-hand end?

What strain is caused at a point 2 feet from the righthand end?

What strain is produced at the middle of the beam?

208.—A beam 20 feet long is loaded with three weights; one, A', of 3000 pounds, at 3 feet from the left-hand end; one, B', of 2000 pounds, at 11 feet from the same end; and the third weight, C', of 4000 pounds, at 4 feet from the right-hand end.

What is the full effect of the three weights at the location of each weight, at 2 feet from the left-hand end, at 2 feet from the right-hand end, at 6 feet from the same end, and at the middle of the beam?

209.—A beam 16 feet long is loaded with 20 weights of 100 pounds each, the weights being equally distributed.

What strain do these weights produce in the beam at the ninth weight from one end?

CHAPTER X.

STRAINS FROM UNIFORMLY DISTRIBUTED LOADS.

Veights and a Thoroughly Distributed Lond.—The distribution of the load upon a beam, as shown in Figs. 39, 40 and 41, is essentially that of a uniform distribution over the entire length of the beam. For if the beam be divided into as many parts as there are weights, by vertical lines located midway between each two weights, it is seen that the parts into which these lines divide the beam are all equal one with another, and the weight upon each part is located in a tertical line passing through the centre of gravity of that the Hence this beam, taken with the loads upon it, is an exparently parallel case with a beam having an equally distributed load.

An application of formula (68.), however, will show that we case is that of a beam loaded with a series of concentrated another, and not with a thoroughly distributed load, although closely approximates the latter. We find that the results computations made with this formula differ according to mumber of weights upon the beam, but approach a certain limit as the number of weights is increased; a limit which is that of a beam with an equally distributed load.

211.—Demonstration.—For example, let us find by formula 660, the effects at the middle of the beam under ulering numbers of weights.

What is the full effect of the three weights of each weight, at 2 feet from the left-hand (from the right-hand end, at 6 feet from the sai the middle of the beam?

209.—A beam 16 feet long is loaded with 100 pounds each, the weights being equally di What strain do these weights produce in t ninth weight from one end?



158 STRAINS FROM UNIFORMLY DISTRIBUTED LOADS. CHAP. X.




Fig. 42.

To do this we may proceed as follows: Let the ordinate AG represent by scale the strain caused at A by a small weight A', concentrated at A. Then will $E\mathcal{F}$ represent (Art. 190) the effect of A' at E. Again, let the ordinate BH represent by scale the strain at B caused by a small weight B', concentrated at B. Then will EK represent the effect of B' at E. The sum of these, $E\mathcal{F} + EK$, will equal the joint effect of the weights A' and B' at E. Or (Art. 190)

$$D = \frac{A'hx}{l} + \frac{B'tx_{l}}{l}$$

Let the loads A' and B' be very small; equal to a small portion of the equally distributed load SRPT, and represented graphically by the thin vertical slices at A and B respectively, and let these slices be reduced to the smallest possible thickness. By the rules of the calculus we may represent the thickness of the slices, when infinitely reduced by dx, the differential of x, or rate of increase. If e be put to represent the weight per lineal foot of the equally distributed load SRPT, then edx will represent the weight of the thin slice at A, or equal A'. So also edx, will represent the weight of the slice at B, or equal B'.

Substituting these values for A' and B' in the above expression, we obtain

$$D = \frac{ehxdx}{l} + \frac{etx_idx_i}{l} = \frac{e}{l} (hxdx + tx_idx_i)$$

This is the effect at E of the two loads at A and B, but these loads are infinitesimally small, therefore the expression is to be considered merely as the sum of the differential, or rates of increase of the strains produced by the two parts into which the whole of the equally distributed load RSTP is divided by the ordinate EF. The strain itself is to be had by the integral which is to be derived from the above differential of the strain. Therefore, by integration, we have (Arts. 462 and 463)

$$\int \frac{e}{l} \left(hxdx + tx_i dx_i \right) = \frac{e}{l} \left(\frac{1}{2} hx^2 + \frac{1}{2} tx_i^2 \right) = y$$

By integrating between x = 0 and x = t, also between $x_i = 0$ and $x_i = h$, or making the integral definite, we have

$$y = \frac{e}{l} \left(\frac{1}{2}ht^2 + \frac{1}{2}th^2 \right)$$

$$y = \frac{et}{2l} (ht + h^2) = EF$$

$$h = l - t$$

$$ht = (l - t) t$$

$$h^2 = (l - t)^2$$

therefore and

but

therefore

$$ht+h^2=(l-t)t+(l-t)^2=lt-t^2+l^2-2lt+t^2=l^2-lt$$

160 STRAINS FROM UNIFORMLY DISTRIBUTED LOADS. CHAP. X.

and the formula

$$y = \frac{et}{2l} (ht + h^s)$$
 becomes
$$y = \frac{et}{2l} (l^s - lt)$$

$$y = \frac{1}{2}et (l - t)$$
 (70.)

This result gives the value of the ordinate y, drawn at any point, and is comparable with the formula for the parabola*, in which l equals the base, and the maximum ordinate, y, equals the height. Therefore, if the curve line RFDP be that of the parabola, it will limit all the ordinates, y, which may be drawn from the line RP.

In the above discussion e was put for the weight of one foot lineal of the load, therefore the whole load U equals cl, or $e = \frac{U}{l}$. If in formula (70.) we substitute for e this value of it, we have

$$y = \frac{1}{2}U\frac{t}{l}(l-t)$$

$$y = \frac{1}{2}U\frac{ht}{l} \tag{71.}$$

and when $h = t = \frac{1}{2}l$ we have, for the ordinate at its maximum or at the centre,

$$y = \frac{1}{2}U\frac{\frac{1}{2}l \times \frac{1}{4}l}{l} = \frac{1}{2} \times \frac{Ul}{4}$$

$$y = \frac{1}{8}Ul \qquad (72.)$$

^{*} For here we have an ordinate to the curve from any point in the base, which is in proportion to the rectangle $[t \times (t-t)]$ of the two parts into which the base is divided by that point, a property of the parabola. (See Cape's Mathematics, 1850, Vol. II., p. 48.)

We thus see that the true value of the coefficient discussed in Art. 211 is equal to one half.

This result $(\frac{1}{8}Ul)$ is the effect at the middle of the beam, and shows that an equally distributed load will need to be twice the weight of a concentrated load to produce like effects upon any given beam; a like result with that which was obtained in another way at Art. 59.

213. — Distinction Shown by Scales of Strains.—By the calculus, the coefficient, as has just been shown, is equal to $\frac{1}{2}$, but those by formula (69.) exceed $\frac{1}{2}$ by a certain fraction (Art. 211).

A comparison of the scales of strains in Figs. 41 and 42 will show that the line limiting the ordinates is not a parabola, but a polygonal line. In proportion to the increase in the number of the weights, and their consequent diminution in size and distance apart, this polygonal figure approximates the parabolic curve; and in like proportion do the corresponding coefficients approach the coefficient obtained by the calculus; until finally, when the number of the weights becomes infinite, or the load is absolutely an equably distributed one, then the coefficients are identical. The difference between the two expressions is that which is shown between the areas of the polygonal and parabolic figures.

214.—Effect at Any Point by an Equally Distributed Lead.—One other lesson may be learned from this discussion.

It has been shown (Arts. 59 and 61) that the effect at the middle of the beam, from an equably distributed weight, is equal to that which would be produced by just one half of the weight if concentrated there; and now we see (Arts. 211 and 212) that this proportion holds good, not only at the middle of the beam, but also at any point in its length.

162 STRAINS FROM UNIFORMLY DISTRIBUTED LOADS. CHAP. X.

The expression (71.) just obtained,

$$y = \frac{1}{2}U\frac{ht}{l}$$

gives the effect produced by an equally distributed load at any point in the beam.

It was shown (Art. 56) that the effect at any point of a load concentrated at that point, is equal to

$$W \frac{mn}{l} = W \frac{ht}{l}$$

Now when the effects in the two cases are equal, we have

 $\frac{1}{2}U\frac{ht}{l} = W\frac{ht}{l}$ $\frac{1}{2}U = W$

or,

showing that when the effects at any point are equal, the concentrated load is equal to just half of the uniformly distributed load.

215.—Shape of-Side of Beam for an Equably Distributed Load.—We have seen (form. 71.) that the effect at any point in a beam from an equably distributed load is

$$y = \frac{1}{2}U\frac{ht}{l}$$

and that the curve drawn through the ends of a series of ordinates obtained by this formula is a parabola (Art. 212, foot note).

From this may easily be derived the form of the depth of a beam (the breadth being constant), which shall be equally strong throughout its length to bear safely an equably distributed load. The formula (71.) gives the strain at any point, and when put equal to the resistance (Art. 35) is

$$\frac{1}{2}U\frac{ht}{l} = Sbd^2$$

Substituting for S its value $\frac{B}{4}$ we have for the safe weight (Art. 73)

$$\frac{2Uaht}{l} = Bbd^2$$

from which

$$d^2 = \frac{2 \, Uaht}{Bbl}$$


This gives the square of the depth at any point, and when $h = t = \frac{1}{2}l$ we have

$$d^2 = \frac{Ual}{2Bb} \tag{73.}$$

equals the square of the depth at the middle.

Now make CD, Fig. 43, equal by formula (73.) to d^2 equals $\frac{Ual}{2Bb}$, and through D draw the parabolic curve RDFP. Across the figure draw a series of ordinates, as CD and EF. Then any one of these ordinates is equal to d^2 or the square of the required depth of the beam at the location of that ordinate. To find d, the depth, at each of these points, we have but to make CG equal to the square root of CD, and EH equal to the square root of EF, and in like manner find corresponding points to G and G on each ordinate, and draw the curve line G and G through these points; then this curve line will define the top edge of a beam G being the bottom edge), which shall be equally strong at all points to bear safely the equably distributed load.

164 STRAINS FROM UNIFORMLY DISTRIBUTED LOADS. CHAP. X.



216.—The Form of Side of Beam a Semi-cilipse.—The form of the top edge of the beam as obtained in the last article is elliptical, as may be shown thus:

The equation to the ellipse, the co-ordinates taken as in Fig. 43, is*

$$u^{s}=\frac{\dot{b}^{s}}{a^{s}}\left(2ax-x^{s}\right)$$

in which x (= RE, Fig. 43) is the abscissa, u (= EH) is its ordinate, $a (= RC = \frac{1}{2}l)$ is the semi-transverse diameter, and $b (= CG = \sqrt{CD})$ is the semi-conjugate diameter: therefore $b^a = \overline{CG}^a = CD$ and, by formula (72.), in which CD, the height of the parabola at the middle in Figs. 42 and 43, is represented by y, at its maximum we have $y = \frac{1}{2}Ul$. In the above value of u^a substituting for a, and b, their values as here shown, we have

$$u^{a} = \frac{U}{2l} (lx - x^{a})$$

and since $lx - x^2 = x (l - x) = th$ of Fig. 42, therefore

$$u^4 = \frac{1}{4}U\frac{ht}{l}$$

By referring to formula (71.) it will be seen that this value of u^{s} is identical with that given for y, the ordinate to the

^{*}Cape's Mathematics, Vol. II., p. 21, putting # for y.

parabola, consequently $y = u^s$, and therefore the curve RGHP is elliptical.

To obtain the shape of the beam, instead of drawing a series of ordinates in a parabola, and taking the square root of each ordinate, we may at once draw the semi-ellipse RGHP.

Formula (73.) gives the value of d^* at middle, therefore for d at middle make CG, Fig. 44, equal to

$$d = \sqrt{\frac{Ual}{2Bb}} \tag{74.}$$

and through RGP draw a semi-ellipse, then RGPCR will be the shape of the beam.





Fig. 44.

As an example:—With a beam of white pine 10 feet long, 5 inches broad, and loaded with 10,000 pounds equably distributed, and with a factor of safety a=4, what should be the height at the middle?

Formula (74.) becomes

$$d = \sqrt{\frac{10000 \times 4 \times 10}{2 \times 500 \times 5}} = 8.94$$

or the height of the beam is to be 9 inches, and the form of the side is to be that of a semi-ellipse, with 10 feet for its transverse diameter, and 9 inches for its semi-conjugate diameter.



QUESTIONS FOR PRACTICE.

- 217.—In a scale of strains for an equally distributed load, what curve forms the upper edge?
- 218.—In a beam, 10 feet long, having 1000 pounds equably distributed over its length, what are the strains at 2, 3, and 4 feet respectively, from one end?
- 219.—What should be the depth at the middle of this beam, if it be of white pine, if the breadth be made equal to of the depth, and if 4 be the value of the factor of safety?
- 220.—In order that the beam be of equal strength throughout its length, of what form should the upper edge be when the lower edge is straight, and the beam of parallel breadth throughout?

CHAPTER XI.

STRAINS IN LEVERS, GRAPHICALLY EXPRESSED.

ART. 221.—Scale of Strains for Promiscuously Loaded ver.—In Fig. 45 we have a semi-beam loaded promiscusly with the concentrated weights A, B, C and D.





Fig. 45.

 In the construction of this figure, each triangle of strains is made upon the principle shown in Art. 168, and the several triangles are successively added. An ordinate crossing all these triangles must necessarily be equal to the sum of the strains at its location caused by all the weights.

The strain at any ordinate may also be found arithmetically, by taking the sum of the products of each weight into its horizontal distance to the ordinate, measured from the weight towards the wall; those weights which occur between the ordinate and the wall not being considered, as they add nothing to the strain at the ordinate.

222.—Strains and Sizes of Lever Uniformly Loaded.— When the weights are equably distributed over a semi-beam, the equation to the curve CFA, Fig. 46, limiting the ordi-



nates of strains, may be found by the use of the calculus, as in Art. 212; for if $ABH\mathcal{F}$ be taken to represent the equably distributed load, then in considering the effect at the wall of a very thin slice of this load, as EG (reducing it infinitely) we obtain the differential of the strain.

Let AE = y, then dy, its differential, may be taken as the thickness of the thin slice of the load at EG, when reduced to its smallest possible limits. Putting e for the weight of a lineal foot of the load, then edy will equal the weight of the thin slice. The effect or moment of this slice,

at the wall, equals its weight into its distance from the wall, therefore we have for the differential of the moment

$$edy \times (n-y) = du$$
 or,
 $endy - eydy = du$

The integral of this expression is (Arts. 462 and 463)

$$\int (endy - eydy) = eny - \frac{1}{2}ey^2 = u$$

Applying this, or integrating between y equals zero and y equals n, we have

$$en^{2} - \frac{1}{2}en^{2} = \frac{1}{2}en^{2} = BC = u$$

or for the strain at the wall, BC,

$$u = \frac{1}{2}en^2 \tag{75.}$$

and for the strain at any point, E,

$$x = \frac{1}{2}ey^{2} \tag{76.}$$

From this latter, by transposing, we have

$$y^* = \frac{2}{e}x$$

which is the equation to the parabola;* a proof that the curve CFA is that of a semi-parabola, in which A is the apex, and CD the base.

These considerations pertain to the scale for strains. A scale for depths may be had by proceeding as follows:

The value of e in formulas (75.) and (76.) is, from U = cn (in which U equals the whole load upon the semi-beam)

For, putting $\frac{1}{e} = p$, then $y^2 = \frac{2}{e}x$ becomes $y^2 = 2px$, the equation to the parabola. See Cape's Mathematics, Vol. II., p. 47.

170 STRAINS IN LEVERS, GRAPHICALLY EXPRESSED. CHAP. XI.

 $e = \frac{U}{n}$. Substituting this value for e in formula (75.) we have

$$u = \frac{1}{2} \frac{U}{n} n^s = \frac{1}{2} U n$$

Putting this equal to the resistance (Art. 35) gives us

$$\frac{1}{2}Un = Sbd^2$$

and substituting for S its equivalent $\frac{1}{2}B$, and inserting the symbol for safety (Art. 73), we have

$$4a_{\frac{1}{2}}Un = Bbd^{2}$$
 or,
$$2Uan = Bbd^{2}$$

[which agrees with formula (20.)] for the size of the semibeam at the wall.

Again, subjecting formula (76.) to like changes, we have for the size of the semi-beam at any point

$$2U\frac{a}{n}y^{s} = Bbd^{s} \tag{77.}$$

in which y is the distance of that point from the free end of the semi-beam.

223.—The Form of Side of Lever a Triangle.—If a semibeam, subjected to an equally distributed load, be of rectangular section throughout, and of constant breadth, then, in order that it may be equally strong at all points of its length, the form of its side must be a triangle.

This may be shown as follows:

Formula (77.) gives by transposition

$$d^{2} = \frac{2Ua}{Bbn}y^{2} \tag{78.}$$

in which the coefficient $\frac{2Ua}{Bbn}$, for the case above cited is

composed of constant factors; hence d^2 will vary as y^2 , and therefore d will be in proportion to y. From this, formula (78.) is shown to be the equation to a straight line, and in such form that when y equals zero, d also becomes zero. From this, the side elevation of the semi-beam must be a triangle, with the depth at the wall (for then y becomes equal to π) equal [from formula (78.) or (20.)] to


$$d = \sqrt{\frac{2Uan}{Bb}} \tag{79.}$$

As an example, let it be required to define the depth of a semi-beam of white pine, 10 feet long and 5 inches broad, carrying 5000 pounds equably distributed along its length, and with a factor of safety, a, equal to 4.

Formula (79.) becomes

$$d = \sqrt{\frac{2 \times 5000 \times 4 \times 10}{500 \times 5}} = 12.65$$

This is the depth at the wall, as at AC, Fig. 47, in which AB is the length of the semi-beam. By joining B and C we have ABC for the shape of the side of the required semi-beam.



224.—Combinations of Conditions.—The forms of strain scales for loads under various simple conditions having been defined, we may now consider those arising from combinations of conditions.

225.—Strains and Dimensions for Compound Load.— Take the case of a semi-beam or lever, carrying an equably distributed load, and also a concentrated load at the free end.

172 STRAINS IN LEVERS, GRAPHICALLY EXPRESSED. CHAP. XI.

Let the line AB, Fig. 48, represent the length of the




FIG. 48.

lever, R a weight suspended from its free end, and DC the face of the wall into which the lever is secured. In formula (75.) we have the strain at the wall, in which ϵ equals the weight per lineal foot of the load, or $\epsilon = \frac{U}{n}$. Substituting this value in the formula, we have $u = \frac{1}{2}Un$ as the strain at the wall; therefore make $AD = \frac{1}{2}Un$, and by the same scale make $AC = R \times AB = Rn$. Join B and C, and describe a semi-parabola from B to D with the apex at B, and the base extended from D parallel with AB; then any vertical ordinate drawn from the curve DB to the straight line CB will measure the strain at the point of intersection with the line AB.

The scale here given is that for strains; the scale for depths will now be shown.

We have seen in Art. 223 that the form of the side of a lever required by a uniformly distributed load is that of a triangle, the vertical base of which is determined by formula (79.); and it is shown at Art. 178, that the form, for a load concentrated at the end of a lever, is a semi-parabola, with its apex at the free end of the lever, and its base vertical at the fixed end and equal to

$$d = \sqrt{\frac{4Pan}{Bb}}$$

Therefore let AB, Fig. 49, be the length of the lever




Fig. 49.

secured at A in the wall DC, and having suspended from its free end, B, the weight P, and also carrying an equably distributed load ABEF. Make, by formula (79.),

$$AD = \sqrt{\frac{2Uan}{Bb}}$$

and join B and D; then ABD is the scale for the depths required by the equally distributed load U. Make, as above,

$$AC = \sqrt{\frac{4Pan}{Bb}}$$

and upon AC as a base and AB for the height describe the semi-parabola ABC, which gives the scale for depths due to the concentrated load P.

Now, an ordinate drawn at any point, as G, vertically across the combined scales of depths, as H to \mathcal{F} , measures, by scale, the required depth for the lever at the point G.

The length of any ordinate, as $H\mathcal{F}$, may be determined analytically thus. The portion of the ordinate representing the equably distributed load is, by formula (77.),

$$\sqrt{\frac{2Ua}{Rbn}y^{1}} = d$$

174 STRAINS IN LEVERS, GRAPHICALLY EXPRESSED. CHAP. XI.

For the remaining part of the ordinate we have formula (36.) (in which x is equivalent to the y of this case),


$$\sqrt{\frac{4Pa}{Bb}y} = d'$$

Adding these we have for the full length of the ordinate $H\mathcal{F}$, or for the depth at the point G,

$$d = \sqrt{\frac{2Ua}{Bbn}} y^2 + \sqrt{\frac{4Pa}{Bb}} y \tag{80.}$$

in which U is the weight equably distributed over the length of the lever; P, the weight concentrated at the end of the lever; n, the length of the lever; p, the horizontal distance from the free end of the lever to the location of the ordinate at which the strain is being measured; a, the factor of safety; b, the breadth of the lever, and B the resistance to rupture as per Table XX.

226.—Scale of Strains for Compound Loads.—Fig. 50 represents the case of a semi-beam like the preceding, except that the concentrated load is located at some other point than the extreme end.



The curve DB is found as in Fig. 48, and the line CE in the same manner as there, except that, in finding AC, the distance m from the wall to the weight R is to be substituted for n, the length of the lever.

227.—Scale of Strains for Promiseuous Load.—A semibeam, equably loaded, may also have to carry two or more concentrated loads. In this case, for the scale of strains we combine the methods required for the two kinds of loads, as in Fig. 51. Here AB represents the length of the semibeam; the curve DB, for the equably distributed load, is




Fig. 51.

obtained as in Art. 222; and the triangles for the concentrated weights are found as in Art. 221.

A vertical ordinate drawn anywhere across the figure, and terminated by the curve DB and the line $K\mathcal{F}HEB$, will measure the strain at the location of that ordinate. The depth of the beam at that point may be found by putting the strain as above found equal to-the resistance; or,

$$D = Sbd^{2}$$
 or (Art. 35),
$$D = \frac{1}{4}Bbd^{2}$$
 from which,
$$\sqrt{\frac{4Da}{Bb}} = d$$

in which D represents the destructive energy or the strain as shown by the length of the vertical ordinate obtained as above directed; a, the symbol for safety (Art. 73); B equals the resistance to rupture as per Table XX., and b and d are the breadth and depth, respectively—the breadth being constant.

QUESTIONS FOR PRACTICE.

228.—In a semi-beam 6 feet long, carrying 500 pounds at 2 feet from the wall, and 300 pounds at 5 feet from the wall, what are the respective strains at 1, 2, 3, 4 and 5 feet from the free end?

What is the strain at the wall?

- 229.—In a scale of strains for a semi-beam equably loaded, what curve limits the upper edge?
- 230.—A semi-beam, 8 feet long, is equably loaded with 100 pounds per foot lineal.

What is the strain produced at 5 feet from the free end?

- 231.—Of what form is the side of the last-named semibeam required to be, in order that the beam may be of equal strength at all points, the breadth being constant?
- 232.—In a semi-beam 7 feet long, carrying 1000 pounds at its free end, and 100 pounds per foot lineal, equably distributed, what are the respective strains at 3, 5 and 7 feet from the free end?
- 233.—In a semi-beam 10 feet long, carrying an equably distributed load of 1000 pounds, and concentrated loads of 800, 500 and 700 pounds, at the several distances of 3, 6 and 8 feet from the free end, what are the respective strains at 2, 4, 7 and 9 feet from the free end?


CHAPTER XII.

COMPOUND STRAINS IN BEAMS, GRAPHICALLY EXPRESSED.

ART. 234.—Equably Distributed and Concentrated Loads on a Beam.—We have now to consider the effect of compound weights upon whole beams.

Of this class we shall take first the case of an equably distributed weight, together with a concentrated one, as in Fig. 52.

In this figure the curve of strains RFDP for the equably distributed load is a parabola, with its apex at D. The



height CD is, by formula (72.), to be made equal to $\frac{1}{8}Ul$; and $H\mathcal{F}$, by the same scale, and by Art. 192, is to be made equal to $A'\frac{mn}{l}$. Join \mathcal{F} with R and with P. Then any vertical ordinate FG drawn across the figure, and termi-

nated by the curve RFDP at top, and by the line RP at bottom, will measure the strain, y, at E, the point of intersection of the ordinate with the line RP.

To obtain this strain analytically, we have, for the ordinate EF, formula (71.), which is (putting u for y)

$$u = \frac{1}{2}U\frac{ht}{l}$$

and, for the ordinate EG, formula (44.), which is (putting b' for y, A' for W and h for x)

$$b'=A'\frac{m}{l}h$$

Now, since b'+u=EG+EF=y, therefore

$$y = u + b' = \frac{1}{2}U\frac{ht}{l} + A'\frac{m}{l}h$$

$$y = \frac{h}{l}(\frac{1}{2}Ut + A'm)$$
 (81.)

equals the strain at any point between H and P.

To find the requisite depth of the beam at any point, the breadth being constant, we put the strain equal to the resistance, or (Art. 35)

$$y = Sbd' = 1Bbd'$$

or, for the safe weight,

$$4ay = Bbd^2$$
 from which


$$d = \sqrt{\frac{4ah\left(\frac{1}{2}Ut + A'm\right)}{Bbl}}$$
 (82.)

235.—Greatest Strain Graphically Represented.—To find the longest ordinate, and consequently the greatest strain, arising from the compound loads of Fig. 52, draw the tangent KL parallel with $\mathcal{F}P$; then an ordinate FG drawn from

he point of contact, F, will be greater than any other rhich may be drawn across the figure.

236.—Location of Greatest Strain Analytically Defined.

-The point of contact between a curve and its tangent is not asily found by mere inspection, but analytically its exact osition may be defined.



To do this, let (Fig. 52) $a' = H\mathcal{F}$, b' = EG, u = EF, = EP and h+t=l=RP.

We now have, from the similar triangles $H\mathcal{F}P$ and EGP,

$$n: a':: h: b' = \frac{a'h}{n}$$

From formula (70.), in which $y = u = \frac{1}{2}et(l-t)$, we have

$$u = \frac{1}{2}eh(l-h) = \frac{1}{2}ehl - \frac{1}{2}eh^{2}$$
 therefore
$$\frac{a'h}{n} + \frac{1}{2}ehl - \frac{1}{2}eh^{2} = b' + u = FG = y$$

$$y = h\left(\frac{a'}{n} + \frac{1}{2}el\right) - \frac{1}{2}eh^{2}$$
 (83.)

This is the value of an ordinate drawn at any point beween H and P. But it is required to find where this ordinate will be at its maximum. This may be done by the calculus. Obtain the differential of formula (83.), and placing it equal to zero, derive its integral; from which the value of h will be obtained. This represents the distance from P to the ordinate y, when at its maximum, and therefore determines the point E, the location of the ordinate, as required.

237.—Location of Greatest Strain Differentially Defined.

—First. For the value of h we are to find the differential of formula (83.) and put it equal to zero; thus:

$$dy = \left(\frac{a'}{n} + \frac{1}{2}cl\right)dh - \frac{1}{2}e \times 2hdh = 0$$

$$\left(\frac{a'}{n} + \frac{9}{2}cl\right)dh = ehdh$$

$$\frac{a'}{n} + \frac{1}{2}cl = eh$$

$$\frac{a'}{n} + \frac{1}{2}el = \frac{a'}{n} + \frac{1}{2}l = h$$

Now, since el = U, therefore $e = \frac{U}{l}$, and

$$h = \frac{a'}{\frac{U}{l}n} + \frac{1}{2}l = \frac{1}{2}l + \frac{a'l}{Un}$$

Again,

$$a' = H\mathcal{F} = A' \frac{mn}{l}$$

therefore

$$h = \frac{1}{2}l + \frac{A'\frac{mn}{l}l}{Un}$$

$$h = \frac{1}{2}l + \frac{A'm}{U} \tag{84.}$$

or the distance of the ordinate from the remote end of the beam is equal to half the length of the beam, plus a fraction which has for its numerator the product of the concentrated weight into its distance from the nearest bearing, and for its denominator the weight which is equably distributed along the beam.

This formula of the value of h is limited in its application to those cases in which n exceeds h in value. When, on the contrary, h exceeds n, then the longest ordinate is at the location of the concentrated weight, and n is to be substituted for h. The reason for this may be seen by an inspection of the figure.

238.—Greatest Strain Analytically Defined.—Second. To find the length of the ordinate y, we have, by formula (83.),

$$y = \frac{a'h}{n} + \frac{1}{2}\epsilon lh - \frac{1}{2}\epsilon h^2$$

and by substituting for l its value, $h + \dot{t}$,

$$y = \frac{a'h}{n} + \frac{1}{2}\epsilon h(h+t) - \frac{1}{2}\epsilon h^{2}$$

$$\dot{y} = \frac{a'h}{n} + \frac{1}{2}(\epsilon h^{2} + \epsilon ht) - \frac{1}{2}\epsilon h^{2}$$

$$y = \frac{a'h}{n} + \frac{1}{2}\epsilon ht$$

Now, $a' = A' \frac{mn}{l}$, and $e = \frac{U}{l}$, therefore

$$y = \frac{A'\frac{mn}{l}h}{n} + \frac{1}{2}U\frac{ht}{l}$$

$$y = \frac{h}{l}(A'm + \frac{1}{2}Ut)$$

which gives the greatest strain resulting from both the concentrated and distributed loads.

This formula is identical with formula (81.), obtained by another process.

239.—Example.—As an example, let it be required to find the location and length of the longest ordinate of strains produced by a load of 4000 pounds, concentrated at three feet from one end of a beam 16 feet long, together with a load of 3000 pounds, equably distributed over its length.

First. The location of the ordinate, or the value of h. This, from formula (84.), is

$$8 + \frac{4000 \times 3}{3000} = 8 + 4 = 12 = h$$

or the longest ordinate is situated within one foot of the location of the concentrated weight.

Second. The amount of strain at this ordinate. This, by the above formula, is

$$y = \frac{12}{16} (\overline{4000 \times 3} + \overline{\frac{1}{2} \times 3000 \times 4}) = 13500$$

or the greatest resulting strain at any one point of the combined weights equals 13,500 pounds.

240.—Dimensions of Beam for Distributed and Concentrated Loads.—The amount of strain just found is the actual moment of the loads. Putting this equal to the resistance (Art. 35), we have, for the safe weight,

$$a\frac{h}{l}(A'm + \frac{1}{2}Ut) = Sbd^2 = \frac{1}{2}Bbd^2 \qquad \text{or}$$

$$4a\frac{h}{l}(A'm+\frac{1}{2}Ut)=Bbd^{2} \qquad (85.)$$

which is a rule for obtaining the dimensions requisite for resisting effectually the greatest strain arising from the combined action of a concentrated and an equably distributed load; and in which A' equals the concentrated load, and U the equably distributed load, both in pounds; l is the length of the beam between bearings; m the distance from the concentrated weight to the nearer end of the beam; h the distance from the location of the greatest strain to the more distant end of the beam; and t equals l-h. l, m, h and t are all to be taken in feet, and the value of h is to be had from formula (84); care being exercised that when h exceeds n in value, then n is to be used in place of h, and m in place of t. In the latter case formula (85) becomes

$$4a \frac{n}{l} (A'm + \frac{1}{2}Um) = Bbd^{2}$$

$$4a \frac{mn}{l} (A' + \frac{1}{2}U) = Bbd^{2}$$
(86.)


241.—Comparison of Formulas, Here and in Art. 150.—Formula (29.), given in Art. 150, for a carriage beam with one header, is for a case similar to that of the last article, but is not strictly accurate. Instead of the two strains being taken at the same point, E (the location of the longest ordinate), as in Fig. 52, they are taken, the one for the concentrated load, at the location of this load, and the other, that for the equably distributed load, at the middle of the beam; or, the maximum strain for each load.

Taken in this manner the result is in excess of the truth, as $H\mathcal{F} + CD$ is greater than FG. The error is upon the safe side, the strains being estimated greater than they really are. In most cases this error would not be large, and the only objection to it would be that it requires a little more material in the beam. Formula (29.) may therefore be employed

in ordinary cases where a low priced material, such as wood for example, is used for the beams; but where a more costly material is involved, economy would dictate that the strain be not over-estimated, and that it be correctly obtained by the use of formula (85.) in Art. 240. (See also caution in Art. 88.)

242.—Location of Greatest Strain Differentially Defined.—In Fig. 53 we have a scale of strains, RABPF, by which is found the effect arising at any point in the length of the beam from two concentrated loads, together with an equably distributed load.

The curve RFP is a parabola (foot note, Art. 212) found as in Fig. 52, and the moment of the two concentrated loads equals AH at H and $B\mathcal{F}$ at \mathcal{F} , and is found as in Art. 194 and Fig. 37. FG is the ordinate for strains occurring between H and \mathcal{F} , and is defined thus:



Let $H\mathcal{F} = d'$, $E\mathcal{F} = x$, EG = v = b' + p, EF = u, AH = a', $B\mathcal{F} = b'$ and a' - b' = c. Then, from similar triangles,

$$d': c:: x: p = \frac{c}{d'}x$$

and, since x = h-s, v = b'+p and c = a'-b', therefore

$$p = \frac{c}{d'}(h-s)$$

and

$$v = b' + \frac{a'-b'}{d'}(h-s)$$

Formula (70.),

$$y = \frac{1}{2}et (l-t)$$

gives [putting ht for t(l-t) and u for y]

$$u = \frac{1}{2}eht$$

and since

$$y = u + v$$

consequently

$$y = \frac{1}{2}eht + b' + \frac{a'-b'}{d'}(h-s)$$
 (87.)

This is the value of the ordinate for the strain at any point between H and \mathcal{F} .

To obtain the *longest* ordinate which can be drawn here, proceed as in Arts. 235 to 237, and as follows:

First reduce formula (87.) thus,

$$\frac{1}{2}eht = \frac{1}{2}eh(l-h) = \frac{1}{2}ehl - \frac{1}{2}eh^2$$

$$\frac{a'-b'}{d'}(h-s) = \frac{a'-b'}{d'}h - \frac{a'-b'}{d'}s$$

then
$$v + u = y = \frac{1}{2}ehl - \frac{1}{2}eh^2 + b' + \frac{a'-b'}{d'}h - \frac{a'-b'}{d'}s$$

In this expression, rejecting the quantities unaffected by the variable h, we have, for the differential of y,

$$dy = \left(\frac{1}{2}el + \frac{a' - b'}{d'}\right)dh - ehdh = 0$$

or,

$$\left(\frac{1}{2}el + \frac{a'-b'}{d'}\right)dh = ehdh$$

or, its integral gives

$$h = \frac{1}{2}l + \frac{a' - b'}{d'e} \tag{88.}$$

243.—Greatest Strain and Dimensions.—The above gives the value of h. To obtain the value of y at its maximum take formula (87.). In this, for the value of a' we have AH, equal to the joint effect at H of the two concentrated loads; or, putting a' for the D of formula (51.),

$$a' = \frac{m}{I}(A'n + B's)$$

and for the value of b' (form. 52.)


$$b' = \frac{s}{l}(B'r + A'm)$$

The value of e (from el = U) is equal to $\frac{U}{l}$. By substituting this value for e we have

$$y = U \frac{ht}{2l} + b' + \frac{a'-b'}{d'}(h-s)$$
 (89.)

This equals the strain from the compound weights of Fig. 53, and is the same as (87.), for $\frac{U}{2l} = \frac{1}{2}e$.

Either formula will give the strain at any required point between H and \mathcal{F} (Fig. 53) by putting h equal to the dis-



tance between that point and P; but when the greatest strain is required, h must be obtained from its value in formula (88.). To obtain the dimensions in this case, we put the strain equal to the resistance, and have, with a as the factor for safe weight (Arts. 35 and 73)

$$a \left[U \frac{ht}{2l} + b' + \frac{a' - b'}{d'} (h - s) \right] = Sbd^{2} = \frac{1}{2}Bbd^{2}$$

$$4a \left[U \frac{ht}{2l} + b' + \frac{a' - b'}{d'} (h - s) \right] = Bbd^{2}$$
 (90.)

and from this formula may be found the dimensions required for resisting effectually the greatest strain in the beam, the value of h being derived from formula (88.).

244.—Assigning the Symbols.—It is important to observe here that of the two moments a' and b', a' designates the larger of the two, while m and n represent the distances from a' to the two ends of the beam, m being the distance to that support which may be reached without passing the

other weight. Again r and s are to be regarded as the distances from b' to the two ends of the beam; h and s dating from the same end of the beam as n; and as n is the greatest possible value of h, it is to be substituted for it when by the formula for h its value is found equal to or greater than n.

In order to ascertain which of the two moments a' and b' is the greater, a trial must be had by the use of the expressions in the last article designating their respective values. When the two concentrated weights are equal, then the nearer weight to the middle of the beam will produce the greater moment, and may at once be designated as a'.

245.—Example—Strain and Size at a Given Point.—As an example, let a beam, 10 feet long, be required to carry an equably distributed load of 100 pounds per foot lineal, a concentrated load of 2000 pounds at a point two feet from the left-hand end, and a second concentrated load of 800 pounds located at 3 feet from the right-hand end. What will be the resulting strain at 4 feet from the right-hand end?

Formula (87.) is

$$y = \frac{1}{2}eht + b' + \frac{a'-b'}{d'}(h-s)$$

equals the required strain.

In designating m and s we find (Art. 243) for the larger weight

$$\frac{2}{10}(\overline{2000 \times 8} + \overline{800 \times 3}) = 3680$$

and for the smaller

$$\frac{3}{10} (\overline{800 \times 7} + \overline{2000 \times 2}) = 2880$$

and hence (Art. 153) m=2 and s=3.

We now have e = 100, h = 4, l = 10, t = l - h = 6, m = 2, n = 8, s = 3, r = 7 and d' = 5.

$$\frac{1}{2}$$
eht becomes $\frac{1}{2} \times 100 \times 4 \times 6 = 1200$

With A' = 2000 and B' = 800, $a' = \frac{m}{l}(A'n + B's) =$ (as above) 3680, and $b' = \frac{s}{l}(B'r + A'm) =$ (as above) 2880 and a' - b' = 3680 - 2880 = 800.

We therefore have, as a resulting value of y in formula (87.),

$$1200 + 2880 + \frac{800}{5}(4-3) = 4240 = y$$

This equals the effect at 4 feet from the right-hand end produced by the three weights.

To find the dimensions of the beam at this point, make the strain just found equal to the resistance [see Art. 243 at formula (90.)], and we have

$$4a \times 4240 = Bbd^{2}$$

and, if a = 4 and B = 500 (see Table XX.), we have

$$bd^2 = \frac{4 \times 4 \times 4240}{500} = 135.68$$

Let b=3, then we have d=6.73; or, the beam at 4 feet from the right-hand end should be 3×6.73 inches in cross-section.

246.—Example—Greatest Strain.—Again, let it be required to show the *greatest* strain produced at any one point by the three weights of the last article.

The first dimension required here is that of h. For this we have, as per formula (88.),

$$h = \frac{1}{2}l + \frac{a'-b'}{d'e}$$

from which

$$h = 5 + \frac{800}{5 \times 100} \Rightarrow 6.6$$

This result being less than n, since n equals 8, is therefore the correct value of h, and from it we obtain (from t+h=l) $t=3\cdot 4$. Formula (89.) now gives

$$y = 1000 \frac{6.6 \times 3.4}{2 \times 10} + 2880 + \frac{800}{5} (6.6 - 3) = 4578$$

which is the required greatest strain.

247.—Example—Dimensions.—What sized beam of equal cross-section throughout would be required to carry safely the loads upon the beam of the last article, when B = 500 and a = 4?

The greatest strain at any point was found to be 4578 pounds, therefore

$$4a \times 4578 = Bbd^{2}$$

$$bd^{2} = \frac{4 \times 4 \times 4578}{500} = 146.5$$

and with b taken equal to 3, then d = 6.99. The beam must be 3×7 inches.

248.—Dimensions for Greatest Strain when h Equals n.—When, in formula (90.), h = n, or is greater than n, then t = m, h-s = d', and

$$b' + \frac{a' - b'}{d'}(h - s) = b' + \left(\frac{a' - b'}{d'} \times d'\right) = b' + a' - b' = a'$$

also,

$$U\frac{ht}{2l} = \frac{1}{2}U\frac{mn}{l}$$

and the formula becomes

$$4a\left(\frac{1}{2}U\frac{mn}{l}+a'\right)=Bbd^2$$

or, supplying the value of a' (Art. 243),

$$4a\left[\frac{1}{2}U\frac{mn}{l} + \frac{m}{l}(A'n + B's)\right] = Bbd^{2} \qquad (91.)$$

which is a rule for a beam carrying two concentrated loads and a uniformly distributed load, when h = n as above stated.

249.—Dimensions for Greatest Strain when h is Greater than **.—As an example under this rule, what are the breadth and depth of a Georgia pine beam 20 feet long, carrying 2000 pounds uniformly distributed over its whole length, 10,000 pounds at 7 feet from the left-hand end, and 8000 pounds at 5 feet from the right-hand end; the factor of safety being 4?

Here a=4, U=2000, l=20, B=850, m=7 and s=5 (since $7 \times 10,000 = 70,000$ exceeds $5 \times 8000 = 40,000$), m=13, r=15 and d'=8. The value of h is to be tested, to know whether it is equal to or greater than m.

By formula (88.), and Art. 243,

$$h = \frac{1}{2}l + \frac{a'-b'}{d'e} = \frac{1}{2}l + \frac{a'-b'}{\frac{d'}{l}}$$

$$a' = \frac{m}{l}(A'n+B's) = \frac{7}{20}(\overline{10000\times13} + \overline{8000\times5}) = 59500$$

$$b' = \frac{s}{l}(B'r+A'm) = \frac{5}{20}(\overline{8000\times15} + \overline{10000\times7}) = 47500$$

$$a'-b' = 59500 - 47500 = 12000$$

$$h = 10 + \frac{12000}{8 \times \frac{2000}{20}} = 25$$

This gives a value to h greater than that of n and shows (Art. 244) that n must be substituted for h, and that the problem is a proper one for solving by formula (91.); therefore

$$bd^{2} = \frac{4 \times 4 \left[1000 \frac{7 \times 13}{20} + \frac{7}{20} (\overline{10000 \times 13} + \overline{8000 \times 5})\right]}{850} = 1205.65$$

If the breadth b be taken at 8 inches, then $d = 12 \cdot 28$; that is, the beam should be 8×12 inches.

250.—Rule for Carriage Beams with Two Headers and Two Sets of Tail Beams.—By proper modifications, formula (90.) may be adapted to the requirements of a carriage beam with two headers, as in Fig. 25. These modifications are as follows: By Art. 150 we have

hence

$$U = \frac{1}{2}cfl$$

$$U\frac{ht}{2l} = \frac{1}{4}cfht$$

also, from Arts. 153 and 243,

$$a' = \frac{m}{I}(A'n + B's)$$

and, from Art. 155,

$$A' = \frac{1}{4} fgm$$
 and $B' = \frac{1}{4} fgs$

therefore

$$a' = \frac{m}{l} (\frac{1}{4} fgmn + \frac{1}{4} fgs^{s})$$

$$a' = fg\frac{m}{4l}(mn+s')$$

Similarly we find

$$b' = fg \frac{s}{4l} (rs + m^2)$$

To obtain the maximum strain, h is to be determined by formula (88.), in which for e we have

$$e = \frac{U}{l} = \frac{cfl}{2l} = \frac{1}{2}cf$$

and therefore

$$h = \frac{1}{2}l + \frac{a'-b'}{\frac{1}{2}cd'f}$$

In these deductions, f equals the weight per superficial foot of the floor, c the distance apart from centres at which the beams in the floor are placed, and g the length of the header. (For cautions in distinguishing between m and s, and between a' and b', see Art. 244.) By formula (90.) and the modifications proposed, we therefore: have

$$4a \left[\frac{1}{4} cfht + b' + \frac{a'-b'}{d'} (h-s) \right] = Bbd^{2}$$
 (92.)

and as auxiliary thereto we have, as above,

$$a' = fg\frac{m}{4l}(mn + s^{s})$$

$$b' = fg\frac{s}{4l}(rs + m^{s})$$

$$h = \frac{1}{2}l + \frac{a' - b'}{\frac{1}{2}cd'f}$$
and

and thus we have in formula (92.) a rule for a carriage beam carrying two headers and two sets of tail beams. (See caution in Art. 88).

251.—Example.—To show the application of this rule, let it be required to find the breadth of a white pine carriage beam, 20 feet long and 10 inches deep; the beam to carry two headers 10 feet long, one located 9 feet from the left-hand end, and the other 6 feet from the right-hand end. The floor beams are to be placed 15 inches from centres, and the floor is to carry 100 pounds per superficial foot, with the factor of safety a = 4.

Here the header at the left-hand end is the nearer of the two to the middle of the carriage beam, and therefore (Art. 244) m = 9.

From formula (92.) we have, for the value of b,

$$b = \frac{4a}{Bd^2} \left[\frac{1}{4} cfht + b' + \frac{a'-b'}{d'} (h-s) \right]$$
 (93.)

in which a = 4, $B = 5\infty$, $d' = 10^2$, $f = 1\infty$, $c = 1\frac{1}{4}$, g = 10, l = 20, m = 9, n = 11, r = 14, s = 6 and d' = 5. From the auxiliary formulas of Art. 250,

$$a' = 100 \times 10 \times \frac{.9}{4 \times 20} (9 \times 11 + 6^{2}) = 15187.5$$

$$b' = 100 \times 10 \times \frac{6}{4 \times 20} (14 \times 6 + 9^{2}) = 12375$$

$$a' - b' = 15187.5 - 12375 = 2812.5$$

$$h = 10 + \frac{2812.5}{\frac{1}{4} \times 1\frac{1}{4} \times 5 \times 100} = 19$$

Here n, since it is but 11, is less in value than h, and must be used in its place; we therefore have recourse to formula (91.), Art. 248. By this formula the value of b is

$$b = \frac{4a}{Bd^{s}} \left[\frac{1}{2} U \frac{mn}{l} + \frac{m}{l} (A'n + B's) \right]$$

This is a general rule. To make it conform to the requirements for a carriage beam, we have for U the equally distributed load $\frac{1}{2}cfl$ (Art. 150).

$$A' = \frac{1}{2}fgm \quad (Art. 250), \text{ and } B' = \frac{1}{2}fgs. \text{ Hence}$$

$$b = \frac{4a}{Bd^2} \left[\frac{1}{2}cfmn + \frac{m}{l} (\frac{1}{2}fgmn + \frac{1}{2}fgs^3)^2 \right]$$

$$b = \frac{4a}{Bd^2} \left[\frac{1}{2}cfmn + \frac{fgm}{4l}(mn + s^3) \right]$$

$$b = \frac{afm}{Bd^2} \left[cn + \frac{g}{l}(mn + s^3) \right] \qquad (94.)$$


$$b = \frac{4 \times 100 \times 9}{500 \times 100} \left[\frac{1}{1} \times 11 + \frac{10}{20} (9 \times 11 + 36) \right] = 5 \cdot 85$$

or, the carriage beam should be 57 or, say 6 inches broad.

In this computation, no allowance is made for the weakening effect of mortising, it being understood that no mortises are to be made; the headers being hung in bridle irons (Art. 147). (See Art. 88).

252.—Carriage Beam with Three Headers.—It sometimes occurs in the plan of a floor that two openings, the one a stairway at the wall, the other an opening for light at or near the middle of the floor, are opposite each other, as in Fig. 54.

In this arrangement the carriage beam has three headers to carry, besides its load as an ordinary floor beam.



Cases of this kind may be divided into two classes: one

that in which the header causing the greatest strain occurs between the other two; the other, that in which it occurs next to one of the walls. We will first consider the latter case.

253.—Three Headers—Strains of the First Class.—When the well hole for light occurs at the middle of the distance between the walls, its two headers will be equally near the centre of the length of the carriage beam; and, were their loads alike, the headers would produce equal strains upon the carriage beam; but the loads are not alike, for the tail beams carried by one header, those which reach to the wall, are longer than those carried by the other.

Hence the header carrying the tail beams, one end of which rest on the wall, has the heavier load; and, as it has the same leverage as the header on the other side of the well hole, it will therefore have the greater moment, and will produce the greater strain upon the carriage beam.

The stair header will add to the strains upon the carriage beam at the points of location of the other two headers, and this addition will be greater at the middle header than at the farther one, but still not so much greater as to cause the total strains at the one to preponderate over those at the other.

254.—Graphical Representation.—Let Fig. 55, constructed similarly with Fig. 53, represent the strains in a carriage beam supporting three headers, one of the outside ones, as at A, producing the greatest strain. In this figure the curve DKE is a parabola (Art. 212) and is the curve of strains for the uniformly distributed load upon the carriage beam,




Fig. 55.

of which KL represents the strain at the middle of the beam; and CF, BG and AH, vertical lines, by the same scale, represent the strains caused by the three headers at the points C, B and A, respectively. Any ordinate drawn, parallel to AH, across this figure, and terminated by the boundary line DFGHEKD, will measure the strain in the carriage beam at its location. Hence that point at which an ordinate thus drawn proves to be longest of any which may be drawn, is the point where the strain upon the carriage beam is the greatest, and the length of this ordinate measures the amount of this strain.

Draw the tangent ST parallel to GH. If its point of contact with the curve occurs between Q and E, then HQ will be the longest possible ordinate; but, if it occur between K and Q, then HQ will not be the longest. When AH and BG are equal, the point of contact will be at K. In the case under consideration (the well hole in the middle of the floor) the tangent will usually touch between Q and E, giving HQ as the longest ordinate.

255.—Greatest Strain.—With the loads A, B and C in position as in Fig. 55, the longest ordinate may be found




Fig. 55.

by formula (87.), where

$$y = \frac{1}{2}cht + b' + \frac{a'-b'}{d'}(h-s)$$

and in which m+n=r+s=h+t=l (for the position of these letters see 'Art. 244), $\frac{1}{2}cht$ represents the strain from the uniformly distributed load, and $b'+\frac{a'-b'}{d'}(h-s)$ stands for the length of an ordinate drawn from GH to BA at the distance h from D towards A, and represents at the location of the ordinate the strain from the three concentrated loads. In all cases, except where b' is very nearly or quite equal to a', h will exceed n, and, in

general, for all problems of the class of which we are treating, it may be assumed, without material error, that h will always exceed n. Then m and n take the place of t and h in formula (87.), and it becomes (Art. 248)

$$y = \frac{1}{2}emn + a'$$
or,
$$y = \frac{1}{2}U\frac{mn}{l} + a'$$

The value of a' is (form. 58.)

$$a' = \frac{m}{l} (A'n + B's + C'v)$$

$$y = \frac{1}{2} U \frac{mn}{l} + \frac{m}{l} (A'n + B's + C'v)$$
 (95.)

hence

In this formula y equals the greatest strain in the beam.

256.—General Rule for Equably Distributed and Three Concentrated Loads.—Putting the strain y of last article equal to the resistance (Art. 35) gives us

$$\frac{1}{2}U\frac{mn}{l} + \frac{m}{l}(A'n + B's + C'v) = Sbd^{2}$$

and with B = 4S and a as the coefficient of safety,

$$4a\frac{m}{l}(\frac{1}{2}Un + A'n + B's + C'v) = Bbd^{2}$$
 (96.)

which is a general rule for beams carrying a uniformly distributed load and three concentrated loads similarly placed with those in Fig. 55. In this rule, U is the uniformly distributed load, and A', B' and C' the three loads concentrated at A, B and C in the figure.

257.—Example.—As an example, we will ascertain the required breadth of a Georgia pine beam of average quality,

20 feet long and 14 inches deep, with a load of 2000 pounds equally distributed over its length, a concentrated load of 4000 pounds at 3 feet from the left-hand end, a like load at 7 feet from the same end, and one of 7000 pounds at 7 feet from the right-hand end. Take as the factor of safety a = 4. Then l = 20, m = 7, n = 13, s = 7, r = 13, v = 3, u = 17, d = 14, U = 2000, A' = 7000, B' = 4000 = C' and B = 850, and from formula (96.)

$$b = \frac{4 \times 4 \times 7}{850 \times 14^{2} \times 20} \left(\frac{1}{2} \times 2000 \times 13 + \frac{1}{7000 \times 13} + \frac{1}{4000 \times 7} + \frac{1}{4000 \times 3} \right) = 4.84$$
or the breadth should be $4\frac{7}{8}$ inches.

258.—Rule for Carriage Beams with Three Headers and Two Sets of Tail Beams.—To modify formula (96.) so as to make it applicable to a carriage beam, we have for U, the uniformly distributed load, (Art. 150) $U = \frac{1}{2}cfl$; for the load at A, caused by the header carrying the tail beams, one end of which rests upon the wall, $A' = \frac{1}{2}fgm$; for the load at B, $B' = \frac{1}{2}fg(s-v)$; and for the load at C the same, $C' = \frac{1}{4}fg(s-v)$. Formula (96.) now becomes

$$b = \frac{4am}{Bd^{2}l} \left[\frac{1}{4}cfln + \frac{1}{4}fgmn + \frac{1}{4}fg(s-v)s + \frac{1}{4}fg(s-v)v \right]$$

$$b = \frac{amf}{Bd^{2}l} \left[cnl + gmn + g(s-v)(s+v) \right]$$

$$b = \frac{amf}{Bd^{2}l} \left[cnl + g(mn + s^{2} - v^{2}) \right]$$
(97.)

which is a rule for carriage beams carrying three headers and two sets of tail beams, located, as in Fig. 55, with A, the heaviest strained header in an outside position relative to the other two headers.

259.—Example.—Under the above rule, what should be the breadth of a spruce carriage beam 20 feet long and 12

inches deep, carrying three headers 15 feet long, located as in Fig. 54. The well-hole for light, in the middle of the width of the floor, is 6 feet wide, and the stairway opening, at one of the walls, 3 feet wide. The beams of the floor are placed 15 inches from centres, and are to carry 90 pounds per superficial foot, with 4 as the factor of safety.

Here
$$l = 20$$
, $m = s = \frac{l-6}{2} = 7$, $n = 13$, $v = 3$, $g = 15$, $d = 12$, $c = 1\frac{1}{4}$, $f = 90$, $a = 4$ and $B = 550$.


By formula (97.)

$$b = \frac{4 \times 7 \times 90}{550 \times 12^{3} \times 20} \left[\overline{1\frac{1}{4} \times 13 \times 20} + 15 \left(\overline{7 \times 13} + 7^{2} - 3^{2} \right) \right] = 3.64$$

or the breadth should be 3\frac{2}{3} inches.

260.—Three Headers—Strains of the Second Class.—We will now consider the other class named in Art. 252, that in which the header causing the greatest strain occurs between the other two.


The conditions of this class of cases are represented in Fig. 56, in which AH=a', BG=b' and CF=c', representing by scale the combined concentrated strains at A, B



and C respectively, and KL is the strain at the middle due to the uniformly distributed load. The parabolic curve

(Art. 212) EKD and the line DGHFE form the boundaries of the scale of strains, as in Art. 254.

For the proper assignment of the symbols m, n, r, s, etc. see Art. 244, taking the two larger of the strains of Fig. 56 for the two given in that article.



The longest vertical ordinate across the scale of strains will ordinarily be at QH; the exceptions being when the strain at B is nearly or quite equal to that at A. In the latter case, however, the diminution at QH will be so small that that ordinate may be assumed, without material error, to be the greatest. Taking it as the greatest, formula (87.) becomes, as in Art. 255,

$$y = \frac{1}{2}U\frac{mn}{l} + a'$$

261.—Greatest Strain.—The manner of obtaining the value of a', the strain produced by the three concentrated loads, will now be shown.

The strain at A, produced by the load A', is (Art. 56) $A'\frac{mn}{l}$. The strain at B, produced by B', is $B'\frac{rs}{l}$. The effect at A of the strain at B may be had by the proportions shown in the triangles BGE and ARE; for the effect is proportional to the horizontal distance from E is the effect, therefore,

$$r: m:: B'\frac{rs}{l}: B'\frac{rsm}{rl} = B'\frac{ms}{l}$$

equals the effect of the weight B' at the point A.

Also, for the effect at A of the weight at C, the effect of C' at C being $C'\frac{uv}{l}$, we have

$$u:n::\frac{C'uv}{l}:\frac{C'nuv}{lu}=\frac{C'nv}{l}$$

equals the effect at A of the weight at C.

The joint effect at A of the three weights is therefore

$$a' = A'\frac{mn}{l} + B'\frac{ms}{l} + C'\frac{nv}{l}$$
$$a' = \frac{m}{l}(A'n + B's) + C'\frac{nv}{l}$$

or,

Adding this to the effect of the uniformly distributed load, $\frac{1}{2}U\frac{mn}{l}$, gives

$$y = \frac{1}{2}U\frac{mn}{l} + \frac{m}{l}(A'n + B's) + C'\frac{nv}{l}$$
 or
$$y = \frac{m}{l}(\frac{1}{2}Un + A'n + B's) + C'\frac{nv}{l}$$
 (98.)

This represents the greatest strain arising from the uniformly distributed load and the three weights disposed as in Fig. 56; A' at the middle being the greatest strain and B' the next greatest.

262.—General Rule for Equally Distributed and Three Concentrated Loads.—Putting the strain [form. (98.)] in equilibrium with the resistance (Art. 35) we have

$$\frac{m}{l}(\frac{1}{2}Un + A'n + B's) + C'\frac{nv}{l} = Sbd^{2} = \frac{1}{4}Bbd^{2}$$

204 COMPOUND STRAINS, GRAPHICALLY EXPRESSED. CHAP. XII. and with the symbol for safety added,

$$b = \frac{4a}{Bd^{2}l} [m(\frac{1}{2}Un + A'n + B's) + C'nv] \qquad (99.)$$

which is a rule for beams loaded with an equally distributed load and with three loads relatively disposed as in Fig. 56; A' being the greatest strain, and B' the next greatest, and A' being at the middle.

263.—Example.—As an example under this rule: What should be the breadth of a Georgia pine beam of average quality, 20 feet long and 12 inches deep, carrying 4000 pounds uniformly distributed, 6000 pounds at 4 feet from the left-hand end, 6000 pounds at 9 feet from the same end, and 7000 pounds at 6 feet from the right hand end; with the factor of safety a = 4?

Assigning the symbols to the loads and spaces as in Fig. 56, we have

$$a = 4$$
, $B = 850$, $d = 12$, $l = 20$, $m = 9$, $n = 11$, $r = 14$, $s = 6$, $v = 4$, $U = 4000$, $A' = 6000$, $B' = 7000$ and $C' = 6000$.

Substituting these values in formula (99.) gives

$$b = \frac{4\times4}{850\times12^{3}\times20} [9(\frac{1}{2}\times4000\times11+6000\times11+7000\times6) + (6000\times11\times4)] = 9\cdot37$$

or the breadth should be 9\frac{3}{8} inches.

264.—Assigning the Symbols.—In working a problem of the kind just given, it is of prime importance to have the symbols denoting the weights and distances properly located. In doing this, the first point to settle is as to which of the two classes (Fig. 55 or 56) the case in hand belongs.

Make a sketch, such as Fig. 55 or 56, according to the probable position of the largest strain, letter the weights and

distances as there shown, and then compute the three strains by the following formulas.

For Fig 55 the strains will be as follows (Art. 195):

At A, the strain
$$a' = \frac{m}{l}(A'n + B's + C'v)$$
 (100.)

"
$$B$$
, " $b' = \frac{s}{l}(A'm + B'r) + C'\frac{rv}{l}$ (101.)

"
$$C_{\bullet}$$
" $c' = \frac{v}{l}(A'm + B'r + C'u)$ (102.)

In the diagram, AH is to be made, by any convenient scale, equal to a', BG to b', and CF to c', as found by these three formulas, and KL, the height of the parabola, is, by the same scale, to be made equal to $\frac{1}{2}U\frac{mn}{l}$. U is the load equably diffused over the beam; A', B' and C' are the loads concentrated at A, B and C respectively, and l is the span, or length of the beam between bearings.

For Fig. 56 the strains will be as follows:

At A, the strain
$$a' = \frac{m}{l}(A'n + B's) + C\frac{nv}{l}$$
 (103.)

"
$$B$$
, " $b' = \frac{s}{l}(A'm + B'r + C'v)$ (104.)

"
$$C$$
, " $c' = \frac{v}{l}(A'n + B's + C'u)$ (105.)

In the case of a carriage beam the loads A', B' and C' in the formulas (100.) to (105.) are those from the headers; and equal $\frac{1}{2}fgm$, etc. In this, f and g are constant, as to the three loads in any given case, and m represents the length of one set of tail beams; consequently the loads A' B' and C' will vary as the length of the tail beams.

Hence, in the preliminary work required to ascertain to which of the two classes any given case belongs, it will suffice to use simply the length of the tail beams, instead of the full weights A', B' and C'.

For example: Take the case given in Art. 259, where l=20, m=7, s=7, n=13, r=13 and v=3, the letters being assigned as required by Fig. 55. Here the tableams carried by the header at A are 7 feet long, and those carried by the two other headers are 4 feet; therefore A=7 and B=C=4, and by formulas (100.) and (101.)

$$a' = \frac{7}{20}(\overline{7 \times 13} + \overline{4 \times 7} + \overline{4 \times 3}) = 45 \cdot 85$$

$$b' = \frac{7}{20}(\overline{7 \times 7} + \overline{4 \times 13}) + \frac{4 \times 13 \times 3}{20} = 43 \cdot 15$$

The result here obtained, a' being larger than b', shows that the case has been rightly assigned to the first class, that of Fig. 55.

- 265.—Reassigning the Symbols.—The result of a computation of the strains may show that the arrangement of the symbols was erroneous; instead of the greatest strain being in the middle it may be found at one side, or vice versa. Then the lettering of the loads and spaces must be changed, to agree with the proper diagram and formulas, before computing the dimensions of the beam; using formula (96.) or (97.) for the class shown in Fig. 55, and formula (99.) for the class shown in Fig. 56.
- 266.—Example.—As an illustration of the above, take a case presumably belonging to the class first treated (Fig. 55), where the greatest strain is an outside one. Let l = 20; and let the greatest load, 1750 pounds, be designated by A', with its distances m = 7 and n = 13; the second load, 1250 pounds, be designated by B', with its distances r = 12 and s = 8; and the third load, 1250 pounds, be called C, and its distances v = 3 and u = 17. To find

the united effect at each station, we have, according to formulas (100.) and (101.),

$$a' = \frac{7}{20} \left(\overline{1750 \times 13} + \overline{1250 \times 8} + \overline{1250 \times 3} \right) = 12775$$

$$b' = \frac{8}{20} \left(\overline{1750 \times 7} + \overline{1250 \times 12} \right) + \frac{1250 \times 12 \times 3}{20} = 13150$$

Here b' exceeds a' and shows that a mistake has been made as to the class to which the case belongs. We must change the symbols and arrange them for the second class (Fig. 56).

The middle weight is to be called A'; the weight before called A', at 7 feet from one of the walls, is now to be B'; and the third weight C'. With these changes made, we have A' = 1250, B' = 1750, C' = 1250, l = 20, m = 8, n = 12, s = 7, r = 13 and v = 3; and, from formulas (103.) and (104.),

$$a' = \frac{8}{20} \left(\overline{1250 \times 12} + \overline{1750 \times 7} \right) + \frac{1250 \times 12 \times 3}{20} = 13150$$


$$b' = \frac{7}{20} \left(\overline{1250 \times 8} + \overline{1750 \times 13} + \overline{1250 \times 3} \right) = 12775$$

The result is now satisfactory, and shows that the problem belongs to the second class, the one in which the greatest strain occurs at the middle, and this notwithstanding the fact that the greatest of the three weights is at the outside. It will be seen that the results of the two trials are the same, but reversed, that which was at first taken for a' being now taken for b'.

267.—Rule for Carriage Beam with Three Headers and Two Sets of Tail Beams.—Formula (99.) may be transformed so as to make it specially applicable to carriage beams.

If, in Fig. 56, we suppose the spaces EC and AB to be openings in the floor, then one set of tail beams will extend

208 COMPOUND STRAINS, GRAPHICALLY EXPRESSED. CHAP. XII.



from C to A, and another from B to D, giving three headers, one each at A, B and C. The load on the header A will equal that upon C, and will equal one quarter of the load upon the space occupied by the tail beams AC, or $\frac{1}{4}fg(m-v)$. Similarly the load at B will be $\frac{1}{4}fgs$. Of the several factors composing formula (99.) we now have

$$A'n = \frac{1}{4} fgn (m-v)$$

$$B's = \frac{1}{4} fgs^{2}$$

$$C'nv = \frac{1}{4} fgnv (m-v)$$

$$U = \frac{1}{2} cfl$$

$$\frac{1}{2} Un = \frac{1}{4} cfln$$

and since

and the formula itself becomes

$$b = \frac{4a}{Bd^{2}l} [m(\frac{1}{4}cfln + \frac{1}{4}fgn\overline{m-v} + \frac{1}{4}fgs^{2}) + \frac{1}{4}fgnv(m-v)]$$

$$b = \frac{4a}{Bd^{2}l} [\frac{1}{4}fm(cnl + gn\overline{m-v} + gs^{2}) + \frac{1}{4}fgnv(m-v)]$$

$$b = \frac{4af}{4Bd^{2}l} [cnlm + gmn(m-v) + gms^{2} + gnv(m-v)]$$

$$b = \frac{af}{Bd^{2}l} [cnlm + gn(m-v)(m+v) + gms^{2}]$$

$$b = \frac{af}{Bd^{2}l} [m(cnl + gs^{2}) + gn(m^{2}-v^{2})] \qquad (106).$$

which is a rule for carriage beams carrying three headers and two sets of tail beams relatively placed as in Fig. 56, the header producing the greatest strain being between the other two.

268.—Example.—What should be the width of a carriage beam 20 feet long, 12 inches deep, of Georgia pine of average quality, carrying three headers 14 feet long; the headers placed so as to afford a stair opening 4 feet wide at one wall, and a light well 5 feet wide, 6 feet from the other wall? The floor beams are 15 inches from centres and carry 200 pounds per foot superficial, with the factor of safety a = 4.

In this case we have B = 850, f = 200, a = 4, $c = 1\frac{1}{4}$, d = 12, l = 20, v = 4, m = 9, n = 11, s = 6, r = 14 and g = 14, and by formula (106.)

$$b = \frac{4 \times 200}{850 \times 12^{2} \times 20} \left[9 \left(\frac{11 \times 11 \times 20 + 14 \times 6^{3}}{14 \times 6^{3}} \right) + 14 \times 11 \left(9^{2} - 4^{2} \right) \right] = 5.56$$

or the breadth should be, say 6 inches.

210 COMPOUND STRAINS, GRAPHICALLY EXPRESSED. CHAP. XII.

QUESTIONS FOR PRACTICE.

269.—In a beam 20 feet long, carrying an equably distributed load of 2000 pounds, and, at 4 feet from one end, a concentrated load of 5000 pounds, what is the greatest strain produced, and where is it located?

270.—In a floor composed of beams 12 inches deep, and set 15 inches from centres, there is a Georgia pine carriage beam 22 feet long, carrying two headers with an opening between them. The headers are 14 feet long, and are placed at 5 and 12 feet respectively from the left-hand wall. The floor is required to carry 200 pounds per superficial foot, with the factor of safety a = 4.

What must be the breadth of the carriage beam?

CHAPTER XIII.

DEFLECTING ENERGY.

- ART. 271.—Previously Given Rules are for Rupture.—In the discussion of the subject of transverse strains, the rules adduced thus far have all been based upon the resistance of the material to rupture, or the power of the material to resist the destructive effect produced by the load which the beam is required to carry.
- 272.—Beam not only to Be Safe, but to Appear Safe.—
 It is requisite in good construction that a loaded beam be not only safe, but that it also appear safe; or, that the amount of deflection shall not appear to be excessive. In determining the pressure a beam may receive without injury, real or apparent, it is requisite to investigate the power of a beam to resist bending, rather than breaking—that is, to ascertain the Laws of Deflection.
- 273.—All Materials Possess Elasticity.—Any load, however small, will bend a beam. If the load be not excessive, the beam will, upon the removal of the load, recover its straightness.

The power of the beam by which it returns to its original shape upon the removal of its load, is due to the *elasticity* of the material. All materials possess elasticity, though some, as lead and clay, have but little, while others, as indiarubber and whalebone, have a large measure of it.

274.—Limits of Elasticity Defined.—When a beam is bent, some of its fibres are extended and some compressed, as was shown at Art. 22; and when the pressure by which the bending was effected is removed, the fibres resume their original length. Should the pressure, however, have been excessive, then the resumption will not be complete, but the extended fibres will remain a trifle longer than they were before the pressure, and the compressed fibres a trifle shorter. When this occurs, the elasticity is said to be injured; or, the pressure has exceeded the limits of elasticity.

When the fibres are thus injured, they are not only incapable of recovering their original length, but (the pressure being renewed and continued) they are not able to maintain even their present length, and therefore the deflection must gradually increase, and the fibres continue to alter in length, until finally rupture will ensue.

275.—A Knowledge of the Limits of Elasticity Requisite. —To secure durability, it is evident that a beam subject to transverse strain should not be loaded beyond its limit of elasticity. Hence the desirability of ascertaining this limit-

of force in producing extension be first considered. Suspend a weight of one pound, by a strip of india-rubber one foot long, and measure the increase in the length of the rubber. Then, double the weight, and it will be found that the increase in length will be double. If the extension caused by one pound be one inch, then that caused by two pounds will be two inches. Three pounds will increase the length by three inches; or, whatever weight be suspended, it will be found that the extensions will be directly in proportion to the forces producing them, provided always that the force

applied shall not be so great as to destroy the elasticity of the material; shall not so injure it as to prevent it from recovering its original length upon the removal of the force.

277.—Extension Directly as the Length.—The above shows the relation between the weight and the extension. The relation will now be shown between the extension and the length of the piece extended. At 5 inches from the upper end of a strip of rubber attach a one-pound weight. This will produce an extension of, say a quarter of an inch. Detach the weight and re-attach it at double the length, or at 10 inches from the upper end. It will now be found that the 10 inches has become 10½ inches; the elongation being a half inch, or double what it was before. Again, remove the weight and attach it at 15 inches from the upper end, and the strip will be extended to 15% inches; an elongation of three quarters of an inch, or three times the amount of the first trial. From this we conclude that, under the same amount of pressure, the extensions will vary directly as the lengths of the pieces extended.

278.—Amount of Deflection.—When the projecting beam

ABCD, Fig. 57, is deflected by a weight, P, suspended from the free end, it bends the beam, not only at the point A, at the wall, but also at every point of its length from A to B, so that the line AB becomes a convex curve, as shown.




FIG. 57.

The exact shape of this *elastic*

were is defined by writers upon that subject. A full discussion

of the laws of deflection would include the development of this curve. The purpose of this work, however, will be attained without carrying the discussion so far. All that will here be attempted will be to show the amount of deflection; or, in the present example, the distance, EB, which the point B is depressed from its original position.

279.—The First Step.—In bending a beam, the fibres at the concave side are shortened and those at the convex side are lengthened. The first step, therefore, in finding the amount of deflection, will be to ascertain the manner of this change in length of fibre, and the method by which the amount of alteration may be measured.

It is manifest that the elongation of the fibres in the upper edge of the beam AC, Fig. 57, must occur not only at A_1 , but at every point in the length of the line AB. The fibres at every point suffer an exceedingly small elongation, and if we can determine the sum of this large number of small elongations, we shall have the amount of extension of the line AB. This may be done in a simple manner, for we may, without serious error in the result to be obtained, consider them all as though they were collected and concentrated at one place in the line, instead of considering each one at the point where it occurs.

To effect this, let the line AB be drawn straight, as in Fig. 58, and the line FG be drawn at right angles to FK, the neutral line—the line which divides between those fibres which are extended and those which are compressed,

and therefore a line in which the fibres are not altered

in length. The line AG may be taken as the sum of the numerous small extensions which have occurred in the fibres at the line AB of Fig. 57.

In order to show the relation between the extension and the deflection, we will investigate the proportion between AG, the mea-




Fig 53.

sure of the one, and EB, the measure of the other.

281. -Deflection Directly as the Extension.—Make $G\mathcal{F}$, Fi_E . 58. equal to AG, and draw $\mathcal{F}L$ parallel with AE. The two triangles AGF and $\mathcal{F}GL$ are both right-angled triangles, and if AGF be revolved ninety degrees upon G as a centre, then the line AG will coincide with the line $G\mathcal{F}$, the line GF with the line GL, and AF with $\mathcal{F}L$; and we have the triangle $\mathcal{F}GL$, equal in all respects to the triangle AGF.

The triangle $G\mathcal{F}L$ is homologous with the triangle EBA, for the right line AB cuts the two parallel lines AE and $\mathcal{F}L$, making the angles $GL\mathcal{F}$ and EAB equal; the angles at E and G are by construction right angles, and hence the remaining angles at \mathcal{F} and E must be equal, and the two triangles, having all their respective angles equal, must have their respective sides in proportion, or be homologous. Now, since the triangle $\mathcal{F}GL$ is identical with the triangle AGF, we have the two triangles AGF and BEA with their corresponding sides in proportion, or

GF: AE :: AG : EB

and as AG measures the extension and EB the deflection,

it results that the extension is in direct proportion to the deflection.

282.—Deflection Directly as the Force, and as the Length.—By the experiment of Art. 276, it was shown that the extensions are in proportion to the forces producing them, and since, as just shown, they are also in proportion to the deflection, therefore the deflections are in direct proportion to the forces producing them.




Fig. 59.

In the case of a semi-beam projecting from a wall, as AC, Fig. 59, the force producing the deflection EB, is the product of the weight P, into the arm of leverage AE, at the end of which the weight acts; or, the force producing the deflection is in proportion to the weight and the length.

This is shown in Fig. 60. Here let it be required that the weight P remain constant in amount and location, while the length of the semi-beam be increased. We shall then




Fig. 60.

have at E, in Fig. 60, the same deflection as at E in Fig. 59, because the force producing the deflection $(P \times AE)$ is the ne in each figure. But at F, the end of the increased

length, the deflection is greater, owing to an increase in the size of the triangle AEB, from AEB to AFC. The increase at F over that at E is in proportion to the increase of AF over AE, because EB and FC, the lines measuring the deflections, are similar sides of the two homologous triangles AEB and AFC; and AE and AF, the lines measuring the lengths, are also similar sides of these triangles. For example, if AF equal twice AE, then we will have FC equal to twice EB; or, in whatever proportion AF is to AE, we shall have the like proportion between FC and EB. In every case, the deflections will be in direct proportion to the lengths.

283.—Deflection Directly as the Length.—Again: If the weight be moved from E to F, Fig. 61, the end of the above increased length, then the force with which it acts is increased, and the deflection FC, caused by the weight when




Fig. 61.

located at E, now becomes $F\mathcal{F}$. If AF equals twice AE, then the force producing deflection is doubled, because the leverage at which the weight acts is doubled; and since the deflections are in proportion to the forces producing them, $F\mathcal{F}$ is double FC; and in whatever proportion the arm of leverage be increased, it will be found that the deflections at the two locations will be in proportion to the dis-

tances of the weights from the wall AD, or in proportion to the lengths.

284.—Deflection Directly as the Length.—Once more: When the weight was located at E, the length of fibres suffering extension was from A to E, but now this length is increased to AF.

This increase in length of fibres will increase the extension (Art. 277), and consequently the deflection (Art. 281). If AF, Fig. 62, be double the length of AE, then, owing to the extension of double the length of fibres, the deflection $F\mathcal{F}$, Fig. 61, will be doubled, or increased to FK, Fig. 62;




Fig. 62.

and in whatever proportion the beam be lengthened, the deflection will increase in like proportion, or the deflections will be in proportion to the lengths.

285.—Total Deflection Directly as the Cube of the Length.—Summing up the results as found in the above several steps in the increase of deflection, we find, by a comparison of Figs. 59 and 62, that, owing to an increase of the beam to twice its original length, we have an increase in deflection to eight times its original amount. If EB = 1,

then FC = 2, $F\mathcal{F} = 2FC = 4$, and $FK = 2F\mathcal{F} = 8EB$. With lengths of beam in proportion as 1 to 2, the deflections are as 1 to 8, or as the cubes of the lengths.

This is true not only when the length is doubled, but also for any increase of length, for a reference to the discussion will show that the deflection was found to be in proportion to the length on three several considerations: first (Art. 282), on account of an increase in the size of the triangle containing the line measuring the deflection; second (Art. 283), on account of the additional energy given to the weight by the increase of the leverage with which it acted; and, third (Art. 284), on account of the extension of an additional length of fibres. The deflection and the length being necessarily of the same denomination, and the deflection being taken in inches, we therefore take the length, N, in inches, and we have the deflection in proportion to NNN or to N².

286.—Deflecting Energy Directly as the Weight and Cube of the Length.—From Art. 276 the extensions are in proportion to the weights, and since, from Art. 281, the deflections are as the extensions, therefore we have the deflections in proportion to the weights. Combining this with the result in the last article, we have, for the sum of the effects, the deflection in proportion to the weight and the cube of the length; or,

 $\delta: PN^{s}$

QUESTIONS FOR PRACTICE.

287.—The rules given in former chapters for beams exposed to cross strains were based upon the power of resistance to rupture.

Upon what power of the material may other rules be based?

- 288.—To what degree may beams be deflected without injury?
- 289.—What relation exists between extensions and the forces producing them?
- 290.—What relation exists between extensions and deflections?
- 291.—What relation, in a beam, is there between the deflections, the weights and the lengths?

CHAPTER XIV.

RESISTANCE TO FLEXURE.

ART. 292.—Resistance to Rupture, Directly as the square of the Depth.—Having considered, in the last chapter, the power exerted by a weight in bending a beam, attention will now be given to the resistance of the beam.


It was shown in the third chapter, that the resistance to rupture is in proportion to the square of the depth of the beam. It will now be shown that the resistance to bending is in proportion to the cube of the depth.

293.—Resistance to Extension Graphically Shown.— For the greater convenience in measuring the extension of the fibres at the top of a bent lever (Fig. 57), it was proposed in Art. 280 to consider this extension as occurring at one point; at the wall. In an investigation of the resistance to bending, the whole extension may still be considered as being concentrated at that point.

Let the triangle AGF, Fig. 63, represent the triangle AGF of Fig. 58, in which AF is the face of the wall, and AG, at the top edge of the lever, is the measure of the extension of the fibres there; while at F, the location of the neutral line, the fibres are not extended in any degree.

It is evident that the fibres suffer extension in proportion to their distance from F towards G, so that the lines BC, DE, etc., severally measure the extensions at their respective locations. Within the limits of elasticity, the resistance

of a fibre to extension is measured by its reaction when released from tension. Thus, the line *BC* measures the extension of the fibres at that location, and when the load is



fibres contract and resume their original length. Hence, BC also measures the resistance to extension. The resistance of the lever to bending, therefore, is in proportion to the sum of the extensions. The extensions of that portion of the lever occurring between the lines AG and BC

is measured by the sum of the lengths of all the fibres within the space ABCG. The average length of these fibres will be that of the one at the middle, and the number of fibres is measured by CG, the width they occupy. The sum, therefore, of the lengths of all the fibres will be equal to the area of the figure ABCG.

Again, the sum of the lengths of all the fibres between the lines BC and DE is equal to the area of the figure BDEC; so in each of the other figures into which the triangle AGF is divided a similar result is found. From this we conclude that the sum of the lengths of all the fibres exposed to tension is equal to the area of the whole triangle AGF; and, therefore, that the resistance of the lever is in proportion to the area of this triangle.

294.—Resistance to Extension in Proportion to the Number of Fibres and their Distance from Neutral Line.—In the measure of the extensions, we have the reaction or power of resistance; but there is still another fact connected

with the act of bending which needs consideration. The power of a fibre to resist deflection will be in proportion to its distance from F, the location of the neutral line; or, to the leverage with which it acts, as was shown in Figs. 8 and 9. Thus at AG a fibre will resist more than one at DE, while farther down, each fibre resists less until at F, where there is no leverage, the power to resist entirely disappears. It may, therefore, be concluded that the power of each fibre to resist is in proportion to its distance from F; and adding this power of resistance to that before named, we have, as the total resistance, the sum of the products of the lengths of the several fibres into their respective distances from F.

295.—Illustration.—As an illustration of the above, we may find an approximate result thus:

Let the line FG, Fig. 63, be divided into any number of equal parts, and through these points of division draw the lines BC, DE, etc., parallel with AG. These lines will divide the triangle into the thin slices ABCG, BDEC, etc. Now, the resistance of the top slice, ABCG, will be approximately equal to its area into its distance from F; or, if CG, the thickness of the slice, be represented by t, and the average length of fibres in the slice, $\frac{1}{2}(AG+BC)$, by b_i , then the area of the slice will equal $b_i t$; and, if a_i be put for FG, the average distance of the slice from F will be $a_i-\frac{1}{2}t$; and therefore the resistance of the top slice will be

$$R = b_{i}t(a_{i} - \frac{1}{2}t)$$

In like manner, if c_i be put for the average length of the fibres of the second slice, we shall have, to represent its resistance,

$$R_{i} = c_{i}t(a_{i} - \frac{3}{2}t)$$

For the third we shall have

$$R_{\prime\prime}=d_{\prime}t(a_{\prime}-\frac{\epsilon}{2}t)$$

Thus, obtaining the resistance of all the slices and adding the results, we have the total resistance.

296.—Summing up the Resistances of the Fibres.—To make a general statement, let x be put for the distance from F to the middle of the thickness of any one of the slices into which the triangle is divided, and let r, a constant, be the length of an ordinate, as DE, located at the distance unity from F. Then we have by similar triangles the proportion

and therefore xr will equal the breadth of the slice at any point distant x from F, or putting x equal to the distance from F to the middle of the slice, then xr will be equal to the average length of the fibres of the slice. The resistance then of one of the slices, say the top slice, will be $x \times xr \times t = x^2rt$. For the top slice, $x = a_1 - \frac{1}{2}t$, therefore

$$x^{s}rt = (a_{r} - \frac{1}{2}t)^{s}rt = R$$

Again; for the second slice, $x = a_i - \frac{3}{2}t$ therefore

$$(a_1 - \frac{3}{2}t)^2 rt = R_1$$

For the third slice we have

$$(a_{i}-\frac{5}{2}t)^{2}rt=R_{u}$$

In like manner we obtain the resistance of each successive slice, each result being the same as the preceding one, excepting the fractional coefficient of t, which differs as shown, the numerator increasing by the constant number 2. When

represents the total number of slices, then the last result the resistance of the last slice will be

$$[a_{1}-\frac{1}{2}(2n-1)t]^{s}rt=R_{n}$$

the sum of all the resistances, or

$$R_{1} + R_{2} + R_{3} + \text{etc.} + R_{8} = M$$

I equal the total resistance of all the fibres, thus:

$$M = (a_1 - \frac{1}{2}t)^2 rt + (a_1 - \frac{3}{2}t)^2 rt + \text{etc.} + (a_1 - \frac{1}{2}\overline{2n - 1}t)^2 rt$$

$$M = rt \left[(a_1 - \frac{1}{2}t)^2 + (a_1 - \frac{3}{2}t)^2 + \text{etc.} + (a_1 - \frac{1}{2}\overline{2n - 1}t)^2 \right]$$

Now the number of slices multiplied by the thickness of the highest hand to have the slices multiplied by the thickness of the highest hand, and the highest hand, and highest highest hand, and highest hand, hi

$$a_{1} - \frac{1}{2}t = a_{1} - \frac{1}{2}\frac{a'}{n} = a_{1}\left(1 - \frac{1}{2n}\right) = a_{1}\frac{2n - 1}{2n}$$

$$(a_{1} - \frac{1}{2}t)^{2} = a_{1}\frac{(2n - 1)^{2}}{4n^{2}} \qquad \text{therefore}$$

$$(2n - 1)^{2} = (2n - 2)^{2} \qquad (2n - 2)^{2}$$

$$M = rt \left[a_{1}^{s} \frac{(2n-1)^{2}}{4n^{s}} + a_{1}^{s} \frac{(2n-3)^{2}}{4n^{s}} + \text{etc.} + a_{1}^{s} \frac{(2n-\overline{2n-1})^{2}}{4n^{s}} \right]$$

$$M = \frac{rta_1^2}{4n^2} [(2n-1)^2 + (2n-3)^2 + \text{etc.} + (2n-2n-1)^2]$$

$$W, \qquad (2n-1)^2 = 4n^2 - 1 \times 4n + 1$$

$$(2n-3)^2 = 4n^2 - 3 \times 4n + 9$$

$$(2n-5)^2 = 4n^2 - \overline{5 \times 4n} + 25$$

get the sum of these, we have, first, for the sum of the t terms, $n \times 4n^2 = 4n^3$.

The coefficients of the second terms, namely, 1, 3, 5, etc., equal in amount the sum of an arithmetical series composed of these odd numbers; or, n^2 (Art. 200), and hence the sum of these several second terms is $n^2 \times 4n = 4n^2$. The first and second terms summing up alike cancel each other, and we have but the third terms remaining. The sum of these is that of the squares of the odd numbers 1, 3, 5, etc., and our last formula becomes

$$M = \frac{a_1^2 rt}{4n^2} \left[1^2 + 3^2 + 5^2 + \text{etc.} + (2n - 1)^2 \right]$$

Now, $t = \frac{a_i}{n}$ and $\frac{a_i^2 rt}{4n^2} = \frac{a_i^2 r}{4n^2}$, therefore

$$M = a_1^2 r \left(\frac{1^2 + 3^2 + 5^2 + \text{etc.} + (2n - 1)^2}{4n^2} \right) \quad (107.)$$

297.—True Value to which these Results Approximate. As an example to test this formula, let n = 3, then

$$M = a_i^3 r \left(\frac{1+9+25}{4 \times 27} \right) = \frac{35}{108} a_i^3 r$$

Again, let n = 4, then

$$M = a_1^{s} r \left(\frac{1+9+25+49}{4\times 4^{s}} \right) = \frac{84}{256} a_1^{s} r$$

and if n = 5, then

$$M = a_{1}^{3}r\left(\frac{1+9+25+49+(2\times 5-1)^{2}}{4\times 5^{3}}\right) = \frac{185a_{1}^{3}r}{4\times 5^{3}}$$

If # 10, then

$$M = \frac{1330a}{1000}$$

If n = 20, then

$$M = \frac{19999}{32000} a'r$$

Reducing these five fractions to their least common denominator, 43,200, we have

When
$$n = 3$$
, the numerator = 14,000
" $n = 4$, " = 14,175
" $n = 5$, " = 14,256
" $n = 10$, " = 14,364
" $n = 20$, " = 14,391

It will be noticed that these numerators increase as n increases, but not so rapidly. As n becomes larger, the increase in the numerator is more gradual, but still remains an increase, for however large n becomes, the numerator will still increase, until n becomes infinite, when its limit is reached.

This limit is equal in this particular case to 14,400, or one third of 43,200, the denominator; or, in general, the value of the fraction tends towards $\frac{1}{3}$, and

$$M=\frac{1}{3}a_{i}^{s}r$$

298.—True Value Defined by the Calculus.—This definite result is reached more easily and directly by means of the calculus.

Taking the notation of Art: 296, we have, for the resistance of one of the slices, the expression

$$R = x^{q}rt$$

This gives the resistance for a slice at any distance, x, from F, and if the thickness of the slice be reduced to the smallest conceivable dimension, then t, its thickness, may

be taken for the differential of x, or dx, and we have as the differential of the resistance

$$dR = x^{2}rdx$$

from which, by integration, is obtained (Art. 463)

$$R = \frac{1}{8}x^3r$$

and when the result is made definite by taking the integral between limits, or between x = 0 and $x = a_i$, we have

$$R = \frac{1}{8}a_i^3 r \tag{108.}$$

299.—Sum of the Two Resistances, to Extension and to Compression.—The foregoing discussion has been confined to the resistance offered by that portion of the lever the fibres of which suffer extension.

A similar result may be obtained from a consideration of the resistance offered by the remaining fibres to compression.

If c be put to represent the depth of that part of the beam in which the fibres are compressed, then it will be found that the resistance to compression will, from (108.), be equal to

$$R_{\prime} = \frac{1}{3}c^3r \tag{109.}$$

and the total resistance offered by the lever will be

$$R + R_1 = \frac{1}{3}a_1^3r + \frac{1}{3}c^3r = \frac{1}{3}r(a_1^3 + c^3)$$

It may be shown also, by a farther investigation, that in levers suffering small deflections, or when not deflected beyond the limits of elasticity, $a_i = c$, or the neutral line is at the middle of the depth. In the latter case, we have $a_i = c = \frac{1}{2}d$, and therefore

$$R + R_1 = \frac{1}{3}r[(\frac{1}{2}d)^3 + (\frac{1}{2}d)^3] = \frac{2}{3}r\frac{1}{3}d^3 = \frac{1}{3}rd^3$$

300.—Formula for Deflection in Levers.—The above is the result in a lever one inch broad. A lever two inches broad would bear twice as much; one three inches broad would bear three times as much; or, generally, the resistance will be in proportion to the breadth. We have then for a lever of any breadth

$$R + R_{\prime} = \frac{1}{12} rbd^{3} \tag{110.}$$

This expression gives the resistance to the deflecting energy, which is (Art. 286) equal to PN^3 . This power, PN^3 , however, not only overcomes the resistance, $\frac{1}{12}rbd^3$, but in the act also accomplishes the deflection; moves the lever through a certain distance. Representing this distance by δ , we have, as the full measure of the work accomplished, $\delta \times \frac{1}{12}rbd^3$. When the power and the work are equal, we have

$$PN^{s} = \frac{1}{12}\delta rbd^{s}$$
 from which,

$$\delta = \frac{PN^{s}}{\frac{1}{12}rbd^{s}}$$
 (111.)

301.—Formula for Deflection in Beams.—The expression (111.) is for a semi-beam or lever. When a full beam, supported at each end, is deflected by W, a weight located at the middle, we have to consider that for P we must take $\frac{1}{2}W$, and for N take $\frac{1}{2}L$ (see Art. 35). These alterations will produce

$$\delta = \frac{\frac{1}{2}W(\frac{1}{2}L)^{3}}{\frac{1}{12}rbd^{3}} \qquad \text{or}$$

$$\delta = \frac{WL^{3}}{\frac{4}{rbd^{3}}} \qquad (112.)$$

for the deflection of a beam supported at both ends and loaded in the middle.

302.—Value of F, the symbol for Resistance to Flexure.

—In formula (112.) the dimensions are all in inches. As it is more convenient that the length be taken in feet, let I represent the length in feet, then

$$\frac{L}{12} = l$$
, $L = 12l$ and $L^3 = \overline{12l}^3 = 1728l^3$

By substitution in formula (112.) we have

$$\delta = \frac{1728Wl^{s}}{\frac{4}{3}rbd^{s}} = \frac{1296Wl^{s}}{rbd^{s}}$$
or
$$\frac{r}{1296} = \frac{Wl^{s}}{bd^{s}\delta}$$

The symbol r is a measure of the extension, differing in different materials, but constant, or nearly so, in each. Putting for $\frac{r}{1206}$ the letter F we have

$$F = \frac{Wl^3}{bd^3\delta} \tag{113.}$$

The respective values of F for several materials have been obtained by experiment, and may be found in Table XX. Its value in each case is that for a beam supported at each end, and with the load in pounds applied at the middle of l, the distance in feet between the bearings; while b, d and δ are in inches; δ being the deflection within the limits of elasticity.

303.—Comparison of F with E, the Modulus of Elasticity.—The common expression for flexure of beams when laid on two supports and loaded at the middle is [Tate's Strength of Materials, London, 1850, p. 24, formula (49.)]

$$\delta = \frac{WL^3}{48EI} \tag{114.}$$

in which E represents what is termed the Modulus or Coefficient of Elasticity, which is (same work, p. 3), "that force,
which is necessary to elongate a uniform bar, one square
inch section, to double its length (supposing such a thing
possible) or to compress it to one half its length"; and I
represents the Moment of Inertia (Arts. 457 to 463) of the
cross-section of the beam.

In this expression the dimensions are all in inches. To change L to feet we have $\frac{L}{L^2} = l$ equals the length in feet,

or

$$L^{s} = \overline{12l}^{s} = 1728l^{s}.$$

Substituting this value in (114.) we obtain

$$\delta = \frac{1728Wl^3}{48EI} = \frac{36Wl^3}{EI}$$

$$\frac{E}{36} = \frac{Wl^3}{l\delta}$$

or

In formula (113.) we have

$$F = \frac{Wl^s}{bd^s\delta}$$

Multiplying this by 12 gives

$$12F = \frac{Wl^s}{\frac{1}{16}bd^s\delta}$$

and since $\frac{1}{12}bd^3 = I$ (see Art. 463)

$$12F = \frac{Wl^3}{I\delta} \tag{115.}$$

Comparing this with above value of $\frac{E}{36}$ we have

$$\frac{E}{36} = 12F \quad \text{or} \quad E = 432F$$

304.—Relative Value of F and E.—In Table XX. the value of F for wrought iron is, from experiments on rolled iron beams, 62,000. Then

$$432F = E = 432 \times 62000 = 26784000$$

equals the modulus of clasticity for the wrought-iron of which these beams were made. They were of American metal. Tredgold found the value for English iron to be E = 24,900,000; and Hodgkinson from 19,000,000 to 28,000,000.

An average of the results in seven cases gives 25,300,000 as the modulus of elasticity for English wrought-iron.

305.—Comparison of F with E common, and with the E of Barlow.—Barlow, in his "Materials and Construction," p. 93, foot-note (Ed. of 1851), uses the expression $\frac{L^sW}{bd^s\delta} = E$, instead of $\frac{L^sW}{3bd^s\delta}$, for a lever loaded at one end; and on p. 94, $\frac{L^sW}{16bd^s\delta} = E$. The dimensions are all in inches. Changing the length to feet, we have

$$E = \frac{1728l^3W}{16bd^3\delta} = \frac{108l^3W}{bd^3\delta}$$
$$\frac{E}{108} = \frac{Wl^3}{bd^3\delta}$$

or

Comparing this with (113.), which is

$$F = \frac{Wl^{3}}{hd^{3}\delta}$$

we have $\frac{E}{108} = F$, or 108F = E. We found before (Art. 303) that E = 432F, and since $4 \times 108 = 432$, therefore

the E of Barlow equals one quarter of the E in common use, and his values of E are equal to 108 times the values of F as given in this book.

For example; on p. 147, in an experiment on New England fir, he gives, by an error in computation, E=547800, but which, corrected, equals 373026. Dividing this by 108 as above, gives

$$\frac{373026}{108} = F = 3454$$

By reference to Table XX. we find that for spruce, the wood most probably intended for New England fir,

$$F = 3500$$

Again; taking Barlow's four experiments on oak, p. 146, and correcting the arithmetical errors, we have E=361758, 482344, 291227 and 242860. This gives an average of 344547, and dividing it by 108 as above, we have

$$F = 3190$$

By reference to Table XX. we find that by my experiments

$$F = 3100$$

306.—Example under the Rule for Flexure.—To make a practical application of the rule in formula (113.), let it be required to find the depth of a white pine beam 10 feet long between bearings and 4 inches broad; and which, with a load of 2000 pounds at the middle of its length, shall be deflected 0.3 of an inch.

We obtain from (113.)

$$d^{s} = \frac{Wl^{s}}{Fb\delta}$$

or, in this case,

$$d^{3} = \frac{2000 \times 10^{3}}{2900 \times 4 \times 0.3}$$

$$d^{3} = \frac{2000000}{3480} = 574.7$$

$$d = 8.31$$

or the depth should be 8.31, say 81 inches.

QUESTIONS FOR PRACTICE.

- 307.—How may the resistance of a fibre to extension be measured when the elasticity remains uninjured?
- 308.—In a beam exposed to transverse strain, what is the resistance to extension in proportion to?
- 309.—When the bending energy and the resistance of a beam are in equilibrium, what is the expression for this relation?
- 310.—Given a white pine beam 20 feet long, 6 inches broad and 12 inches deep, and loaded with 1000 pounds at the middle. What will be the deflection, the value of F being 2900?

CHAPTER XV.

RESISTANCE TO FLEXURE—LIMIT OF ELASTICITY.

ART. 311.—Rules for Rupture and for Flexure Compared.—The rules for determining the strength of materials differ from those denoting their stiffness. The former are more simple; all their symbols being unaffected except one, and this only to the second power, or square; in the latter, two of the symbols are involved to the third power or cube.

Many, in determining the dimensions of timbers exposed to transverse strains, are induced, by the greater simplicity of the rules for strength, to use them in preference to those for stiffness, even when the latter only should be used.

A beam apportioned by the rules for strength will not bend so as to strain the fibres beyond their elastic limit, and will therefore be safe; but in many cases the beam will bend more than a due regard for appearance will justify.

When timbers, therefore, as those in the ceiling or floor of a room, might deflect so much as to be readily perceptible, and unpleasant to the eye, they should have their dimensions fixed by the rules for stiffness only.

312.—The Value of a, the Symbol for Safe Weight.—In order that the symbol a in the rules for strength, denoting the number of times the safe weight is contained in the breaking weight, may be of the proper value to preserve the fibres of the timber from being strained beyond the elastic

236 RESISTANCE TO FLEXURE—LIMIT OF ELASTICITY. CHAP. XV.

limit, a few considerations will now be presented showing the manner in which this value is ascertained.

In Fig. 64 let ABCD represent a lever with one end, AD, imbedded in a wall, AD being the face of the wall, and car-




Fig. 64.

rying at the other end, BC, a weight P; the weight deflecting the lever from the line AE to the extent EB. The line FH is the neutral line, and FG is drawn at right angles to FH.

As in Figs. 58 and 63, so here the triangle AFG shows the elongation of the fibres in the upper half of the beam,

and AG the elongation to the limits of elasticity of the fibres at the upper edge AB. The triangle AFG is in proportion to the triangle ABE, as shown in Art. 281. If AB = N (this being a semi-beam), and e equals the extension per unit of N, then AG = eN.

We have by similar triangles

Then if AD = d and $EB = \delta$

$$\frac{1}{2}d: N:: cN: \delta = \frac{cN^2}{\frac{1}{2}d}$$
$$\delta = \frac{2cN^2}{d}$$

The dimensions here are all in inches. To change N in inches to n in feet, we have

$$\frac{N}{12} = n$$
, $N = 12n$ and $N'' = 144n''$

from which

$$\delta = \frac{288en^s}{d}$$

and from this we obtain

$$e=\frac{d\delta}{288\pi^6}$$

in which δ is the deflection when at the limit of elasticity, and in which e, d and δ are in inches, and n in feet. This is for a semi-beam, and it will be perceived that the deflection EB, in Fig. 64, caused by the weight P, is precisely the same as would be produced in a full beam by double this weight placed at D, the beam being in a reversed position.

When, therefore, l equals the length of the full beam in feet, n will equal $\frac{1}{2}l$. Substituting this value of n in the above expressions, we have

$$\delta = \frac{288e(\frac{1}{2}l)^2}{d}$$

$$\delta = \frac{72el^2}{d} \tag{116.}$$

and for the value of e,

$$e = \frac{d\delta}{72l^2} \tag{117.}$$

In Art. 302 we have, for the stiffness of materials, formula (113.),

$$F = \frac{Wl^{s}}{bd^{s}\delta}$$

For δ substitute $\frac{72el^2}{d}$, its value as just found, and, in order to distinguish the weight used to produce flexure from that used to produce rupture, let us for the moment indicate the former by G, and the latter by W. Then,

238 RESISTANCE TO FLEXURE—LIMIT OF ELASTICITY. CHAP. XV. from the above,

$$Gl^{s} = Fbd^{s} \frac{72el^{s}}{d}$$

$$Gl = 72Fbd^{s}e$$

The relation between F, the measure of the elasticity of materials, and B, the resistance to rupture, may be put thus:

$$B : F :: 1 : m = \frac{F}{B}; \text{ or, } F = Bm$$

Substituting this value for F in the above, we have

$$Gl = 72Bmbd^{*}e$$

$$\frac{Gl}{72em} = Bbd^{*}$$

Now the formula for strength, $B = \frac{Wl}{bd^2}$, [form. (10.) in Art. 36] gives $Wl = Bbd^2$; a comparison of this value of Bbd^2 with that above shown gives

$$\frac{Gl}{72em} = Wl$$

Since G is the deflecting weight which bends the lever to the limit of elasticity, it is therefore the ultimate weight which may be trusted safely upon the beam, and as a is a symbol put to denote the number of times G is contained in W, the breaking weight, therefore

$$G:W:: I: a = \frac{W}{G}$$
 and $Ga = W$

Substituting this value for W in the above, we have

$$\frac{Gl}{72\epsilon m} = Gal$$

$$\frac{1}{72\epsilon m} = a$$

As above found, $m = \frac{F}{B}$, therefore

$$a = \frac{I}{72e\frac{F}{B}}$$

$$a = \frac{B}{72Fe}$$
(118.)

From this expression the values of a for various materials have been computed, and the results are to be found in Table XX.

313.—Rate of Deflection per Foot Length of Beam.— The value of a as just found is based upon the elasticity of the material, and is measured by this elasticity at its limit.

This limit is that to which bending is allowable in beams apportioned for strength. In beams required to sustain their loads without bending so much as to be perceptible or offensive to the eye, the bending is generally far within the elastic limit. The deflection in these beams is rated in proportion to the length of the beam; or, when r in inches equals the rate of deflection per foot in length of the beam, then $rl = \delta$. The deflection by formula (116.) is

therefore
$$rl = \frac{72el^2}{d}$$

$$r = \frac{72el}{d}$$

$$(119.)$$

This gives r at its greatest possible value, and shows that it should never exceed 72 times the ratio between the length and depth, multiplied by e; e being the measure of extension as recorded in Table XX. The ratio between

240 RESISTANCE TO FLEXURE—LIMIT OF ELASTICITY. CHAP.XV.

the length and depth is to be taken with l in feet and d in inches.

The value of r as required in beams of the usual proportions and deflection, will not be as great as that here shown to be allowable. In cases where the rate of deflection, r, is as great as 0.05 of an inch per foot, and the length of the beam is short in comparison with the depth $\left(\text{say } \frac{l}{d} \text{ is as small as } \frac{5}{7}\right)$, then there will be danger of r exceeding the limit fixed by this rule. When the fraction $\frac{l}{d}$ is less than $\frac{5}{7}$ then the rate r should be tested to know whether it has exceeded the proper limit. It is seldom, however, that a beam 7 inches high is used shorter than 5 feet, or one 14 inches high shorter than 10 feet. Generally the number of feet in the length exceeds the number of inches in the depth.

314.—Rate of Deflection in Floors.—The rate of deflection allowable so as not to be unsightly is a matter of judgment. Tredgold, in his rules for floor beams, fixed it at $\frac{1}{15}$ of an inch per foot of the length, or 0.025. This is thought by some to be rather small, especially since in floors the limit of the rate is seldom reached; in fact never, except when the floor is loaded to its fullest capacity, a circumstance which occurs but seldom, and then only for a limited period. For this reason, it is proper to fix the rate at say $\frac{1}{33}$, or 0.03 of an inch per foot. With this as the rate for a full load, the usual rate of deflection under ordinary loads will probably not exceed 0.01 or 0.015. In the rules, the symbol r is left undetermined, so that the rate may be fixed as judgment or circumstances may dictate in each special case.

QUESTIONS FOR PRACTICE.

- 315.—What is the distinction between the rules for strength and those for stiffness?
- 316.—What expression shows δ , the deflection at the elastic limit?
- 317.—What expression gives the measure of extension at the elastic limit?
- 318.—What expression shows the ultimate value of a, the factor of safety?
- 319.—What expression gives the ultimate value of r, the rate of deflection?

· CHAPTER XVI.

RESISTANCE TO FLEXURE—RULES.

320.—Deflection of a Beam, with Example.—The simula 223.) for the deflection of beams supported at each and leaded at the middle, is

$$F = \frac{Wl^s}{bd^s\delta}$$
som which,
$$\delta = \frac{Wl^s}{Fbd^s} \tag{120.}$$

This is the deflection of any beam placed and loaded as For example: What is the deflection of a white pine can of 4×9 inches, set edgewise upon bearings 16 feet and loaded with 5000 pounds at the middle; the calls of F being 2900, the average of experiments, the calls of which are recorded in Table XX.?

The deflection in this case will be

$$\delta = \frac{5000 \times 16^3}{2900 \times 4 \times 9^3} = \frac{50 \times 1024}{29 \times 729} = 2.4218$$

This is a large deflection, much beyond what would be support in a good floor, for at 0.03 inch per foot of the length of the beam, the rate of deflection adopted (Art. 314), we should have

$$\delta = 16 \times 0.03 = 0.48$$

or, say half an inch, whereas the 5000 pounds upon this

beam produces five times this amount. Although so greatly in excess of what a respect for appearance will allow, it is still, however, within the limits of elasticity, as will be seen by the use of formula (116.), in which we have

$$\delta = \frac{72el^2}{d}$$

Obtaining from Table XX. the average value of e, equal 0.0014, we have

$$\delta = \frac{72 \times 0.0014 \times 16^2}{9} = 8 \times 0.0014 \times 256 = 2.8672$$

as the greatest deflection allowable.

321.—Precautions as to Values of Constants F and e.— The above is the ultimate deflection within the limits of elasticity, and is 0.4454 in excess of the 2.4218 produced by the 5000 pounds. In general, it would be undesirable to load a beam so heavily as this, or to deflect it to a point so near the limit of elasticity, and, unless the timber be of fair quality, would hardly be safe.

Some pine timber would be deflected by this weight much more than is here shown—in fact, beyond the limits of elasticity. In the above computation, F was taken at 2900, the average value, and the measure of elasticity, e, was taken at 0.0014, also the average value; whereas, had these constants been taken at their lowest value, such as pertain to the poorer qualities of white pine, and in which F = 2000 and e = 0.001016, the limits of elasticity would have been found at a trifle over 2 inches, while the deflection would have reached $3\frac{1}{2}$ inches.

Actual Experiment in Certain Cases.—For any important work, the capacity of the timber selected for use should be tested by actual experiment. This may be done by submitting several pieces to the test of known weights placed at the centre, by increasing the weights by equal increments, and by noting the corresponding deflections. From these deflections, the specific values of F and e for that timber may be loaded with certainty as to the result. In the absence of a knowledge of the elastic power of the particular material to be used, a sufficiently wide margin should be allowed, in order that the timber may not be loaded beyond what the poorer kinds would be able to carry safely.

323.—Deflection of a Lever.—The rule for deflection, and discussed in these last articles, is appropriate for a beam supported at both ends and loaded in the middle. A rule will now be developed for a semi-beam or lever; a timber fixed at one end in a wall, and with a weight suspended from the other. The deflection in this case is precisely the same at that produced by twice the weight, laid at the middle of whole beam, double the length of the lever, and supported a each end.

Let the weight at the end of the lever be represented by P, and the length of the lever by n, then W of formula (120), which is $\delta = \frac{Wl^s}{Fbd^s}$, will equal 2P, and l will equal 2n, and we have, by substituting these values for W and l

$$\delta = \frac{2P \times \overline{2n}^{s}}{Fbd^{s}}$$

$$\delta = \frac{16Pn^{s}}{Fbd^{s}}$$
(121.)

'324.—Example.—The deflection above found is that protect in a lever by a weight suspended from its free end.

As an example: What would be the deflection caused by weight of 1500 pounds suspended from the free end of a very of Georgia pine, of average quality, 3×6 inches ware and 5 feet long?

Here we have P = 1500, n = 5, F = 5900, b = 3 and E = 6; and therefore

$$\delta = \frac{16 \times 1500 \times 5^{3}}{5900 \times 3 \times 6^{3}} = \frac{80 \times 125}{59 \times 216} = 0.7847$$

325.—Test by Rule for Elastic Limit in a Lever.—To est the above, to ascertain as to whether the deflection is eithin the limits of elasticity, take l=2n=10, and by smula (116.) we get

$$\delta = \frac{72el^2}{d} = \frac{72 \times 0.00109 \times 10^2}{6} = 12 \times 0.109 = 1.308$$

This is satisfactory, as it shows that the lever has a delection (0.7847) of not much more than half that within the distic limit (1.308), and therefore a safe one.

326.—Load Producing a Given Deflection in a Beam.— By inversions of formulas (120.) and (121.), we may have tales for ascertaining the weight which any beam or lever will carry with a given deflection.

First; for a beam, we take formula (120.)

$$\delta = \frac{Wl^{s}}{Fbd^{s}}$$

$$W = \frac{Fbd^{s}\delta}{I^{s}} \qquad (122.)$$

and have

CHAP. XVL

327.—Example.—For an example: What weight upon the middle of a beam of spruce, of average quality, 5 inches broad, 10 inches high, and 20 feet long between the bearings, will produce a deflection of 0.03 inch per foot, or 0.6 inch in all?

Here we have $F = 35\infty$, b = 5, d = 10, $\delta = 0.6$ and l = 20; therefore

$$W = \frac{3500 \times 5 \times 10^{3} \times 0.6}{20^{3}} = \frac{10500}{8} = 1312.5$$

328.—Load at the Limit of Elasticity in a Beam.—Again: What weight could be carried upon this beam if the defection were permitted to extend to the limit of elasticity?

Formula (116.) gives us

$$\delta = \frac{72cl^*}{d}$$

and from Table XX. we have the average value of ϵ for spruce equal to 0.00098, and therefore

$$\delta = \frac{72 \times 0.00098 \times 20^{2}}{10} = 72 \times 0.00098 \times 40 = 2.8224$$

Substituting this new deflection in the former statement, we have

$$W = \frac{3500 \times 5 \times 10^3 \times 2 \cdot 8224}{20^3} = \frac{49392}{8} = 6174$$

This 6174 pounds for good timber would be a safe load but if there be doubts as to the quality, the load should be made less according to the lower values of F and c.

329.—Load Producing a Given Deflection in a Lever— Example.—Second; for a lever, we take formula (121.)

$$\delta = \frac{16Pn^3}{Fbd^3}$$

and find by inversion

$$P = \frac{Fbd^3\delta}{16n^3} \tag{123.}$$

An application of this rule may be shown in the answer to the question: What weight may be sustained at the end of a hemlock lever, 6 inches broad and 9 inches high, firmly imbedded in a wall, and projecting 8 feet from its face? The hemlock is of good quality, and the deflection is limited to 1 inch.

Here we have $F = 28\infty$, b = 6, d = 9, $\delta = 1$, and n = 8; therefore

$$P = \frac{2800 \times 6 \times 9^3 \times 1}{16 \times 8^3} = 1495$$

that is, 1495 pounds at the end of the lever would deflect it one inch.

330.—Deflection in a Lever at the Limit of Elasticity.—What deflection in this lever would mark the limit of elasticity?

Formula (116.) is

$$\delta = \frac{72\epsilon l^2}{d}$$

Taking l at twice n we have l = 16, d = 9, and e = 0.00095; and as a result

$$\delta = \frac{72 \times 0.00095 \times 16^{2}}{9} = 8 \times 0.00095 \times 256 = 1.9456$$

331.—Load on Lever at the Limit of Elasticity.—What weight would deflect this lever to the limit of elasticity?

For this we have

$$P = \frac{2800 \times 6 \times 9^3 \times 1.9456}{16 \times 8^3} = 2909$$

This is nearly double the weight required to deflect it one inch, as before found; and the deflection is also nearly double. The weight and the deflection are directly in proportion. If 1500 pounds deflect a beam one inch, 3000 pounds will deflect it two inches.

332.—Values of W, l, b, d and d in a Beam.—By a proper inversion of the formulas for beams, any one of the dimensions may be obtained, provided the other dimensions and the weight are known.

Thus we have (form. 122.)

$$W = \frac{Fbd^3\delta}{l^3}$$

and from this find

the length,
$$l = \sqrt[3]{\frac{Fbd^3\delta}{W}}$$
 (124)

the breadth,
$$b = \frac{Wl^2}{Fd^2\delta}$$
 (125.)

and the depth,
$$d = \sqrt[3]{\frac{Wl^3}{Fh\delta}}$$
 (126.)

and, as in formula (120.),

the deflection,
$$\delta = \frac{Wl^s}{Fbd^s}$$

333.—Example—Value of & in a Beam.—Take an example under formula (124.). What should be the length of a beam of locust of average quality, 4 inches broad and 8 inches high, to carry 5000 pounds at the middle, with a deflection of one inch?

In formula (124.) F = 5050, b = 4, d = 8, d = 1 and W = 5000; hence

$$l = \sqrt[3]{\frac{5050 \times 4 \times 8^{1} \times 1}{5000}} = 12.74$$

or the answer is 12‡ feet.

334.—Example—Value of b in a Beam.—As an example under formula (125.), let it be required to know the proper breadth of an oak beam of average quality. The depth is 6 inches and the length 10 feet. The load to be carried is 500 pounds placed at the middle, and the deflection allowed is 0.3 inch.

In this case, W = 500, l = 10, F = 3100, d = 6 and $\delta = 0.3$; and by substitution

$$b = \frac{500 \times 10^3}{3100 \times 6^3 \times 0.3} = \frac{50000}{20088} = 2.489$$

or 21 inches for the breadth.

335.—Example—Value of d in a Beam.—As an example under formula (126.), find the depth of a beam of maple of average quality, which is 5 inches broad and 20 feet long, and which is to carry 3000 pounds at the middle, with one inch deflection.

Here we have F = 5150, W = 3000, l = 20, b = 5 and $\delta = 1$; and hence

$$d = \sqrt[3]{\frac{3000 \times 20^3}{5150 \times 5 \times 1}} = 9.768$$

or a depth of 91 inches.



336.—Values of P, n, b, d and δ in a Lever.—The rules for the quantities in a semi-beam or lever are derived from formula (121.), which is

$$\delta = \frac{16Pn^3}{Fhd^3}$$

and are as follows:

The load,
$$P = \frac{Fbd^3\delta}{16n^3} \qquad (123.)$$

The length,
$$n = \sqrt[3]{\frac{Fbd^3\delta}{16P}}$$
 (127.)

The breadth,
$$b = \frac{16Pn^3}{Fd^3\delta}$$
 (128.)

The depth,
$$d = \sqrt[3]{\frac{16Pn^3}{Fb\delta}}$$
 (129.)

337.—Example—Value of n in a Lever.—As an example under (127.): What length is required in a semi-beam or lever of ash of average quality, 3×7 inches cross-section, and carrying 200 pounds at the free end, with a deflection of half an inch?

In this example, P = 200, F = 4000, b = 3, d = 7 and $\delta = 0.5$; and we have

$$n = \sqrt[3]{\frac{4000 \times 3 \times 7^3 \times 0.5}{16 \times 200}} = \sqrt[3]{\frac{10290}{16}} = 8.63$$

or the length is to be 8 feet 7½ inches.

338.—Example—Value of b in a Lever.—Under formula (128.): What is the proper breadth for a lever of hickory of average quality, 3 inches deep, projecting 4 feet from

the wall in which it is fixed, carrying a load of 200 pounds at the free end, and having a deflection of one inch?

In the formula, F = 3850, d = 3, $\delta = 1$, P = 200 and n = 4. Substituting these values, we have

$$b = \frac{16 \times 200 \times 4^{3}}{3850 \times 3^{3} \times 1} = 1.97$$

The breadth must be 2 inches.

339.—Example—Value of d in a Lever.—What must be the depth of a bar of cherry of average quality, 1½ inches broad, projecting 3 feet from the wall in which it is imbedded, and carrying at its end a load of 100 pounds, with a deflection of \{\frac{2}{3}} of an inch?

Here P = 100, n = 3, F = 2850, b = 1.5 and $\delta = 0.75$; and formula (129.) becomes

$$d = \sqrt[3]{\frac{16 \times 100 \times 3^{\circ}}{2850 \times 1 \cdot 5 \times 0.75}} = 2 \cdot 38$$

The depth required is 23 inches.

340.—Deflection—Uniformly Distributed Load on a Beam.—The cases hitherto considered in this chapter have all had the load concentrated either at the middle of a beam or at the end of a lever. When the weight is distributed equably over the length of the beam or lever, the deflection is less than when the same weight is so concentrated.

In comparing the values of the deflecting energies producing equal deflections in the two cases, we have [formula (511.), p. 477, of "Mechanics of Engineering and Architecture," by Prof. Moseley, Am. ed. by Prof. Mahan, 1856,

and changing the symbols to agree with ours], for a beam loaded at the middle,

$$\delta = \frac{WL^3}{48EI}$$

and [formula (530.), p. 484, same work], for a beam uniformly loaded,

$$\delta = \frac{5}{8} \times \frac{UL^s}{48EI}$$

Comparing these two equal values of δ , we have

$$\frac{WL^{s}}{48EI} = \frac{5}{8} \frac{UL^{s}}{48EI} \qquad \text{or,}$$

$$W = AU$$

or, with equal deflections, the weight at the middle of the beam is equal to $\frac{5}{8}$ of the uniformly distributed load. Thus, 100 pounds uniformly distributed over the length of a beam will deflect it to the same extent that 62½ pounds would were it concentrated at the middle of the length.

Then, since U represents a uniformly distributed load, $\{U\}U$ will equal the W of formula (120.), which formula is

$$\delta = \frac{Wl^s}{Fbd^s}$$

Substituting the value of W, as above, and transposing, we have

$$\frac{8}{8}Ul^s = Fbd^s\delta \tag{130.}$$

for the relation of the elements in the deflection of a beam by a uniformly distributed load.

341.—Values of U, l, b, d and δ in a Beam.—By inversions of formula (130.) we have the following rules—namely:

The weight,
$$U = \frac{Fbd^3\delta}{\frac{5}{8}l^3}$$
 (131.)

The length,
$$l = \sqrt[3]{\frac{Fbd^3\delta}{\frac{5}{8}U}}$$
 (132.)

The breadth,
$$b = \frac{\frac{b}{8}Ul^{s}}{Fd^{s}\delta}$$
 (133.)

The depth,
$$d = \sqrt[4]{\frac{\frac{5}{8}Ul^3}{Fb\delta}}$$
 (134.)

The deflection,
$$\delta = \frac{\frac{5}{8}Ul^s}{Fbd^s}$$
 (135.)

342.—Example—Value of U, the Weight, in a Beam.—In a spruce beam of average quality, 20 feet long between bearings, 4 inches broad and 12 inches deep: What weight uniformly distributed over the beam will deflect it 2 inches?

In this example, F = 3500, b = 4, d = 12, $\delta = 2$ and l = 20; and by formula (131.)

$$U = \frac{3500 \times 4 \times 12^3 \times 2}{\frac{5}{8} \times 20^3} = 9676 \cdot 8$$

or the weight required is 9677 pounds.

343.—Example—Value of 1, the Length, in a Beam.— In a 3 x 10 white pine beam of average quality: What is the proper length to carry 6000 pounds uniformly distributed, with a deflection of 2 inches? Here F = 2900, b = 3, d = 10, $\delta = 2$ and U = 6000; and by the substitution of these in formula (132.)

$$l = \sqrt[3]{\frac{2900 \times 3 \times 10^{9} \times 2}{\frac{5}{8} \times 6000}} = 16.68$$

or the required length is 16 feet 8 inches.

344.—Example—Value of b, the Breadth, in a Beam.—Given a beam of average quality of Georgia pine, 20 feet long and 10 inches deep. If this beam carry a uniformly distributed load of 8000 pounds, with a deflection of 1½ inches, what must be the breadth?

We have, as values of the known elements, U=8000, l=20, F=5900, d=10 and $\delta=1.75$; and formula (133.) gives us

$$b = \frac{5 \times 8000 \times 20^3}{8 \times 5900 \times 10^3 \times 1.75} = 3.874$$

The breadth must be 37 inches.

345.—Example—Value of d, the Depth, in a Beam.—A girder of average oak, 8 inches broad, and 10 feet long between bearings, is required to carry 10,000 pounds uniformly distributed over its length, with a deflection not to exceed $\frac{3}{10}$ of an inch. What must be its depth?

The elements of this case are U = 10000, l = 10, F = 3100, b = 8 and $\delta = 0.3$. Applying formula (134.) we find

$$d = \sqrt[3]{\frac{5 \times 10000 \times 10^{3}}{8 \times 3100 \times 8 \times 0.3}} = 9.436$$

or we must make the depth 91 inches.

346.—Example—Value of δ , the Deflection, in a Beam.—We have a 3×6 inch beam of hemlock of average quality, 10 feet long. What amount of deflection would be produced by 3000 pounds uniformly distributed over its length? U=3000, l=10, F=2800, b=3 and d=6; and the formula applicable, (135.), becomes

$$\delta = \frac{5 \times 3000 \times 10^3}{8 \times 2800 \times 3 \times 6^3} = 1.0334$$

or a resulting deflection of I inch.

347.—Deflection—Uniformly Distributed Load on a Lever.—For a load at the free end of a lever [Moseley's Mechanics (cited in Art. 340), formula (509.), p. 476, changing the symbols] we have

 $\delta = \frac{PN^3}{3EI}$

and [page 482, same work, formula (525.)] for a lever with a uniformly distributed load, we have

$$\delta = \frac{UN^s}{8EI}$$

Comparing these equal values of δ we have

$$\frac{PN^{s}}{3EI} = \frac{UN^{s}}{8EI}$$
 or,
$$\frac{P}{3} = \frac{U}{8}$$
 or,
$$P = \frac{8}{8}U$$

or, the deflection by a uniformly distributed load is equal to that which would be produced by $\frac{2}{3}$ of that load if suspended from the end of the lever.

348.—Values of U, n, b, d and δ in a Lever.—In formula (123.), which is $P = \frac{Fbd^3\delta}{16n^3}$, we have the relations existing between the elements involved in the case of a lever under strain.

If the weight uniformly distributed over the length of the lever be represented by U, then $P = \{U \text{ and formula } (123.)\}$ becomes

$$\frac{8}{8}U = \frac{Fbd^3\delta}{16n^3}$$

and from this we have the following:

The weight,
$$U = \frac{Fbd^3\delta}{6n^3}$$
 (136.)

The length,
$$n = \sqrt[3]{\frac{Fbd^3\delta}{6U}}$$
 (137.)

The breadth,
$$b = \frac{6Un^3}{Fd^3\delta}$$
 (138.)

The depth,
$$d = \sqrt[3]{\frac{6Un^3}{Fb\delta}}$$
 (139.)

The deflection,
$$\delta = \frac{6Un^3}{Fbd^3}$$
 (140.)

349.—Example—Value of U, the Weight, in a Lever.—. In a Georgia pine lever of average quality, 6 inches broad and 10 inches deep, and projecting 10 feet from the wall in which it is imbedded: What weight uniformly distributed over the lever will deflect it 2 inches?

In this example, F = 5900, b = 6, d = 10, $\delta = 2$ and n = 10; and by formula (136.),

$$U = \frac{5900 \times 6 \times 10^3 \times 2}{6 \times 10^3} = 11800$$

or the uniformly distributed weight required is 11,800 pounds.

Three eighths of this weight, or 4425 pounds, concentrated at the free end of the lever, will deflect it the same amount, viz.: 2' inches.

350.—Example—Value of n, the Length, in a Lever.—In a lever of the same description as in the last article, except as to length and load: What is the proper length to carry 8000 pounds uniformly distributed, with a deflection of 2 inches?

Here we have F = 5900, b = 6, d = 10, $\delta = 2$ and U = 8000; and by the substitution of these in formula (137.)

$$n = \sqrt[3]{\frac{5900 \times 6 \times 10^3 \times 2}{6 \times 8000}} = \sqrt[3]{1475} = 11.383$$

or the required length is 11 feet 4½ inches.

351.—Example—Value of b, the Breadth, in a Lever.—Given a lever of like description as in Art. 349, except as to breadth and load. If this lever carry a uniformly distributed load of 6000 pounds, what must be the breadth?

We have, as values of the known elements, U=6000, n=10, F=5900, d=10 and $\delta=2$; and formula (138.) gives us

$$b = \frac{6 \times 6000 \times 10^3}{5900 \times 10^3 \times 2} = 3.051$$

The breadth must be 3 inches.

352.—Example—Value of d, the Depth, in a Lever.—A lever of like description as in Art. 349, except as to depth and load, is required to carry 10,000 pounds uniformly distributed over its length: What must be its depth?

The elements of this case are U = 10000, n = 10, F = 5900, b = 6 and $\delta = 2$. We apply formula (139.) and find

$$d = \sqrt[3]{\frac{6 \times 10000 \times 10^3}{5900 \times 6 \times 2}} = 9.463$$

or we must make the depth 91 inches.

353.—Example—Value of d, the Deflection, in a Lever.—We have a lever of like description as that in Art. 349, except as to load and deflection: What amount of deflection would be produced by 5000 pounds uniformly distributed over its length?

U=5000, n=10, F=5900, b=6 and d=10; and the formula applicable, (140.), becomes

$$\delta = \frac{6 \times 5000 \times 10^3}{5900 \times 6 \times 10^3} = 0.8475$$

or a resulting deflection of $\frac{7}{8}$ of an inch.

QUESTIONS FOR PRACTICE.

- 354.—Given a beam loaded at middle: What are the rules by which to find the weight, length, breadth, depth and deflection?
- 355.—Given a lever loaded at the free end: What are the rules by which to find the weight, length, breadth, depth and deflection?
- 356.—In a beam with the load uniformly distributed: What are the rules by which to obtain the weight, length, breadth, depth and deflection?
- 357.—In a lever with the load uniformly distributed: What are the rules by which to obtain the weight, length, breadth, depth and deflection?

CHAPTER XVII.

RESISTANCE TO FLEXURE—FLOOR BEAMS.

ART. 358.—Stiffness a Requisite in Floor Beams.—The rules given in Chap. VI. for the dimensions of floor beams are based upon the ascertained resistance of the material to rupture, and are useful in all cases in which the question of absolute strength is alone to be considered. For warehouses and those buildings in which strength is principally required, the rules referred to are safe and proper; but for buildings of good character, in which the apartments are finished with plastering, the floor timbers are required to possess stiffness as well as strength; for it is desirable that the deflection of the beams shall not be readily noticed, nor be injurious to the plastering.

359.—General Rule for Floor Beams.—The relations of the several elements in the question of stiffness, in beams uniformly loaded throughout their entire length, are found in formula (130.),

$$\frac{5}{8}Ul^s = Fbd^s\delta$$

The load upon the floor beam is here represented by U_i and its value is U = cfl (see Art. 92); in which c is the distance apart between the centres of the floor beams, f is the number of pounds weight upon each square foot of the floor, and l is the length of the beam; c and l both

being in feet. If for U we substitute this value, and for δ put rl (see Arts. 313 and 314), we have

$$\frac{5}{8}cfl^s = Fbd^sr \tag{141.}$$

360.—The Rule Modified.—For the floors of dwellings and assembly rooms, f, the load per foot, may be taken (see Art. 115) at 70 pounds for the loading and 20 pounds for the weight of the materials, or 90 pounds in all; and r, the rate of deflection per foot of the length, at 0.03 (see Art. 314). Formula (141.) thus modified becomes

$$90 \times \frac{6}{8}cl^{3} = 0.03Fbd^{3}$$

$$\frac{90 \times 5}{8 \times 0.03}cl^{3} = Fbd^{3}$$

$$1875cl^{3} = Fbd^{3}$$

$$cl^{3} = \frac{F}{1875}bd^{3}$$
(142.)

This coefficient, $\frac{F}{1875}$, taking F at its average value for six of the woods in common use, reduces to

$$\frac{5898}{1898} = 3.15$$
 for Georgia pine,
 $\frac{5898}{1898} = 2.69$ "locust,
 $\frac{81998}{1898} = 1.65$ "oak,
 $\frac{35998}{1898} = 1.87$ "spruce,
 $\frac{28998}{1898} = 1.55$ "white pine,
 $\frac{28998}{1898} = 1.49$ "hemlock.

361.—Rule for Dwellings and Assembly Rooms.—For the coefficient in (142.), $\frac{F}{1875}$, putting the symbol i, we

have this simple rule for problems involving the dimensions of floor beams in dwellings and assembly rooms, namely,

$$cl^s = ibd^s (143.)$$

and we have the value of i for average qualities of six of the more common woods, as taken in Art. 360, as follows:

For Georgia pine, i = 3.15" locust, i = 2.69" oak, i = 1.65" spruce, i = 1.87" white pine, i = 1.55" hemlock, i = 1.49

362.—Rules giving the Values of c, l, b and d.—Taking formula (143.) we derive by inversions the following rules, namely:

The distance from centres,
$$c = \frac{ibd^s}{l^s}$$
 (144.)

The length,
$$l = \sqrt[3]{\frac{ibd^3}{c}} \qquad (145.)$$

The breadth,
$$b = \frac{cl^s}{id^s}$$
 (146.)

The depth,
$$d = \sqrt[3]{\frac{cl^3}{ib}} \qquad (147.)$$

363.—Example—Distance from Centres.—At what distance from centres should 3×12 inch Georgia pine beams of average quality, 24 feet long, be placed in a dwelling-house floor?

Here we have $i=3\cdot 15$, b=3, d=12 and l=24; and by formula (144.)

$$c = \frac{3 \cdot 15 \times 3 \times 12^{3}}{24^{3}} = 1 \cdot 181$$

or the distance c should be about 14½ inches.

364.—Example—Length.—Of what length may average quality white pine beams 3 × 10 inches square be used, when placed 16 inches from centres?

In this case i = 1.55, b = 3, d = 10 and $c = 1\frac{1}{8}$; and formula (145.) gives

$$l = \sqrt[3]{\frac{1 \cdot 55 \times 3 \times 10^3}{1\frac{1}{3}}} = \sqrt[3]{3487 \cdot 5} = 15 \cdot 165$$

or these beams may be used 15 feet 2 inches long between bearings.

365.—Example—Breadth.—In floor beams 20 feet long and 12 inches deep, of oak of average quality, placed one foot from centres: What should be the breadth?

Here, c = 1, l = 20, d = 12 and i = 1.65. With formula (146.), therefore, we have

$$b = \frac{1 \times 20^3}{1.65 \times 12^3} = 2.806$$

The breadth should be nearly 27, or say 3 inches.

366.—Example—Depth.—What should be the depth of spruce beams of average quality when 3 inches broad and 20 feet long, and placed 20 inches from centres? The symbols in this case are $c = 1\frac{9}{8}$, l = 20, b = 3, and i = 1.87; and by formula (147.) we find

$$d = \sqrt[3]{\frac{1\frac{2}{8} \times 20^3}{1 \cdot 87 \times 3}} = 13 \cdot 345$$

or the depth required is 13% inches. Beams 3×13 could be used, provided the distances apart from centres were correspondingly decreased. The new distance would be (form. 144.) 18½ instead of 20 inches.

367.—Floor Beams for Stores.—The several values of *i* for dwellings and assembly rooms, as given in Art. 361, will be appropriate also for stores for light goods, because timbers apportioned by the rules having these values of *i*, will bear a load of 200 pounds per superficial foot before their deflection will reach the limit of elasticity.

For first-class stores—those intended for wholesale business, as that of dry-goods—the values of *i*, as above given, are too large. The proper values for this constant may be derived as below.

368.—Floor Beams of First-class Stores.—The load upon the floors of first-class stores may be taken at 250 pounds per superficial foot, and the deflection at 0.04 of an inch per foot lineal (see Arts. 313 and 314). Beams proportioned by these requirements will bear a load of about $3 \times 250 = 750$ pounds per foot before the deflection will reach the limit of elasticity. With 250 as the loading, and, say 25 pounds (Art. 99) for the weight of the materials of construction, we have f = 275.

Formula (141.), modified in accordance herewith, putting r = 0.04, becomes

$$5 \times 275cl^{3} = 8 \times 0.04Fbd^{3}$$

$$cl^{3} = \frac{F}{4296\frac{7}{8}}bd^{3} \qquad (148.)$$

369.—Rule for Beams of First-class Stores.—Reducing the above constant, $\frac{F}{4296\frac{7}{8}}$, for six of the more common woods of average quality, and putting the symbol k for the results, we have for

Georgia pine,	k = 1.37
Locust,	$k = 1 \cdot 18$
Oak,	k = 0.72
Spruce,	k = 0.81
White pine,	k = 0.67
Hemlock,	k = 0.65

With this symbol k, the rule for floor beams of first-class stores is reduced to this simple form,

$$cl^s = kbd^s \tag{149.}$$

370.—Values of c, l, b and d.—By proper inversions, we obtain from formula (149.), rules for the several values required, thus:

The distance from centres,
$$c = \frac{kbd^3}{l^3}$$
 (150.)

The length,
$$l = \sqrt[3]{\frac{kbd^3}{c}} \quad (151.)$$

The breadth,
$$b = \frac{cl^3}{kd^3}$$
 (152.)

The depth,
$$d = \sqrt[3]{\frac{cl^3}{kb}} \qquad (153.)$$

371.—Example—Distance from Centres.—In a first-class store: How far from centres should floor beams of Georgia pine of an average quality be placed, when said beams are 4 × 12, and 20 feet long between bearings?

In this example, we have k = 1.37, b = 4, d = 12 and l = 20. Then by formula (150.)

$$c = \frac{1 \cdot 37 \times 4 \times 12^3}{20^3} = 1 \cdot 184$$

or the distance from centres is 1.184 feet, equal to about 142 inches.

372.—Example—Length.—At what length may 4×10 inch beams of average oak be used in the floors of a first-class store, when placed 12 inches from centres? Here we have k = 0.72, b = 4, d = 10 and c = 1; and by formula (151.)

$$l = \sqrt[3]{\frac{0 \cdot 72 \times 4 \times 10^3}{1}} = 14 \cdot 23$$

or the length should be 14 feet 3 inches.

373.—Example—Breadth.—The floor beams in a first-class store are to be 20 feet long and 14 inches deep, of white pine of average quality. When placed 12 inches from centres, what should be their breadth? Taking formula (152.) we have, as values of the symbols, c = 1, l = 20, k = 0.67 and d = 14; and

$$b = \frac{1 \times 20^3}{0.67 \times 14^3} = 4.35$$

The breadth should be 41 inches.

374.—Example—Depth.—What should be the depth, in a first-class store, of spruce beams, of average quality, 4 inches thick and 16 feet long, and placed 14 inches from centres?

In this case, we have $c = 1\frac{1}{6}$, l = 16, k = 0.81 and b = 4. Therefore, by formula (153.)

$$d = \sqrt[3]{\frac{11}{0.81 \times 4}} = 11.383$$

or a depth of 118 inches.

375.—Headers and Trimmers.—In Chap. VII., in Arts. 143 to 158, rules for headers and trimmers, based upon the resistance of the material to rupture, are given. These rules

contain the symbol a, which represents the number of times the weight to be carried is contained in the breaking weight.

The value of this symbol may be assigned at any quantity not less than that which is given for it in Table XX., and, when made so great that the deflection shall not exceed 0.03 of an inch per foot of the length, the rules referred to will be proper for use for headers and trimmers for the floors of dwellings and assembly rooms.

376.—Strength and Stiffness—Relation of Formulas.—
The value of a, the symbol for safety, may be determined from the following considerations:

Taking formula (113.), which is

$$F = \frac{Wl^{s}}{bd^{s}\delta}$$

and substituting G for W we have

$$Gl^s = Fbd^s\delta$$

A comparison of the constants for rupture (B) and for elasticity (F) shows that

$$B:F:: \mathbf{1}: m = \frac{F}{B}$$

or

$$Bm = F$$

and putting rl equal to δ we have, by substitution,

$$Gl^{s} = Bmbd^{s}rl$$

$$Gl^{s} = Bmbd^{s}r$$

$$\frac{Gl^2}{dmr} = Bbd^2$$

We have by formula (10.), Art. 36,

$$B = \frac{Wl}{bd^3}$$

or

$$Wl = Bbd^*$$

Comparing this value of Bbd' with that above, we have

$$Wl = \frac{Gl^2}{dmr}$$

In this formula, G is the weight which may be carried by the beam, with a deflection per foot of the length equal to r; and W is the breaking weight. Putting these symbols in a proportion, we have

$$G:W:: \mathbf{1}: a = \frac{W}{G}$$
$$Ga = W$$

or

Substitute for W this value of it, and we obtain

$$Gal = \frac{Gl^{2}}{dmr}$$

$$a = \frac{l}{dmr} = \frac{l}{d\frac{F}{B}r}$$

$$a = \frac{Bl}{Fdr}$$
(154.)

377.—Strength and Stiffness—Value of a, in Terms of B and F.—The values of B and F (form. 154.) are found in Table XX., and r = 0.03. The ratio $\frac{l}{d}$ (l in feet and d in inches) cannot be exactly determined until the length and depth have been established. An approximation may be

assumed, however, for a preliminary calculation, and then, if found to err materially, it may be taken more nearly correct in a final calculation. In all ordinary cases, the ratio $\frac{l}{d}$ will be found nearly equal to $\frac{17}{10} = 1.7$. Taking this value in formula (154.) we have

$$a = \frac{56\frac{2}{3}B}{F} \tag{155.}$$

378.—Example.—Let us apply this in the use of formula (21.), namely:

 $Wal = Bbd^*$

What weight may be carried at the middle of a Georgia pine beam of average quality, 3×10 inches $\times 17$ feet, so as to deflect it no more than would be proper for the floors of a dwelling?

Here b = 3, d = 10, $a = \frac{56\frac{2}{3}B}{F}$, F = 5900 and l = 17;

therefore

$$W = \frac{B \times 3 \times 10^{3}}{\frac{56\frac{3}{3}B}{F} \times 17} = \frac{5900 \times 3 \times 10^{3}}{\frac{56\frac{3}{3} \times 17}{66\frac{3}{3} \times 17}}$$

$$W = \frac{1770000}{063\frac{1}{6}} = 1837.4$$

379.—Test of the Rule.—To test the accuracy of the result just found, the same problem may be solved by formula (113.),

$$F = \frac{Wl^{s}}{bd^{s}\delta}$$

from which we have, when $\delta = rl$, and substituting G for W,

$$Gl^s = Fbd^s r$$

and

$$G = \frac{Fbd^3r}{l^2}$$

In this expression, in the above example, F = 5900, b = 3, d = 10, l = 17 and r = 0.03; and hence

$$G = \frac{5900 \times 3 \times 10^3 \times 0.03}{17^2} = \frac{531000}{289} = 1837.4$$

380.—Rules for Strength and Stiffness Resolvable.— The result in the last article is the same as the one before found, and indeed could not be otherwise, since the one formula is derived directly from the other, and is readily resolvable into it; for if, in formula (21.),

$$Wal = Bbd^{2}$$

we substitute for a its equivalent as in formula (154.), we have

$$W\frac{Bl}{Fdr}l = Bbd^{3}$$

$$Wl^{3} = Fbd^{3}r$$

so that instead of computing the value of a for use in any particular case by formula (155.), we may introduce into the rule its value as given by (154.), and reduce to the lowest terms, as in the next article.

381.—Rule for the Breadth of a Header.—A rule for a header is given in formula (27.), Art. 145. Substituting for a its value as in (154.), we have, taking U instead of U, Art. 340,

$$\frac{5}{16}\frac{Bl}{Fdr}fng^2 = Bb(d-1)^2$$

In this expression, l and g are the same, both representing the length of the header, and the (d-1) is put for the

effective depth, and is equal to the d of the first member; therefore, reducing, we have

$$\frac{5}{16} fng^{3} = Fbr (d-1)^{3}$$

$$b = \frac{5 fng^{3}}{16Fr (d-1)^{3}}$$
 (156.)

which is a rule for the breadth of a header, based upon the resistance to flexure.

382.—Example of a Header for a Dwelling.—In a dwelling having spruce floor beams of an average quality, so inches deep: What would be the required breadth of a header of the same material, so feet long, carrying tail beams 12 feet long?

The values of the symbols are, f = 90 (Art. 115), n = 12, g = 10, F = 3500 (Table XX.), r = 0.03 and d = 10; and

$$b = \frac{5 \times 90 \times 12 \times 10^{3}}{16 \times 3500 \times 0.03 \times 9^{3}} = 4.409$$

or the required breadth is 4\forall inches full.

383.—Example of a Header in a First-class Store.—In a first-class store, where the beams are 14 inches deep, what is the required breadth of a header of Georgia pine of average quality, 16 feet long, and carrying tail beams 17 feet long?

Here f = 275, r = 0.04 (Art. 368), n = 17, g = 16, F = 5900 (Table XX.) and d = 14; and by formula (156.),

$$b = \frac{5 \times 275 \times 17 \times 16^{3}}{16 \times 5900 \times 0.04 \times 13^{3}} = 11.541$$

The breadth should be 11½ inches full.

384.—Carriage Beam with One Header.—(See. Art. 389.) In Art. 150 a rule (form. 29.) is given for this case, based upon the resistance of the material to rupture. As with a header (Art. 381), so here, the rule given may be resolved into one depending upon the resistance to deflection.

Taking formula (29.), and for a substituting its value as per formula (154.), we have, taking $\{U\}$ instead of $\{U\}$, Art. 340,

$$\frac{Bl}{Fdr}f\left(\frac{5}{16}cl^{2}+gn^{3}\frac{m}{l}\right)=Bbd^{2}$$

$$f\left(\frac{5}{16}cl^{3}+gn^{3}m\right)=Fbd^{3}r$$
(157.)

which is the required rule.

385.—Carriage Beam with one Header, for Dwellings.— In this rule, putting f = 90 and r = 0.03, we obtain

$$3000 \left(\frac{5}{16}cl^{3} + gn^{2}m \right) = Fbd^{3}$$

$$b = \frac{3000 \left(\frac{5}{16}cl^{3} + gn^{2}m \right)}{Fd^{3}}$$
 (158.)

which is a rule for carriage beams with one header, in dwellings and assembly rooms. (See Art. 389.)

386.—Example.—What should be the breadth, in a dwelling, of a carriage beam of average quality white pine, 20 feet long by 12 inches deep, and carrying a header 16 feet long at a point 5 feet from one end? The floor beams among which this carriage beam is placed are set at 16 inches from centres.

Here $c = 1\frac{1}{3}$, l = 20, g = 16, n = 15, m = 5, F = 2900 and d = 12; and by formula (158.)

$$b = \frac{3000 \left[\left(\frac{5}{16} \times 1\frac{1}{3} \times 20^{3} \right) + \left(16 \times 15^{2} \times 5 \right) \right]}{2900 \times 12^{3}} = 12.771$$

The breadth should be 12} inches.

387.—Carriage Beam with One Header, for First-class Stores.—If in formula (157.) we take the value of f equal to 275, and of r equal to 0.04, we shall then have

$$6875 \left(\frac{5}{16}cl^{3} + gn^{3}m \right) = Fbd^{3}$$

$$b = \frac{6875 \left(\frac{5}{16}cl^{3} + gn^{3}m \right)}{Fd^{3}}$$
 (159.)

which is the required rule (see Art. 389).

388.—Example.—Of what breadth, in a first-class store, should be a Georgia pine carriage beam of average quality, 25 feet long, and carrying at 6 feet from one end a header 16 feet long; the floor beams being 15 inches deep, and placed 15 inches from centres?

Here $c = 1\frac{1}{4}$, l = 25, g = 16, n = 19, m = 6, d = 15 and F = 5900; and formula (159.) becomes

$$b = \frac{6875 \left[\left(\frac{1}{16} \times 1\frac{1}{4} \times 25^{3} \right) + \left(16 \times 19^{3} \times 6 \right) \right]}{5900 \times 15^{3}} = 14.073$$

or the breadth required is 14% inches.

389.—Carriage Beam with One Header, for Dweilings— More Precise Rule.—The rules above given (157., 158. and 159.) are not strictly correct: they give a slight excess of material (see Art. 241).

The rule shown in formula (86.), taking $\S U$, Art. 340,

$$4a\frac{mn}{l}(A' + \S U) = Bbd^*$$

is accurate,* and should be the one employed in special cases

Except when h is less than n (Art. 240). In this case the result is slightly in excess, but so slightly that the difference is unimportant.

in which a costly material is used. Substituting for a in this formula, its value, as in formula (154.), we have

$$4\frac{Bl}{Fdr}\frac{mn}{l}(A' + \S U) = Bbd^*$$

$$4mn(A' + \S U) = Fbd^*r \qquad (160.)$$

in which A' is the concentrated load, and U the uniformly distributed load. Formula (160.) may be modified, in the case of a carriage beam, by using for these symbols their values, thus:

From Arts. 92 and 150, $A' = \frac{1}{4} fng$, and $U = \frac{1}{4} cfl$, and hence

$$fmn(ng + \frac{\epsilon}{2}cl) = Fbd^{\epsilon}r$$
 (161.)

which is a more precise general rule for a carriage beam carrying one header.

If, now, we put f equal to 90, and r equal to 0.03, we shall have

$$3000mn (ng + \frac{4}{5}cl) = Fbd^{3}$$

$$b = \frac{3000mn (ng + \frac{4}{5}cl)}{Fd^{3}}$$
 (162.)

which is a more precise rule for carriage beams with one header, in floors of dwellings and assembly rooms.

390.—Example.—Taking the example given in Art. 386, we have m = 5, n = 15, g = 16, $c = 1\frac{1}{3}$, l = 20, F = 2900 and d = 12; and, in formula (162.)

$$b = \frac{3000 \times 5 \times 15 \left(\overline{15 \times 16} + \frac{7}{4} \times 1\frac{1}{3} \times 20\right)}{2900 \times 12^{3}} = 12.273$$

showing that by this, the more exact rule, the breadth should be 12½ inches, while by the former rule it was determined to be 12½ inches.

391.—Carriage Beam with one Header, for First-class Stores—More Precise Rule.—Modifying formula (161.), by putting 275 for f, and 0.04 for r, we have

$$6875mn (ng + \frac{1}{4}cl) = Fbd^{3}$$

$$b = \frac{6875mn (ng + \frac{1}{4}cl)}{Fd^{3}}$$
 (163.)

which is the more precise rule required.

392.—Example.—Applying this rule to the example given in Art. 388, we find, m = 6, n = 19, g = 16, $c = 1\frac{1}{4}$, l = 25, F = 5900 and d = 15; and hence

$$b = \frac{6875 \times 6 \times 19(\overline{19 \times 16} + \frac{5}{4} \times 1\frac{1}{4} \times 25)}{5900 \times 15^{\circ}} = 13.503$$

giving the breadth, by this more precise rule, at 13½ inches. This is nearly half an inch less than by the former rule, which gave for the breadth, 14.073, or 14½ inches nearly.

393.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for Dwellings, etc.—Formula (32.) in Art. 155 gives the relations of the symbols referring to a case in which a carriage beam has to carry two headers, with two sets of tail beams. From this formula we have, taking $\S U$, Art. 340,

$$b = \frac{af}{Bd^{2}} [m\frac{g}{l}(mn + s^{2}) + \frac{5}{16}cl^{2}]$$

If in this equation the value of a, as in formula (154.), be substituted, there results

$$b = \frac{Blf}{Bd^{3}Fdr} \left(\frac{gm (mn + s^{2})}{l} + \frac{5}{16}cl^{3} \right)$$

$$b = \frac{f}{Fd^{3}r} \left[gm (mn + s^{2}) + \frac{5}{16}cl^{3} \right]$$
 (164.)

which is a general rule for these cases.

Putting f = 90 and r = 0.03, we have

$$b = \frac{3000}{Fd^{2}} \left[gm \left(mn + s^{2} \right) + \frac{5}{16}cl^{2} \right]$$
 (165.)

which is a rule for a carriage beam, carrying two headers, with two sets of tail beams, in the floor of a dwelling or assembly room. (See Arts. 402, 405, 415 and 417.)

394.—Example.—Under rule (165.) take the example given in Art. 156, in which F = 5900, d = 14, g = 12, $c = 1\frac{1}{2}$ and l = 25. For m and s there are given 5 and 15, and taking m as the larger, m = 15, n = 10, s = 5 and r = 20; so that (165.) becomes

$$b = \frac{3000}{5900 \times 14^3} \left[\overline{12 \times 15 (\overline{15 \times 10} + 5^2)} + \overline{\frac{5}{16} \times 1\frac{1}{8} \times 25^3} \right] = 7.194$$

or the breadth should be 71 inches.

395.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for First-class Stores.—If, in formula (164), f be put at 275 and r at 0.04, we shall have

$$b = \frac{6875}{Fd^{s}} \left[gm \left(mn + s^{s} \right) + \frac{6}{16}cl^{s} \right] \qquad (166.)$$

which is a rule for a carriage beam carrying two headers, with two sets of tail beams, in a first-class store (see Arts 402, 407 and 417).

396.—Example.—Referring to the same example (And 156) we have F = 5900, d = 14, g = 12, m = 15, n = 10; s = 5, $c = 1\frac{1}{2}$ and l = 25; and the formula is

$$b = \frac{6875}{5900 \times 14^3} \left[\overline{12 \times 15 (15 \times 10 + 5^2) + \frac{5}{16} \times 1\frac{1}{2} \times 25^2} \right] = 16.486$$

or the breadth should be 16½ inches.

397.—Carriage Beam with Two Headers and One Set of Tail Beams.—Formula (34.), in Art. 157, is a rule for a carriage beam with two headers, carrying but one set of tail beams. Substituting, in this formula, for a its value (form. 154.) $\frac{Bl}{Fdr}$, we have, taking $\S U$, Art. 340,

$$\frac{Bfl}{Fdr}\left[\frac{jg}{l}m(n+s) + \frac{5}{16}cl^2\right] = Bbd^2$$

from which

$$b = \frac{f}{Fd^{3}r} [jgm(n+s) + \frac{5}{16}cl^{3}] \qquad (167.)$$

which is a general rule for a carriage beam carrying two headers, with but one set of tail beams, with a given rate of deflection. (See Arts. 402, 409, 411, 419 and 421.)

398.—Carriage Beam with Two Headers and One Set of Tail Beams, for Dwellings.—If, in formula (167.), f be put at 90 and r at 0.03, we shall have

$$b = \frac{3000}{Fd^{2}} \left[jgm (n+s) + \frac{5}{16}cl^{2} \right]$$
 (168.)

a rule for a carriage beam with two headers, carrying only one set of tail beams, in a dwelling or assembly room. (See Arts. 402, 409, 411, 419 and 421.)

399.—Example.—Let it be required to find, under this rule, the breadth of a carriage beam 20 feet long, of spruce of average quality; said beam carrying two headers, each 12 feet long, with tail beams 11 feet long between them, leaving an opening 4 feet wide on one side, and another 5 feet wide on the other side. The beams among which this carriage beam is placed are 12 inches deep and 16 inches from centres.

For the symbols, we have, F = 3500, d = 12, j = 11, g = 12, $c = 1\frac{1}{8}$ and l = 20. Having for m and s the values 4 and 5, we make m equal to the larger one, and therefore m = 5, n = 15 and s = 4. These values substituted in formula (168.) produce

$$b = \frac{3000 \left[\overline{11 \times 12 \times 5 (15 + 4)} + \overline{\frac{5}{16} \times 1\frac{1}{8} \times 20^{3}}\right]}{3500 \times 12^{3}} = 7.874$$

The breadth should be, say 7% inches.

400.—Carriage Beam with Two Headers and One Set of Tail Beams, for First-class Stores.—If, in formula (167.), we put 275 for f and 0.04 for r, we shall have

$$b = \frac{6875}{Fd^{2}} [jgm(n+s) + \frac{6}{16}cl^{2}] \qquad (169.)$$

which is a rule for carriage beams carrying two headers, with one set of tail beams between them, in a first-class store. (See Arts. 402, 409 and 413.)

401.—Example.—What should be the breadth, under this rule, of a carriage beam of average quality Georgia pine, 25 feet long, with two headers each 20 feet long, carrying tail beams 10 feet long between them? The tail beams are so located that there is an opening 10 feet wide at the left-hand end, and one 5 feet wide at the right-hand end. The tier of beams is 15 inches deep and placed 15 inches from centres.

Here F = 5900, d = 15, j = 10, g = 20, $c = 1\frac{1}{2}$ and l = 25. For the values of m and s we have 10 and 5; and 10 being the larger it follows that m = 10, n = 15 and s = 5; and by formula (169.),

$$6875 \left[\frac{10 \times 20 \times 10 (15+5) + \frac{1}{16} \times 1\frac{1}{4} \times 25^{2}}{5900 \times 15^{2}} = 15.918$$

on the breadth should be 15% inches.

402.—Carriage Beam with Two Headers and Two Sets of Tail Beams—More Precise Rules.—The rules for carriage beams given in Arts. 393 to 401 are drawn from formulas which are but close approximations to the truth. The resulting dimensions are always in excess slightly of the true amounts, and the rules therefore are safe.

The rule embodied in formula (92.), however, is deduced from exact premises, and its results are precise.

If for a its value (form. 154.) be substituted in formula (92.), we shall have, taking $\{U, Art. 340,$

$$4\frac{Bl}{Fdr}\left[\frac{5}{16}cfht + b' + \frac{a' - b'}{d'}(h - s)\right] = Bbd^{2}$$

$$b = \frac{4l}{Fd^{2}r}\left[\frac{5}{16}cfht + b' + \frac{a' - b'}{d'}(h - s)\right] \quad (170.)$$

and, as auxiliary thereto,

$$a' = fg \frac{m}{4l} (mn + s^s)$$
 (171.)

$$b' = fg \frac{s}{4l} (rs + m^s)$$
 (172.)

$$h = \frac{1}{2}l + \frac{a' - b'}{\frac{5}{8}cd'f}$$
 (173.)

When h is equal to or exceeds n, then n is to be substituted for h, and the portion

$$b' + \frac{a'-b'}{d'}(h-s)$$

of formula (170.) equals a' (see Art. 248), and the formula itself reduces to

$$b = \frac{4l}{Fd^3r} \left(\frac{5}{16} cfmn + a' \right)$$

Substituting for a' its value (form. 171.) we have

$$b = \frac{4^{l}}{Fd^{3}r} \left[\frac{5}{16}cfmn + fg\frac{m}{4^{l}}(mn + s^{3}) \right]$$

$$b = \frac{4flm}{Fd^{3}r} \left[\frac{5}{16}cn + \frac{g}{4^{l}}(mn + s^{3}) \right]$$

$$b = \frac{fm}{Fd^{3}r} \left[\frac{5}{4}cnl + g(mn + s^{3}) \right] \qquad (174)$$

We have here, in formula (170.), a general rule, and in formula (174.), a rule, general when h equals or exceeds n, for a carriage beam carrying two headers, with two sets of tail beams, with a given deflection.

403.—Example—h less than n.—Let it be shown, under these rules, what should be the breadth of a carriage beam of spruce of average quality, 20 feet long and 12 inches deep, carrying two headers each 12 feet long, so placed as to leave an opening 4½ feet wide; said opening being 7½ feet distant from one wall and 8 feet from the other.

The floor is to carry 100 pounds per superficial foot, with a deflection of 0.03 per foot, and the beams are placed 15 inches from centres.

Here we have f = 100, g = 12, m = 8, l = 20, n = 13, $s = 7\frac{1}{2}$, $r = 12\frac{1}{2}$, $c = 1\frac{1}{4}$, $d' = l - (m+s) = 20 - (8+7\frac{1}{4}) = 20 - 15\frac{1}{2} = 4\frac{1}{2}$, F = 3500 and d = 12.

Preliminary to finding the value of h we have to determine the values of a' and b'.

By formulas (171.) and (172.)

$$a' = \frac{100 \times 12 \times 8}{4 \times 20} (\overline{8 \times 12} + 7.5^{2}) = 18270$$

$$b' = \frac{100 \times 12 \times 7.5}{4 \times 20} (\overline{12.5 \times 7.5} + 8^{2}) = 17746.875$$

$$a' - b' = 523.125$$

From these and formula (173.) we have

$$h = 10 + \frac{523 \cdot 125}{\frac{5}{5} \times 1\frac{1}{4} \times 4 \cdot 5 \times 100} = 11.49$$

So h = 11.49, and since it is less than n (as n equals 12) is therefore to be retained; and we have (form. 170.)

$$b = \frac{4 \times 20}{3500 \times 12^{3} \times 0.03} \left[\frac{\frac{5}{16} \times 1\frac{1}{4} \times 100 \times 11.49 \times 8.51}{\frac{523 \cdot 125}{4 \cdot 5} \times (11.49 - 7.5)} \right] = 9.714$$

or the required breadth is 93 inches.

404.—Example— h greater than n.—What should be the breadth of a white pine carriage beam 20 feet long, 12 inches deep, and carrying two headers 10 feet long—one located at 9 feet from one wall and the other at 6 feet from the other wall; the floor to carry 100 pounds per foot superficial, with a deflection of 0.03 of an inch per foot lineal, and the beams to be placed 15 inches from centres?

Here f = 100, F = 2900, d = 12, r = 0.03, $c = 1\frac{1}{4}$, l = 20 and g = 10. Comparing m and s we have m = 9, m = 11 and s = 6.

Proceeding as in the last article, we find that h exceeds n, therefore, according to Art. 402, we have formula (174.) appropriate to this case; from which

$$b = \frac{100 \times 9}{2900 \times 12^{3} \times 0.03} \left[(\frac{4}{1} \times 1\frac{1}{4} \times 11 \times 20) + 10(9 \times 11 + 6^{3}) \right] = 10.140$$

or the breadth should be 10% inches.

405.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for Dwellings—More Precise Ruic.—If, in formula (174.), f = 90 and r = 0.03, we shall have

$$b = \frac{3000m}{Fd^2} \left[\{ cnl + g (mn + s^2) \} \right]$$
 (175.)

which is a precise rule for carriage beams carrying two headers, with two sets of tail beams, in dwellings and assembly rooms. (See Arts. 393 and 402.)

406.—Example.—An example under this rule may be had in that given in Art. 404; in which we have F = 2900, d = 12, $c = 1\frac{1}{4}$, i = 20, g = 10, m = 9, n = 11 and s = 6. Then by formula (175.)

$$b = \frac{3000 \times 9}{2900 \times 12^3} \left[\left(\frac{5}{4} \times 1\frac{1}{4} \times 11 \times 20 \right) + 10 \left(9 \times 11 + 6^4 \right) \right] = 9 \cdot 126$$

or the breadth should be 94 inches.

407.—Carriage Beam with Two Headers and Two Sets of Tall Beams, for First-class Stores—More Precise Rule.—If, in formula (174.), f = 275 and r = 0.04, we shall have

$$b = \frac{6875m}{Fd^3} \left[\frac{4}{5} cnl + g(mn + s^3) \right]$$
 (176.)

which is a precise rule for carriage beams carrying two headers, with two sets of tail beams, in first-class stores. (See Arts. 395 and 402.)

408.—Example.—What should be the breadth, under this rule, of a carriage beam of Georgia pine of average quality, 23 feet long, 14 inches deep, carrying two headers each 17 feet long, with tail beams on one side 7 feet long, and on the other 10 feet long; the beams being placed 14 inches from centres?

Here F = 5900, d = 14, $c = 1\frac{1}{4}$, l = 23 and g = 17. Taking the larger of the two, 10 and 7, for m, we have m = 10, n = 13, and s = 7; and by formula (176.)

$$b = \frac{6875 \times 10}{5900 \times 14} \left[\left(\frac{5}{4} \times 1\frac{1}{6} \times 13 \times 23 \right) + 17 \left(\frac{10 \times 13}{10 \times 13} + 7^{3} \right) \right] = 14 \cdot 774$$

the breadth should be, say 14\frac{3}{4} inches.

409.—Carriage Ream with Two Headers and One Set of Tail Beams—More Precise Rule.—In a case where there are two openings in the floor, one at each wall, then the two headers carry but one set of tail beams, and these are between the headers. The load at each header is the same; and when g equals the length of header, j the length of tail beams, and f the load per superficial foot, then the load at each end of each header is

$$W = \frac{1}{4} fgj$$

and the expression for the load at one point, as in Art. 153, $\frac{m}{l}(Wn+Vs)$, becomes $\frac{Wm}{l}(n+s)$, and therefore (Art. 243)

$$a' = \frac{fgjm}{\Delta l} (n+s) \tag{177.}$$

$$b' = \frac{fgjs}{4l}(r+m)$$
 (17.8.)

In the case under consideration, these two expressions are auxiliary to formula (170.), in the place of those given in formulas (171.) and (172.), and with h equal to, or exceeding n, formula (170.) becomes

$$b = \frac{4l}{Fd^3r'} \left(\frac{5}{16} cfmn + a' \right)$$

Substituting for a' its value, as in formula (177.), we have

$$b = \frac{4l}{Fd^{3}r'} \left[\frac{5}{16} cfmn + \frac{fgjm}{4l} (n+s) \right]$$

$$b = \frac{fm}{Fd^{3}r'} \left[\frac{5}{4} cnl + gj(n+s) \right]$$
 (179.)

which is a *precise* rule for carriage beams carrying two headers, with one set of tail beams, and with a given rate of deflection. (See Arts. 397, 398 and 402.)

410.—Example.—What should be the breadth of a carriage beam of locust of average quality, 16 feet long and 8 inches deep, carrying two headers of 8 feet length, with one set of tail beams 7 feet long between them, so placed as to leave an opening of 6 feet width at one wall, and another of 3 feet at the other? The floor beams are placed 15 inches from centres, and are to carry 90 pounds per superficial foot, with a deflection of 0.04 of an inch per foot lineal.

We have from this statement f = 90, m = 6, n = 10, l = 16, r = 13, s = 3, $c = 1\frac{1}{4}$, F = 5050, d = 8, r' = 0.04, g = 8 and j = 7.

To test the value of h we have, preliminary thereto, formula (177.), which gives

$$a' = \frac{90 \times 8 \times 7 \times 6}{4 \times 16} \times \overline{10 + 3} = 6142.5$$

and, formula (178.),

$$b' = \frac{90 \times 8 \times 7 \times 3}{4 \times 16} \times \overline{13 + 6} = 4488.75$$

$$a' - b' = 1653.75$$

Then, by formula (173.),

$$h = \frac{1}{2} \times 16 + \frac{1653 \cdot 75}{\frac{5}{8} \times 1\frac{1}{4} \times 7 \times 90} = 11 \cdot 36$$

As n = 10, h exceeds n. We must, therefore, substitute n for h; and by formula (179.) we have

$$b = \frac{90 \times 6}{5050 \times 8^3 \times 0.04} \left[\left(\frac{5}{4} \times 1\frac{1}{4} \times 10 \times 16 \right) + \left(8 \times 7 \times \overline{10 + 3} \right) \right] = 5 \cdot 106$$

or the breadth should be 51, say 5 inches.

411.—Carriage Beam with Two Headers and One Set of Tail Beams, for Dwellings—More Precise Rule.—If, in formula (179.), f = 90 and r' = 0.03, we shall have

$$b = \frac{3000m}{Fd^{1}} [\frac{5}{4}cnl + gj(n+s)]$$
 (180.)

which is a precise rule (in cases where h exceeds n) for carriage beams carrying two headers, with one set of tail beams, in a dwelling or assembly room. (See Arts. 398, 402 and 409.)

412.—Example.—What should be the breadth, in a dwelling, of a carriage beam of spruce of average quality, 18 feet long and 10 inches deep, carrying two headers of 12 feet length, with a set of tail beams between them 7 feet long? The headers are placed so as to leave an opening of 8 feet on one side and 3 feet on the other, and the beams are set 15 inches from centres.

Here f = 90, g = 12, j = 7, m = 8, n = 10, s = 3, r = 15, l = 18, F = 3500, d = 10, r' = 0.03 and $c = 1\frac{1}{4}$.

Preliminary to seeking the value of k we find, by formulas (177.) and (178.),

$$a' = \frac{90 \times 12 \times 7 \times 8}{4 \times 18} (10+3) = 10920$$

$$b' = \frac{90 \times 12 \times 7 \times 3}{4 \times 18} (15+8) = 7245$$

$$a' - b' = 3675$$

Now, by formula (173.),

$$h = \frac{3675}{\frac{1}{2} \times 18} + \frac{3675}{\frac{1}{8} \times 1\frac{1}{4} \times 7 \times 90} = 16.467$$

But n = 10; therefore n is to be used in the place of h, and formula (180.) is the proper one to use in this example. This latter formula gives us

$$b = \frac{3000 \times 8}{3500 \times 10^3} \left[\left(\frac{5}{4} \times 1\frac{1}{4} \times 10 \times 18 \right) + \left(12 \times 7 \times 10 + 3 \right) \right] = 9 \cdot 417$$

Thus the breadth should be $9\frac{8}{5}$ inches; or the beam be $9\frac{8}{5} \times 10$ inches.

413.—Carriage Beam with Two Headers and One Set of Tail Beams, for First-class Stores—More Precise Rule.—
If, in formula (179.), f = 275 and r = 0.04, we shall have

$$b = \frac{6875m}{Fd} \left[\frac{5}{4} cnl + gj(n+s) \right]$$
 (181.)

which is a *precise* rule, when h exceeds n, for a carriage beam carrying two headers, with one set of tail beams, in a first-class store. (See *Arts.* 400 and 402.)

414.—Example.—The example given in Art. 412 may be used to exemplify this rule, excepting the depth, which we will put at 14 inches instead of 10.

Formulas (180.) and (181.) are alike, with the exception of the numerical constant. The result found in Art. 412, b = 9.417, multiplied and divided to correct the constant, will give the result required in this case. The constant 6875 is to take the place of 3000, and the depth 14 is to replace 10. With these changes, we have

$$b = 9.417 \times \frac{6875}{3000} \times \frac{1000}{2744} = 7.865$$

or the breadth should be 7.86; say 7\frac{1}{8} inches.

415.—Carriage Beam with Two Headers, Equidistant from Centre, and Two Sets of Tail Beams—Precise Rule.— In case the opening in the floor be at the middle, leaving tail beams of equal length on either side, then the moments of the two concentrated loads upon the carriage beam are equal, or a' = b' and, in formula (170.),

$$\frac{a'-b'}{d'}(h-s)=\frac{0}{d'}(h-s)=0$$

and the formula itself becomes

$$b = \frac{4l}{Fd^3r} \left(\frac{5}{16} cfht + b' \right)$$
 (182.)

in which b' represents the combined effect of the two loads, as acting at the location of either of them.

This effect is shown (Art. 153) to be

$$b' = W \frac{mn}{I} + V \frac{ms}{I} = \frac{m}{I} (Wn + Vs)$$

In the case under consideration, $W = V \cdot \text{and} \quad m = s$, and therefore

$$b' = W \frac{m}{l} (n+m) = W \frac{ml}{l} = Wm$$

Now, W represents the weight concentrated in one end of one of the headers. The load on a header is $\frac{1}{2}fgm$, and the load at one end of the header is $\frac{1}{2}fgm$; therefore

$$b' = \frac{1}{4} fgm^2$$

and formula (182.) becomes

$$b = \frac{4^{l}}{Fd^{3}r} \left(\frac{5}{16} cfht + \frac{1}{4} fgm^{3} \right)$$

$$b = \frac{fl}{Fd^{3}r} \left(\frac{5}{4} cht + gm^{3} \right)$$

By formula (173.)

$$h = \frac{1}{2}l + \frac{a'-b'}{\frac{5}{8}cd'f}$$

and since in this case a' - b' = 0

$$h = \frac{1}{2}l = t$$
 and
$$\frac{5}{4}cht = \frac{5}{8}cl \times \frac{1}{2}l = \frac{5}{16}cl^2$$
 and therefore
$$b = \frac{fl}{Fd^3r} \left(\frac{5}{16}cl^2 + gm^2\right)$$
 (183.)

which is a *precise* rule for carriage beams carrying two headers, equidistant from the centre, with two sets of tail beams, and with a given rate of deflection. (See *Arts.* 393, 395 and 402.)

416.—Example.—Under this rule, what should be the breadth of a Georgia pine carriage beam of average quality. 20 feet long and 12 inches deep, to carry two headers each

12 feet long; the headers so placed as to leave an opening 6 feet wide in the middle of the width of the floor? The floor beams are set 16 inches from centres, and are to carry 200 pounds per foot superficial, with a deflection of 0.04 of an inch per foot lineal.

Here
$$l=20$$
, $m=\frac{l-d''}{2}=\frac{20-6}{2}=7$; $g=12$, $d=12$,

 $c = 1\frac{1}{8}$, F = 5900, f = 200 and r = 0.04; and by formula (183.)

$$b = \frac{200 \times 20}{5900 \times 12^3 \times 0.04} \left[\left(\frac{5}{16} \times 1\frac{1}{3} \times 20^3 \right) + \left(12 \times 7^3 \right) \right] = 7.402$$

or the breadth should be 78 inches.

417.—Carriage Beams with Two Headers, Equidistant from Centre, and Two Sets of Tail Beams, for Dwellings and for First-class Stores—Precise Rules.—If, in formula (183.), f = 90 and r = 0.03, we shall have

$$b = \frac{3000l}{Fd^3} \left(\frac{5}{16}cl^2 + gm^2 \right) \tag{184.}$$

which is a *precise* rule for carriage beams carrying two headers, equidistant from the centre, with two sets of tail beams, in a dwelling or assembly room. (For an example, see Art. 418.) But if, instead, f = 275 and r = 0.04, then we shall have

$$b = \frac{6875l}{Fd^2} (\frac{5}{16}cl^2 + gm^2)$$
 (185.)

which is a precise rule for carriage beams carrying two headers, equidistant from the centre, with two sets of tail beams, in a first-class store. (See Arts. 393, 395 and 402.)

290

418.—Examples.—Formulas (184.) and (185.) are alike, except in the numerical coefficient. One example will therefore suffice for an exemplification of the two. Let it be required to show what, in a dwelling, should be the breadth of a carriage beam, 20 feet long and 12 inches deep, of average quality of spruce, carrying two headers 10 feet long; these headers being so placed as to leave at the middle of the width of the floor an opening 8 feet wide. The beams are to be placed 16 inches from centres.

Here we have l = 20, m = 6, g = 10, d = 12, $c = 1\frac{1}{8}$ and F = 3500; and by formula (184.)

$$b = \frac{3000 \times 20}{3500 \times 12^3} \left[\left(\frac{5}{16} \times 1\frac{1}{3} \times 20^3 \right) + \left(10 \times 6^3 \right) \right] = 5 \cdot 225$$

or the breadth should be, say 5½ inches.

For a first-class store this carriage beam, if of Georgia pine, would be required to be $7 \cdot 103$, say $7\frac{1}{8}$ inches broad. This result is found by eliminating the two constants 3000 and 3500 in the above and replacing them by those required by the new conditions, namely, 6875 and 5900. Doing this, we find

$$b = 5.225 \times \frac{6875}{3000} \times \frac{3500}{5900} = 7.103$$

419.—Carriage Beam with Two Headers, Equidistant from Centre, and One Set of Tail Beams—Precise Rule.—In some cases the wells or openings are at the wall on each side, and the tail beams at the middle of the floor. In this arrangement, if j equals the length of the tail beams, f(j) will equal the load at the end of one header.

By Art. 415, b' = Wm, from which

$$b' = Wm = \frac{1}{4}fgjm$$

and formula (182.) becomes

$$b = \frac{4^l}{Fd^2r} \left(\frac{5}{16} cfht + \frac{1}{4} fgjm \right)$$

and since (Art. 415) $h = t = \frac{1}{2}l$, therefore

$$\frac{5}{16}cht = \frac{5}{54}cl^2$$

By substituting this in the above,

$$b = \frac{4l}{Fd^3r} \left(\frac{5}{54} cfl^2 + \frac{1}{4} fgjm \right)$$

$$b = \frac{fl}{Fd^3r} \left(\frac{5}{15} cl^2 + gjm \right)$$
 (186.)

which is a *precise* rule for carriage beams, carrying two headers, equidistant from the centre, with one set of tail beams, the rate of deflection being given. (See *Arts.* 397, 398, 402, 409 and 411.)

420.—Example.—What should be the breadth of a carriage beam of hemlock of average quality, 16 feet long and 11 inches deep, carrying two headers, each 10 feet long, placed equidistant from the centre of the width of the floor, and having between them one set of tail beams 6 feet long? The floor beams, placed 15 inches from centres, are to carry 100 pounds per foot superficial, with a deflection of 0.035 of an inch per foot lineal.

Here we have l = 16, m = 5, g = 10, j = 6, d = 11, $c = 1\frac{1}{4}$, F = 2800, f = 100 and r = 0.035; and by formula (186.)

$$b = \frac{100 \times 16}{2800 \times 11^{2} \times 0.035} \left[\left(\frac{5}{16} \times 1\frac{1}{4} \times 16^{2} \right) + \left(10 \times 6 \times 5 \right) \right] = 4.907$$

or the breadth should be 47 inches.

421.—Carriage Beams with Two Headers, Equidistant from Centre, and One Set of Tail Beams, for Dwellings and for First-ciass Stores—Precise Rules.—If, in formula (186.), f = 90 and r = 0.03, then we shall have

$$b = \frac{3000l}{Fd^3} \left(\frac{5}{16}cl^2 + gjm \right) \tag{187.}$$

which is a *precise* rule for carriage beams, carrying two headers, with one set of tail beams between them, at the middle of the floor, in a dwelling or assembly room.

For an example, see Art. 422.

But if, instead of these, f = 275 and r = 0.04, we shall have

$$b = \frac{6875l}{Fd^3} \left(\frac{5}{16}cl^3 + gjm \right) \tag{188.}$$

which is a *precise* rule for carriage beams, carrying two headers, with one set of tail beams between them, at the middle of the floor, in a first-class store.

422.—Example.—Formulas (187.) and (188.) are alike, except in the numerical coefficient. One example will suffice to show the application of both.

Take one coming under formula (187.), and in which l=20, m=6, g=10, j=8, d=12, $c=1\frac{1}{8}$ and $F=35\infty$. Then, by the formula,

$$b = \frac{3000 \times 20}{3500 \times 12^3} \left[\left(\frac{5}{16} \times 1\frac{1}{3} \times 20^3 \right) + (10 \times 8 \times 6) \right] = 6.415$$

or the breadth should be 63 inches full.

423.—Beam with Uniformly Distributed and Three Concentrated Loads, the Greatest Strain being Outside.—In Art. 256, formula (96.) is a general rule for this case, but

based upon the resistance to rupture. This rule may be modified so that it shall be based upon the resistance to flexure. To this end let a, in formula (96.), be substituted by its value in formula (154.), $\frac{Bl}{Fdr}$, and we have, taking U, Art. 340,

$$b = \frac{4m}{Fd^3r} (\S Un + A'n + B's + C'v) \qquad (189.)$$

which is a rule, based upon the resistance to *flexure*, for a beam uniformly loaded, and also carrying three concentrated loads, the largest of which is *not* between the other two.

424.—Example.—What ought to be the breadth of a beam of Georgia pine of average quality, 20 feet long and 12 inches deep, carrying an equally distributed load of 4000 pounds, together with three concentrated loads, namely, 7000 pounds at 7 feet from the right-hand end, 4000 pounds at 7 feet from the left-hand end, and 3000 pounds at 3 feet from the same end. (See Art. 264.) Allotting the symbols to accord with the arrangement required under rule (189.), (the largest strain, as in Fig. 55, not between the other two), we have U = 4000, A' = 7000, B' = 4000, C' = 3000, l = 20, m = 7, n = 13, s = 7, v = 3, d = 12 and F = 5900, and let r = 0.04; and by formula (189.)

$$b = \frac{4 \times 7}{5900 \times 12^{3} \times 0.04} \left[(\frac{5}{8} \times 4000 \times 13) + (7000 \times 13) + (4000 \times 7) + (3000 \times 3) \right] = 11.020$$

or the breadth should be II inches.

425.—Carriage Beam with Three Headers, the Greatest Strain being at Outside Header.—If, in formula (97.), (Art. 258), we substitute for a its value, $\frac{Bl}{Fdr}$ (form. 154.), we shall have, taking § U, Art. 340.

$$b = \frac{mf}{Fd^2r} \left[\frac{5}{4} cnl + g(mn + s^2 - v^2) \right] , \quad (190.)$$

which is a rule, based upon the resistance to flexure, for carriage beams carrying three headers, with two sets of tail beams, so located (as in Figs. 54 and 55) that the header at which there is the greatest strain shall not be between the other two headers.

riage beam of Georgia pine of average quality, 20 feet long and 12 inches deep, carrying three headers 15 feet long, two of them, for a light-well 6 feet wide, located centrally as to the width of the floor, and the third header, at the side of an opening for a stairway 3 feet wide at one of the walls? The floor beams, placed 15 inches from centres, are to carry 200 pounds per superficial foot, with a deflection of 0.04 of an inch per foot lineal. (See Art. 264.)

Allotting the symbols as in Fig. 55, we have l=20, m=7, n=13, s=7, v=3, g=15, d=12, $c=1\frac{1}{2}$, F=5900, f=200 and r=0.04; and by formula (190.) we have

$$b = \frac{7 \times 200}{5900 \times 12^3 \times 0.04} \left[\left(\frac{5}{4} \times 1\frac{1}{4} \times 13 \times 20 \right) + 15 \left(\frac{1}{7} \times 13 + 7^2 - 3^2 \right) \right] = 8.140$$

or the breadth should be 81 inches.

427.—Carriage Beam with Three Headers, the Greatest train being at Outside Header, for Dwellings.—If, in forula (190.), f=90 and r=0.03, we shall have

$$b = \frac{3000m}{Fd^{3}} [\frac{5}{4}cnl + g(mn + s^{3} - v^{3})] \qquad (191.)$$

hich is a rule, based upon the resistance to flexure, for carage beams in dwellings and assembly rooms, to carry tree headers, with two sets of tail beams, so located that is in Fig. 55) the header at which there is the greatest strain tall not be between the other two.

For an example, see Art. 429.

428.—Carriage Beam with Three Headers, the Greatest train being at Outside Header, for First-class Stores.—If, formula (190.), f = 275 and r = 0.04, we shall have

$$b = \frac{6875m}{Fd^3} \left[\frac{5}{4} cnl + g(mn + s^2 - v^2) \right]$$
 (192.)

hich is a rule, based upon the resistance to flexure, for carage beams in first-class stores, to carry three headers, with vo sets of tail beams, so located that (as in Fig. 55) the eader at which there is the greatest strain shall not be cated between the other two.

429.—Examples.—Formulas (191.) and (192.) are alike, cept in the numerical coefficient, which, in the rule for vellings and assembly rooms, is 3000, while for first-class ores it is 6875. An example under one rule will serve to ustrate the other, by a simple substitution of the proper efficient.

As an example under rule (191.): What should be the

breadth, in a dwelling, of a carriage beam of white pine of average quality, 20 feet long and 12 inches deep, carrying three headers 12 feet long, so placed as to provide an opening 4 feet wide for a stairs at one wall, and a light-well 6 feet wide at the middle of the width of the floor? The floor beams are placed 16 inches from centres. (See Art. 264.)

Allotting the symbols as in Fig. 55 we have l=20, m=7, n=13, s=7, v=4, g=12, d=12, $c=1\frac{1}{3}$ and F=2900; and by formula (191.)

$$b = \frac{3000 \times 7}{2900 \times 12^3} \left[\left(\frac{5}{4} \times 1\frac{1}{3} \times 13 \times 20 \right) + 12 \left(\frac{7 \times 13}{7 \times 13} + 7^3 - 4^3 \right) \right] = 8.052$$

or the breadth should be 8 inches.

This is the breadth when of white pine, and in a dwelling. If, instead, it be required of Georgia pine, and for a first-class store, then the breadth just obtained, treated by the proper constant and numerical coefficient, and at the same time relieved from those applying to the previous case, will be

$$b = 8.052 \times \frac{6875}{3000} \times \frac{2900}{5900} = 9.070$$

or the breadth, when of Georgia pine, and for a first-class store, should be 9_8^1 inches.

430.—Beams with Uniformly Distributed and Three Concentrated Loads, the Greatest Strain being at Middle Load.—In Art. 262 a rule is given for beams uniformly loaded, and also carrying three concentrated loads, the middle one of which produces the greatest strain. This rule is based upon the resistance to rupture. It may be modified to

depend upon the resistance to *flexure* by substituting, in formula (99.), for a its value $\frac{Bl}{Fdr}$ (form. 154.), (taking § U, Art. 340), thus

 $b = \frac{4}{Fd^{3}r} \left[m(\frac{5}{8}Un + A'n + B's) + C'nv \right] \quad (193.)$

which is a rule, based upon resistance to flexure, for beams carrying a uniform load (U) and three concentrated loads (A', B') and (A'), the middle one of which produces the greatest strain of the three, as in Fig. 56.

431.—Example.—What should be the breadth of a beam of Georgia pine of average quality, 20 feet long and 14 inches deep, and carrying 4000 pounds uniformly distributed, 6000 pounds at 4 feet from one end, 6000 pounds at 9 feet from the same end, and 7000 pounds at 6 feet from the other end; with a deflection of 0.04 of an inch per lineal foot? (See Art. 264.)

Assigning the symbols as per figure, we have, U=4000, A'=6000, B'=7000, C'=6000, l=20, m=9, n=11, s=6, v=4, d=14, F=5900 and r=0.04; and by formula (193.),

$$b = \frac{4}{5900 \times 14^{3} \times 0.04} \left[9 \left(\frac{5}{8} \times 4000 \times 11 + \overline{6000 \times 11} + \overline{7000 \times 6} \right) + (6000 \times 11 \times 4) \right] = 9.163$$

or the breadth should be 91 inches.

432.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header.—If, in formula (106.), (Art. 267), there be substituted for a its value $\frac{Bl}{Fdr}$ (form. 154.) we shall have, taking $\frac{5}{8}U$, Art. 340,

$$b = \frac{f}{Fd^{2}r} \left[m \left(\frac{5}{4} cnl + gs^{2} \right) + gn \left(m^{2} - v^{2} \right) \right] \quad (194.)$$

which is a rule, based upon resistance to flexure, for carriage beams carrying three headers and two sets of tail beams, so placed (as in Fig. 56) that of the strains produced at the headers, the greatest shall be at the header which is between the other two.

433.—Example.—What should be the breadth of a carriage beam, 20 feet long and 12 inches deep, of Georgia pine of average quality, carrying three headers 14 feet long, so placed as to provide a stair opening 4 feet wide at one wall, and a light-well 5 feet wide 6 feet from the other wall? The floor beams, placed 15 inches from centres, are to carry 200 pounds per foot superficial, with a deflection of 0.04 of an inch per foot lineal. (See Art. 264.)

Assigning the symbols as per Fig. 56 we have, l=20, m=9, n=11, s=6, v=4, g=14, d=12, $c=1\frac{1}{4}$, F=5900, f=200 and r=0.04; and by formula (194.)

$$b = \frac{200}{5900 \times 12^{3} \times 0.04} \left[9(\frac{5}{4} \times 1\frac{1}{4} \times 11 \times 20 + 14 \times 6^{2}) + (14 \times 11 \times 9^{2} - 4^{2}) \right] = 8.651$$

or the breadth should be, say 85 inches.

434.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for Dwellings.—If, in formula (194.), f = 90 and r = 0.03, we shall have

$$b = \frac{3000}{Fd^{2}} \left[m \left(\frac{5}{4} cnl + gs^{2} \right) + gn \left(m^{2} - v^{2} \right) \right] \quad (195.)$$

which is a rule, based on resistance to flexure, for carriage beams in dwellings and assembly rooms, to carry three headers, with two sets of tail beams relatively placed as in Fig. 56, so that, of the three strains produced at the headers, the greatest shall be at the header which is between the other two. (For an example, see Art. 436.)

435.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for First-class Stores.—If, in formula (194.), f = 275 and r = 0.04, then we shall have

$$b = \frac{6875}{Fd^2} \left[m \left(\frac{5}{4} cnl + gs^2 \right) + gn \left(m^2 - v^2 \right) \right] \quad (196.)$$

which is a rule, based on resistance to flexure, for carriage beams in first-class stores, to carry three headers, with two sets of tail beams relatively placed as in Fig. 56, so that, of the three strains produced at the headers, the greatest shall be at the header which is between the other two.

436.—Example.—Formulas (195.) and (196.) being alike, except in the numerical coefficient, a single example will suffice to illustrate them.

In a dwelling, what should be the breadth of a carriage beam of oak of average quality, 20 feet long and 12 inches deep, to carry three headers 15 feet long, with two sets of tail beams, so placed as to provide a stair opening 4 feet wide at one wall, and a light-well 7 feet wide, distant 5 feet from the other wall? The beams are to be placed 15 inches from centres. (See Art. 264.)

Arranging the symbols in the order in which they appear in Fig. 56, we have, l=20, m=8, n=12, s=5, v=4, g=15, d=12, $c=1\frac{1}{4}$ and F=3100; and, by formula (195.),

$$b = \frac{3000}{3100 \times 12^3} \left[8(\frac{1}{4} \times 1\frac{1}{4} \times 12 \times 20 + 15 \times 5^2) + (15 \times 12 \times 8^3 - 4^3) \right] = 8 \cdot 199$$

or the breadth should be, say 81 inches.

QUESTIONS FOR PRACTICE.

- 437.—In a dwelling: What should be the depth of white pine beams of average quality; they being 18 feet long and 3 inches broad, placed 18 inches from centres, and allowed to deflect 0.03 of an inch per foot?
- 438.—In a first-class store: What should be the breadth of the floor beams of spruce of average quality, 19 feet long, 13 inches deep, placed 13 inches from centres, and with a deflection of 0.04 of an inch per foot?
- 439.—In a dwelling: What ought to be the breadth of a header of white pine of average quality, 14 feet long and 13 inches deep, carrying one end of a set of tail beams 15 feet long, and with a rate of deflection of 0.03 of an inch per foot?
- 440.—In the floor of an assembly room in which the beams are 15 inches from centres: What should be the breadth of a carriage beam of spruce of average quality, 20 feet long and 12 inches deep, carrying one header 13 feet long, located at 5 feet from open end? The deflection allowable is 0.03 of an inch per foot.
- 441.—In the floor of a first-class store, where the beams are 15 inches deep and set 14 inches from centres: What should be the breadth of a carriage beam 24 feet long, of Georgia pine of average quality, carrying two headers

16 feet long, located, one at 9 feet from one end, and the other at 7 feet from the other end, with two sets of tail beams? The deflection is 0.04 of an inch per foot.

442.—In the floor of a first-class store, with beams 16 inches deep placed 15 inches from centres: What should be the breadth of a carriage beam of Georgia pine of average quality, 26 feet long, and carrying three headers 18 feet long, located as in Fig. 54, one at 4 feet from one wall, another at 8 feet from the same wall, and the third at 8 feet from the other wall? The deflection to be 0.04 of an inch per foot.

CHAPTER XVIII.

BRIDGING FLOOR BEAMS.*

ART. 443.—Bridging Defined.—Bridging is a system of bracing floor beams. Small struts are cut to fit between each pair of beams, and secured by nails or spikes: as shown in Fig. 65. The effect of this bracing is decidedly



Fig. 65.

beneficial in sustaining any concentrated weight upon a floor. The beam immediately beneath the weight is materially as-

^{*} The principles upon which this chapter is based the author first made public in an article which appeared in the Scientific American, July 26th, 1873, entitled "On Girders and Floor Beams—The Effect of Bridging."

sisted, through these braces, by the beams on each side of it.

It is customary to insert rows of cross-bridging at every five to eight feet in the length of the beams.

It is the usual practice, where the ceiling of a room is plastered, to attach the plastering laths to cross-furring, or narrow strips of boards crossing the beams at right angles, and nailed to their bottom edge. These strips are set at, say 12 inches from centres, and when firmly nailed to the beams act as a tie to sustain the lateral thrust of the bridging struts. The floor plank at the top serve a like purpose.

444.—Experimental Test.—To test the effect of bridging, about three years since I constructed a model, and subjected it to pressure. It was made upon a scale of 1½ inches to the foot, or ½ of full size, and represented a floor of seven beams placed 16 inches from centres, each beam being 3.10 inches and 14¾ feet long. These beams were connected by two rows of cross-bridging, and secured against lateral movement by strips representing floor plank and ceiling boards, which were nailed on top and beneath. There were four strips at each row of bridging, two above and two below.

Before putting these beams in position in the model, I submitted each beam to a separate test, and ascertained that to deflect it one tenth of an inch required from 37 to 40 pounds, or on the average 38½ pounds.

With the model completed, the beams being bridged, it required a pressure of 155# pounds applied at the centre of the middle beam to deflect it as before, one tenth of an inch. And while this pressure deflected the central beam to this extent, the beam next adjoining on each side was deflected o 0808 of an inch, the ones next adjoining these were each deflected o 0617 of an inch, while the two outside beams

were each depressed 0.0425 of an inch. Had there been more than seven beams, and all bridged together, the effect would doubtless have been still better.

445.—Bridging—Principles of Resistance.—The assistance contributed by the adjacent beams to a beam under pressure may be computed, but preliminary thereto we have these considerations, namely:

First.—The deflections of a beam are (within the limits of elasticity) in proportion to the weights producing the deflections. Thus, if one hundred pounds deflect a beam one tenth of an inch, two hundred pounds will deflect it two tenths of an inch. From which, knowing the deflection of a beam, we can compute the resistance it offers.

Second.—The resistance thus offered, being at a distance from the beam suffering the direct pressure, is not so effectual as it would be were it in direct opposition to the pressure. It is diminished in proportion to its distance from that beam.

446.—Resistance of a Bridged Beam.—Based upon the two preceding considerations, we will construct a rule by which to measure the increase of resistance derived from the adjacent beams through their connection by cross-bridging.

Let Fig. 66 represent the cross-section of a tier of floor

beams connected by cross-bridging, in which C is the location of a concentrated weight, AB the distance on one side of the weight to which the deflecting influence acting




Fig. 66.

through the cross-bridging is extended, BC the deflection at the weight, and DE the deflection of one of the beams E, caused by the weight at C. The triangles ABC and ADE are similar, and their sides are in proportion. Putting p for AB, m for AD, a' for BC, and b' for DE, we have

$$p:a'::m:b'=a'\frac{m}{p}$$

This is the measure of the deflection at E, or at any one of the beams the distance of which from A is equal to m_i , and, since the deflections are as the weights producing them, therefore b', the deflection at E, measures the strain there, when a' measures that at C.

It is required, however, to know not only the resistance offered by each beam, but also what weight r, acting at C, would be required to overcome this resistance. The line AB (or p) may be considered to serve as a lever, having its fulcrum at A. The weight r, at B, acting in the line BC, is opposed at D by b', the resistance of the beam at E, acting in the line ED, with the leverage m. The weight r will act with the moment rp, and b' will resist with the moment b'm. Putting these moments in equilibrium, we have b'm = rp, or $n = b'\frac{m}{p}$.

In this, substituting for b' its value as above found, we have

$$r = a' \frac{m}{p} \times \frac{m}{p}$$

$$r = a' \frac{m^{s}}{p^{s}} \qquad (197.)$$

This weight r represents the effect at C of the resistance to deflection of any beam whose distance from A is equal to m, and where a' equals the load borne by the beam at B, and p is put for the distance AB.

447.—Summing the Resistances.—Let the distance from centres between the floor beams be represented by c, and the number of spaces from A to any beam, as, for example, that at D, by n; then m = nc, and substituting this value for m in (197.) we have

$$r = a' \frac{n^2 c^2}{p^2} \cdot r = n^2 \frac{a' c^2}{p^2} \quad (198.)$$

In this expression, a', c' and p' are constants, or quantities which remain constant for the several values of r which are to be obtained from the resistances of the several

beams. For convenience, put t for $\frac{a'c'}{p'}$ and then

$$r=n^{t}t \qquad \qquad (199.)$$

With this expression, the various values of r may be obtained and grouped together. In doing this, we have, for the first beam from A, n = 1; for the second, n = 2; for

the third, n = 3, and so on to the middle or point of greatest depression. Therefore the whole resistance will be

$$R' = t + 2^{3}t + 3^{3}t + 4^{3}t + \text{etc.}$$

 $R' = t (1 + 4 + 9 + 16 + \text{etc.})$

This gives the resistance on one side of the point C. The beams on the other side afford a like resistance; and the sum of the two resistances will be

$$R = 2t (1 + 4 + 9 + 16 + \text{etc.})$$

$$R = 2 \frac{a'c''}{p''} (1 + 4 + 9 + 16 + \text{etc.}) \qquad (200.)$$

448.—Example.—When a concentrated weight deflects six beams on each side of it, they being placed 16 inches from centres: What will be the amount of resistance to deflection offered by the twelve beams, the beam upon which the weight rests being capable of sustaining alone, unaided by the adjoining beams, 1000 pounds?

Here a' = 1000, $c = 1\frac{1}{8}$ and $p = 7 \times 1\frac{1}{8} = 9\frac{1}{8}$. Therefore, by formula (200.),

$$R = \frac{2 \times 1000 \times 1\frac{1}{8}^{2}}{9\frac{1}{8}^{2}} (1 + 4 + 9 + 16 + 25 + 36) = 3714 \cdot 3$$

This 3714 pounds is the resistance offered by the twelve beams, through the means of bridging, and is nearly four times the amount that the centre beam, unaided by the bridging, would carry with a like deflection. The combined resistance of all the beams would be 3714 + 1000 = 4714 pounds.

how many beams on each side will be affected, and by their resistance contribute in aiding the beam at C, will depend upon circumstances. The bridging will be effective in resisting deflection in proportion to the elevation of the angle at which the bridging pieces are placed, which will be directly as the depth of the beams and inversely as their distance apart. It will also be in proportion to the faithfulness with which the work of bridging is executed. From these considerations, and from the experiment of Art. 444, we conclude that, in well-executed work, we shall have

$$p = \frac{d}{c}$$

An equally distributed load upon a floor beam is represented (Art. 92) by cfl. A load at the centre of the beam producing an equal effect will be $\frac{1}{2}$ of this, or $\frac{1}{2}$ cfl. The symbol a' (form. 200.) represents the load at the middle of a floor beam, and therefore

$$a' = \frac{5}{8}cfl$$

These values of p and a' may be substituted for these symbols in formula (200.), and the result will be

$$R = 2 \frac{\frac{6}{8} cflc^3}{\left(\frac{d}{c}\right)^3} (1 + 4 + 9 + \text{etc.})$$
 or,

$$R = \frac{5c^{3}fl}{4d^{2}} (1 + 4 + 9 + \text{etc.})$$
 (201.)

In this rule R equals the additional resistance to a concentrated weight on a beam, obtained from adjacent beams through the cross-bridging.

450.— Number of Beams Affording Assistance.— The value of p, as above, is $\frac{d}{c}$. The symbol n being put for the number of spaces on each side of the beam sustaining the concentrated weight, over which this weight exerts an influence; or p, the distance AB of Fig. 66; and c for the distance apart from centres at which the beams are placed; then, $p = \frac{d}{c} = nc$; from which we have

$$n=\frac{d}{c^*} \qquad (202.)$$

To apply this rule: How many beams on each side of a concentrated weight would contribute towards sustaining it, when they are 12 inches deep, and 16 inches from centres? Here we have d = 12 and $c = 1\frac{1}{8}$, and therefore

$$n = \frac{12}{1\frac{1}{8}} = 6\frac{8}{4}$$
 say 7 spaces.

In seven spaces, six beams will be affected.

Weights.—The results shown in Art. 448 illustrate the advantage of cross-bridging in resisting concentrated weights, and show the importance of always having floor beams bridged, and the work faithfully executed. The advantage, however, of cross-bridging inheres only in the case of concentrated weights. For, although in the example of Art. 448, the 13 beams sustained by their united resistance a concentrated weight of 4714 pounds, yet it will be observed that this is not the limit of their power, for they are each capable of sustaining 1000 pounds placed at the middle, or together, 13,000 pounds; nearly three times the previous amount.

452.—Increased Resistance Due to Bridging.—A useful application of the results of this investigation is found in determining the amount of concentrated weight which may be borne upon a floor beam. As an example: In a dwelling with well-bridged floor beams of an average quality of white pine, 3×10 inches, and 16 feet long, what concentrated weight may be safely sustained at the middle of one of them?

The distance from centres at which these beams should be placed is had by formula (144.), Art. 362,

$$c = \frac{ibd^3}{l^3} = \frac{1.55 \times 3 \times 10^3}{16^3} = 1.135$$

the value of i being taken as found in Art. 361.

With the above value, c = 1.135, we may, by formula (202.), find the distance to which the effect of the weight extends on each side, thus:

$$n = \frac{d}{c^2} = \frac{10}{1 \cdot 135^2} = \frac{10}{1 \cdot 289} = 7 \cdot 762$$

say 8 spaces, or 7 beams. The symbols of formula (201.). applied in this case, will be as follows: c = 1.135, f = 90, l = 16 and d = 10, and the squares in the parenthesis extend to 7 places. Therefore

$$R = \frac{5 \times \overline{1 \cdot 135}^{\circ} \times 90 \times 16}{4 \times 10^{2}} (1 + 4 + 9 + 16 + 25 + 36 + 49)$$

$$R = 18 \times \overline{1 \cdot 135} \times 140$$

The product of these factors, one of them being raised to a high power, will best be obtained by logarithms, thus:

The product of the factors, or the value of R, is therefore equal to 4746.6 pounds. This is the *increased* resistance. The resistance offered by the beam upon which the weight is laid equals (Art. 449)

$$\frac{\$cfl = \frac{5 \times 1 \cdot 135 \times 90 \times 16}{8} = 1021 \cdot 5}{8}$$
To this, adding the increase = $\frac{4746 \cdot 6}{5768 \cdot 1}$

as the total resistance to a concentrated load at the middle of the beam, when assisted by 7 beams on each side by cross-bridging.

CHAPTER XIX.

ROLLED-IRON BEAMS.

ART. 453.—Iron a Substitute for Wood.—When the beams composing a floor are of wood, they are of rectangular form in cross-section. Investigations into the philosophy of the transverse strain, by which the importance of depth was developed, led to the use of beams of which the rectangle of cross-section was narrow and high. Owing to the liability, in wooden beams as generally used, of destruction by conflagration and by other causes, iron was introduced as a substitute. The greater cost of this material over that of wood, made it important, now more than ever, to give to the beam that shape which should prove the strongest.

454.—Iron Beam-Its Progressive Development.—In the use of iron as a floor beam, economical considerations



Fig. 67.

reduced the breadth until the beam became weak laterally. To remedy this defect, metal was added at the top and bottom in the form of horizontal plates, and these were connected to the thin vertical beam by angle irons as in Fig. 67; the whole forming what is known as the plate beam or girder. This expedient served not only to stiffen the thin

vertical beam laterally, but added very greatly to its ab-

solute strength. The added material had been placed just where it would do the greatest possible good; at a point far removed from the neutral axis of the beam.

455.—Rolled-Iron Beam—Its Introduction.—The increase of strength obtained in the plate beam (Fig. 67) was so great that it became popular. To supply the demand, iron manufacturers, at great expense, made rolls similar to those for making railroad iron, by which they were enabled to furnish beams (Fig. 68) rolled out in one piece, with all the best features of the plate beam, and which could be much more

readily and cheaply made. Owing to the large cost of the rolls, only a very few sizes were at first made, but these few only increased the demand. The manufacturer, thus encouraged, made rolls for other sizes, and thus the number of beams was increased, until now we have them in great variety, from 4 to 15 inches high.*



Fig. 68.

456.—Proportions between Flanges and Web.—These beams, as usually made, have the top and bottom plates, or flanges, of the same form and size. In wrought-iron the resistances to rupture, by compression and by tension, are not equal. When the load upon the beam, however, is not so large as to strain the metal beyond the limits of elasticity,

There were exhibited at the Centennial Exposition at Philadelphia, by the Union Iron Co., of Buffalo, a 15 inch beam 52 feet in length, and a 9 inch beam 80 feet long. This is believed to be the limit reached in American manufacture at the present time. The English and Germans, however, are rolling them larger. A German exhibit in Machinery Hall contained beams from Butbach half a metre (19-69 inches) high by 15 metres (49-21 feet) long.

then it resists both compression and tension equally well, and hence the propriety of having the top and bottom flanges equally large.

The manifest advantage of having the material accumulated at a distance from the neutral axis, has led to putting as much as possible of the area of the whole section into the flanges, and thereby reducing the web or vertical part to the smallest practical thickness. The web is required to maintain the connection between the top and bottom flanges, and to resist the shearing effects of the load. In rolled-iron beams, as usually made, the thickness of the web is more than sufficient to resist these strains.

457.-The Moment of Inertia Arithmetically Considered.

—For the intelligent use of the rolled-iron beam as a substitute for the wooden beam in floors, as well as for other uses, the rules already given need modification.

The resistance of a beam to flexure or bending is termed its moment of inertia. This is represented in symbolic formulas by the letter I. In formula (111.), (Art. 300), the coefficient $\frac{1}{12}$ and the symbols bd^2 represent the moment of inertia, and I, its symbol, may be substituted for them, thus:

$$\delta = \frac{PN^s}{rbd^s} = \frac{PN^s}{rI}$$

The moment of inertia for any cross-section is equal to the sum of the products of each particle of the area of the cross-section, into the square of its distance from the neutral axis.* For example: in a beam with a cross-section of the I form, a horizontal line drawn through the centre of area of the cross-section will be the neutral line for strains within

^{*} Rankine's Applied Mechanics, Art. 573.

Fig. 69.

the limits of clasticity. Let the area be divided into a large number of small areas. Then, for the portion of the figure above the neutral line, multiply each of these small areas by the square of its vertical distance above the neutral line, and the sum of these products will equal the moment of inertia for the upper half of the section. A like process will give the moment of inertia for the lower half. The two in this case will be equal, and their sum is the moment of inertia for the whole section. The result thus obtained will not be exact, but will approach accuracy in proportion to the smallmess of the parts into which the area of the cross-section is divided.

458.—Example A.—As an illustration, let ABCD, in Fig. n represent the cross-section of a beam; MN, drawn through the middle of the height AD, being theneutral axis; and let the lines EF, GH, IJ, KL, OP, QR, and ST divide the area ABMN into twenty equal parts. The four squares in each horizontal row are equally distant from the neutral line MN, and may therefore ω be taken together. Suppose each of these squares to measure 2 × 2 inches, then the area of each will be 4 inches, and of the four in each horizontal row will be $4 \times 4 = 16$ inches p area. The distances from the neutral line to the centre of each square will be as follows:

> In the first row, D = 1" second " D=3D = 5" third " fourth " D=7" fifth D = 9

Their moment of inertia will be as follows:

In the first row,
$$I_1 = 16 \times 1^2 = 16 \times 1$$

" " second " $I_2 = 16 \times 3^2 = 16 \times 9$
" " third " $I_3 = 16 \times 5^2 = 16 \times 25$
" " fourth " $I_4 = 16 \times 7^2 = 16 \times 49$
" " fifth " $I_4 = 16 \times 9^2 = 16 \times 81$

and their sum $I = 16(1+9+25+49+81) = 16 \times 165 = 2640$.

459.—Example B.—If we subdivide each of the squares in Fig. 69, and take the sum of the products as before, the result will be larger and nearer the truth. For example: divide each of the squares into four equal parts, each one inch square. There will be eight of these parts in a row, and ten rows. The area of each row will be $8 \times 1 = 8$, and their distances from the neutral line will be $\frac{1}{2}$, $\frac{$

In the first row,
$$I_1 = 8 \times (\frac{1}{2})^2 = 8 \times \frac{1}{4} = 2 \times 1$$

" second " $I_2 = 8 \times (\frac{3}{2})^2 = 8 \times \frac{9}{4} = 2 \times 9$
" third " $I_3 = 8 \times (\frac{5}{2})^2 = 8 \times \frac{95}{4} = 2 \times 25$
" fourth " $I_4 = 8 \times (\frac{7}{2})^3 = 8 \times \frac{49}{4} = 2 \times 49$
" fifth " $I_5 = 8 \times (\frac{9}{2})^2 = 8 \times \frac{81}{4} = 2 \times 81$
" sixth " $I_6 = 8 \times (\frac{11}{3})^3 = 8 \times \frac{191}{4} = 2 \times 121$
" seventh " $I_7 = 8 \times (\frac{13}{3})^3 = 8 \times \frac{191}{4} = 2 \times 169$
" eighth " $I_6 = 8 \times (\frac{15}{3})^3 = 8 \times \frac{235}{4} = 2 \times 225$
" ninth " $I_9 = 8 \times (\frac{17}{3})^3 = 8 \times \frac{235}{4} = 2 \times 289$
" tenth " $I_{10} = 8 \times (\frac{19}{3})^3 = 8 \times \frac{351}{4} = 2 \times 361$

which is equal to twice the sum of the series of

or,
$$I + 9 + 25 + \text{etc.}$$

$$I = 2 \times 1330 = 2660$$

This result exceeds in amount the previous one (2640).

460.—Example C.—If the eighty squares of this last trial be each subdivided into four equal parts, the whole cross-section will contain $4 \times 80 = 320$ parts; there will be twenty rows, with sixteen in each row; the area of each part will be $\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$; and the perpendicular distance from the neutral line to the centres of these 320 parts will be:

In the first row, \frac{1}{2}

" second " \frac{2}{2}

" third " \frac{4}{2}

" fourth " \frac{7}{2}

and so on, each distance being a fraction having 4 for a denominator, and for a numerator one of the arithmetical series of the odd numbers 1, 3, 5, 7, 9, 11, etc., to 39. The moment of inertia will be the sum of the products, as follows:

In the first row,
$$I_1 = 16 \times \frac{1}{4} \times (\frac{1}{4})^2$$

"second" $I_2 = 16 \times \frac{1}{4} \times (\frac{8}{4})^2$
"third" $I_3 = 16 \times \frac{1}{4} \times (\frac{5}{4})^2$ etc.

These are equal to:

In the first row,
$$I_1 = 16 \times \frac{1}{4} \times \frac{1}{16} \times 1^2 = \frac{1}{4} \times 1^2$$

" second " $I_2 = 16 \times \frac{1}{4} \times \frac{1}{16} \times 3^2 = \frac{1}{4} \times 3^2$
" third " $I_3 = 16 \times \frac{1}{4} \times \frac{1}{16} \times 5^2 = \frac{1}{4} \times 5^2$ etc.

Thus the sum of all the products will be equal to a quarter of the sum of the squares of the arithmetical series of the odd numbers 1, 3, 5, 7, 9, 11, etc., to 39.

Selecting the squares of these numbers from a table of squares, we find their sum to equal 10,660, and then, as above,

$$I = \frac{1}{4} \times 10660 = 2665$$

461.—Comparison of Results.—We have now the three results, 2640, 2660, and 2665, gradually increasing as the number of parts into which the sectional area is divided i creases, and tending towards the true amount, to which it ca only arrive when the parts become infinitely small and ir finite in number. To compute these by the arithmetica. method would be impossible, but by the calculus it is exceedingly simple and direct. The formula for the moment of inertia, as generally used, is complicated, but for a rectangular section in a horizontal beam, subject to limited vertical pressure, is simple.

462.-Moment of Inertia, by the Calculus-Preliminary Statement.—Let ABCD in Fig. 70 represent the rectangular cross-section of a beam; let MN be the neutral line. and the two lines at EF be drawn parallel to MN. Let



Fig. 70.

the breadth of the section EF equal y, and the perpendicular distance from the neutral line to the lower line EF equal x. The two parallel lines at EF may be taken at any distance, x, from the neutral line. This distance is variable; x is a variable representing any and every distance possible on the line GH, from zero to its full length. It is always the distance from the line MN to y, the lower line at EF, wherever y be taken. The vertical distance between the two lines at

dx, which means the differential of x, or EF is termed the difference in the length of x when slightly increased by the movement of y farther from MN. This augmentation, dx, is taken infinitesimally small.

Now the area of the space between the two lines at EF will be the product of its length by its height, or $y \times dx$.

463.—Moment of Inertia, by the Calculus.—The moment of inertia is equal (Art. 457) to the sum of the products of each particle of the area of the cross-section, into the square of its distance from the neutral axis. In the last article, the expression ydx represents the area of the infinitesimally small space at the lines EF, Fig. 70. The distance from this small area to the neutral axis is x, and the square of the distance is x^2 ; therefore x^2ydx equals the area into the square of its distance, equals the moment of inertia of the small area ydx; or, the differential of the moment of the area of the whole figure ABMN. This differential is expressed thus,

$$dI = x^{2}ydx \qquad (203.)$$

This expression represents the moment of only one of the infinitesimal parts into which the area ABMN is supposed to be divided. To obtain the moment of the whole area, it is requisite to add together the moments of all the infinitesimal parts; or, to obtain from the differential (form. 203.) its integral. The rule for this is,* "Add one to the index of the variable, and divide by the index thus increased and by the differential of the variable." Applying this rule to formula (203.) it becomes

$$I = \frac{1}{8}yx^8$$

This is in its general form. To make it definite, we have y = b, the breadth; and x, at its maximum, equals $\frac{1}{2}d$, half the depth. These values substituted for y and x, we have

$$I = \frac{1}{24}bd^{2}$$
 (204.)

^{*} Ritchie, Dif. and Integ. Calculus, p. 21.

This result is the moment of inertia for the upper half of the section of the beam, and represents the resistance to compression. The resistance to tension in the lower half of the beam is (under the circumstances of the case we are considering) an equal amount; hence for the two we have*

$$I = 2 \times \frac{1}{34}bd^{3}$$
 $I = \frac{1}{12}bd^{3}$ (205.)

464.—Application and Comparison.—This formula gives, the value of the moment of inertia for the whole section; for the two parts, one above and the other below the neutral line. To obtain the value of the part above the line, for comparison with the results obtained in Arts. 458 to 460, we take formula (204.)

$$I = \frac{1}{34}bd^3$$

in which b is the breadth and d the depth of the beam. The section of beam given in Art. 458, Fig. 69, was proposed to be 8 inches broad and 20 inches high, or AB = b = 8 and AD = d = 20. With these figures in the formula, we have


$$I = \frac{1}{34} \times 8 \times 20^3 = 2666\frac{3}{5}$$

This is the *exact* amount. In the three trials of Arts. 458 to 460, we had the approximate values 2640, 2660 and 2665. In the last trial, in which the parts were small and numerous, the result was a close approximation.

^{*} Moseley, Am. Ed. by Mahan, Art. 362.

465.—Moment of Inertia Graphically Represented.— The two processes, arithmetical and by the calculus,

are graphically represented in Fig. 71, in which the area of the figure contained within the straight lines OB and AB and the curved line OA, is the correct area by the calculus, to which the sum of the squares of the arithmetical progression 1, 3, 5, 7, 9 and 11 closely approximates. Here x and y, indicating the distances along the axes OX and OY, are co-ordinates to points in the curve, as A, C, D, E, etc., these points being midway in the difference between the sides of each two contiguous squares. The values of yfor these points are 2, 4, 6, 8, 10 and 12: a difference between



each two consecutive values equal to 2. The consecutive ordinates x are 1, 4, 9, 16, 25 and 36; or 12, 22, 32, 4', 5' and 6'.

Comparing these values of y and x in each pair, we have

and $x = 1 = 1^2$ In the first pair, y = 2" second " $x = 4 = 2^{2}$ y = 4 $x = 9 = 3^{\circ}$ third " " y = 6fourth " y = 8" x = 16 = 4" fifth " y = 10" $x = 25 = 5^2$ 66 sixth " $x = 36 = 6^{\circ}$ " y = 12

From this, the relation between y and x is readily seen to be represented by the following expressions:

$$\left(\frac{y}{2}\right)^2 = x = \frac{1}{4}y^4$$

$$y^2 = 4x \tag{206.}$$

466. — Parabolic Curve—Area of Figure.—The expression just obtained is the equation to the curve, and this curve is a parabola, with p = 2, or $y^2 = 2px$.* By formula (206.) any number of points in the curve may be found, and the curve itself drawn through them. Also, by it and by the rules of the calculus, the area of the figure inclosed between the curved line and the two lines AB and BO may be found. To this end, let the narrow space included between the two lines GH, drawn perpendicular to OB from H to G (a point in the curve), be a small portion of the area of the whole figure; dx, the distance between the two lines, being exceedingly small. The area of this narrow space will be the product of its length by its breadth, or $y \times dx$. The differential of formula (206.), the equation to the curve, \dagger is

$$2ydy = 4dx$$
$$\frac{1}{2}ydy = dx$$

Multiplying both sides by y gives

$$\frac{1}{2}y^{2}dy = ydx$$

^{*} Robinson's Conic Sections and Analytical Geometry, 1863, p. 50.

[†] Ritchie's Dif. and Integ. Calculus, p. 20.

which equals the differential of the area as above shown. The integral of this value of ydx is, by the rule (Art. 463),

$$\frac{1}{2}\int y^3dy=\frac{1}{6}y^3$$

or the area

$$A = \frac{1}{6} y^3 \qquad (207.)$$

This is the area of the figure bounded by the curved line OA and the straight lines AB and BO.

467.—Example.—The example given in Art. **460** may be taken to show an application of the last formula. The number of horizontal rows of parts into which the area is there divided is 20, and the last number of the arithmetical series is 39. By an examination of Fig. 71, it will be seen that AB, the base of the figure, is equal to the side of the last square plus unity. Therefore, 39+1=40 is the base of the area proposed in Art. **460**, or y=40. From the discussion in that article, it appears that the small squares considered are each $\frac{1}{4}$ of unity in area, from which the area of the figure in that case is found to be one quarter of the sum of the squares of the arithmetical series; or, by formula (207.),

$$A = \frac{1}{4} \times \frac{1}{6} y^3 = \frac{1}{24} y^3$$

To apply this result to the present case, where y = 40, we have

$$A = \frac{1}{24} \times 40^3 = 2666\frac{3}{3}$$

the same result as in Art. 464.

468.—Moment of Inertia—General Rule.—That formula (207.) may be general in its application, we need to find a proper coefficient.

Let the beam, instead of being 8 inches wide, as in Fig. 69, be only one inch wide, and let the portion above the neutral line be divided by horizontal lines into any number of equal parts. Put n for the number of parts, and t for the thickness of each part. The area of each part will be $1 \times t = t$ inches, and the several distances from the neutral line to the centre of each part will be, respectively, $\frac{1}{2}t$, $\frac{1}{4}t$, $\frac{1}{4}t$, etc., to the last, which will be $\frac{2n-1}{2}t$.

Now, the moment of inertia of each part being its area into the square of the distance to its centre of gravity, therefore the several moments will be as follows:

In the first piece,
$$t\left(1 \times \frac{t}{2}\right)^2 = 1^2 \times \frac{1}{4}t^2$$

" " second " $t\left(3 \times \frac{t}{2}\right)^2 = 3^2 \times \frac{1}{4}t^2$

" " third " $t\left(5 \times \frac{t}{2}\right)^2 = 5^2 \times \frac{1}{4}t^2$

" " fourth " $t\left(7 \times \frac{t}{2}\right)^2 = 7^2 \times \frac{1}{4}t^2$

" " last " $t\left((2n-1)\frac{t}{2}\right)^2 = (2n-1)^2 \times \frac{1}{4}t^2$

The sum of these will be

$$S = \frac{1}{4}t^{3} \left[1^{2} + 3^{2} + 5^{2} + 7^{2} + \cdots + (2n-1)^{2} \right] \quad (208.)$$

But the sum of the series $1^2 + 3^2 + 5^2 +$ etc., is the area of the parabolic figure (Fig. 71), and has been found to be equal to $\frac{1}{2}y^2$ (form. 207.)

Now y, when at its maximum, coincides with the base AB of Fig. 71, and is equal to the side of the last square plus unity. As above, the side of the last square is 2n-1, from which y'=2n, and

$$\frac{1}{6}y^3 = \frac{1}{6}2^3n^3 = \frac{8}{6}n^3$$

and therefore formula (208.) becomes

$$S = \frac{1}{4}t^3 \times \frac{8}{6}n^3$$

$$S = \frac{1}{8}t^3n^3 \qquad (209.)$$

which is a rule for ascertaining correctly the moment of inertia for a beam one inch broad.

469.—Application.—To show the application of the above, take the example of Art. 458, where the number of slices is 5 and the thickness is 2, and we have, by the use of formula (209.),

$$S = \frac{1}{8} \times 2^3 \times 5^3 = 333\frac{1}{8}$$

The formula gives the result for a beam one inch broad. The beam in Art. 458 is 8 inches broad. Therefore, for the full amount we have

$$8 \times 333\frac{1}{8} = 2666\frac{2}{3}$$

Again, take the example of Art. 460, where $t = \frac{1}{2}$ and n = 20, and we find as the result

$$S = \frac{1}{8} \times (\frac{1}{2})^3 \times 20^3 = 333\frac{1}{8}.$$
$$8 \times 333\frac{1}{8} = 2666\frac{2}{8}.$$

and

Thus in both cases we have the same result as that obtained directly by the calculus. If b, for the breadth, be added to formula (209.) we shall have the complete rule, thus:

$$I=\frac{1}{8}bt^3n^3$$

and since tn equals the height above the neutral line, equals $\frac{d}{2}$, the half of the depth of the beam,

$$t^{s}n^{s} = (tn)^{s} = (\frac{1}{2}d)^{s} = \frac{1}{8}d^{s}$$

and this value of t'n' substituted for it in the above equation, gives

$$I = \frac{1}{8}b \times \frac{1}{8}d^3$$

$$I = \frac{1}{24}bd^s$$

This is for one half the beam. For the whole beam we have twice this amount, or

$$I = \frac{1}{12}bd^2$$

the same as found directly by the calculus in formula (205.)

470. - Rolled-Iron Beam - Moment of Inertia - Top Flange.—An expression for the moment of inertia appropriate to rolled-iron beams of the I form of section (Fig. 68)




Fig. 72.

may be obtained directly from the formula (205.) for the rectangular section. In Fig. 72, showing the cross-section required, b equals the breadth of the beam, or the width of the top and bottom flanges, and t equals the width or thickness of the web; b minus t equals b_{i} , d equals the entire height of the section, and d, the height between the flanges. MN is the neutral line drawn at half height.

By formulas (203.) and (204.) the moment of inertia for the part above the neutral axis is

$$I = \int y x^s dx$$

If this be applied so that $x = \frac{1}{2}d$, the result $(\frac{1}{24}bd^3)$, as in (204), is the moment for the rectangle ABMN. Again, if it be applied with $x = \frac{1}{2}d$, the result $(\frac{1}{24}bd^3)$ will be the moment for the rectangle EFMN. Now, if the latter result be subtracted from the former, the remainder will be the moment for the area ABEF, the upper flange, or

$$I_{f} = \frac{1}{24}bd^{3} - \frac{1}{24}bd^{3}$$

$$I_{f} = \frac{1}{24}b(d^{3} - d^{3}) \qquad (210.)$$

471.—Rolled-Iron Beam—Moment of Inertia—Web.—Formula (210.) is the moment of inertia for the top flange. The moment of inertia for the upper half of the web is that due to a rectangle having for its breadth y = t, and for its height $x = \frac{1}{2}d_t$, and by Art. 463,

$$I = \frac{1}{8}yx^{3} = \frac{1}{8}t(\frac{1}{2}d_{i})^{3}$$

$$I_{w} = \frac{1}{24}td_{i}^{3}$$

and since $t = b - b_{i}$, therefore

$$I_{w} = \frac{1}{24}(b-b_{i})d_{i}^{s}$$
 (211.)

472.—Rolled-Iron Beam—Moment of Inertia—Flange and Web.—Formula (211.) is the moment of inertia for the upper half of the web. Added to formula (210.), the sum, representing the moment of inertia for all of the beam above the neutral line, will be

$$I_{s} = \frac{1}{34}b(d^{3}-d_{i}^{3}) + \frac{1}{34}(b-b_{i})d_{i}^{3}$$

$$I_{s} = \frac{1}{34}(bd^{3}-bd_{i}^{3}+bd_{i}^{3}-b_{i}d_{i}^{3})$$

$$I_{s} = \frac{1}{34}(bd^{3}-b_{i}d_{i}^{3}) \qquad (212.)$$

473.—Rolled-Iron Beam—Moment of Inertia—Whole Section.—Formula (212.) is the moment of inertia for that half of the rolled-iron beam which is located above the neutral line. The moment for the portion below the line will be equal in amount; and therefore, for the moment of the entire section, we have twice the amount of formula (212.) or

$$I = \frac{1}{12} (bd^3 - b_i d_i^3) \tag{213.}$$

474.—Rolled-Iron Beam—Moment of Inertia—Comparson with other Formulas.—Formula (213.) is the same as that given by Professor Rankine* and others, and is in general use. Canon Moseley† gives an expression which is complicated. Mr. Edwin Clark, in his valuable work on the Britannia and Conway Tubular Bridges, Vol. I., p. 247, gives the formula

$$I = \frac{1}{12}d_{1}^{2}(6a + a_{1}) \tag{214.}$$

in which d_{s} is the distance between the centres of gravity of the top and bottom flanges, a is the area of the top or bottom flange, and a_{s} is the area of the web. This is more simple than the common formula (213.), but is not exact. It is only an approximation. Its relation to the true formula will now be shown.

From formula (213.) we have, multiplying by 12,

$$12I = bd^3 - b_i d_i^3$$

Of these symbols we have (Fig. 72, putting k = AE),

$$d = d_2 + h$$
, $b_i = b - t$ and $d_i = d_2 - h$

By substitution, we now have

$$12I = b(d_s + h)^s - (b-t)d_t^s$$

^{*} Rankine's Applied Mechanics, pp. 316 and 317.

[†] Moseley's Mech. of Eng., Am. Ed. by Mahan, Artt 504.

and since $(b-t)d^3 = bd^3 - td^3 = bd^3 - a_id^3$ (putting a_i for the area of the web); and since $d_i = d_2 - h$, therefore we have

$$12I = b(d_{s} + h)^{s} - [b(d_{s} - h)^{s} - a_{i}d_{i}^{s}]$$

$$12I = b(d_{s} + h)^{s} - b(d_{s} - h)^{s} + a_{i}d_{i}^{s}$$

$$12I = b[(d_{s} + h)^{s} - (d_{s} - h)^{s}] + a_{i}d_{i}^{s}$$

Then we have

$$(d_{s}+h)^{s} = d_{s}^{s} + 3d_{s}^{s}h + 3d_{s}h^{s} + h^{s}$$

$$(d_{s}-h)^{s} = d_{s}^{s} - 3d_{s}^{s}h + 3d_{s}h^{s} - h^{s}$$

$$(d_{s}+h)^{s} - (d_{s}-h)^{s} = 0 + 6d_{s}^{s}h + 0 + 2h^{s}$$

Substituting these in the above, we have

$$12I = b(6d_{2}^{2}h + 2h^{2}) + a_{1}d_{1}^{2}$$

The area of the top flange equals bh = a, therefore

$$I2I = 6a(d_s^2 + \frac{1}{8}h^s) + a_i d_i^s$$
 or,

$$I = \frac{1}{12} [6a(d_s^2 + \frac{1}{8}h^s) + a_i d_i^s]$$
 (215.)

In Mr. Clark's formula, (214.), we have

$$I = \frac{1}{12} d_s^2 (6a + a_i)$$
 or,

$$I = \frac{1}{12} (6a d_s^2 + a_i d_s^2)$$

Comparing this with the reduction of the common formula as just found [form. (215.)], the difference is readily seen to be, that while in the one the quantities a and a_i are each multiplied by the factor d_i^2 , in the other the factor for a is $(d_i^2 + \frac{1}{3}h^2)$ and that for a_i is d_i^2 .

475.—Rolled-Iron Beam—Moment of Inertia—Comparson of Results.—To show, by an application, the difference in the results obtained by the two formulas (214.) and (215.), let it be required to find the moment of inertia for a rolled-iron beam 12 inches high and 4 inches broad, and in which the top and bottom flanges are one inch thick, and the web one half inch thick. Here we have d = 12, $d_i = 10$, $d_2 = 11$, $t = \frac{1}{2}$, b = 4, $b_i = 3\frac{1}{2}$, $a = 4 \times 1 = 4$, $a_i = 10 \times \frac{1}{2} = \frac{1}{2}$ and b = 1; and by formula (214.) we have

$$I = \frac{1}{13} \times 11^{3} \times (\overline{6 \times 4} + 5) = 292\frac{5}{13}$$

The value by formula (215.) is

in all important cases.

$$I = \frac{1}{13} \left[\frac{6 \times 4 \times (1^{1^{2}} + \frac{1}{8} \times 1^{2})}{6 \times 4 \times (1^{1^{2}} + \frac{1}{8} \times 1^{2})} + (5 \times 10^{2}) \right] = 284\frac{1}{8}$$

The value by the common formula, (213.), is

$$I = \frac{1}{13}[(4 \times 12^3) - (3.5 \times 10^3)] = 284\frac{1}{8}$$

Thus we have by either of the two formulas (213.) or (215.) the exact value, $I=284\frac{1}{8}$, while by formula (214.) the value obtained is $I=292\frac{5}{18}$.

476.—Rolled-Iron Beam-Moment of Inertia-Remarks

—When, in a rolled-iron beam, the top and bottom flanges are comparatively thin, the difference between d, and d will be small, and in consequence the value of I as derived by formula (214.) will differ but little from the truth. This formula, therefore, for such cases, is a near approximation, and for some purposes may be useful; but formula (215.) and that from which it is derived, (213.), are exact in their results, and should be used in preference to formula (214)

477.—Reduction of Formula—Load at Middle.—The expression (213.), then, is that which is proper for the moment of inertia for rolled-iron beams—namely:

$$I = \frac{1}{12}(bd^s - b_i d_i^s)$$

In Art. 303, formula (115.), we have

$$12F = \frac{Wl^3}{I\delta}$$

This is for a beam supported at each end, with the load in pounds at the middle, the length in feet and the other dimensions in inches. F is a constant, which, from an average of experiments (Art. 701) upon rolled-iron beams, has been ascertained to be 62,000. The value of I, the moment of inertia, has been computed, for many of the sizes of beams in use, by formula (213.), and will be found in Table XVII.

We have, therefore, from (115.)

$$12 \times 62000 = \frac{Wl^3}{I\delta}$$

$$744000 = \frac{Wl^3}{I\delta}$$
(216.)

478.—Rules—Values of W, l, δ and I.—Rule (216.) is for a load at the middle of a rolled-iron beam. The values of the several symbols in (216.) may be had by transpositions, as follows:

The weight,
$$W = \frac{744000 I \delta}{l^3}$$
 (217.)

" length,
$$l = \sqrt[3]{\frac{744000I\delta}{W}}$$
 (218.)

" deflection, $\delta = \frac{Wl^3}{744000I}$ (219.)

" moment of inertia, $I = \frac{Wl^3}{744000\delta}$ (220.)

" deflection,
$$\delta = \frac{Wl^3}{744000I}$$
 (219.)

" moment of inertia,
$$I = \frac{Wl^3}{744000\delta}$$
 (220.)

479.—Example—Weight.—Formula (217.) is a rule by which to find the weight in pounds which may be carried at the middle of a rolled-iron beam, with a given deflection. As an example: What weight may be carried at the middle of a 9 inch 90 pound beam, 20 feet long between bearings, with a deflection of one inch?

Here we have $\delta = 1$, l = 20 and (from Table XVII.) $I = 109 \cdot 117$; and, by the formula,

$$W = \frac{744000 \times 109 \cdot 117 \times 1}{20^3} = 10147 \cdot 881$$

or the weight to be carried equals 10,148 pounds, or say 5 net tons.

480.—Example—Length.—Formula (218.) is a rule by which to find the length at which a beam may be used when required to carry at the middle a given load, with a given deflection. For example: To what length may a Buffalo 6 inch 50 pound rolled-iron beam be used, when required to carry 5000 pounds at the middle, with a deflection of of an inch?

Here I = 29.074 (from Table XVII.), $\delta = 0.3$ and W = 5000; and, by the formula,

$$l = \sqrt[3]{\frac{744000 \times 29 \cdot 074 \times 0 \cdot 3}{5000}} = 10.908$$

or the length may be 10 feet 11 inches.

481.—Example—Deflection.—Formula (219.) is a rule for finding the deflection in a rolled-iron beam, when can ing at the middle a given load. As an example: What deflection will be caused in a Phænix 9 inch 70 pound beam 20 feet long, by a load of 7500 pounds at the middle?

Here W = 7500, l = 20 and (from Table XVII.) $l = 92 \cdot 207$; and, by the formula,

$$\delta = \frac{7500 \times 20^3}{744000 \times 92 \cdot 207} = 0.87461$$

or the deflection will be $\frac{7}{8}$ of an inch.

وم

16

CU

14.

30

482.—Example—Moment of Inertia.—In formula (220.) we have a rule by which to ascertain the moment of inertia of a rolled-iron beam, laid on two supports, and carrying a load at the middle. To exemplify the rule: Which of the beams in Table XVII. would be proper to carry 10,000 pounds at the middle, with a deflection of one inch; the length between the bearings being twenty feet?

Here W = 10000, l = 20 and $\delta = 1$, and by the formula,

$$I = \frac{10000 \times 20^{3}}{744000 \times 1} = 107.527$$

or the required moment of inertia is 107.527. The nearest amount to this in Table XVII. is 107.793, pertaining to the Phænix 9 inch 84 pound beam. This beam, therefore, would be the one required.

483.—Load at Any Point—General Rule.—The rules just given are for cases where the loads are at the middle. Rules for loads at any other place in the length will now be developed.

Formula (23.) is

$$4Wa\frac{mn}{l} = Bbd^*$$

If bd' be multiplied by $\frac{12d}{12d}$ its value will not be changed, and there will result

$$bd^2 = \frac{12bd^3}{12d} = \frac{12 \times \frac{1}{12}bd^2}{d} = \frac{12I}{d}$$
 [see form. (205.

and formula (23.) becomes

$$4Wa\frac{mn}{l} = B\frac{12I}{d}$$

By formula (154.), in Art. 376,

$$a = \frac{Bl}{Fdr}$$

and as $rl = \delta$, or $r = \frac{\delta}{l}$, therefore

$$a = \frac{Bl}{Fd\delta} = \frac{Bl^s}{Fd\delta}$$

For a in the above, substituting this value, we have

$$4W \frac{Bl^{2}}{Fd\delta} \times \frac{mn}{l} = B \frac{12I}{d}$$

$$4BWlmn = B \frac{12I}{d}Fd\delta$$

$$4Wlmn = 12FI\delta \qquad (221.)$$

484.—Load at Any Point on Rolled-Iron Beams.—The moment of inertia, I, in formula (221.) is [form. (205.) $I = \frac{1}{12}bd^3$ for a rectangular beam. For a tube, or for beam of the I form, it is, by formula (213.),

$$I = \frac{1}{12}(bd^3 - b_i d_i^3)$$

If in (221.) we substitute for I this value of it, we have

$$4Wlmn = F\delta(bd^3 - b_i d_i^3)$$
 (222.)

This is a rule for rolled-iron beams supported at each end and carrying a load at any point in the length, with a given deflection; and in which W is the weight in pounds, m and n the distances from the load to the two supports, and m plus n equals l equals the length; m, n and l all being in feet; δ is the deflection, b and d are the breadth and depth of the beam, b_i and d_i the breadth and depth of the part which is wanting of the solid bd (Art. 470); δ , b, d, b, and d, all being in inches; and F is the constant for rolled iron (Table XX.).

485.—Load at Any Point on Rolled-Iron Beams of Table XVII.—The value of F is 62,000. If it be substituted for F in (221.) we shall have

$$4Wlmn = 12 \times 62000 l\delta$$

$$4Wlmn = 744000 l\delta$$

$$Wlmn = 186000 l\delta$$

$$W = \frac{186000 l\delta}{lmn}$$
(223.)

which is a rule for ascertaining the weight which may be carried, with a given deflection, at any point in the length of any of the rolled-iron beams of Table XVII.

486.—Example.—What weight may be carried on a Paterson 12½ inch 125 pound rolled-iron beam, 25 feet long between bearings, at 10 feet from one of the bearings, with a deflection of 1.5 inches?

Here we have $\delta = 1.5$, m = 10, n = 15, l = 25 and l = 292.05 (from Table XVII.); and hence

$$W = \frac{186000 \times 292 \cdot 05 \times 1\frac{1}{2}}{25 \times 10 \times 15} = 21728 \cdot 52$$

or the weight allowable is, say 21,730 pounds.

487.—Load at End of Rolled-Iron Lever.—In formula (115.) we have

$$12F = \frac{Wl^s}{I\delta}$$
 or,
 $Wl^s = 12FI\delta$

This expression is for a beam supported at each end and loaded at the middle. In a *lever* the strains will be the same when the weight and length are each just one half those in a beam supported at each end. Hence if for W we take 2P, and for l take 2n, P being the weight at the end of a lever and n the length of the lever, we shall have, by substitution in the above,

$$2P \times \overline{2n}^{3} = 12FI\delta$$
 $16Pn^{3} = 12FI\delta$
 $16Pn^{3} = F\delta (bd^{3} - b_{i}d_{i}^{3})$ (224.)
 $Pn^{3} = \frac{3}{4}FI\delta$ (225.)

and

and further, since F = 62000 (Table XX.), therefore

$$Pn^{s} = 46500I\delta$$

$$P = \frac{46500I\delta}{n^{s}} \tag{226.}$$

which is a rule for ascertaining the weight which may be supported at the free end of a lever, with a given deflection, the lever being made of any one of the rolled-iron beams of Table XVII.

488.—Example.—Let it be required to show the weight which may be sustained at the free end of a Trenton 151 inch 150 pound rolled-iron beam, firmly imbedded in a wall, and projecting therefrom 20 feet; the deflection not to exceed 2 inches.

Here $I = 528 \cdot 223$ (Table XVII.), $\delta = 2$ and n = 20; and by formula (226.)

$$P = \frac{46500 \times 528 \cdot 223 \times 2}{20^3} = 6140 \cdot 59$$

or the weight which may be carried is 6140 pounds.

489.—Uniformly Distributed Load on Rolled-Iron Beam.—By formula (115.) we have

$$Wl^3 = 12FI\delta$$

This is for a load at the middle of a beam. Let U represent an equally distributed load; then $\frac{4}{8}U$ will have an effect upon the beam equal to the concentrated load W, (Art. 340), and hence, substituting this value,

$$\frac{5}{8}Ul^{s} = 12FI\delta$$

$$\frac{5}{8}Ul^{s} = F\delta (bd^{s} - b_{i}d_{i}^{s}) \qquad (227.)$$

By Table XX. F = 62000, and the formula reduces to

$$Ul^{s} = 1190400I\delta$$

$$U = \frac{1190400I\delta}{I^{s}} \qquad (228.)$$

which is a rule for ascertaining the amount of weight, equally distributed, which, with a given deflection, may be borne upon any of the rolled-iron beams of Table XVII.

490.—Example.—What weight, uniformly distributed, may be sustained upon a Buffalo 10½ inch 105 pound rolled-iron beam, 25 feet long between bearings, with a deflection of ‡ of an inch?

Here I = 175.645 (Table XVII.), $\delta = 0.75$ and l=25; and therefore, by (228.),

$$U = \frac{1190400 \times 175.645 \times 0.75}{25^{3}} = 10036.21$$

or the weight uniformly distributed is 10,036 pounds.

491.—Uniformly Distributed Load on Rolled-Irea Lever.—A rule for a lever loaded at the free end is given in formula (225.),

$$Pn^s = \frac{3}{4}FI\delta$$

When a load concentrated at the free end of a lever is equal to $\frac{4}{5}$ of a load uniformly distributed over the length of the lever, the effects are equal. (Art. 347.)*

If U equals the load equally distributed, and P the load concentrated at the free end, then $\frac{2}{3}U = P$, and substituting this value for P in formula (225.) gives

$$\frac{8}{8}Un^{3} = \frac{8}{4}FI\delta$$
 $6Un^{3} = 12FI\delta$
 $6Un^{3} = F\delta(bd^{3} - b_{1}d_{1}^{3})$ (229.)

Putting for F its value 62,000, and reducing, we have

$$Un^{3} = 124000I\delta$$

$$U = \frac{124000I\delta}{n^{3}} \qquad (230.)$$

which is a rule for ascertaining the load, uniformly distributed, which may be sustained upon any of the rolled-ing beams of Table XVII., with a given deflection, when used as a lever.

^{*} Rankine, Applied Mechanics, p. 329.

492.—Example.—What weight, uniformly distributed, may be sustained upon a Trenton 6 inch 40 pound rolled-iron beam, used as a lever, and projecting 10 feet from a wall in which it is firmly imbedded; the deflection not exceeding ‡ of an inch?

Here I = 23.761, $\delta = \frac{9}{8}$ and n = 10; and by (230.)

$$U = \frac{124000 \times 23.761 \times \frac{9}{8}}{10^3} = 1964.24$$

or the weight will be 1965 pounds.

493.—Components of Load on Floor.—When rollediron beams are used as floor beams, they have to sustain a compound load. This load may be considered as composed of three parts, namely:

First: The superincumbent load, or load proper;

Second: The weights of the materials within the spaces between the beams, and of the covering; and,

Third: The weight of the beams themselves.

494.—The Superincumbent Lond.—This will be in proportion to the use to which the floor is to be subjected. If for the storage of merchandise, the weight will vary according to the weight of the particular merchandise intended to be stored. Warehouses are sometimes loaded heavily, and for these each case needs special computation. For general purposes, such as our first-class stores are intended for, the load may be taken at 250 pounds per superficial foot (Art. 368). A portion of the floor may in some cases be loaded heavier than this, but as there is always a considerable part they free for passage ways, 250 pounds per foot will in general be found ample to cover the heavier loads on floors of this class.

On the floors of assembly rooms, banks, insurance offices—dwellings, and of all buildings in which the floors are likely—to be covered with people, the weight may be taken at 66—or say 70 pounds per foot; 66 pounds being the weight of a crowd of people (Art. 114).

495.—The Materials of Construction—Their Weight.—These (not including the iron beam) will differ in accordance with the plan of construction. As usually made, with brick arches, concrete filling, and wooden floor laid on strips bedded in the concrete, this weight will not differ much from 70 pounds per superficial foot, and, in general, it may be taken at this amount.

496.—The Rolled-Iron Beam—Its Weight.—The difference in the weight of rolled-iron beams is too great to permit the use in the rule of a definite amount, taken as an average. To represent this weight, therefore, we shall have to make use of a symbolic expression.

Let y equal the weight of the beam in pounds per lineal yard, and c equal the distance in feet between the centres of two adjacent beams. Then $\frac{1}{8}y$ will equal the weight of the beam per lineal foot; and this divided by c will give, as a quotient,

$$m=\frac{y}{3c} \tag{231.}$$

equals the weight of beam per superficial foot of the floor.

497.—Total Load on Floors.—Putting together the three weights, as above, we have the total weight per superficial foot as follows:

For the floors of dwellings, assembly rooms, banks, etc.,

the superincumbent load is 70 pounds; the brick arches, concrete, etc., equal 70 "
and the rolled-iron beams equal $\frac{y}{3c}$ "

These amount in all to

$$f = 140 + \frac{y}{3c} \tag{232.}$$

For the floors of first-class stores,

the superincumbent load is
the brick arches, concrete, etc., equal

and the rolled-iron beams equal $\frac{y}{3c}$ "

or, in all,

$$f = 320 + \frac{y}{3c} \tag{233.}$$

498.—Floor Beams—Distance from Centres.—In formula (228.) U stands for the weight uniformly distributed over the length of the beam. When f is taken to represent the total load in pounds per superficial foot of the floor, c the distance apart in feet between the centres of two adjacent beams, and l the length of the beam in feet, then

$$U = fcl$$

Substituting for U in formula (228.) its value as here shown, we have

$$fcl = \frac{1190400I\delta}{l^3}$$
 (234.)

When r represents the rate of deflection per foot lineal of the beam, we have $rl = \delta$, equals the whole deflection. Substituting for δ in formula (234.) this equivalent value we have

$$fcl = \frac{1190400Irl}{l^{3}}$$

$$fc = \frac{1190400Ir}{l^{3}}$$
(235.)

Again; for f substituting its value as in (232.), we have

$$(140 + \frac{y}{3c})c = \frac{1190400Ir}{l^3}$$

$$140c + \frac{y}{3} = \frac{1190400Ir}{l^3}$$

$$140c = \frac{1190400Ir}{l^3} - \frac{y}{3}$$

$$c = \frac{8502\frac{6}{7}Ir}{l^3} - \frac{y}{420}$$
(236.)

which is a rule for ascertaining the distance apart from centres between rolled-iron beams, in the floors of assembly rooms, banks, etc., with a given rate of deflection.

499.—Example.—It is required to show at what distance from centres, Paterson 10½ inch 105 pound rollediron beams, 25 feet long, should be placed in the floors of a bank, in which the rate of deflection is fixed at 0.035 of an inch.

Here we have I = 191.04 (Table XVII.), r = 0.035, l = 25 and y = 105; and by (236.)

$$c = \frac{8502\% \times 191.04 \times 0.035}{25^3} - \frac{105}{420} = 3.39$$

or the distance from centres should be, say 3 feet 4\frac{3}{4} inches.

500.—Floor Beams—Distance from Centres—Dwellings, etc.—If the rate of deflection be fixed, and at 0.03 (Art. 314), then formula (236.), so modified, becomes

$$c = \frac{255 \cdot 0\frac{6}{7} \times I}{l^3} - \frac{y}{420} \tag{237.}$$

which is a rule for ascertaining the distance apart from centres of rolled-iron beams, in the floors of assembly rooms, banks, etc., with a rate of deflection fixed at 0.03 of an inch per foot lineal of the beam.

501.—Example.—What distance apart from centres should Buffalo 12½ inch 125 pound rolled-iron beams 25 feet long be placed, in the floor of an assembly room?

Here I=286.019 (Table XVII.), l=25 and y=125; and by formula (237.)

$$c = \frac{255 \cdot 0.9 \times 286 \cdot 0.09}{25^{\circ}} - \frac{125}{420} = 4 \cdot 37$$

or the distance from centres should be 4\frac{1}{8} feet, or 4 feet inches.

The distances from centres of various sizes of beams have been computed by formula (237.), and the results are recorded in Table XVIII.

502.—Floor Beams—Distance from Centres.—If in formula (235.) we substitute for f its value in (235.) we shall have

$$(320 + \frac{y}{3c})c = \frac{1190400Ir}{l^3}$$

$$320c + \frac{y}{3} = \frac{1190400Ir}{l^3}$$

$$320c = \frac{1190400Ir}{l^3} - \frac{y}{3}$$

$$c = \frac{1190400Ir}{320l^3} - \frac{y}{320 \times 3}$$

$$c = \frac{3720Ir}{l^3} - \frac{y}{960}$$
(238.)

This is a rule for ascertaining the distance apart from centres between rolled-iron beams, in floors of first-class stores, with a given rate of deflection.

503.—Example.—At what distance apart should Phœnix inch 150 pound beams 25 feet long be placed, with a rate of deflection of r = 0.045?

Here we have I = 514.87 (Table XVII.), r = 0.045, l = 25 and y = 150; and in formula (238.)

$$c = \frac{3720 \times 514 \cdot 87 \times 0.045}{25^{\circ}} - \frac{150}{960} = 5.36$$

or the distance required is 5.36 feet, or 5 feet 41 inches.

504.—Floor Beams—Distance from Centres—First-class Stores.—If the rate of deflection be fixed, and at 0.04 of an inch (Arts. 313, 314 and 368), then formula (238.) becomes

$$c = \frac{148 \cdot 8I}{l^3} - \frac{y}{960} \tag{239.}$$

which is a rule for ascertaining the distance apart from centres of rolled-iron beams, in floors of first-class stores, with a rate of deflection fixed at 0.04 of an inch per foot lineal of the beam.

505.—Example.—At what distance apart should Buffalo 12½ inch 180 pound rolled-iron beams 20 feet long be placed, in a first-class store?

Here I = 418.945 (Table XVII.), l = 20 and y = 180; and, by the above formula,

$$c = \frac{148 \cdot 8 \times 418 \cdot 945}{20^{1}} - \frac{180}{960} = 7 \cdot 60$$

or the distance from centres should be 7.6 feet, or 7 feet 7½ inches nearly.


The distances from centres, as per formula (239.), have been computed for rolled-iron beams of various sizes, and the results are recorded in Table XIX.

spaces between the iron floor beams be filled with brick arches and concrete, as in Art. 495, care is necessary that these arches be constructed with very hard whole brick of good shape, be laid without mortar, in contact with each other, and that the joints be all well filled with best cement grout and be keyed with slate. As to dimensions, the arch when well built need not be over four inches thick for spans of seven or eight feet, except for about a foot at each springing, where it should be eight inches thick, and where care should be taken to form the skew-back quite solid and at right angles to the line of pressure.

In order to economize the height devoted to the floor, it

But there is a limit, beyond which a reduction of the rise will cause so great a strain that the material of which the bricks are made will be rendered liable to crushing. Experiments have shown that this limit of rise is not much less than 1½ inches per foot width of the span, and in practice it is found to be safe to make the rise 1½ inches per foot.

507.—Floor Arches—Tie-Rods.—The lateral thrust exerted by the brick arches may be counteracted by tie-rods of iron. The arches, if made with a small rise, will differ but little in form from the parabolic curve. Let Fig. 73 represent one half of the arch and tie-rod. Draw the lines AD and DC tangent to the points A and C. Then AE = EB*



equals $\frac{1}{4}$ of the span, or $\frac{1}{4}s$, and DE = BC equals the versed sine, or height of the arch. If DE, by scale, be equal to the load upon the half arch AC, then AE equals the horizontal strain; or

$$DE : AE :: \frac{1}{2}U : H$$

$$v : \frac{1}{4}s :: \frac{1}{2}U : H$$

$$H = \frac{Us}{8v}$$
(240.)

in which U is the load, in pounds, and s is the span and v the versed sine, both in feet. To resist this strain

^{*} Tredgold's Elementary Principles of Carpentry, Art. 57 and Fig. 28.

the rod must contain the requisite amount of metal. The ultimate tensile strength of wrought-iron may be taken at an average of 55,000 pounds per inch. Owing, however, to defects in material and in workmanship (such, for instance, as an oblique bearing, which, by throwing the strain out of the axis and along one side of the rod, would materially increase the destructive effect of the load), the metal should be trusted with not over 9000 pounds per inch. If a represent the area of the tie-rod in inches, then

$$9000a = H$$

Substituting this value of H in formula (240.) we have

$$9000a = \frac{Us}{8v} \tag{241.}$$

For U we may put its equivalent, which is the load per foot multiplied by the superficial area of the floor sustained by the rod, or

U = cfs

being the distance from centres between the rods, and s the span of the arch, both in feet, and f the weight of the brick-work and the superimposed load, in pounds, or 70+q. If the arch be made to rise $1\frac{1}{2}$ inches per foot of width, or $\frac{1}{3}$ of the span, then 8v = s, and formula (241.) becomes

$$a = \frac{70 + q}{9000} cs \qquad (242.)$$

Putting q, the superimposed load, at seventy pounds, we have

$$a = \frac{140}{9000}cs$$

$$a = 0.015 \times cs$$
(243.)

which is a rule for the area, in inches, of a tie-rod in a bank, office building, or assembly room floor.

If q be put equal to 250 pounds, then

$$a = \frac{320}{9000}cs$$

$$a = 0.03\frac{5}{4} \times cs \qquad (2.44.)$$

which is a rule for the area, in inches, of a tie-rod in the floor of a first-class store.

For general use, the diameter, rather than the area, of the tie-rod is desirable. We have as the area of any rod,

$$a = \cdot 7854d^{2}$$

and therefore $\cdot 7854d^2 = 0.01\frac{6}{5} \times cs$

and
$$d = \sqrt{0.0198cs} \qquad (245.)$$

which is a rule for banks, etc.; and

$$d = \sqrt{0.04527cs} \qquad (246.)$$

which is a rule for first-class stores.

508.—Example.—In a first-class store, with beams 20 feet long, and arches 6 feet span: What is the required diameter of tie-rods?

Here s=6, and if there are to be, say two rods in the length of each arch, then $c=6\frac{3}{3}$, and therefore

$$d = \sqrt{0.04527 \times 6^{2} \times 6} = 1.35$$

or the required rods are to be 18 inches diameter.

Tie-rods should be placed at or near the bottom flange, and so close together that the horizontal strain between them from the thrust of the arch shall not be greater than the bottom flange of the beam is capable of resisting.

509.—Headers.—In Art. 381 we have the expression

$$fings = Fbr(d-1)^{s}$$

a rule for a header of rectangular section. We have also in formula (205.)

$$I = \frac{1}{12}bd^3$$

or

$$12I = bd^{s}$$

Substituting this 12I for b(d-1) in the above equation gives

$$\frac{5}{16} fng^3 = 12 IFr$$

and

$$I = \frac{fng^*}{38 \cdot 4Fr} \tag{247.}$$

which is a rule for rolled-iron headers; and in which f is the load in pounds per superficial foot, n is the length of the tail beams having one end resting on the header, and g is the length of the header; n and g both being in feet.

510.—Headers for Dwellings, etc.—If in (247.) we substitute for f its value as per formula (232.), and for F its value 62,000 (Table XX.), and make r = 0.03 (Art. 314), we shall have

$$I = \frac{\left(140 + \frac{y}{3c}\right)ng^{*}}{38 \cdot 4 \times 62000 \times 0.03}$$

$$I = \frac{140 + \frac{y}{3c}}{71424}ng^{*}$$
(248.)

which is a rule for ascertaining the moment of inertia of a rolled-iron header, in a floor of an assembly room, bank, etc.; from which an inspection of Table XVII. will show the required header.

511.—Example.—In the floors of a bank, constructed of Buffalo 10½ inch 105 pound beams, placed 4 feet from centres: What ought a header to be which is 20 feet long, and which carries tail beams 16 feet long?

Here y = 105, c = 4, n = 16 and g = 20; and by (2.48.)

$$I = \frac{140 + \frac{105}{18}}{71424} \times 16 \times 20^{3} = 266.577$$

or the beam should be of such size that its moment of inertia be not less than 266.577. By reference to Table XVII. we find the beam, the moment of inertia of which is next greater than this, to be the Pottsville 12 inch 125 pound beam, for which I = 276.162. This may be taken for the header, although it is stronger than needed. Should the depth be objectionable, we may use two of the Pottsville 10½ inch 90 pound beams, bolted together; for of this latter beam I = 150.763, and

$$2 \times 150.763 = 301.526$$

considerably more than 266.577, the result of the computation by formula (248.). But these two beams, although nearer the required depth, yet, when taken together, weigh 180 pounds per yard; while the 12 inch beam weighs but 125 pounds. On the score of economy, therefore, it is preferable to use the 12 inch beam.

512.—Headers for First-class Stores.—If, in formula (247.), for f, F and r, there be substituted their proper values, namely, $f = 320 + \frac{y}{3c}$ (form. 233.), F = 62000 and r = 0.04, as in Arts. 367 and 368, we shall have

$$I = \frac{320 + \frac{y}{3c}}{95232} ng^{3} \tag{249.}$$

which is a rule for rolled-iron headers in the floors of first-class stores.

As this expression is the same as (248.), excepting the numerical coefficients, the example of the last article will suffice to illustrate it, by simply substituting the coefficient

$$\frac{320 + \frac{y}{3c}}{95232} \text{ in place of } \frac{140 + \frac{y}{3c}}{71424}$$

513.—Carriage Beam with One Header.—Formula (161.) is appropriate for a case of this kind, but it is for a beam of rectangular section. To modify it for use in this case, we have (205.) $I = \frac{1}{12}bd^3$; or $12I = bd^3$. Substituting for bd^3 , in (161.), this value, we have

$$fmn(ng + \frac{5}{4}cl) = 12IFr$$

$$I = \frac{fmn}{12Fr}(ng + \frac{5}{4}cl) \qquad (250.)$$

which is a general rule for this case.

514.—Carriage Beam with One Header, for Dwellings, etc.—In formula (250.), putting for f its value 140 + $\frac{y}{3c}$ (form. 232.), for F its value 62,000 (Table XX.), and for r its value 0.03 (Art. 314), we have

$$I = \frac{\left(140 + \frac{y}{3c}\right)mn}{12 \times 62000 \times 0.03} (ng + \frac{1}{4}cl)$$

$$I = \frac{\left(140 + \frac{y}{3c}\right)mn}{22320} (ng + \frac{5}{4}cl) \qquad (251.)$$

which is a rule for the moment of inertia of a rolled-iron carriage beam, with one header, in floors of assembly rooms, banks, etc. With the moment of inertia found by this rule, the required beam may be selected from Table XVII.

515.—Example.—In a dwelling floor of Paterson 9 inch 70 pound beams, 20 feet long and $2\frac{8}{10}$ feet from centres: Of what size should be a carriage beam which at 5 feet from one end carries a header 17 feet long, with tail beams 15 feet long?

Here y = 70, c = 2.8, m = 5, n = 15, g = 17 and l = 20; and by (251.) we have

$$I = \frac{\left(140 + \frac{70}{3 \times 2 \cdot 8}\right) \times 5 \times 15}{22320} \times \left(\overline{15 \times 17} + \frac{1}{4} \times 2 \cdot 8 \times 20\right) = 161.990$$

or the moment of inertia required is 161.990.

By reference to Table XVII. we find I = 159.597 as the moment of inertia of the 9 inch 135 pound Pittsburgh beam, being nearly the amount called for. If the construction of the floor permit the use of a beam $1\frac{1}{2}$ inches higher, then it would be preferable to use for this carriage beam one of the Trenton $10\frac{1}{2}$ inch 90 pound beams; as these beams, although stronger than we require, are yet (being 45 pounds lighter) more economical.

516.—Carriage Beam with One Header, for First-class Stores.—If, in formula (250.), f be substituted by its value $320 + \frac{y}{3c}$ (form. 233.), F by its value 62,000 (Table XX.), and r by 0.04 (Arts. 367 and 368), we shall have

$$I = \frac{\left(320 + \frac{y}{3c}\right)mn}{12 \times 62000 \times 0.04} (ng + \frac{5}{4}cl)$$

$$I = \frac{\left(320 + \frac{y}{3c}\right)mn}{29760} (ng + \frac{5}{4}cl) \qquad (252.)$$

which is a rule for the moment of inertia for rolled-iron carriage beams, carrying one header, in first-class stores.

517.—Example.—Of what size, in a first-class store, should be a rolled-iron carriage beam 25 feet long, which carries at 5 feet from one end a header 20 feet long, with tail beams 25 feet in length; the tail beams being Trenton 12½ inch 125 pound beams, placed $2\frac{3}{8}$ feet from centres? Here n = 125 n = 20 n = 20 and

Here y = 125, $c = 2\frac{9}{8}$, m = 5, n = 20, g = 20 and l = 25; and by formula (252.) we have

$$I = \frac{\left(320 + \frac{125}{3 \times 2\frac{2}{3}}\right) \times 5 \times 20}{29760} \times \left(\frac{20 \times 20 + \frac{5}{4} \times 2\frac{2}{3} \times 25}{5}\right) = 545.090$$

or the moment of inertia required is 545.090.

To supply the strength needed in this case, we may take a Trenton 10½ inch 135 pound beam, with one of their 12½ inch 125 pound beams; as these two bolted together will give a moment of inertia a little less than the computed amount. It will be more economical, however, to take two of the 12 inch 125 pound beams, since the weight of metal will be less, although the strength will be greater than required.

518.—Carriage Beam with Two Headers and Two Sets of Tail Beams.—Formula (170) contains the elements appropriate to this case, but is for beams of rectangular section. It is quite general in its application, although somewhat complicated. A more simple rule is found in formula (174.). This is not quite so general in application, but still sufficiently so to use in ordinary cases (see Art. 402). In any event, the result derived from its use, if not accurate, deviates so slightly from accuracy that it may be safely taken. We will take, then, formula (174.) and modify it as required

for the present purpose. For bd' putting 121, its value (form. \$00.), we have

$$12IFr = fm \left[\frac{1}{4}cnl + g(mn + s^{2}) \right]$$

$$I = \frac{fm}{12Fr} \left[\frac{1}{4}cnl + g(mn + s^{2}) \right] \qquad (253.)$$

which is a general rule for the case above stated (see Arts. 153 and 243).

\$19.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for Dwellings, etc.—If, in formula (253.), $140 + \frac{y}{3^{c}}$ be substituted for f (form. 232.), 62,000 for F (Table XX.), and 0.03 for r (Art. 314), then we have as a result

$$I = \frac{140 + \frac{y}{3c}}{22320} m \left[\frac{5}{4} cnl + g \left(mn + s^2 \right) \right] \qquad (254.)$$

which is a rule for the moment of inertia for this case as above stated (see Arts. 153 and 243).

\$20.—Example.—In a dwelling having a floor of Paterson 101 inch 105 pound rolled-iron beams, 20 feet long, and placed 5.84 feet from centres: Which of the beams of Table XVII. would be appropriate for a carriage beam to carry two headers 16 feet long, one located 9 feet, and the other 15 feet, both from the same end of the carriage beam? (See Arts. 153 and 243.)

Here the two headers are respectively 9 feet and 5 leet from the walls. The one 9 feet from its wall, being that their away than the other, will create the greater strain,

CARRIAGE BEAM WITH TWO HEADERS, FOR STORES. 355 and therefore m = 9, n = 11, r = 15, s = 5, l = 20, c = 5.84 and y = 105; and by formula (254.) we have

$$I = \frac{140 + \frac{105}{3 \times 5.84}}{22320} \times 9[(\frac{1}{4} \times 5.84 \times 11 \times 20) + 16(9 \times 11 + 5^{\circ})] = 211.337$$

or the required moment of inertia is $211\cdot337$. By reference to Table XVII., we find, as the nearest above this amount, the Trenton or Paterson 10½ inch 135 pound beam, of which $I = 241\cdot478$, and which will be the proper beam for this case.

521.—Carriage Beam with Two Headers and Two Sets of Tail Beams, for First-class Stores.—If, in formula (253.), there be substituted for F its value 62,000 (Table XX.), for f its value $320 + \frac{y}{3c}$ (form. 233.), and for r its value 0.04 (Arts. 367 and 368), we shall have

$$I = \frac{320 + \frac{y}{3c}}{29760} m \left[\frac{5}{4} cnl + g(mn + s^2) \right] \qquad (255.)$$

which is a rule for the moment of inertia required in this case, as above stated (see Arts. 153 and 243).

522.—Example.—In a store having a floor of Trenton 1516 inch 150 pound rolled-iron beams, 25 feet long and 4.87 feet from centres: What ought a carriage beam to be which carries two headers 20 feet long, one located 10 feet from one wall, and the other at 7 feet from the other wall?

Here the distances to the header more remote from its wall are to be called (see Arts. 153 and 243) m and n.

ţ.

Then m = 10, n = 15, r = 18, s = 7, g = 20, l = 25, c = 4.87 and y = 150; and by formula (255.)

$$I = \frac{320 + \frac{150}{3 \times 4.87}}{29760} \times 10[(\frac{1}{4} \times 4.87 \times 15 \times 25) + 20(\overline{10 \times 15} + 7^{\circ})]$$

$$= 695.027$$

or the moment required is 695.027. By an examination of Table XVII., we find that the moment of the Trenton 15% inch 200 pound beam is more than enough for this case, and its use more economical than any combination of other beams affording the requisite strength.

523.—Carriage Beam with Two Headers, Equidistant from Centre, and Two Sets of Tail Beams, for Dwellings, etc.—If for f, F, bd^3 and r, in formula (183.), their respective values be substituted, namely, $f = 140 + \frac{y}{3c}$ (form. 232.), F = 62000 (Table XX.), $bd^3 = 12I$ (form. 205.), and r = 0.03 (Art. 314); then formula (183.) becomes

$$I = \frac{140 + \frac{y}{3c}}{22320} l\left(\frac{5}{16}cl^2 + gm^2\right) \qquad (256.)$$

which is a rule for a rolled-iron carriage beam, carrying two headers equidistant from the centre, with two sets of tail beams, in assembly rooms, banks, etc.

524.—Example.—In an assembly room, having a floor of Buffalo 10½ inch 105 pound rolled-iron beams, 20 feet long and 5.35 feet from centres: What ought a carriage beam to be which carries two headers 16 feet long, located equidistant from the centre of the width of the floor, with an opening between them 6 feet wide?

CARRIAGE BEAM WITH TWO EQUIDISTANT HEADERS. 357

Here c = 5.35, y = 105, l = 20, g = 16 and m = 7; therefore by formula (256.) we have

$$I = \frac{140 + \frac{105}{3 \times 5.35}}{22320} \times 20 \left(\frac{5 \times 5.35 \times 20^{3} + 16 \times 7^{3}}{16 \times 5.35 \times 20^{3} + 16 \times 7^{3}} \right) = 190.761$$

By reference to Table XVII. we find that either the Paterson or Trenton 10½ inch 105 pound beam is sufficiently strong to serve for the required carriage beam.

525.—Carriage Beam with Two Headers, Equidistant from Centre, and Two Sets of Tail Beams, for First-class Stores.—In formula (183.), if we substitute for f, F, bd^3 and r their respective values, as follows, $f = 320 + \frac{y}{3c}$ (form. 233.), F = 62000 (Table XX.), $bd^3 = 12I$ (form. 205.) and r = 0.04 (Arts. 367 and 368), we shall have

$$I = \frac{320 + \frac{y}{3c}}{29760} l\left(\frac{5}{16}cl^2 + gm^2\right) \qquad (257.)$$

which is a rule for a rolled-iron carriage beam carrying two headers equidistant from the centre, with two sets of tail beams, in first-class stores.

526.—Example.—In a first-class store, having a floor of Phoenix 15 inch 150 pound beams 25 feet long and 4.75 feet from centres: What ought a carriage beam to be which carries two headers 20 feet long, located equidistant from the centre of the width of the floor, with an opening between them 8 feet wide?

Here we have y = 150, c = 4.75, l = 25, g = 20 and $m = 8\frac{1}{2}$; therefore formula (257.) becomes

$$I = \frac{320 + \frac{150}{3 \times 4.75}}{29760} \times 25 \left(\frac{5 \times 4.75 \times 25^{3} + 20 \times 81^{3}}{16 \times 4.75 \times 25^{3} + 20 \times 81^{3}} \right) = 658.813$$

or the moment required is 658.813. Table XVII. shows that either of the 15 inch 200 pound beams is of sufficient strength to satisfy the requirements of this case.

527.—Carriage Beam with Two Headers and One set of Tail Beams, for Dwellings, etc.—If, in formula (179.), we substitute for the symbols bd^2 , f, F and r, their respective values, as follows, $bd^2 = 12I$ (form. 205.), $f = 140 + \frac{J}{3}$ (form. 232.), F = 62000 (Table XX.) and r' = 0.03 (Art. 314), we shall have

$$I = \frac{140 + \frac{y}{3c}}{22320} m \left[\{cnl + gj(n+s)\} \right] \qquad (258.)$$

which is a rule for the moment of inertia of a rolled-iron carriage beam, carrying two headers with one set of tail beams, for floors of assembly rooms, banks, etc. (See Arts. 153 and 409.)

528.—Example.—In a bank having a floor of Paterson 10½ inch 105 pound rolled-iron beams, 20 feet long and 5.84 feet from centres: What ought a carriage beam to be which carries two headers 16 feet long, located one at 5 feet from one wall and the other at 6 feet from the other wall, the tail beams being between them?

Here (Art. 157) m is to be put at the wider opening, hence m = 6, n = 14, s = 5, l = 20, c = 5.84, g = 16, j = l - (m + s) = 20 - 11 = 9 and y = 105; and by formula (258.)

$$I = \frac{140 + \frac{105}{3 \times 5.84}}{22320} \times 6 \left[\frac{1}{4} \times 5.84 \times 14 \times 20 + \frac{16 \times 9 \times (14 + 5)}{16 \times 9 \times (14 + 5)} \right]$$

$$= 187.593$$

or, the moment required is 187.593. Referring to Table XVII. we find that either the Paterson or Trenton 10½ inch 105 pound beam will be suitable for this case.

529.—Carriage Beam with Two Headers and One Set of Tail Beams, for First-class Stores.—If, in formula (258),

we substitute (as in Art. 525) $\frac{320 + \frac{y}{3c}}{29760}$ for $\frac{140 + \frac{y}{3c}}{22320}$ we shall have

$$I = \frac{320 + \frac{y}{3c}}{29760} m \left[\frac{1}{4} cnl + gj(n+s) \right]$$
 (259.)

which is a rule for the moment of inertia for a rolled-iron carriage beam, carrying two headers and one set of tail beams, in a first-class store.

530.—Example.—In a first-class store having a floor of Buffalo 15 inch 150 pound beams 25 feet long and 4½ feet from centres: What ought a carriage beam to be which carries two headers 20 feet long, located, one at 5 feet from one wall, and the other at 8 feet from the other wall, with tail beams between them?

Here (Art. 157) m = 8, n = 17, s = 5, l = 25, g = 20, j = 25 - (5 + 8) = 12, $c = 4\frac{1}{2}$ and y = 150; and by (259.)

$$I = \frac{320 + \frac{150}{3 \times 4^{\frac{1}{2}}}}{29760} \times 8 \left[\frac{1}{4} \times 4^{\frac{1}{2}} \times 17 \times 25 + 20 \times 12 \times (17 + 5) \right]$$
$$= 682.750$$

which is the moment required. Either of the 15 inch 200 pound beams of Table XVII. will serve the present purpose.

Strain being at Outside Header, for Dwellings, etc.—As in Fig. 54, floor beams are sometimes framed with two openings, one for a stairway at the wall, and another for light at or near the middle of the floor. In this arrangement the carriage beams are required to sustain three headers. Formula (190.) in Art. 425 is appropriate to this case, but is adapted to a beam of rectangular section. Substituting for bd^3 its value 12I (form. 205.), for f its value $140 + \frac{y}{3c}$ (form. 232.), for F its value 62,000 (Table XX.), and for r its value 0.03 (Art. 314), we have

$$I = \frac{140 + \frac{y}{3c}}{22320} m \left[\frac{1}{4} cnl + g(mn + s^2 - v^3) \right] \quad (260.)$$

which is a rule for the moment of inertia for a rolled-iron carriage beam carrying three headers, in an assembly room, bank, etc.; the headers placed, as in Fig. 54, so that the one causing the greatest strain shall not be between the other two. (See Arts. 252 to 254.)

532.—Example.—In an assembly room having a floor of Trenton 9 inch 70 pound beams 20 feet long and 2.80 feet from centres: Of what size should be a carriage beam carrying, as in Fig. 54, three headers 15 feet long; two of them located at the sides of an opening 6 feet wide, which is placed at the middle of the width of the floor, and the other header located at 3 feet from one of the side walls?

As two of these headers are equidistant from the centre of the floor, the one carrying the longer tail beams will produce the greater strain upon the carriage beam (Art. 253). The distances from this header, therefore, are to be designated by m and n (Art. 244), while r and s are to represent the distances from the other, and v and u are to be the distances from the third header; the one at the stairway.

Here m = 7, n = 13, s = 7, v = 3, l = 20, g = 15, c = 2.8 and y = 70; and by formula (260.) we have

$$I = \frac{140 + \frac{70}{3 \times 2 \cdot 8}}{22320} \times 7 \left[\left(\frac{5}{4} \times 2 \cdot 8 \times 13 \times 20 \right) + 15 \left(\frac{7 \times 13}{7 \times 13} + 7^{2} - 3^{2} \right) \right]$$

$$= 133 \cdot 746$$

which is the required moment. An examination of Table XVII. shows that the Trenton 9 inch 125 pound beam will be more than sufficient for this case.

533.—Carriage Beam with Three Headers, the Greatest Strain being at Outside Header, for First-class Stores.—Here, with the headers located, as in Fig. 54, so that the one causing the greatest strain in the carriage beam shall not be between the other two, the rule is the same, with the excep-

tion of the coefficient, as in the case last presented (for

(see form. 259.) in place of $\frac{140 + \frac{y}{3c}}{22320}$, we shall have

$$I = \frac{320 + \frac{y}{3c}}{29760} m \left[\frac{4}{5} cnl + g(mn + s^2 - v^2) \right] \quad (261.)$$

which is a rule for the moment of inertia required for a rolled-iron carriage beam carrying three headers, in a first-class store; the headers being placed, as in Fig. 54, so that the one carrying the greatest strain shall not be between the other two. (See Arts. 252 to 254.)

The example given in Art. 532 will serve to illustrate this rule, for the two rules are alike except in the coefficient, as above explained.

534.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for Dwellings, etc.—If the headers be located as in Fig. 56, so that the header causing the greatest strain in the carriage beam shall be between the other two (Arts. 260 and 264), then we have formula (194.) (in Art. 432) appropriate to this case, except that it is for a beam of rectangular section. To modify it to suit our present purpose, we have only to substitute for bd^s , f, F and r, their respective values as in Art. 531, and we have

$$I = \frac{140 + \frac{y}{3c}}{22320} [m(\frac{1}{4}cnl + gs^3) + gn(m^2 - v^3)] \quad (262.)$$

as a rule for the moment of inertia required for rolled-iron

etc.; the headers so located that the one causing the greatest strain shall be between the other two. (See Art. 264.)

535.—Example.—In a bank, having a floor of Phænix 10½ inch 105 pound rolled-iron beams, 20 feet long and placed 5.59 feet from centres: Of what size ought a carriage beam to be which carries three headers, 16 feet long, placed, as in Fig. 54, so that the opening in the floor at the wall shall be 4 feet wide, and the other opening 5 feet wide, and distant 6 feet from the other wall?

The middle header in this case being the one which causes the greatest strain in the carriage beam, the distances from it to the two walls are to be called m and n. (See Arts. 244 and 253.) The header carrying the tail beams, one end of which rest upon the wall causing the next greatest strain, the distances from it to the walls are to be called and s. The distances from the third header are v and We have, therefore, m = 9, n = 11, s = 6, v = 4, s = 10, s = 10,

$$I = \frac{140 + \frac{105}{3 \times 5.59}}{22320} [9(\frac{1}{4} \times 5.59 \times 11 \times 20 + 16 \times 6^{4}) + 16(11 \times 9^{2} - 4^{4})] = 199.597$$

Table XVII. we find that the Phænix and Pittsburgh 10½ inch 135 pound beams are a trifle stronger than the required amount. The Trenton and Paterson 10½ inch 135 pound beams are still stronger than this. Being of the same weight, either of the four named beams will serve the purpose.

536.—Carriage Beam with Three Headers, the Greatest Strain being at Middle Header, for First-class Stores.—Take a case where the header causing the greatest strain in the carriage beam occurs between the other two, as in Fig. 56. Formula (262.) is suitable for this case, except in its coeffi-

cient. To modify it to suit our purpose, let $\frac{320 + \frac{y}{3c}}{29760}$ in

formula (261.) be substituted for $\frac{140 + \frac{y}{3c}}{22320}$ in formula (262.); and we have

$$I = \frac{320 + \frac{y}{3c}}{29760} [m(\frac{5}{4}cnl + gs^2) + gn(m^2 - v^2)] \quad (263.)$$

which is a rule for the moment of inertia for rolled-iron carriage beams carrying three headers, in first-class stores; the header causing the greatest strain being between the other two. (See Art. 264.)

The example given in Art. 535 will be sufficient to illustrate this rule, as the two formulas are alike, except in their coefficients.

QUESTIONS FOR PRACTICE.

- 537.—What is the moment of inertia for a beam having a rectangular section?
- 538.—What is the moment of inertia for a beam of section, or of the form of rolled-iron beams?
- 539.—Which of the beams of Table XVII. would be appropriate, when laid upon two supports 25 feet apart, to sustain 15,000 pounds at the middle, with a deflection of for an inch?
- 540.—What weight could be sustained at 10 feet from one end of a Trenton 10½ inch 105 pound beam, 25 feet long between bearings, with a deflection of one inch?
- 541.—What weight uniformly distributed could be sustained upon a Buffalo 9 inch 90 pound beam, projecting as a lever 15 feet from a wall (in which one end is firmly imbedded), with a deflection of $\frac{1}{2}$ an inch?
- 542.—In the floors of a first-class store, constructed with Phœnix 12 inch 125 pound beams, 3½ feet from centres: Which of the beams of Table XVII. ought to be used for a header 15 feet long, carrying one end of a set of tail beams 12 feet long?

- 543.—In the floor of a first-class store, constructed with 12 inch 125 pound beams 2½ feet from centres: Which of the beams of Table XVII. ought to be used for a carriage beam 25 feet long between bearings, carrying, with 0.04 of an inch per foot deflection, a header 20 feet long, located at 7 feet from one end of the carriage beam, and carrying one end of a set of tail beams 18 feet long?
- 544.—In the floor of a first-class store, constructed of 15 inch 150 pound beams 4½ feet from centres: What size should be a carriage beam 25 feet long, which carries two headers 19 feet long, one located at 9 feet from one wall, and the other at 8 feet from the other wall; the two headers having an opening between them?
- 545.—In the floor of a bank, constructed of 101 inch 105 pound beams 22 feet long, and placed 4 feet 4 inches from centres: Of what size should be a carriage beam which carries three headers, 16 feet long, and located, as in Fig. 56, so that one opening at the wall shall be 3 feet wide, and the other opening 6 feet wide, with a width of floor of 6 feet between the two openings?

CHAPTER XX.

TUBULAR IRON GIRDERS.

ART. 546.—Introduction of the Tubular Girder.—During the construction of the great tubular bridges over the Conway River and the Menai Straits, Wales (1846 to 1850), engineers and architects were moved with new interest in discussions and investigations as to the possibilities of constructions involving transverse strains. Since the complete success of those justly celebrated feats of engineering skill, the tubular girder (Fig. 74), as also the plate girder (Fig. 67),

and the rolled-iron beam (Fig. 68), all of which owe their utility to the same principle as that involved in the construction of the tubular girder, have become deservedly popular. They are now extensively used, not only by the engineer in spanning rivers for the passage of railway trains, but also by the architect in the lesser, but by no means unimportant, work of constructing floors over




FIG. 74.

halls of the largest dimensions, without the use of columns as intermediate supports.

547.—Load at Middle—Rule Essentially the Same as that for Rolled-Iron Beams.—The capacity of tubular gir-

ders may be computed by the rules already given. For example: Formula (216.) affords a rule for a load at the middle of a rolled-iron beam, in which (form. 213.),

$$I = \frac{1}{12} (bd^3 - b_i d_i^3)$$

whereof b is the width of top or bottom flange, and b_i equals b, less the thickness of the two upright parts, or webs: d is the entire depth, and d_i is the depth, or height, in the clear between the top and bottom flanges. bd then is the area of the whole cross-section, measured over all, while bd_i represents the area of the vacuity, or of so much of the cross-section as is wanting to make it a solid. The numerical coefficient in formula (216.) is based upon a value of F equal to 62,000, which is the amount derived from experiments on solid rolled-iron beams. For built beams, such as the tubular girder, F by experiment would prove to be less, but the formula (216.) may be used as given, provided that proper allowance be made in the flanges on account of the rivet holes; that is, taking instead of the actual breadths of the flanges only so much of them as remains uncut for rivets.

548.—Load at Any Point—Load Uniformly Distributed.

—For a load at any point in the length of a beam, formula (222.) will serve, while for a load uniformly distributed, formula (228.) affords a rule. In general, any rule adapted to rolled-iron beams will serve for the tubular or plate girder, by taking as the areas of metal the uncut portion only.

549.—Load at Middle—Common Rule.—The rules just quoted are not those which are generally used for tubular beams. Preliminary to planning the Conway and Britannia

tubular bridges, the engineers tested several model tubes, and from them deduced the formula

$$W = \frac{a'dC}{l}$$

in which C is a constant, found to be equal to 80 when W represents gross tons. Changing W to pounds, we have

$$W = \frac{2240 \times 80 \times a'd}{l} = 179200 \frac{a'd}{l}$$

This is for the breaking weight. Taking the safe weight as 9000 pounds per inch, or \(\frac{1}{4}\) of the breaking weight, we have

$$\frac{179200}{5} = 35840$$

and, as an expression for the safe weight, the area of the bottom flange equals.

$$a' = \frac{Wl}{35840d}$$

or, if instead of the above constant, 80, we put 80.357, we shall have our constant in round numbers, thus,

$$a' = \frac{Wl}{36000d} \tag{264.}$$

which is a rule for the area of the bottom flange of a tubular girder, with the load at the middle; a' being in inches, l and d in feet, and W in pounds. This rule is identical with formula (265.), deduced in another manner.

550.—Capacity by the Principle of Moments.—Generally, the strength of tubular beams is ascertained by the principle of moments or leverage. Sufficient material must be

provided in the top flange to resist crushing, and in the bottom flange to resist tearing asunder, while the material in the web or upright part should be adequate to resist shearing.

551.—Load at Middle—Moments.—We will first consider the requirements in the flanges.

The leverage, or action of the power tending to break the beam, as also that of the resistance of the materials, is represented in Figs. 8 and 9. When the load upon a beam is concentrated at the middle, it acts with a power of half the weight into half the length of the beam (Art. 35), and the tension thereby produced in the bottom flange is resisted by a leverage equal to the height of the beam; or, if d equals the height of the beam between the centres of gravity of the cross-sections of the top and bottom flanges, and I equals the amount of tension produced in the lower flange by the action of a weight W upon the middle of the beam, then

$$\frac{1}{2}W \times \frac{1}{2}l = dT$$

$$\frac{1}{2}Wl = dT$$

Again, if k equals the pounds per square inch of section with which the metal in the lower flange may be safely trusted, and a' equals the area in inches in the bottom flange, then a'k = T, and

$$\frac{1}{4}Wl = a'kd$$

$$a' = \frac{Wl}{4dk} \tag{265.}$$

which is a rule for the area of the bottom flange of a tubular girder, loaded at the middle, and in which W and k are in pounds, a' is in inches, and d and l are in feet. (The

F. I

72

K

. .

- ph.

T.

Car

Ē

Sist

if i

MODE

63-

.d

area of the top flange is to be made equal to that of the bottom flange. See Art. 456.) If k be taken at 9000, as in Art. 549, then 4k = 36000, and formula (265.) becomes identical with formula (264.).

552.—Example.—What area of metal would be required in the bottom flange of a tubular girder 40 feet long and 3 feet high, to sustain at the middle 75,000 pounds; 9000 pounds being the weight allowed upon one inch of the wrought-iron of which the flanges are to be made?

Here W = 75000, l = 40, d = 3 and k = 9000; and we have, by formula (265.),

$$a' = \frac{75000 \times 40}{4 \times 3 \times 9000} = 27.77$$

or the area equals 27% inches. This is the amount of metal in addition to that required for rivet holes.

553.—Load at Any Point.—A load concentrated at any point in the length of the beam acts with a leverage equal to $W\frac{mn}{l}$ (see Art. 56), and the resistance is Td = a'kd; therefore

$$W\frac{mn}{l} = a'dk$$

$$a' = W\frac{mn}{dkl} \qquad (266.)$$

which is a rule for this case, as above stated, in which a' is in inches, W is in pounds, and m, n, d and l are in feet.

554.—Example.—What amount of metal would be required in the bottom flange of a tubular girder 50 feet long

and $3\frac{1}{2}$ feet high, to sustain a load of 50,000 pounds at 2° feet from one end, when k = 9000?

Here W = 50000, m = 20, n = 30, $d = 3\frac{1}{2}$, k = 9000 and l = 50; and, by formula (266.),

$$a' = \frac{50000 \times 20 \times 30}{3\frac{1}{2} \times 9000 \times 50} = 19.05$$

or the area should have 19 inches of solid metal, uncut by rivet holes. The top flange should contain an equal amount. (See Art. 456.)

555.—Load Uniformly Distributed.—For this load the effect at any point in the beam is equal to that of half the load, if concentrated at that point (see Art. 214); or, from formula (266.),

$$a' = U \frac{mn}{2dkl} \tag{267.}$$

which is a rule for the area of the bottom flange at any point in its length, and in which a' is in inches, U is in pounds, and m, n, d and l are in feet.

556.—Example.—In a tubular girder 50 feet long, $3\frac{1}{2}$ feet high, and loaded with an equably distributed load of 120,000 pounds: What should be the area of the bottom flange at the middle, and at each 5 feet of the length thence to each support, k being taken at 9000?

Here U=12000, $d=3\frac{1}{2}$, k=9000 and l=50; and by formula (267.) we have

$$a' = \frac{120000mn}{2 \times 3\frac{1}{2} \times 9000 \times 50} = 0.038095mn$$

When m = n = 25, then

$$a' = 0.038095 \times 25 \times 25 = 23.81$$

or the area required in the bottom flange at mid-length is 23.81 inches.

When m = 20, then n = 30, and

$$a' = 0.038095 \times 20 \times 30 = 22.86$$

or the required area at 5 feet from the middle, either way, equals 22% inches.

When m = 15, then n = 35, and

$$a' = 0.038095 \times 15 \times 35 = 20.00$$

or, at 10' feet each side of the middle, the area should be 20 inches.

When m = 10, then n = 40, and

$$a' = 0.038095 \times 10 \times 40 = 15.24$$

or, at 15 feet each side of the middle, the area should be 15} inches.

When m = 5, then n = 45, and

$$a' = 0.038095 \times 5 \times 45 = 8.57$$

or, at 20 feet each side of the middle, the area should be inches.

557.—Thickness of Flanges.—In the results of the example just given, it will be observed that the area of metal required in the flanges increases gradually from the points of support each way to the middle of the beam (see Art. 178). In practice, this requirement is met by building up the flanges with laminas or plates of metal, lapping on according

to the computed necessary amount. In this process, the plates used are generally not less than f of an inch thick. For an example, take the results just found. Adding, say f for rivet holes, and dividing the sum by the width of the girder, which we will call 12 inches, there results as the thickness of metal required,

```
at the middle, 2.31, say 2½ inches;

" 5 feet from middle, 2.22, " 2½ "

" 10 " " 1.95, " 2 "

" 15 " " 1.48, " 1½ "

" 20 " " 0.83, " 1 inch.
```

article might be built with the two flanges in plates 12 inches wide, thus: Lay down first a plate one inch thick the whole length of the girder. (With an addition for supports on the walls, say \(\frac{1}{10}\) of the length, or 2\(\frac{1}{2}\) feet at each end, this plate would be 55 feet long.) Upon this place a plate \(\frac{1}{2}\) inch thick and 40 feet long; on this a plate \(\frac{1}{2}\) inch thick and 30 feet long; on this a plate \(\frac{1}{2}\) inch thick and 10 feet long; and on this a plate \(\frac{1}{2}\) inch thick and 10 feet long. The plates are all to extend to equal length each side of the middle of the girder, and to be well secured together by riveting. The longer plates, probably, will have to be in more than one piece in length. Where heading joints occur, a covering plate should be provided for the joint and riveted.

559.—Shearing Strain.—A sufficient area having been provided in the top and bottom flanges to resist the compressive and tensile strains, there will be needed in the web metal sufficient to resist only the shearing strain. This strain

is, theoretically, nothing at the middle of a beam uniformly loaded, but from thence increases by equal increments to each support, at which place it is equal to one half of the whole load (Arts. 172 and 174). For example: In the case considered in Art. 556, the beam, 50 feet long, carries 120,000 pounds uniformly distributed over its whole length; half of the load over half of the beam. At the centre, the shearing strain is nothing; at 5 feet from the centre, it is equal to $\frac{1}{2}$ of half the load, or is equal to $\frac{1}{2}$,000 pounds; at 10 feet it is 24,000; at 15 feet it is 36,000; at 20 feet it is 48,000; and at 25 feet, or at the supports, it is 60,000 pounds, or half the whole load.

560.—Thickness of Web.—If G be put for the shearing stress, then

$$G = a'k'$$

in which a' is the area in inches of the web at the point of the stress, and k' is the effective resistance of wroughtiron to shearing, per inch area of cross-section. If t equals the thickness, and d the height of the web, then a' = td, and the above equation becomes

$$G = k'td$$
 or
$$t = \frac{G}{dk'}$$
 (268.)

which is a rule for the thickness of the web, at any point in the length of the beam, and in which t and d are in inches.

561.—Example.—What should be the thickness of the web of the tubular girder considered in Art. 556, computed

at every 5 feet in length of the girder? If k' be taken 7000 pounds, it will be but little more than three quarters, 6000, the amount taken in tensile strain (Art. 173),* and taking d at, say 38 inches, we have, by formula (268.),

$$t = \frac{G}{38 \times 7000} = \frac{G}{266000}$$

Therefore, when G equals 60,000 (Art. 559), then

$$t = \frac{60000}{266000} = 0.225$$

When G equals 48,000, then $t = \frac{48000}{266000} = 0.180$. When G equals 36,000, then $t = \frac{36000}{266000} = 0.135$. As these are the greater of the strains, and are all below the practical thickness in girders, it is not worth while to compute those at the remainder of the stations.

562.—Construction of Web.—From the results in the last article, it appears that in this case the web is required, of necessity, to be only a quarter of an inch thick in its thickest part, at the supports. With an increase of load, the thickness of the web would increase, for by the formula it is directly as the load.

The thickness of web just computed is the whole amount required in the two sides of the girder. In practice, it is found unwise to use plates less than a quarter of an inch thick. Following this custom, the two sides of the girder

^{*} The resistance to shearing is generally taken at three quarters of the tensile strength (see Haswell's Engineers' and Mechanics' Pocket Book, p. 485—Weisbach's Mechanics and Engineering, vol. 2, p. 77).

the amount of metal actually required. Hence it may justly be inferred that in similar cases the plate beam (Fig. 67) would be preferable to the tubular girder, as its web, being single, would require only half the metal that would be required in the two sides of the tubular girder. It is also preferable for the reason that it is more easily painted, and thus kept from corrosion. On the other hand, a tubular beam is stiffer laterally. In the construction of the web, as a precaution to prevent buckling, or contortion, it is requisite to provide uprights of T iron, at intervals of, say 3 feet on each side, to which the web is to be riveted.

563.—Floor Girder—Area of Flange.—If for U in formula (267.), there be substituted its value in a floor, c'fl, of which c' is the distance from centres between girders, or the width of floor sustained by the girder, l is the length of the girder between supports (both in feet), and f is the load per foot superficial upon the floor, including the weight of the materials of construction, then

$$a' = c' f l \frac{mn}{2dkl}$$

$$a' = f \frac{c'mn}{2dk}$$
(269.)

which is a rule for the area of the bottom flange of a tubular girder, sustaining a floor, and in which a' is in inches and c', m, n and d are in feet.

564.—Weight of the Girder.—In estimating the load to be carried by a girder, the estimate must include the weight of the girder itself. It is desirable therefore to be able to

measure its weight approximately before its dimensions have been definitely fixed. The weight of a tubular girder will be in proportion to its area of cross-section (which will be approximately as the load it has to carry), and to its length (form.265.); or, when U is the gross load to be carried, and l the length between bearings, then the weight of the girder between the bearings is

$$K = \frac{Ul}{n}$$

in which n is a constant, and U is the whole load, including that of all the materials of construction. The value of n, when derived from so large a structure as that of the tubular bridge over Menai Straits, is about 600, but from several examples of girders from 35 to 50 feet long, in floors of buildings, its value is found to be about 700. For our purpose, then, we have n = 700. If for U we put its equivalent c'fl, as in Art. 563, then

$$K = \frac{c'fl^2}{700} \tag{270.}$$

This is the weight of so much of the girder as occurs within the clear span between the supports.

565.—Weight of Girder per Foot Superficial of Floor.— The area of the floor supported by a girder is c'l. Dividing K by this, the quotient will be f', the weight of the girder per foot superficial of the floor, thus:

$$f' = \frac{K}{c'l} = \frac{\frac{c'fl^*}{700}}{\frac{c'l}{c'l}} = \frac{fl}{700}$$

Now f, the total load per foot superficial of the floor, com-

prises the superimposed load, the weight of the brick arches, etc., and the weight of the girder f'; and, putting m for the weight of all else save that of the girder, we have

$$f = m + f' \qquad \text{and, from the above,}$$

$$f' = \frac{fl}{700} = \frac{(m + f')l}{700}$$

$$f' = \frac{lm + f'l}{700}$$

$$700f' = lm + f'l$$

$$700f' - f'l = lm$$

$$f'(700 - l) = lm$$

$$f' = \frac{lm}{700 - l} \qquad (271.)$$

which is a rule for ascertaining the weight per foot superficial of the floor due to the tubular girder.

566.—Example.—A floor, the weight of which, including that of the superimposed load, is 140 pounds per superficial foot, is carried upon a girder 50 feet in length between its bearings. What additional amount per foot superficial should be added for the weight of the girder?

Here l = 50 and m = 140, and by (271.),

$$f' = \frac{140 \times 50}{700 - 50} = 10.77$$

or the weight to be added for the girder is 10% pounds. Then f = m + f' = 140 + 10% = 150% pounds.

567.—Total Weight of Floor per Foot Superficial, including Girder.—In the last article *m* represents the weight of one foot superficial of a floor, including the load to be car-

ried; also, f' represents the weight due to the girder; f' for the total load, f = m + f'. Using for f' its value f' in formula (271.) we have

$$f = m + f' = m + \frac{lm}{700 - l}$$

$$f = m \left(1 + \frac{l}{700 - l} \right)$$

$$f = m \frac{700}{700 - l}$$

and for m, taking its value as given in formula (232.), it being there represented by f,

$$f = \left(140 + \frac{y}{3c}\right) \frac{700}{700 - l} \tag{272.}$$

which is the value of f, the total load per superficial foot of the floors of assembly rooms, banks, etc., to be used in the calculation of tubular girders; and taking the value of m, as expressed in formula (233.) we have

$$f = \left(320 + \frac{y}{3c}\right) \frac{700}{700 - l} \tag{273.}$$

which is the corresponding value of f for the floors of first-class stores.

568.—Girders for Floors of Dwellings, etc.—If in formula (269.), we substitute for f its value as in formula (272.), we shall have

$$a' = \left(140 + \frac{y}{3c}\right) \frac{700}{700 - l} \times \frac{c'mn}{2dk}$$
 (274.)

which is a rule for the area of the bottom flange of a tubular girder, supporting the floor of an assembly room or bank, and in which a' is in inches, and c, l, c', m, n and d are in feet.

beams, 4 feet from centres: What ought to be the area of the bottom flange of a tubular girder 40 feet long between bearings, 2\frac{3}{2} feet deep, and placed 17 feet from the walls, or from other girders; the area of the flange to be ascertained at every five feet in length of the girder?

Here y = 70, c = 4, l = 40, c' = 17 and $d = 2\frac{9}{8}$. Putting k at 9000 we have, by (274.),

$$a' = \left(140 + \frac{70}{3 \times 4}\right) \frac{700}{700 - 40} \times \frac{17}{2 \times 2\frac{9}{8} \times 9000} \times mn$$

$$a' = 0.05478mn$$

The values of m and n are as follows:

1113

At the middle,
$$m = 20$$
 and $n = 20$
" 5 feet from middle, $m = 15$ " $n = 25$
" 10 " " $m = 10$ " $n = 30$
" 15 " " $m = 5$ " $n = 35$

from which the values of a' are as follows:

At the middle,
$$a' = 0.05478 \times 20 \times 20 = 21.91$$

" 5 feet from middle, $a' = 0.05478 \times 15 \times 25 = 20.54$
" 10 " " $a' = 0.05478 \times 10 \times 30 = 16.43$
" 15 " " $a' = 0.05478 \times 5 \times 35 = 9.59$

These are the areas of cross-section of the lower flange, at the respective points named. The top flange is to be of the same size. (See Art. 456.)

570.—Girders for Floors of First-class Stores.—If, in formula (274,), 320 be substituted for 140 (see form. 233.), we shall have

$$a' = \left(320 + \frac{y}{3c}\right) \frac{700}{700 - l} \times \frac{c'mn}{2dk}$$
 (275.)

As this rule is similar to (274.), the example given to illustrate that rule will suffice also for this.

571.—Ratio of Depth to Length, in Iron Girders.—In order that the requisite strength in tubular girders may be attained with a minimum of metal, the depth of a girder should bear a certain relation to the length. To deduce a rule for this ratio from mathematical considerations purely, is not an easy problem. Baker in his work on the Strength of Beams, p. 288, discusses the subject at some length. No more will be attempted here than to obtain a rule based upon some general considerations, and upon results tested and corrected by experience.

girders for the floors of large buildings, it is found in practice to be unadvisable to use plates of a less thickness than one quarter of an inch. If each side of the girder be a quarter of an inch thick, then the least thickness for the web (using this term technically) is a half inch. This is more than is usually found necessary, in this class of girders, to resist shearing (Art. 562). As the thickness is thus fixed, therefore the area of the web will be in proportion to its height, and consequently it is advisable, in so far as the web is concerned, to have the depth of the girder small; but, on the other hand, as the area of the flanges is inversely proportional to the depth (see form. 265.), a reduction of the flanges will require that the depth be increased. The cost of the girder is in proportion to its weight, which is in proportion

to its area of cross-section, and hence the desirability of making both as small as possible.

The area of the flanges is, by formula (265.), in proportion to $\frac{Wl}{dk}$, and, as before shown, the area of the web will be in proportion to its height; or the whole area will be in proportion to $\frac{Wl}{dk}+d$; and the problem is to find such a value of d as will make this expression a minimum. Putting the differential of this equation equal to zero, we find that the area of the cross-section of the beam will be a minimum when

$$d = \sqrt{\frac{Wl}{kx}}$$

in which x is a constant, to be derived from experience, and which, by an application of the formula to girders of this class, is, when the weight is equally distributed, found to be equal to 30. This reduces the formula to

$$d = \sqrt{\frac{\overline{U}\overline{l}}{30\overline{k}}} \tag{276.}$$

and when for U its value c'fl is substituted

$$d = l\sqrt{\frac{c'f}{30k}} (277.)$$

which is a rule for ascertaining the economical depth of a tubular girder; a rule useful in cases where the depth is not fixed by other considerations.

573.—Example.—In a floor where the girders are 50 feet long and placed 15 feet from centres, and where the total load per foot superficial is 155 pounds: What would be the most economical depth for the girders?

Here l = 50, c' = 15, f = 155 and k = 9000, equal the safe tensile power of wrought-iron; and by (277.)

$$d = 50 \times \sqrt{\frac{15 \times 155}{30 \times 9000}} = 4.64$$

or the depth should be 4 feet 7\frac{1}{8} inches. The depth mages be found by this formula, and then the area of flanges be formula (274.) for assembly rooms, banks, etc.; or, by for mula (275.) for first-class stores.

QUESTIONS FOR PRACTICE

- 574.—In a tubular girder 50 feet long, 3 feet 4 inches high, and loaded with 100,000 pounds at the middle: What ought to be the area of each of the top and bottom flanges, when the metal of which they are made may be safely trusted with 9000 pounds per inch?
- 575.—In the same girder: What should be the area of the top or bottom flange, if the load of 100,000 pounds be placed at 15 feet from one end, instead of at the middle of the beam?
- 576.—In a tubular girder 50 feet long, 40 inches high, and uniformly loaded with 200,000 pounds: What should be the area of the top and bottom flanges, at every five feet of the length of the girder?
- 577.—In the same girder: What ought to be the thickness of the web, at every five feet of the length of the girder. to effectually resist the shearing strain?

- 578.—In a tubular girder 40 feet long, 32 inches high, sustaining, with other girders and the walls, the floor of an assembly room, composed of 9 inch 70 pound beams 5 feet from centres, the girders being placed 16 feet from centres: What should be the area of each of the top and bottom flanges, at every five feet of the length, the metal in the flanges being such as may be safely trusted with 9000 pounds per inch?
 - 579.—In a floor, where the depth of the tubular girders is not arbitrarily fixed, where the girders are 42 feet long and placed 17 feet from centres, and where the total load to be carried is 160 pounds per superficial foot: What would be the proper depth of the girders, putting the safe tensile strain upon the metal at 9000 pounds?

CHAPTER XXI.

CAST-IRON GIRDERS.

ART, 580.—Cast-Iron Superseded by Wrought-Iron.—The means for the manufacture of rolled-iron beams (Chapter XIX.) have so multiplied within the last ten years that the cost of their production has been much reduced, and as a consequence this beam is now so extensively used as to have almost entirely superseded the formerly much used cast-iron beam or girder. Beams and girders of cast-iron, however, are still used in some cases, and it is well to know the proper rules by which to determine their dimensions. A few pages, therefore, will here be devoted to this purpose.

581.—Flanges—Their Relative Proportion.—In Fig. 75 we have the usual form of cross-section of cast-iron beams, in which the bottom flange AB contains four times as much



Ftg. 75.

metal as the top flange *CD*. It was customary, fifty years since, to make the top and bottom flanges equal. (See Tredgold on Cast-Iron, Vol. I., Art. 37. Plate I.)

Mr. Eaton Hodgkinson (who in 1842 edited a fourth edition of Tredgold's first volume, and in 1846 added a second volume to that valuable work) made many important experiments on cast-iron. Among the valuable deduc-

tions resulting from these experiments was this: that cast-

iron resists compression with about seven times the force that it resists tension (Vol. II., Art. 34); and that the form of section of a beam which will resist the greatest transverse strain, is that in which the bottom flange contains six times as much metal as the top flange (Vol. II., Art. 138, page 440). If beams of cast-iron for buildings were required to serve to the full extent of the power of the metal to resist rupture, the proportion between the areas of top and bottom flanges should be as 1 to 6. If, on the other hand, they be subjected only to very light strains, the areas of the two flanges ought to be nearly if not quite equal. In view of the fact that in practice it is usual to submit them to strains greater than the latter, and less than the former, therefore an average of the proportions required in these two cases is that which will give the best form for use. Guided by these considerations, it is found that when the flanges are as 1 to 4, we have a proportion which approximates very warly the requirements of the case.

strain upon the metal; a comparatively small requirement. Owing, however, to a tendency in castings to fracture in cooling, the thickness of the web should not be much less than that of the flanges, and the points of junction between the web and flanges should be graduated by a small bracket or easement in each angle. (Tredgold's Cast-Iron, Vol. II., Art. 124.) The thickness of the three parts web, top flange and bottom flange may with advantage be made in proportion as 5, 6 and 8. Made in these proportions, the width of the top flange will be equal to one third of that of the bottom flange; for if w, equal the width of the bottom flange; for if w, equal the width of the bottom flange; for if the top flange, t, equal the thick-

ness of bottom flange and t_{μ} that of the top, a_{ν} equal the area of the bottom flange and a_{μ} the area of the top flangesthen $a_{\nu} = w_{\nu}t_{\nu}$ and $w_{\nu} = \frac{a_{\nu}}{t_{\nu}}$; also, $a_{\mu} = w_{\mu}t_{\mu}$ and $w_{\mu} = \frac{a_{\mu}}{t_{\mu}}$ and from these, remembering that $a_{\nu} = 4a_{\mu}$, and that

$$t_{\mu}:t_{\nu}:6:8,$$

we have

$$w_{u} = \frac{a_{u}}{t_{u}} = \frac{\frac{1}{4}a_{i}}{\frac{6}{8}t_{i}} = \frac{1}{8}u_{i} = \frac{1}{8}w_{i}$$

or the width of the top flange equals one third of that of the bottom flange.

583.—Load at Middle.—Mr. Hodgkinson found, in his experiments, that the strength was nearly as the depth and as the area of the bottom flange. For the breaking weight, W, he gives

$$W = \frac{ca_i d}{l} \tag{278.}$$

an expression for the relative values of the dimensions and weight; in which W is the breaking weight at the middle, l the length of the beam, d its depth, a_l the area of the bottom flange, and c is a constant, to be derived from experiment. This constant, when the weight was in tons and the dimensions all in inches, he found to be 26. Taking the weight in pounds and the length in feet, we have $4853\frac{1}{2}$ for the constant, or say 4850, and therefore

$$W = \frac{4850a_i d}{l}$$

When a is the factor of safety,

$$W = \frac{4850a_{,}d}{al}$$

$$a_{,} = \frac{Wal}{4850d}$$
 (279.)

or

which is a rule for the area of the bottom flange of a castiron beam, required to sustain safely a load at the middle.

The area of the top flange is to be made equal to $\frac{a_i}{4}$, and the thicknesses of the web and top and bottom flanges are to be in proportion as 5, 6 and 8.

584.—Example.—What should be the dimensions of the cross-section of a cast-iron beam 20 feet long between supports and 24 inches high at the middle, where it is to carry 30,000 pounds; with the factor of safety equal to 5?

Here W = 30000, a = 5, l = 20 and d = 24; and, by formula (279.),

$$a_1 = \frac{30000 \times 5 \times 20}{4850 \times 24} = 25.773$$

Now the thickness will depend upon the width, and this is usually fixed by some requirement of construction. If the width be 12 inches, then the thickness of the bottom flange will be $\frac{25 \cdot 77}{12} = 2 \cdot 15$, or $2\frac{1}{8}$ inches full. The width of the top flange will equal $\frac{w_i}{3} = \frac{12}{3} = 4$ (see Art, 582), and its thickness will be $\frac{8}{8}t_i = \frac{6}{8} \times 2 \cdot 15 = 1 \cdot 61$, or $1\frac{5}{8}$ inches; while the thickness of the web will be $\frac{5}{8}t_i = \frac{5}{8} \times 2 \cdot 15 = 1 \cdot 34$, or $1\frac{1}{8}$ inches.

585.—Load Uniformly Distributed.—A load uniformly distributed will have an effect at any point in a beam equal to that which would be produced by half of the load if it were concentrated at that point (Art. 214). Therefore, if

U equals the load uniformly distributed, $\frac{1}{2}U = W$ in formula (279.), or

$$a_{i} = \frac{\frac{1}{8}Ual}{4850d}$$

$$a_{i} = \frac{Ual}{9700d}$$
 (280.)

which is a rule for cast-iron beams to carry a uniformly distributed load.

This is precisely the same as the previous rule, except in the coefficient. The example given in Art. 584 will therefore serve to illustrate this rule, as well as the previous one.

586.—Load at Any Point—Rupture.—From formula (278.) we have

$$Wl = ca_i d$$

and, by a comparison of formulas (21.) and (23.),

$$Wl = 4W - \frac{mn}{l}$$

therefore, in the above, substituting this value of Wl, we obtain

$$ca_{i}d = 4W\frac{mn}{l}$$
 or
$$a_{i} = W\frac{4mn}{cdl}$$
 (281.)

which is a rule for the area of the bottom flange at any point in the length of the beam. The weight given by this rule is just sufficient to rupture the bottom flange.

587.—Safe Load at Any Point.—The value of c, for a concentrated load, is (Art. 583) 4850, hence

$$\frac{4}{c} = \frac{4}{4850} = \frac{1}{1212\frac{1}{2}}$$

In formula (281.), substituting for $\frac{4}{c}$ this value, and inserting a, the factor of safety, then

$$a_{i} = \frac{Wamn}{1212\frac{1}{2}dl}$$
 (282.)

which is a rule for the area of the bottom flange at any point; W, the safe load, being concentrated at that point.

588.—Example.—In a cast-iron beam 20 feet long between bearings: What should be the area of the bottom flange at eight feet from one end, at which point the beam is 20 inches high and carries 25,000 pounds; the factor of safety being equal to 5?

Here W = 25000, a = 5, m = 8, n = 12, d = 20 and l = 20; and by formula (282.)

$$a_1 = \frac{25000 \times 5 \times 8 \times 12}{1212\frac{1}{2} \times 20 \times 20} = 24.74$$

or the area should be 24% inches.

Point.—This effect at any point is equal to that produced by half the load were it all concentrated at that point (Art. 214); therefore, if U represent the uniformly distributed load, then by formula (282.)

$$a_{i} = \frac{\frac{1}{2}Uamn}{1212\frac{1}{2}dl}$$

$$a_{i} = \frac{Uamn}{2425dl}$$
(283')

which is a rule for the area of the bottom flange of a castiron beam at any point, to carry safely a uniformly distributed load. If the depth of the beam remain constant throughout the length, then a_i will vary as the rectangle mn.

From formula (283.) we have

$$d = \frac{Uamn}{2425a_i l} \tag{284.}$$

which is a rule for the depth of a beam at any point, to carry safely a uniformly distributed load. If the area of the bottom flange remain constant throughout the length, then d will vary as the rectangle mn.

be seen that when a_i , the area of the bottom flange, remains constant throughout the length of the beam, then the depths will vary in proportion to the rectangle of the two segments, m and n, of the length. The corresponding curve which may be drawn through the tops of the ordinates denoting the various depths, is that of a parabola (Art. 212). Instead of computing the depths at frequent intervals, therefore, it will be sufficient to compute the depth at the centre only, and then give to the web the form of a parabola.

591.—Two Concentrated Weights—Safe Load.—Formula (23.) is appropriate for a concentrated load at any point in the length of a beam, and formula (30.) is for two concentrated loads at any given points.

A comparison of these formulas shows that

$$4Wa\frac{mn}{l}=4a\frac{m}{l}(Wn+Vs)$$

In Art. 586 we have

$$ca_{l}d = 4W\frac{mn}{l}$$

which is an expression for the breaking load. Inserting a, the symbol of safety, in this expression, we have

$$ca_{l}d = 4Wa \frac{mn}{l}$$

an expression for the safe load for cast-iron beams. If for the second member of this equation there be substituted its value as above,

$$4a\frac{m}{l}(Wn+Vs)$$

we shall have

$$ca_{i}d = 4a\frac{m}{I}(Wn + Vs)$$

an expression for two concentrated safe loads. From this we have

$$a_{l}d = \frac{4}{c}a\frac{m}{l}(Wn + Vs)$$

In Art. 587 we have $\frac{4}{c} = \frac{1}{1212\frac{1}{2}}$, therefore

$$1212\frac{1}{2}a_{i}d = a\frac{m}{l}(Wn + Vs)$$
 or

$$a_{l} = \frac{a \frac{m}{l} (Wn + Vs)}{1212 \frac{1}{2} d}$$
 (285.)

which, in a beam carrying two concentrated loads, is a rule

for the area of the bottom flange at the location of W, one of the loads, as in Fig. 76; and (see Art. 153)

$$a_{l} = \frac{a \frac{s}{l} (Vr + Wm)}{1212 \frac{1}{2} d}$$
 (286.)

which, in a beam carrying two concentrated loads, is a rule for the area of the bottom flange at the location of V, one of the loads, as in Fig. 76.

592.—Examples.—As an application of rules (285.) and (286.), let it be required to ascertain the dimensions of a cast-




Fig. 76.

iron girder to sustain to brick wall in which there are three windows, as in Fig. 76, so disposed as to concentrate the weight of the wall into two loads, as at W and V. Let L the length in the clear of the supports, = 20, m = 7, n = 13, s = 6 and r = 4

feet, and the height of the girder at W and V equal 35 inches. Also, let the wall be 16 inches thick, and so much of it as is sustained at W measure 250 cubic feet, at 110 pounds per foot, or 27,500 pounds. Likewise, suppose the weight upon V to equal 27,000 pounds.

Taking the factor of safety at 5 we now have, by formula (285.),

$$a_1 = \frac{5 \times \frac{7}{20} \left[(27500 \times 13) + (27000 \times 6) \right]}{1212\frac{1}{2} \times 25} = 29.99$$

or the area of flange is required to be 30 inches at W; and, by formula (286.),

$$a_{1} = \frac{5 \times \frac{6}{20} \left[(27000 \times 14) + (27500 \times 7) \right]}{1212\frac{1}{2} \times 25} = 28 \cdot 23$$

or the area of flange is required to be $28\frac{1}{4}$ inches at V.

As the wall is 16 inches thick, the width of the bottom flange should be 16 inches, and its thickness therefore should be

$$\frac{30}{16} = 1.875$$
 inches at \hat{W}

$$\frac{28 \cdot 23}{16} = 1 \cdot 764 \quad \text{inches at} \quad V$$

From W to V the thickness is to be graded regularly from 1.875 to 1.764; while from W to the end next W it is to be equal to that at W, $1\frac{\pi}{8}$ inches thick, and from V to the end next V it is to be $1\frac{\pi}{4}$ inches thick.

The width of the top flange is to be (Art. 582) one third of the width of the bottom flange, or $\frac{16}{8} = 5\frac{1}{8}$ inches. Proportioning the three parts as 5, 6 and 8 (Art. 582), the thickness of the top flange will be

$$\frac{6}{8} \times 1\frac{3}{4} = 1\frac{6}{16}$$
 inches at V
 $\frac{6}{8} \times 1\frac{7}{8} = 1\frac{13}{3\frac{3}{2}}$ inches at W

The thickness is to be graded regularly between W and V, and thence to each end of the beam the thickness is to be that of W and V respectively. The web is to be of the shape shown in Fig. 76, and is to be (Art. 582)

$$\frac{5}{8} \times 1\frac{8}{4} = 1\frac{3}{3\frac{12}{3}}$$
 at V and $\frac{5}{8} \times 1\frac{7}{8} = 1\frac{1}{6}\frac{1}{4}$ at W

or, say 11 inches, averaging it throughout.

593.—Arched Girder.—A beam such as shown in Fig. 77 is known as the "bow-string girder," in which the curved




Fig. 77.

part is a cast-iron beam of the T form of cross-section, and the feet of the arch are held horizontally by a wrought-iron tie-rod. This beam, although very popular with builders, is by no

means worthy of the confidence which is placed in it. With an appearance of strength, it is in reality one of the weakest beams used. Without the tie-rod its strength is very small, much smaller than if the T section were reversed so as to have the flange at the bottom, thus, 1 (Tredgold, Vol. II., pp. 414 and 415).

594.—Tie-Rod of Arched Girder.—The action of a concentrated weight at the middle of a tubular girder, in producing tension in the bottom flange, is explained in Art. 551. The tension in the tie-rod of an arched girder is produced in precisely the same manner, and therefore the rule (form. 265.) there given will be applicable to this case, when modified as required for a uniformly distributed load; or, for W substituting its value, $\frac{1}{2}U$ (Art. 585). Then, upon the presumption that there is sufficient material in the cast arch to resist the thrust, we have

$$a_{i} = \frac{\frac{1}{2}Ul}{4dk}$$

in which d is in feet. If d be taken in inches, then

$$a_{i}=\frac{Ul}{\frac{2}{3}dk} \tag{287.}$$

which is a rule for the area of the cross-section of the tierod in an arched girder; in which a, is the area of the
cross-section of the rod, U is the weight in pounds equally
distributed over the beam, l is the length in feet between
the supports, d, in inches, is the depth or versed sine of the
arc, or the vertical distance at the middle of the beam from
the axis of the tie-rod to the centre of gravity of the crosssection of the cast-iron arch, and k is the weight in pounds
which may safely be trusted when suspended from the end
of a vertical rod of wrought-iron of one square inch section.
If this latter be put at 9000 pounds, then

$$a_{i} = \frac{Ul}{6000d}$$

Now a_1 is the area of the tie-rod. The area of any circle is equal to the square of its diameter multiplied by .7854, or

$$a_i = .7854D^{\circ}$$

and since, by formula (287.),

$$a_1 = \frac{Ul}{\frac{3}{3}dk}$$
 therefore $.7854D^2 = \frac{Ul}{\frac{3}{3}dk}$ and $D = \sqrt{\frac{Ul}{\cdot 5236dk}}$ (288.)

If k, the safe resistance to tension per inch, be taken at 9000 pounds, the rule becomes

$$D = \sqrt{\frac{Ul}{4712d}} \tag{289.}$$

which is a rule for the diameter of the tie-rod of an arched girder.

595.—Example.—What should be the diameter of the tie-rod of an arched girder, 20 feet long in the clear between supports, and 24 inches high from the axis of the tie-rod the centre of gravity of the cross-section at the middle of the arched beam; the load being 40,000 pounds equally distributed over the length of the beam?

Here we have U = 40000, l = 20 and d = 24; and therefore, by formula (289.),

$$D = \sqrt{\frac{40000 \times 20}{4712 \times 24}} = 2.66$$

or the diameter of the rod, with the safe resistance to tensio taken at 9000 pounds, should be 2 inches.

596.—Substitute for Arched Girder.—The cast-iron arch of an arched girder serves to resist compression. Its place can as well be filled by an arch of brick, footed on a pair of cast-iron skew-backs, and these held in position by a pair of tie-rods, as in Fig. 78.




Fig. 78.

To obtain a rule for the diameter of each rod, we have as above, in Art. 594,

$$a_i = .7854D^4$$

This is for one rod. When a_i is put for the joint area of two rods, we will have

$$a_{i} = .7854D_{i}^{s} \times 2$$

Comparing this with formula (287.), we have

$$.7854 \times 2 \times D_{i}^{2} = \frac{Ul}{\frac{2}{3}dk}$$
 or
$$D_{i}^{2} = \frac{Ul}{\frac{2}{3} \times 2 \times .7854dk}$$

and when k is taken at 9000 (Art. 594)

$$D_{i}^{s} = \frac{Ul}{9425d}$$

$$D_{i} = \sqrt{\frac{Ul}{9425d}} \qquad (290.)$$

This is a rule in which D_i represents the diameter of each of the two required rods.

For example, see Art. 595.

An arch of brick, well laid and secured in this manner, will serve quite as well as the cast-iron arch, and may be had at less cost. The best supports, however, to carry brick walls are those made of rolled-iron beams, putting two or more of them side by side and bolting them together. (See Art. 489, form. 228.)

QUESTIONS FOR PRACTICE.

- 597.—What should be the dimensions of cross-section of a cast-iron girder, 23 feet long between supports, and 27 inches high at the middle, at which point it is to carry 40,000 pounds; with 5 as the factor of safety? The width of bottom flange is 16 inches.
- 598.—In a girder of the same length, height and width: What should be the cross-section if the weight be 60,000 pounds and be uniformly distributed; the factor of safety being 5?
- 599.—In a girder of the same length, and of the same height and width at 8 feet from one end, where it is required to carry 50,000 pounds, with a factor of safety of 5: What should be the dimensions of cross-section?
- 600.—In a girder 25 feet long between bearings, carrying a load of 40,000 pounds at 10 feet from one end, with 5 as the factor of safety, and having 30 inches area of cross-section in the bottom flange: What should be the depth of the girder?
- 601.—A girder, 25 feet long and 30 inches high, is required to carry, with 5 as a factor of safety, two weights, one of 25,000 pounds at 8 feet from one end, and the other of 30,000 pounds at 6 feet from the other end: What should

be the dimensions of cross-section at each weight, the bottom flange being 16 inches wide?

602.—In an arched girder, 24 feet long between bearings, with a versed sine or height of 30 inches from the axis of the rod to the centre of gravity of the arched beam at the middle, and with the load on the girder taken at 80,000 pounds uniformly distributed: What ought the diameter of the tie-rod to be?

CHAPTER XXII.

FRAMED GIRDERS.

work, a treatise elucidating the Transverse Strain, wou seem to have reached completion with the end of the discussion on simple beams; but when it is recognized that the formation of a deep girder, by a combination of various pieces of material, is but a continuation of the effort to gain strength in a beam, by concentrating its material far above and below the neutral axis, as is done in the tubular girder and rolled-iron beam, it is clear that the subject of frame girders is properly included within a treatise upon the transverse strain. The subject of framed girders, however will here be discussed so far as to develop only the more important principles involved. For examples in greater variety, the reader is referred to other works (Merrill's Iron Truss Bridges, and Bow's Economics of Construction).

The use of simple beams is limited to comparatively short spans; for beams cut from even the largest trees can have but comparatively small depth. The power of a beam to resist cross-strain can be considerably increased by a very simple device. Let Fig. 79 represent the side view of a long beam of wood, from which let ACDB, the upper part of the beam, be cut. With the pieces thus removed, and the addition of another small piece of timber, there may be con-

structed the frame shown in Fig. 80, which is capable of sustaining a greatly increased load. This increase will be in




Fig. 80.

Proportion to the depth of the frame (Art. 583), and is obtained here by increasing the distance between the fibres which resist compression and those which resist tension. It is upon this principle that roof trusses and bridge girders, alike with common beams, all depend for their stability.

the horizontal strains produced by the weight W are balanced; or, the tension caused in the tie CD is equal to the compression caused in the short timber on which the weight rests. If the tie CD were removed, it is obvious that the weight W, acting through the two struts AW and BW, would push the two abutments AC and BD from each other, and, descending, fall through between them; unless the abutments were held in place by resistance other than that contained in the frame—such, for instance, as outside buttresses.

From this we learn the importance of a tie-beam; or, in its absence, of sufficient buttresses. From this we may also learn why it is that roof trusses framed without a horizontal tie at foot so invariably push out the walls, when constructed without exterior buttresses.

606.—Parallelogram of Forces—Triangle of Forces—

A discussion of the subject of framed girders can only be intelligently understood by those who are familiar with some of the more simple and fundamental principles of statics. One of these principles is known as the parallelogram of forces, or the triangle of forces, and is useful to the architect in measuring oblique strains due to vertical and horizontal pressures. Proof of the truth of this principle may be found in most mathematical works. (See Cape's Math., Vol. II., p. 118; chap. on Mechs., Art. 20.) In this chapter its application to construction will be shown.

In Fig. 81, let the lines AW and BW represent the axes of two timber struts, which, meeting at the point W, sus-




Fig. 81.

tain a weight, or vertical pressure, as indicated by the arrow at W. Then, let the vertical line WE, drawn by any.

convenient scale, represent the number of pounds, or tons, contained in the vertical weight at W. From E, draw ED parallel with AW, and EC parallel with BW. CWDE is the parallelogram of forces, and possesses this important property—namely, that the three lines WE, EC and CW, forming a triangle, are in proportion to three forces; the weight at W, the strain in WB, and the strain in WA.

The same is true of the other triangle WED; or, to designate more particularly, we have:—as the line WE is to the weight at W, so is the line CE, or WD, to the strain in WB; and also:—as the line WE is to the weight at W, so is the line DE, or WC, to the strain in AW. Indicating the lines by the letters a, b and c, as in the figure, we have

$$c: a:: W_{i}: A_{i}$$

$$A_{i} = W_{i} \frac{a}{c} \qquad (291.)$$

in which A, equals the strain caused by the weight W, through the line WA; and

$$c_{\bullet}: b :: W_{\prime}: B_{\prime}$$

$$B_{\prime} = W_{\prime} \frac{b}{c} \qquad (292)$$

in which B, equals the strain caused by the weight W, through the line WB.

607.—Lines and Forces in Proportion.—The above proportions hold good when the two lines AW and BW are inclined at any angle, and whether they are of equal or of unequal lengths; indeed, the principle is general in its applica-

٦

tion, for in all cases where the three sides of a triangle are respectively drawn parallel to the direction of three several forces which are in equilibrium, then the lengths of the three lines will be respectively in proportion to the three forces.

608.—Horizontal Strain Measured Graphically.—In Fig. 81, and in the triangle WCE, draw, from C, the horizontal line CF, or h; then we have the line b, in proportion




Fig. 81.

to the line h, as B_{i} , the strain in WB, is to H_{i} , the horizontal strain; or,

$$b:h::B_{\prime}:H_{\prime}=B_{\prime}\frac{h}{h}$$

and by substituting the value of B_i in formula (292.) have

$$H_{i}=B_{i}\frac{h}{b}=W_{i}\frac{bh}{cb}=W_{i}\frac{h}{c}$$

or the horizontal strain is measured by the quotient arising from a division by the line c, of the product of the weight

 W_{i} into the line h; or,

$$c:h::W_{i}:H_{i}$$

$$H_{i}=W_{i}\frac{h}{c} \qquad (293.)$$

This measures the horizontal strain at AB, or at W, for it is the same at all points of such a frame, whatever the angle of inclination of the struts, or whether they are inclined at equal or unequal angles.

609.—Measure of Any Number of Forces in Equilibrium.

—In Fig. 82, let AB be the axis of a horizontal timber, supported at A and B, and let AC, CD and DB be three iron rods, with two weights R and P suspended from the




Fig. 82.

points C and D. The iron rods being jointed at A, C, D and B, so as to permit the weights to move freely, and thus to adjust themselves to an equilibrium, the whole frame ABDC will be equilibrated.

From D erect a vertical, DH, and by any convenient scale make DG equal to the weight P, and GH equal to the weight R. From G, draw GE parallel with CD, and from H draw HE parallel with AC. The sides of the

triangle GED are parallel with the three lines CD, DB and DP, and consequently are in proportion as the strains in the three lines CD, DB and DP. Again; the sides of the triangle HEG are parallel with the lines AC, CD and CR, and consequently are in proportion as the strains in the lines AC, CD and CR. From E draw EF horizontal. Then the sides of the triangle FED, being parallel with the lines BA, BD and BK, are in proportion to the strains in these lines. Also, the sides of the triangle HEF, being parallel to the lines AB, AC and AL, are in proportion




Fig. 82.

to the strains in these lines. Thus, in the triangles within HDE, we have the measures of all the strains of the funicular or string polygon ABDCA; FE being the horizontal strain, FD the vertical strain or load on BK, and HF the vertical strain or load on AL.

510.—Strains in an Equilibrated Truss.—In Fig. 82 the strains in the lines AC, CD and DB are tensile, while that in AB is compressive. If the lines AC, CD and DB were above the line AB, instead of below it, then these strains would all be reversed; those which are tensile in the figure would then be compressive, while that which is com-

pressive would then be tensile; but the amount of strain in each would be the same and be measured as in Fig. 82.

For example: Let Fig. 83 represent an equilibrated frame; the pieces AC, CD, DE, EF and FB suffering compression




Fig. 83.

from the vertical pressures indicated by the arrows at C, D, E and F, while AB, a tie, prevents the frame from spreading. Draw the vertical line LQ, and from B draw radiating lines, parallel respectively with the several lines AC, CD, DE and EF, and cutting the line LQ at the points Q, P, O and M. Then the several lines BQ, BP, BO, BM and BL will be in proportion, respectively, to the strains in AC, CD, DE, EF and FB; and the lines LM, MO, OP and PQ will be in proportion, respectively, to the vertical pressures at F, E, D and C; while the line LN will represent the vertical pressure on B, and NQ that on A, and the line NB the horizontal thrust in AB.

611.—From Given Weights to Construct a Scale of Strains.—The construction of the scale of strains LBQ, as here given, is proper in a case where the points C, D, E

and F are fixed, and the weights and strains are required. When the weights at C, D, E and F, with their horizonts distances apart, and the two heights RC and UF, are given; then, to find the scale of strains, and incidentally the heights of the points D and E, proceed thus: From I




Fig. 83.

draw BQ parallel with AC, make the vertical QL equal, by any convenient scale, to the sum of the weights at C, D, E and F, and upon this vertical lay off in succession the distances LM, MO, OP and PQ, equal respectively to the weights at F, E, D and C. Then, the several lines BL, BM, BO, BP and BQ will, by the same scale, measure the several strains in BF, FE, ED, DC and CA, and BN will measure the horizontal strain.

612.—Example.—In constructing Fig. 83, the weights given are 11,899 pounds at F, 4253 pounds at E, 464 at D and 11,384 at C; being a total of 32,000 pounds. The distances AR, RS, etc., are successively 8, 13, 20, 24 and 13; in all 78 feet. The height RC = 15, and UF = 201.

With these dimensions all laid down as in Fig. 83, draw BQ parallel with AC. Draw the line LQ vertical, and at such a distance from B as that its length shall, by a scale of equal parts, be equal to the total load on the four points C, D, E and F; or to a multiple of the total load. For example: a scale of 100 parts to the inch will be convenient in this case, by appropriating 4 parts to the thousand Pounds. The 32,000 pounds require $32 \times 4 = 128$ parts for the length of the line LQ, and the several other weights and distances require as follows:

$$LM = 4 \times 11.899 = 47.596$$

 $MO = 4 \times 4.253 = 17.012$
 $OP = 4 \times 4.464 = 17.856$
 $PQ = 4 \times 11.384 = 45.536$

The sum of these,

$$LQ = 47.596 + 17.012 + 17.856 + 45.536 = 128$$

before. Therefore, draw LQ at such a distance from B that it will, by the scale named, equal 128 parts. On this line lay off the distances LM = 47.596, MO = 17.012, etc., as above given. Join B with each of the points P, O and M. These lines give the directions of the lines CD, DE and EF; therefore, draw FE parallel with BM, ED parallel with BO, and DC parallel with BP.

By applying the scale to the lines radiating from B, the strains in the several lines AC, CD, etc., will be shown.

BQ, by the scale, measures 80 parts, therefore $\frac{80}{4} = 20$; or the strain in AC is 20,000 pounds.

BP measures 45 parts, and $\frac{45}{4} = 11\frac{1}{4}$; or the strain in CD is 11,250 pounds.

BO measures 38, and $\frac{38}{4} = 9\frac{1}{2}$; or the strain in DE is 9500.

BM measures 39, and $\frac{39}{4} = 9\frac{8}{4}$; or the strain in EF is 9750.

BL measures 69.5, and $\frac{69.5}{4} = 17.375$; or the strain in *FB* is 17,375.

BN measures 37.5, and $\frac{37.5}{4} = 9.375$; or the horizoptal strain is 9375 pounds.

Also, as LN measures 58, therefore $\frac{58}{4} = 14,500$, equals the load on B; and as NQ measures 70, therefore $\frac{10}{4} = 17,500$, equals the load on A; and the two loads A, and B, together equal 17500 + 14500 = 32000, equals the total load.

In practice the diagram should be large, for the accuracy of the results will be in proportion to the size of the scale, as well as to the care with which it is drawn and measured. The size above taken is large enough for the purposes of illustration merely, but in practice the diagram should be drawn at a scale of 12 feet to the inch; or, still better, at 8 feet. (See Art. 615.)

the last article, directions were given for locating the line LQ, Fig. 83. This line may be located more precisely by arithmetical computation, and the horizontal thrust be thus defined more accurately than is there done. In Fig. 4, showing parts of Fig. 83 enlarged, we have the triangles ACR and BFU, the same as in Fig. 83.

The triangle ACR, as stated (Art. 612), has a base of 8 and a height of 15. Make AY equal 10, and draw YZ vertical. We now have this proportion,

8 : 15 :: 10 :
$$YZ = \frac{10 \times 15}{8} = 18.75$$


Again; triangle BFU, as stated (Art. 612), has a base of 13 and a height of $20\frac{1}{4}$. Make BX equal 10, and draw XV

vertical. We have now this proportion,

$$BU: UF:: BX: XV$$
 or

$$13:20\frac{1}{2}:: 10:XV = \frac{10 \times 20\frac{1}{2}}{13} = 15.577$$

Thus we have the two angles at A and B comparable, for, with a common base of 10, the one at A has a height of 18.75, while the one at B is 15.577. The two triangles may now be put together at the line BU. Extend the vertical line VX to W, make XW equal to YZ = 18.75, and join W and B. Then the triangle BXW equals the triangle AYZ, and BW is parallel with AZ.




The problem now is to locate the point N, so that the vertical LQ drawn through N shall be equal, by any given scale, to the total of the loads at C, D, E and F. To do this we have

$$BN: NL:: BX: XV = \frac{BX \times NL}{BN}$$

$$BN: NQ:: BX: XW = \frac{BX \times NQ}{BN}$$

By addition we have

$$XV + XW = \frac{BX \times NL}{BN} + \frac{BX \times NQ}{BN} = \frac{BX(NL + NQ)}{BN}$$



By the diagram, XV+XW=VW, and NL+NQ=L and therefore

$$VW = \frac{BX \times LQ}{BN}$$

$$VW: BX:: LQ: BN = \frac{BX \times LQ}{VW}$$

The total load is 32,000, for which we may, putting one for a thousand, make LQ equal to 32; and, since VW equal YZ + VX = 18.75 + 15.577 = 34.327, and BX = 10, where

$$BN = \frac{10 \times 32}{34 \cdot 327} = 9 \cdot 322$$

Efining accurately the horizontal thrust BN as 9.322, r 9322 pounds.

614.—Vertical Pressure upon the Two Points of mpport.—This pressure was shown in Art. 612 by the iagram, but may be more accurately determined by arithetical computation, as follows: In the last article the orizontal thrust BN was shown to be 9322 pounds. We are the proportion

$$BX: XV :: BN : NL$$
10: 15.577:: 9.322: $NL = \frac{15.577 \times 9.322}{10} = 14.521$

The vertical strain upon the support B is 14,521 pounds. O find that upon the support A we have

$$BX: XW :: BN : NQ$$

10: 18.75:: 9.322: $NQ = \frac{18.75 \times 9.322}{10} = 17.479$

or the vertical strain upon the support A is 17,479 pounds and the two, 17479 + 14521 = 32000, equals the total load.

strains in Fig. 83, as obtained by scale in Art. 612, are close approximations, and are near enough for general purposes. The exact results can be had arithmetically, as in Arts. 613 and 614. For example: In Art. 612 the horizontal thrust was found by scale to be 9375, while in Art. 613 it was more accurately defined by arithmetical process to be 9322. So, also, the portions of the total load borne by the two

supports, A and B, were found by scale to be 17,500 and 14,500, respectively, while in Art. 614 they were accurately fixed at 17,479 on A and 14,521 on B. A carefully drawn diagram at a large scale will generally be sufficient for use, but it is well, in important cases, to compute the dimensions also. When both are done, the scale measurements serve as a check against any gross errors in the computations.

In Art. 612 the strains in the several timbers are given, as ascertained by scale. By the rules for computing the sides of a right-angled triangle (the 47th of first book of Euclid), the several strains, as represented by BL, BM, BO, etc. (Fig. 83), may be found arithmetically. The following list shows the results by this method, side by side with those by scale:

By Scale.	By Computation.	
BL = 17,375	and	17,256
BM = 9.750	"	9,684
BO = 9,500	"	9,464
BP = 11,250	"	11,138
BQ = 20,000	46	19,810

When the positions of the supporting timbers AC, CD, DE, etc. (Fig. 83), are regulated in accordance with the weights upon the points C, D, E, etc., and, as shown in Art. 611, the frame is in a state of equilibrium; and a curve drawn through the points A, B, C, D, etc., is called the curve of equilibrium. When the several weights are numerous, are equal, and are located at equal distances apart; or, when the load is uniformly distributed over the length of the frame, this curve is a parabola. In these cases, if the rise

be small in comparison with the base, the curve is nearly the same as a segment of a circle, and the latter may be used without serious error. (Tredgold's Carpentry, Arts. 57 and 171.)

The pressures in an equilibrated frame act only in the axes of the timbers composing the frame, and these carry the effects of the several weights on, from point to point, until they successively arrive at A and B, the points of final support. A frame thus balanced is not, however, stable, for if subjected to additional pressure, however small, at any one of the points of support, it is liable to derangement; and if so deranged it has no inherent tendency to recover itself, but the distortion will increase until total failure ensues. A frame thus conditioned is therefore said to be in a state of unstable equilibrium; while a frame of suspended pieces, as in Fig. 82, is said to be in a state of unstable equilibrium, since, if disturbed by temporary pressures, it will recover its original position when they are removed.

and consequent failure, in a frame such as Fig. 83, can be counteracted by additional pieces termed braces, located in any manner so as to divide the inclosed spaces into triangles. For example: it may be divided into the triangles ACS, USD, DST, DTE, ETF, TFU and UFB. If these additional pieces be adequate to resist such pressures as they may be subjected to, and be firmly connected at the joints, the frame will thereby be rendered completely stable. Treated in this way the frame becomes a truss, from the fact that it has been trussed or braced.


618.—Forces in a Truss Graphically Measured.—When a frame is divided into triangles, as proposed in the last article, sometimes three or more pieces meet at the same

point. In such a case, owing to the complexity of the forces, it becomes difficult to trace, and, by the parallelogram of forces, to measure them all. Professor Rankine, in his "Applied Mechanics," somewhat extended the use of the triangle of forces in its application to such cases. It was afterward more fully developed and generalized by Professor J. Clerk Maxwell in a paper read before the British Association in 1867, and by him termed "Reciprocal Figures," Frames and Diagrams of Forces;" and Mr. R. H. Bow, C.E., F.R.S.E., in his "Economics of Construction," has simplified the method in its use, by a system of reciprocal lettering of lines and angles. By Professor Maxwell's method, the forces in any number of pieces converging at one point are readily determined. The principle involved is very simple, and is this: Construct a closed polygon, with lines parallel to the direction of, and equal in length to, the amount of the forces which in the framed truss meet at any point. A system of such polygons, one for each point of meeting of the forces, so constructed that in it no line representing any one force shall be repeated, is termed a diagram of forces.

vergence of parts of a framed truss, and Fig. 86 be its corresponding diagram of forces, in which latter the lines are drawn parallel to the lines in Fig. 85. Designate a line in the diagram in the usual manner, by two letters, one at each end of the line, and indicate the corresponding line in Fig. 85 by placing the same two letters one on each side of the line. For instance, the line AB of 86 is parallel with that line of 85 which lies between the spaces A and B; and so of each of the other corresponding lines. In Fig. 86 the lines are in proportion to each other, respectively, as the forces in the corresponding lines of Fig. 85. Thus if AD (86), by any scale,

represents the force in the line between A and D (85), then will the line AB equal the force in the line between A and B; and in like manner for the other lines and strains.

620.—Another Example.—Let Fig. 87 represent the axial lines of the timbers of a roof truss, and its two sustaining piers, and let Fig. 88 be its corresponding diagram of forces.



The truss being loaded uniformly, the three arrows (87) one at the ridge and one at the apex of each brace—represent equal loads. Let these three loads be laid down to a Suitable scale on the line $F\mathcal{F}$ (88), one extending from Fto G, another from G to H, and the third from H to The half of these, or FE, is the load sustained on one of the supports of Fig. 87, and the other half, $E\mathcal{F}$, is the load upon the other support. In Fig. 87 a letter is placed in each triangle, and one in each partly-enclosed space outside of Each line of the figure is to be designated by the two letters which it separates; thus, the line between A and E is called line AE, the line between A and B is called line AB, etc. In Fig. 88 the corresponding lines are designated by the same letters; the letters here being, as usual, at the ends of the lines. Also, it will be observed that while in the diagram any point is designated in the usual way by the letter standing at it, it is the practice in

the frame to designate a point by the several letters which cluster around it; for example, the point of support FAE (Fig. 87). The diagram, Fig. 88, is constructed by drawing a line parallel with each of the lines in Fig. 87. Thus the three




Fig. 87.




Fig. 88.

forces converging in Fig. 87 at FAE, the left-hand point of support, are EF, FA and AE; and in Fig. 88 the lines EF. FA and AE, drawn parallel with the corresponding lines of Fig. 87, form the triangle EFA. Taking the forces at

BAF, 87, we find them to be AF, FG, GB and d drawing, in 88, lines parallel with these, we obtain drangle AFGBA. Again, in 87 the forces at point are BG, GH, HC and CB, and drawing, in 88. wallel with these, we obtain the closed polygon At point HCDF (87) the forces are CH, HF, FD and, in 88, drawing the corresponding lines probe quadrangle CHJDC. In 87 the forces at point he right-hand support, are $D\mathcal{F}$, $\mathcal{F}E$ and ED, and corresponding lines produce the triangle DFE. point ABCDE, we have the five forces EA, AB, and DE, and, in 88, the corresponding lines give ed polygon EABCDE. This completes the diaforces, Fig. 88, in which the several lines, measured ame scale with which the three loads were laid off on e equal to the corresponding forces in the similar Fig. 87.

Diagram of Forces.—In this manner the diagram may be drawn to represent the strains in a framed carefully following the directions of Art. 618; comby by first laying down the forces which are known; ich the ones to be found will gradually be determined whole are ascertained.

-Diagram of Forces-Order of Development.

chined in amount, the diagram can not be completed.

here three forces converge it is requisite to know one

Of four forces, two must be known. Of five forces,

ast be known.

the line of loads, as $F\mathcal{F}$ in Fig. 88, then to ascertain on of the total load which bears upon each of the

points of support, AEF and $\mathcal{F}ED$ (Art. 56) (one half one each when the load is disposed symmetrically), and, with this, to obtain the first triangle FEA. From this proceed up the rafters, or to where the points of convergence have the fewest strains, leaving the more complex points to be treated later. In this way the most of the forces which affect the crowded points will be developed before reaching those points.

88, we see that the lines enclosing any one of the lettered spaces in the former are, in the latter, found to radiate from the same letter. The space A (87) has for its boundaries the lines AF, AB and AE, and these same lines in 88 radiate from the letter A. The space E (87) has for its enclosing lines EF, EA, ED and EF, and these same lines are found to radiate from the point E (88). Thus the diagram (88) is a reciprocal of the frame (87).

624.—Proportions in a Framed Girder.—In order to treat of the method of measuring strains in trusses, we have digressed from the main subject. Returning now, and referring to the relations existing between a girder and a simple beam, as in Arts. 603 to 605, we proceed to develop the proportion in a girder, between the length and depth.

A girder, as generally used, serves to support a tier of floor beams at a line intermediate between the walls of the building, and when sustained by posts at points not over 12 to 15 feet apart, may be made of timber in one single piece. But when a girder is required to span greater distances than these, it becomes requisite, by some contrivance, to increase its depth, in order to obtain the requisite strength. An increase of depth, however, may interfere with the demand for clear, unobstructed space in rooms so

large as those in which girders are required. To prevent this interference, the depth of the girder should be the least possible; although diminishing the depth will increase the cost; for the cost will be in proportion to the amount of material in the girder, and this will be in proportion to the strains in its several parts, and the strains will be inversely as the height. For economy's sake, therefore, as well as for strength, the girder should have a fair depth; modified, however, by the demand for unobstructed space.

Where other considerations do not interfere to prevent u, the depth of a framed girder should be from \(\frac{1}{19} \) to \(\frac{1}{8} \) of the length; the former proportion being for girders 25 feet long, and the latter for those 125 feet long. If these two rates be taken as the standard rates, respectively, of two girders thus differing in length 100 feet, and all other girders be required to have their depths proportioned to their lengths in harmony with these standards, their rates will be regularly graduated. In order to develop a rule for this, let the two standards be reduced to a common denominator, or to \(\frac{2}{24} \) and \(\frac{3}{24} \). If their difference, \(\frac{1}{24} \), be divided into 100 parts, each part will equal

and will equal the difference in rate for every foot increase in length of girder; for the two standards are 100 feet apart. The scale of rates thus established is for lengths of girder from 25 to 125 feet, but it is desirable to extend the scale back over the 25 feet to the origin of lengths. To do this, we have for the difference in rates for this 25 feet, $25 \times \frac{1}{2400} = \frac{15}{2400} = \frac{1}{10}$. Deducting this from $\frac{1}{12} = \frac{8}{26}$, the rate between depth and length at the origin of lengths (if such thing were there possible). Now if to this base of rates we

add the increase $(\frac{1}{2400})$ of the length) the sum will be the rate at any given length. As an example: What should be the rate, by this rule, for a girder 125 feet long? For this the difference in rate is $125 \times \frac{1}{2400} = \frac{125}{2400} = \frac{1}{36}$. Adding this to the base of rates, or to $\frac{7}{96}$, as above, and the sum $\frac{5}{96} + \frac{7}{96} = \frac{12}{96} = \frac{1}{8}$, the required rate. This is one of the standard rates. The other standard may be found by the rule thus, $25 \times \frac{1}{2400} = \frac{25}{2400} = \frac{1}{96}$. Adding this to the base $\frac{7}{96}$, gives $\frac{8}{96} = \frac{1}{12}$, the standard rate. We have therefore for the rate at any length

$$r = \frac{7}{96} + \frac{1}{2400} l = \frac{175}{2400} + \frac{l}{2400} = \frac{175 + l}{2400}$$
$$r = \frac{175 + l}{2400}$$

This gives the rate of depth to length, and since the depth is equal to the rate multiplied by the length, therefore

$$rl = \frac{(175 + l) l}{2400}$$
 or
$$d = \frac{(175 + l) l}{2400}$$
 (294.)

in which d is the depth between the axes of the top and bottom chords, and l is the length (between supports), both being in feet.

This rule will give the proper depth of a girder, and may be used when the depth is not fixed arbitrarily by the circumstances of the case. (See Art. 572.)

625.—Example.—What should be the depth of a girder which is 40 feet long between supports?

By formula (294.),

$$d = \frac{(175 + 40) \times 40}{2400} = 3.58\frac{1}{8}$$

or the economical depth is 3 feet and 7 inches, measured from the middle of the depths of the top and bottom chords.

Again: What should be the depth of a girder which is feet long in the clear between supports? By (294.),

$$d = \frac{(175 + 100) \times 100}{2400} = 11.458\frac{1}{8}$$

of the depth between the axes of the chords should be II feet 5½ inches.

A girder 125 feet long would by this rule be 15 feet 7½ inches, or ½ of its length, in depth; while a girder 25 feet long would be 2 feet and 1 inch deep between the axes, or ½ of the span.

626.—Trussing, in a Framed Girder.—One object to be obtained by the trussing pieces—the braces and rods—is to transmit the load from the girder to the abutments. The braces and rods forming the trussing may be arranged in a great variety of ways (see Bow's Economics of Construction), but that system is to be preferred which will take up the load of the girder at proper intervals, and transmit it to its two supports in the most direct and economical manner.

Just which of the great number of systems proposed will the more nearly perform these requirements it will perhaps be somewhat difficult to determine, but the one in which the struts and ties are arranged in a chain of isosceles triangles is quite simple, and offers advantages over many others. It is therefore one which may be adopted with good results.

the height (Art. 624), the next point is as to the number of funds or bays. These should be of such length as to afford points of support at suitable intervals along the girder, and the rods and struts should be placed at such an angle as will

braces and ties always at the same angle, would result in finishing points of support at intervals too short in the girds of short span, and too long in those of long span. So also the width of a bay be a constant quantity, there would too great a difference in the angles at which the rods as struts would be placed. To determine the number of bay so as to avoid as far as practicable these two objections—fir. we have the number of the bays directly as the length of the truss and inversely as the depth, and, second (to vary this preportion as above suggested), we may deduct from this resu a quantity inversely proportioned to the length of the girds Combining these, we have, n being the number of bays,

$$n = \frac{l}{d} - \frac{120 - l}{c}$$

and by substituting for d its value as in formula (294.),

$$n = \frac{l}{\frac{(175+l)l}{2400}} - \frac{120-l}{c}$$

$$n = \frac{2400}{175 + l} - \frac{120 - l}{c}$$

in which l is the length of the girder in feet, and c is constant, to be developed by an application to a given case. To this end we have, from the last formula,

$$\frac{120-l}{c} = \frac{2400}{175+l} - n$$

$$c = \frac{120-l}{\frac{2400}{175+l} - 2}$$

n = 4.5 and l = 20, we have

$$c = \frac{120 - 20}{\frac{2400}{175 + 20} - 4.5} = \frac{100}{12.308 - 4.5} = 12.807$$

or, say c = 12.8; and with this value

$$n = \frac{2400}{175 + l} - \frac{120 - l}{12 \cdot 8} \tag{295.}$$

which is a rule for determining the number of bays in a truss, when not determined arbitrarily by the circumstances of the case, and when the height of the girder is obtained as in formula (294.). In the resulting value of n, the fraction over a whole number is to be disregarded, unless greater than $\frac{1}{4}$, in which latter case unity should be added to the whole number.

628.—Example.—What should be the number of bays in a truss 80 feet long?

Here l = 80, and, by the formula, (295.),

$$n = \frac{2400}{175 + 80} - \frac{120 - 80}{12 \cdot 8} = \frac{2400}{255} - \frac{40}{12 \cdot 8} = 6 \cdot 287$$

or the required number of bays is six; disregarding the decimal $\cdot 287$ because it is less than $\frac{1}{2}$.

629.—Example.—How many bays are required in a girder 110 feet long?

Here l = 110, and, by formula (295.),

$$n = \frac{2400}{175 + 110} - \frac{120 - 110}{12 \cdot 8} = 7.64$$

or, adding unity for the decimal .64, the number required

630.—Number of Bays in a Framed Girder.—Accordi to the above rule, the number of bays or panels required framed girders of different lengths is as follows:

In cases where the length exceeds 120 feet, the quantity of the formula to be deducted $\left(\frac{120-l}{12\cdot8}\right)$ becomes a negative quantity, and, since deducting a negative quantity is equivalent to adding a positive one, the result may be added, thus:

$$-\frac{120-144}{12\cdot8} = -\frac{-24}{12\cdot8} = -(-1\cdot875) = +1\cdot875$$

the axial lines of a framed girder.—Let Fig. 89 represent the axial lines of a framed girder, or the imaginary lines passing through the axes of the several pieces composing the frame. Let the load, equally distributed, be divided into six parts, one of which acts at the apex of each lower triangle. We may notice here that in a truss with an even number of lower triangles, as in Fig. 89, there is an even number of loads, one half of which are carried by the struts and rods to one point of support, and the other half to the other support. Thus the load PQ, at point PEFGQ, is sustained by the top chord, and by the strut EF. The portion passing down this strut is carried by the rod DE up to the top chord, and thence, together with the load OP, at point OCDEP, down by the strut CD to the bottom chord. This accumulated load is carried by the rod BC up to the top chord,

ABCO, finally reaches, through the strut AB, the point of support for that end of the truss. The three weights on the other side are in like manner conveyed to MNT, the other point of support. We here see the manner in which, in a framed girder upon which the load is uniformly distributed, one half is carried by the trussing pieces to each point of support.

632.—Diagram for the above Framed Girder.—Fig. 90 is a diagram constructed as per Arts. 619 and 620, and represents the strains or forces in the framed girder of Fig. 89.




Fig. 89.




Fig. 90.

To construct this diagram, we proceed as follows: Upon the vertical line AN lay off the several distances AO, O PQ, QR, RS and SN; each equal by any convenient

scale to one of the six equal loads resting upon the top of 8. The load at the apex of the triangle B, or point ABCO (89), is placed from A to O in 90. The load OP, at point OCDEP (89), is placed from O to P in 90; and so on with the other loads. The other lines of Fig. 90 are obtained by drawing them parallel with the corresponding lines of Fig. 89, as per directions in Art. 618. Commencing at the point ABT (89), we draw (in 90) three lines parallel with the direction of the forces at that point. The first of these is the vertical pressure upon the point of support ABT, which in this case equals one half the total load, or AQ, or AT of




Fig. 90. Next, from T, draw the horizontal line TB, and from A, the inclined line AB, parallel with the brace AB of 89. These two lines meet at B, and we have the triangle ABT, representing the three forces converging at the point of support ABT. For the four forces at the point

ABCO in 89, we proceed as follows: We already have the forces AO and AB. From B in 90, draw BC parallel with the rod BC of 89; and from O in 90, draw OC parallel with OC of 89. These two lines intersect at C, completing the polygon ABCOA, the sides of which are in proportion as the forces in the several lines converging at the point ABCO of Fig. 89. Proceeding to the point BCDT (Fig. 89), we find, of the four forces converging there, that two are already drawn, TB and BC. From C draw CD parallel with the brace CD of Fig. 89; and from T draw TD. These two lines will meet at D and complete the polycon TBCDT, the sides of which measure the forces in the lines converging at the point BCDT of 89. The next in order is the point OCDEP. Of the five forces concentrating here, we already have, in Fig. 90, three, PO, OC and CD. To find the other two, draw from D the line DE parallel with the line DE of 89, and from P draw PEparallel with line PE of 89. These two lines will meet at E and complete the polygon POCDEP, which measures the forces in the lines concentrating at point OCDEP. Proceeding now to the point DEFT of Fig. 89, we find four forces, two of which, TD and DE, are already determined. For the other two, draw from E the line EF parallel with EF in 89, and from T, TF parallel with the hne TF of 89. These two lines meet in F and complete the polygon TDEFT, which measures the forces in the lines converging at the point DEFT of Fig. 89. The next in order is the point PEFGQ in 89, where five lines converge. The forces in three of these we have already—namely, UP, PE and EF. Draw from F a line parallel with the line FG of 89, and from Q a line parallel with QG of 39. These two intersect at G and complete the polygon QPEFGQ, which gives the forces in the lines around the point PEFGQ of Fig. 89.

In this last proceeding we meet with a peculiarity. The line FG has no length in Fig. 90. It commences and ends at the same point, since G is identical with F. This seems to be an error, but it is not. It is correct, for an examination of Fig. 89 will show that the two inclined lines meeting at the foot of the triangle G do not assist in carrying the weights upon the top chord, and may therefore, in so far as those weights are concerned, be dispensed with, so that the space occupied by the three triangles F, G and H may be left free, and be designated by one letter only instead of three. In place of five, there are in fact only four forces meeting at the point PEFGQ, and these four are represented in Fig. 90 by the polygon QPEFQ.

The above analysis is in theory strictly correct, and yet in practice it is not so, for in such cases as this there is always more or less weight on the lower chord at the middle point. If nothing more, there is the weight of the timber chord itself, and this should be considered.

In Art. 634 a truss with weights at the points of each chord will be found discussed, and the facts as found in practice there developed.

The construction of one half of the diagram (Fig. 90) has now been completed. The other half is but a repetition of it in reversed order, and need not here be shown in detail. In drawing the lines for the latter half, it will be seen that the point H is identical with the point F, and that K and M coincide respectively with D and B.

633.—Gradation of Strains in Chords and Diagonals.—In considering the forces shown in Fig. 90, we find that those in the chords increase towards the middle of the girder, while the forces in the diagonals decrease towards the middle. Thus, in Fig. 90, of the lines representing the upper chord,

PE is longer than OC, and QG is longer than PE, indicating a corresponding increase in the lines OC, PE and QG of 89. So in the lower chord, we have a successive increase of forces, as seen in a comparison of the lengths of the lines TB, TD and TF of Fig. 90, representing the chord at the several bays B, D and F of Fig. 89. The diagonal lines AB, CD and EF in 90 show decreasing forces in the diagonals AB, CD and EF in 89—decreasing towards the middle of the girder. These facts are useful to remember when constructing a diagram of forces, as a knowledge of this law of increase in the chords and decrease in the diagonals will assist in more readily laying out the lines of the diagram correctly.

634.—Framed Girder with Loads on Each Chord.—Let Fig. 91 represent such a girder, and let Fig. 92 be the corresponding diagram of forces. In constructing this diagram, we lay off upon a vertical line, by any convenient scale, the several distances KL, LM, MN, NO and OP, respectively equal to the several loads upon the upper chord of Fig. 91. Make PV equal, by the same scale, to the sum of the several weights suspended from the lower chord. Divide KI' at U into two parts, in proportion to the two parts into which the total load is divided and borne by the two points of support, AUK and FQP, of 91 (Art. 56). In this case, the load being symmetrically disposed, the two parts are equal, or KU UV. From U and K draw lines parallel to the corresponding lines UA and KA (91). These will meet at A and complete the triangle of forces for the point ACK of Fig. 91. From A in 92 draw the line AB, and from L the line LB. These meet at B and complete the polygon KLBAK for the forces at the point KABL of 91. Starting from U, set off upon the vertical

line KV the several distances UT, TS, SR and RQ respectively equal to the several loads UT, TS, SR and RQ as found in 91. For the forces at the point ABCTU draw the line BC from B, and the line TC from T, each parallel with its corresponding line in 91. These lines meet at C and complete the polygon ABCTUA, which gives the forces converging in the point UABCT.




Fig. 91.




Fig. 92,

For the point LBCDM, draw from C the line CD, and from M the line MD, each parallel with its corresponding line in 91. These lines, meeting in D, complete the polygon MLBCDM, which gives the forces surrounding the point LBCDM. For the point TCDES, draw from D the line DE, and from S the line SE, respectively.

parallel with the corresponding lines of Fig. 91. They will meet at E and complete the polygon TCDEST, which measures the forces around the point TCDES. For the point MDEFN, draw from E the line EF, and from N the line NF, parallel with EF and NF of 91; and they, meeting at F, will complete the polygon MDEFNM, thus giving the forces converging at the point MDEFN.

The correspondence of lines in the two figures has now been traced to a point beyond the middle of the framed girder. The remainder of Fig. 92 may be traced for the other half of 91, by a continuance of the process used in tracing the first half. Since, in this instance, the loading and plan of the girder are symmetrical, and hence the several forces in the lines of one half of the girder respectively equal to those in the other half, the lines of the diagram as laid down for the one may be used for the other half.

The gradation of Strains in Chords and Diagonals.—
The gradation of the forces in Fig. 92 may (as was remarked in Art. 633) be observed in the diagonals representing the lines KA, AB, BC, CD and DE, which diagonals decrease from the end towards the middle of the girder; and also in the lines representing the chords AU, BL, CT, DM and ES, which gradually increase from the end towards the middle.

tepresent a framed girder, in which the loads are symmetrically placed, and where L is put for the load on each point of bearing of the upper chord, and N for that suspended at each hearing point of the lower chord. Let a represent the vertical height of the girder, c the length of a diagonal, and b the base of the triangle formed with c and a.

637.—Strains in the Diagonals.—To analyze these, we commence at the middle of the girder. There being an odd number of loads upon the upper chord, one half of the




Fig. 93.

central one, L, is carried at Q, one of the points of support, and the other half at F, the other point. The effect of this upon the brace MC may be had from the relation of the sides of the triangle abc, for

$$a:c::\frac{1}{2}L:\frac{c}{2a}L$$

$$2a:c::L:\frac{c}{2a}L=D$$

equals the strain in the diagonal; or, when W equals the vertical load, equals $\frac{1}{2}L$,

$$D = W\frac{c}{a} \tag{296.}$$

The vertical effect of this at M is $\frac{1}{2}L$, the same as it is at C. This amount, added to the suspended load N at M, equals $\frac{1}{2}L+N$, equals the total vertical force acting at M. This is sustained by the lines MK and BM, the latter standing at the same angle with MK as did MC. Hence the effect upon the diagonal is

$$a:c::\frac{1}{2}L+N:(\frac{1}{2}L+N)\frac{c}{a}$$

equals the strain on the diagonal BM; and the vertical effect at M is equal to $\frac{1}{2}L+N$. Adding this to the load on the top chord at B, the sum, $\frac{3}{2}L+N$, is the total load at B, and it is supported by the forces in the lines PB and BC, constituting, with the weight, three forces, acting in the directions of the three sides of the triangle abc. The effect in the diagonal BP is therefore, as before, the load into the ratio $\frac{c}{a}$, or $(\frac{3}{2}L+N)\frac{c}{a}$. The vertical effect of this at P is equal to the vertical effect at B, or $\frac{3}{2}L+N$. Adding to it the load N at P, their sum, $\frac{3}{4}L + 2N$, is the total vertical effect at P; and, as before, the effect of this on the diagonal AP which carries it is $(\frac{3}{2}L + 2N)\frac{c}{a}$, with a vertical effect at A of $\frac{3}{2}L+2N$, the same as at P. Adding the load L, at A, the sum, $\frac{1}{2}L+2N$, equals the total vertical pressure at A. This is sustained by the forces in the lines QA and AB, which, with the weight, act in the direction of the sides of the triangle abc, and therefore the effect in the diagonal, as before, is $(\frac{5}{2}L + 2N)\frac{c}{a}$, while the vertical effect of this at Q is equal to the same effect as at A, or L+2N.

Thus, the loads on half the girder have, one by one, been picked up and brought along, step by step, until they are finally received upon Q, their point of support at one end of the girder.

It will be observed that this accumulated load, $\frac{1}{2}L+2N$, coincides with the sum of the loads as seen upon one half of the figure, that is, to the $2\frac{1}{2}$ loads on the top chord and the two loads suspended from the bottom chord.

638.—Example.—Let it be required to show the strains in the diagonals of a framed girder 50 feet long, of five bays and 41 feet high.

Here b, the base of the measuring triangle, is equal $\frac{10}{10} = 5$, and a, its height, equals the height of the gird equals 4.5; and c, the hypothenuse of the right-angle triangle, is therefore

$$c = \sqrt{a^3 + b^3} = \sqrt{20 \cdot 25 + 25} = 6 \cdot 7268$$

The load L upon each point of the upper chord is 10,00 pounds, while N, the suspended load at each point of the bottom chord, is 2500 pounds.




Fig. 93.

The strain upon the diagonals is, by formula (296.),

$$D = W \frac{c}{a}$$

The load on CM is $\frac{1}{2}L$, and therefore the strain in the diagonal CM is

$$D_{i} = L \frac{c}{2a} = 10000 \times \frac{6.7268}{9} = 7474 \text{ pounds.}$$

The strain in the diagonal MB is

$$D_s = (\frac{1}{2}L + M)\frac{c}{a} = (5000 + 2500)\frac{6.7268}{4.5} = 11211\frac{1}{8}$$
 pounds.

The strain in the diagonal BP is

$$D_s = (\frac{3}{2}L + N)\frac{c}{a} = (15000 + 2500)\frac{6.7268}{4.5} = 26159\frac{7}{2}$$
 pounds.

The strain in the diagonal PA is

$$D_4 = (\frac{1}{2}L + 2N)\frac{c}{a} = (15000 + 5000)\frac{6.7268}{4.5} = 29896\frac{6}{2}$$
 pounds;

and the strain in the diagonal AQ is

$$D_s = (\frac{5}{2}L + 2N)\frac{c}{a} = (25000 + 5000)\frac{6 \cdot 7268}{4 \cdot 5} = 44845\frac{1}{8}$$
 pounds.

639.—Strains in the Lower Chord.—From the measuring triangle abc of Fig. 93 we have

$$a:b::W:H$$

$$H = W \frac{b}{a}$$
 (297.)

in which H is the strain in the horizontal lines due to W the weight; and with this formula we may ascertain the horizontal forces in the chords of the girder.

First. In the lower chord. At the point Q we have, for W in the formula, one half the total load, or $(\frac{1}{2}L + 2N)$, and therefore

$$H_{i} = (\frac{5}{2}L + 2N)\frac{b}{a}$$

equals the horizontal strain in QP.

For the next bay, PM, we have, for W, the same amounties that caused by the thrust in the strut BP, plus the due to the tension in the rod AP. These three amounties

are respectively $\frac{1}{2}L + 2N$, $\frac{3}{2}L + N$ and $\frac{3}{2}L + 2N$, and their sum is

$$(\frac{5}{2}L + 2N) + (\frac{3}{2}L + N) + (\frac{3}{2}L + 2N) = W = \frac{11}{2}L + 5N$$

equals the total weight causing horizontal strain in PM.

From this, the horizontal strain in PM is

$$H_s = \left(\frac{11}{2}L + 5N\right)\frac{b}{a}$$

For the third, or middle bay, MK, we have the weight the same as for PM, together with that coming from the




Fig. 93.

thrust of the strut CM, and from the tension of the rod BM. These three weights are $\frac{1}{2}L + 5N$, $\frac{1}{2}L$ and $\frac{1}{2}L + N$, or together,

$$(\frac{1}{2}L + 5N) + \frac{1}{2}L + (\frac{1}{2}L + N) = W = \frac{1}{2}L + 6N$$

and for the horizontal strain in MK we have

$$H_s = (\frac{13}{3}L + 6N)\frac{b}{a}$$

This completes the strains in the lower chord, for those of the other end are the same as these.

640.—Strains in the Upper Chord.—For the first bay. AB, there are two compressions, namely: that due to the reaction from the strut AQ, and that from the tension in

the rod AP. The weight causing thrust in the strut is equal to half the total load, or $\frac{1}{2}L + 2N$, and the weight causing tension in the rod is $\frac{1}{2}L + 2N$; or, together, we have for the weight 4L + 4N; and for the compression in AB,

$$H' = (4L + 4N)\frac{b}{a}$$

For the second bay, BC, we have this same thrust, plus that due to the reaction of the strut PB, plus that due to the tension in the rod BM. The three weights are 4L+4N, $\frac{1}{2}L+N$ and $\frac{1}{2}L+N$, and their sum is

$$(4L+4N)+(\frac{3}{2}L+N)+(\frac{1}{2}L+N)=6L+6N$$

and the horizontal compression in BC is

$$H'' = (6L + 6N)\frac{b}{a}$$

641.—Example.—What are the horizontal strains in a girder of five bays, it being 50 feet long and 4½ feet high, and having 10,000 pounds resting upon each bearing point of the upper chord, and 2500 pounds at each point of suspension in the lower chord?

Here, in the measuring triangle abc, $b = \frac{50}{10} = 5$ and a = 4.5; from which $\frac{b}{a} = \frac{5}{4.5} = 1\frac{1}{0}$. Hence, for each horizontal strain, we have

$$H = W \frac{b}{a} = I \frac{1}{9} W = \frac{10}{9} W$$

Now, in the lower chord, we have, as in Art. 639, for the bay QP, the weight

$$W = \frac{5}{2}L + 2N$$
 and, therefore,

$$H_1 = \frac{19}{9}[(2\frac{1}{9} \times 10000) + (2 \times 2500)] = 33333\frac{1}{9}$$
 pounds;

equals the horizontal tension in QP.

For the next bay, PM, we have for the weight, as per Art. 639,

$$W = \frac{1}{2}L + 5N$$
 and, therefore,

$$H_s = \frac{10}{9}[(5\frac{1}{9} \times 10000) + (5 \times 2500)] = 75000 \text{ pounds};$$

equals the horizontal tension in PM.

For the third, or middle bay, MK, for the weight, as per Art. 639, we have

$$W = \frac{13}{2}L + 6N$$
 and, therefore,

$$H_s = \frac{10}{9}[(6\frac{1}{9} \times 10000) + (6 \times 2500)] = 88888\frac{9}{9}$$
 pounds;

equals the horizontal tension in MK.

This completes the work for the lower chord, as the tensions in the other half are the same as those here found for this.

In the upper chord the weight causing compression in the first bay, AB, is, as per the last article,

$$W = 4L + 4N$$
 and, therefore,

$$H' = \frac{1}{9}[(4 \times 10000) + (4 \times 2500)] = 55555$$
 pounds;

equals the horizontal compression in AB.

For the next bay, BC, for the weight causing compression we have, as per last article,

$$W = 6L + 6N$$
 and, therefore,

$$H'' = \frac{10}{9}[(6 \times 10000) + (6 \times 2500)] = 83333\frac{1}{8}$$
 pounds;

equals the horizontal compression in BC.

This completes the strains for the upper chord. Tabulated, these several horizontal strains stand thus:

For the lower chord:

For the upper chord:

In
$$AB$$
 and DE the strains are 55,555\{\frac{1}{2}}\$ pounds.
" BC " CD " " " 83,333\{\frac{1}{2}}\]"

To test the correspondence of these results with those shown by the graphic method in Figs. 91 and 92, the student may make diagrams with the given figures at a scale as large as convenient, giving to L and N the proportions above assigned them, namely, L=4N, and making the bays with a base of 10 and a height equal to 4.5. The results obtained should approximate those above given, in proportion to the accuracy with which the diagrams are made.

642.—Resistance to Tension.—Only in so far as tension is incidental to the transverse strain would it be proper to speak of the former in a work on the latter. In a framed girder, the lower chord and those diagonals which tend downwards towards the middle of the girder are subject to tension. The better material to resist this strain is wroughtiron, and this, in the diagonals at least, is usually employed. The weight with which this material may be safely trusted per square inch of sectional area varies according to the quality of the metal, from 7000 to 15,000 pounds. C parily, it may be taken at 9000 pounds, but when the m

and the work upon it are of superior quality, it is taken at as much as 12,000, or even higher in some special cases. This is the safe power of the metal per square inch of the sectional area. Let k equal this power, W equal the load to be carried, and A the sectional area of the bar, then

$$Ak = W$$

$$A = \frac{W}{k} \tag{298.}$$

As an application of this formula, take the case of the diagonal AP, Fig. 93; the strain in which is 29,8964 pounds. Putting k = 9000, we have

$$A = \frac{29896\frac{8}{9000}}{9000} = 3.3218$$

or the rod should contain $3\frac{1}{8}$ inches in its sectional area. Referring to a table of areas of circles, we find that the rod, if round, should be a trifle over 2 inches in diameter, or, if a flat bar 4 inches wide, it would need to be $\frac{1}{8}$ of an inch thick, since $4 \times \frac{1}{8} = 3 \cdot 333$.

The above is for the diagonals. The chords are usually of wood. When so made, the value per square inch sectional area may be taken at one tenth of the ultimate tensional power of the materials as given in Table XX. Since a chord is usually compounded of three or more pieces in width, and of lengths less than the length of the chord, it is necessary to see that the area of material determined by the use of formula (298.) is that of the uncut material, or of the uncut sectional area at all points in the length. Thus, were the pieces so assembled as to have no two heading joints occur at the same point in the length, or so near each other that the requisite bolts for binding the pieces together could not be introduced between the two joints, then the uncut sectional

area would be equal to that of all the pieces in the width except one. Should two joints occur at or near one point in the length, then the sectional area of all but two pieces in width must be taken; and so on for other cases.

Where care is exercised in locating the joints, the allowance for joints, bolt holes, and other damaging contingencies may be taken as amounting to as much as the net size; or, ordinarily, the net size should be doubled. Then for the total sectional area we have

$$k = \frac{T}{10 \times 2} = \frac{T}{20}$$
 or
$$A = \frac{W}{T}$$
$$A = \frac{20W}{T}$$
 (299.)

in which T is the ultimate resistance to tension, as found in Table XX.

As an illustration, take the case of the lower chord of Fig. 93, which, at the middle bay, has a horizontal strain of 88,889 Pounds. From Table XX. we have the resistance to tension of Georgia pine equal to 16,000 pounds. By formula (299.)

$$A = \frac{20W}{T} = \frac{20 \times 88889}{16000} = 111$$
 inches

or the area should be not less than 111 inches. The chord may be $10 \times 12 = 120$ inches, and may be compounded of three pieces in width—a centre one of 4×12 and two outside pieces of 3×12 each.

643.—Resistance to Compression.—The top chord of framed girder, and the struts or diagonals directed dow

ward towards the points of support, are in a state of compression.

The rules for determining the resistance to compression in posts or struts are numerous, and their discussion has occupied many minds. The theory of the subject will not be rehearsed here. For this the reader is referred to authors who have made it a special point, such as Tredgold, Hodg-kinson, Rankine, Baker, Francis and others.

For short columns, the resistance is, approximately, in proportion to the area of cross-section of the post. As the post increases in length, the resistance per square inch of cross-section gradually diminishes.

In framed girders, the struts, and also the chords, when properly braced against lateral motion, are in lengths comparatively short, and hence the resistance which the material in them offers is not much less than when in short blocks. Baker* gives as the strain upon posts

$$t = t_i \left(1 + \frac{L^2 ma}{8I} \right)$$

Reducing this expression and changing the symbols to agree with those of this work, we have

$$f = \frac{C}{1 + \frac{l^2 ebd}{8 \times \frac{1}{12}bd^3}}$$
$$f = \frac{C}{1 + \frac{3ex^3}{12}}$$

in which f equals the ultimate resistance of the post per inch of sectional area, C equals the ultimate resistance to compression of the material when in a short block, e the extension of the material per foot due to flexure, within

^{*} Strength of Beams, Columns' and Arches, by B. Baker, London, 1870, p. 182.

the limits of elasticity, as found in Table XX., and d is the dimension in the direction of the bending. This in a post will be the smaller of the two, or the thickness. Let h represent this thickness and be substituted in the above for d; then $r = \frac{l}{h}$ is the ratio of the length to the thickness or smallest dimension of the cross-section; l and h both being taken of the same denomination, either inches or feet.

The safe limit of load for posts is variously estimated at from 6 to 10. Putting a to represent this, and taking C for the ultimate resistance, as in Table XX., we have for the safe resistance

$$f = \frac{C}{a(1 + \frac{3}{2}er^2)}$$
 (300.)

and when W equals the load to be carried, and A equals the sectional area, we have

$$Af = W$$
 or $A = \frac{W}{f}$

and, by substituting for f, its value, as in (300.),

$$A = \frac{W}{\overline{C}}$$

$$\overline{a} \overline{(1 + \frac{3}{2}er^2)}$$

$$A = \frac{a(1 + \frac{3}{2}er^2)W}{\overline{C}}$$
(301.)

As an application, let it be required to find the area of the Georgia pine strut AQ in Fig. 93, the strain in which is (Art. 638), say 45,000, and the length of which is 6.73.

The ratio r can not be assigned definitely in the formula, as h is unknown. From experience, however, a value may be assigned it approximating its true value, and after computation, if the result shows that the assigned value deviates materially from the true value, then a nearer a

proximation may be made for a second computation. The ratio in the case now considered is probably about equal to 12. We will take it at this amount for a trial. Take, from Table XX., the values of C = 9500 and e = 0.00109, for Georgia pine. Make a, the factor of safety, equal to 10. The value of W is 45,000. Then, by formula (301.),

$$A = \frac{10 \left[1 + \left(\frac{3}{2} \times 0.00109 \times 12^{2}\right)\right] \times 45000}{9500} = 58.521$$

or the area should be 58½ inches.

Having taken the ratio at 12 we should have the thickness in inches equal to the length in feet, or 6.73. Dividing the area 58.521 by this gives a quotient of 8.696 as the breadth. The dimensions of the piece are $6\frac{9}{4} \times 8\frac{3}{4}$. If it be desirable to have the thickness greater than here given, then a second trial may be had with a less ratio.

644.—Top Chord and Diagonals—Dimensions.—By transformation of formula (301.) a rule may be arrived which shall define the breadth of a diagonal or post exactly.

Let A = hb, and let h, the thickness, bear a certain relation to b, the breadth; or nh = b, n being a constant assumed at will (for example, if $n = 1 \cdot 2$, then $1 \cdot 2h = b$). Then $A = nh^2$. Putting also for r its value $\frac{12l}{h}$ (l being taken in feet) we have

$$h^{2}n = \frac{Wa + \frac{3}{2}Wae \frac{12^{3}l^{2}}{h^{2}}}{C}$$

$$Ch^{2}n = Wa + \frac{3}{2}Wae \frac{12^{3}l^{2}}{h^{2}}$$

$$Ch^{2}n = Wah^{2} + (\frac{3}{2} \times 12^{3}Wael^{3})$$

$$Ch^{2}n = Wah^{2} + (\frac{3}{2} \times 12^{3}Wael^{3})$$

$$Ch^{2}n - Wah^{2} = \frac{3}{2} \times 12^{3}Wael^{3}$$

$$h^{2} - \frac{Wa}{Cn}h^{2} = \frac{432}{2}W\frac{ael^{3}}{Cn}$$

Completing the square and reducing gives

$$h = \sqrt{\sqrt{\frac{43^2}{2}W\frac{ael^2}{Cn} + \left(W\frac{a}{2Cn}\right)^2 + W\frac{a}{2Cn}}}$$

Let $W_{\overline{2Cn}}^{a}$ be called G; then we have

$$G = W \frac{a}{2Cn} \tag{302.}$$

and by substitution the above formula becomes

$$h = \sqrt{\sqrt{432 \ Gel^2 + G^2} + G}$$
 (303.)

which is a rule to ascertain the thickness or smallest diameter of a strut or post, and in which l is in feet and the other dimensions are in inches.

This rule, owing to its complication, will, be found to be dious in practice. For this reason, formula (301.) ordinarily, for its greater simplicity, is to be preferred; although, from the necessity of assuming the value of r, a second computation may be required.

645.—**Example.**—What is the value of h, the thickness of the strut at AQ, Fig. 93; the length being 6.73, and the force pressing in the line of its axis being 45,000 Pounds.

Putting 10 for a, the factor of safety, putting $1 \cdot 2$ for n, the factor defining the relation of the breadth to the thickness, and taking from Table XX. the values of the constants C and e for Georgia pine, we have W = 4500 e = 10, e = 0.00109, l = 6.73, C = 9500 and n = 1.2.

By formula (302.) we have

$$G = W \frac{a}{2Cn} = \frac{45000 \times 10}{2 \times 9500 \times 1 \cdot 2} = 19.737$$

Then, by formula (303.),

$$h = \sqrt[4]{\frac{\sqrt{(432 \times 19.737 \times 0.00109 \times \overline{6.73}^2) + \overline{19.737}^2 + 19.737}}{= 6.943}} + 19.737$$

or the thickness of the strut is required to be, say 7 inches. As nh = b, therefore

$$b = 1 \cdot 2 \times 6 \cdot 943 = 8 \cdot 332$$

equals the breadth of the strut; and since hb = A, therefore

$$A = 6.943 \times 8.332 = 57.849$$

equals the area of the strut; a fraction less than was before found by formula (301.). That value would have been the same as this had the value of r been correctly assumed. Its exact value is 11.632 instead of 12, the amount there taken.

ing to the natural shrinkage of timber in seasoning, the most carefully framed girder will settle or sag more or less, provided adequate measures are not taken to prevent it. The ends of the struts press upon the inside of the chords, while the iron rods have their bearing at the outside. The consequent diminution in height of the girder will be equal to the shrinkage of both the top and bottom chords, and the rods which at first were of the proper length will be found correspondingly long.

By screwing up the nuts upon the rods as the shrinker progresses, the sagging may be prevented; but this would be inconvenient in most cases. It is better, in constructing the girder, to provide bearings of metal extending through

the depth of each chord, and so shaped that the strut and rod shall each have its bearing upon it. The shrinkage will then have no effect upon the integrity of the frame.

647.—Framed Girder with Unequal Leads, Irregularly **Placed.**—Let Fig. 94 represent such a case, wherein A, Band C are the loads upon the top chord, and D and E the loads on the bottom chord, all located as shown. As




Fig. 94.

in other cases, the first requirement is to know the reactions at the two supports R and P. In a girder symmetrically. loaded this involves but little trouble, as the half of the total load equals the reaction at each support. In our present case, we can not thus divide the load, since the reactions are not equal. To obtain the required division of the total load, we must consider each of the several weights separately, dividing it between the two supports according to its distances from them. Thus, putting m and n for the distances of the load A from the two supports, the portion of A bearing upon R is shown by formula (3.) (placing A

$$R = A_{\overline{I}}^n$$

which A, the weight, is multiplied by n, its distant

from the opposite support, and divided by *I*, the length span. In like manner, each of the other weights may divided, and the portion bearing upon each support found

Putting the letters o, p, q, r, s, t, u and v to rep sent the distances shown in the figure, we have, as the to effect upon one of the supports,

$$R = \frac{An}{l} + \frac{Bp}{l} + \frac{Cr}{l} + \frac{Dv}{l} + \frac{Et}{l}$$

$$R = \frac{An + Bp + Cr + Dv + Et}{l} \qquad (304)$$

and for the total effect upon the other support,

$$P = \frac{Am + Bo + Cq + Du + Es}{l}$$
 (305.)

Adding these two formulas, we have as the total effect upon both supports,

$$R + P = \frac{A(m+n) + B(o+p) + C(q+r) + D(u+v) + E(s+t)}{t}$$

Here the sum of the two quantities within each parenthesis is equal to 1 the length, and consequently

$$R+P = \frac{Al+Bl+Cl+Dl+El}{l}$$


$$R+P = A+B+C+D+E$$

or the sum of the reactions of the two supports is equal to the sum of all the weights. In this we have proof of the accuracy of the two formulas (304.) and (305.).

648.—Load upon Each Support—Graphical Representation.—The value of R in formula (304.) may be readily

either arithmetically or graphically. The formula for eight, $R_i = A\frac{n}{l}$ (3.), gives $R_i = An$, or two equal gles. Having three of these quantities, l, A and n, or the quantity, R_i , may be graphically found thus:

Fig. 96 let AB, by any convenient scale, equal n. AC at any angle with AB, and equal in length to




y off AD equal to A. Join B with C, and from aw DE parallel with CB. AE will equal R, the ed quantity, for, from similar triangles, we have

$$AC:AB::AD:AE$$

$$I:n::A:R_{r}=A_{T}^{n}$$


tain the value of R for all of the weights, proceed as . 97, in which the parallel lines FL, GM, HN, $\mathcal{F}O$



KP are each equal to I, the span RP of Fig. 94.

From F lay off upon FL, the first of these lines, the distance FV equal by scale to the weight A of Fig.; and from F on line FW place FQ equal to π . Connect Q with L. From V draw VG parallel with LQ. FG will represent R_I .

From G draw GM parallel with FL. Make G equal to the weight B (94), and GR equal to p. Cornect R with M, and from V draw VH parallel with MR. GH will represent R_{r} .



From H draw HN parallel with FL. Make F equal to the weight C (Fig. 94), and HS equal to Connect S with N, and parallel with NS draw V $H\mathcal{F}$ will represent R_{s} .

In like manner, with the weight D and distance v Fig. 94, obtain $\mathcal{F}K$ equal to R_i ; and with the weight and distance t obtain KU equal to R_i .


We now have the line FU equal to the sum of

$$R_t + R_t + R_s + R_t + R_s = R$$

equals that portion of the total load on the girder whice presses upon the support R.

nilarly, the amount of pressure upon the support P se obtained. The two, R and P, should together the sum of the weights A, B, C, D and E.

9.—Girder Irregularly Loaded-Force Diagram. ig accomplished the division of the total weight, we



F1G. 94.




Fig. 95.

low construct upon the same scale with that of Fig. 97, rce diagram, Fig. 95, for the girder represented in Fig. i described in Art. 647. On a vertical, RP, make RM equal to FU (97); and RS equal to the weight A ST equal to the weight B, and TP equal to the weight C, all as in Fig. 94. Now, since RM equals FU (97). equals the reaction of the support R, therefore, from R draw RE parallel with RE (94), and from M draw ME parallel with ME (94). From M make ML equal to the weight E (94), and LK equal to the weight D (94). Draw the other lines all parallel with the corresponding lines of Fig. 94, as per Arts. 618 and 619, and the force diagram will be complete.

-The reaction of the two supports may be found arithmetically, as before stated, by the use of formulas (304.) and (305.). Thus, let the several weights A, B, C, D and E of Fig. 94 be rated, by the scale of the diagram, at 15. 23, 17, 22 and 19 parts respectively. These parts may represent hundreds or thousands of pounds, or any other denomination at will. Let I, the span, equal 64, and the several distances n, p, r, v and t measure respectively 54, 34, 8, 26 and 44 by the same scale.

Formula (304.) now gives

$$R = \frac{(15 \times 54) + (23 \times 34) + (17 \times 8) + (22 \times 26) + (19 \times 44)}{64} = 49$$

Formula (305.) gives

$$P = \frac{(15 \times 10) + (23 \times 30) + (17 \times 56) + (22 \times 38) + (19 \times 20)}{64} = 47$$

$$R + P = 49 + 47 = 96$$

The sum of the weights is

$$W = 15 + 23 + 17 + 22 + 19 = 96$$

the same amount, thus proving the above computation cor-

QUESTIONS FOR PRACTICE.

- 651.—Given a frame similar to Fig. 87, with a span of 40 feet, a height of 23 feet, with the length of the vertical BC equal to 15 feet, and with AF and BG equal. Draw a diagram of forces, and show what the strains are in each line of the frame; the three loads FG, GH and HF being each equal to 5000 pounds.
- 652.—According to the rule given in Art. 624, show what should be the height of a framed girder which is 75 feet between bearings.
- 653.—According to Art. 627, show how many bays the girder of the last article should have.
- 654.—Show, by the diagram of forces, what are the strains in the several lines of a girder 55 feet long between centres of bearings and 5.27 feet high between axes of chords; the girder to be divided into five equal bays, each being an isosceles triangle as in Fig. 93. The load upon the apex of each triangle is 5000 pounds, and that suspended from the lower chord at each point of intersection with the diagonals is 1250 pounds. Letter the girder as in Fig. 91.
- 655.—To test the accuracy of the results obtained in th last article compute the strains arithmetically.

656.—What should be the areas of cross-section of th___e bottom chord of the girder of Art. 654, at the several bays____>

What should be the sizes of the upper chord and of th diagonal struts? The timber is to be of spruce; a, the factor of safety, to be taken at 10, and n at 1.2.

What should be the areas of cross-section of the diagonarious, taking the safe strength of the metal at 9000 pounds ?

In the questions of this Art. take the strains given by the ediagram of forces.

CHAPTER XXIII.

ROOF TRUSSES.

ART. 657.—Roof Trusses considered as Framed Girders.

—It is proposed, in this chapter, to discuss the subject of roof trusses in so far only as they may be considered to be framed girders, placed in position to carry the roofing material. A full treatise on roofs would include matter extending beyond the limits of a work on the transverse strain. Those desirous of pursuing the subject farther are referred to Tredgold, Bow and others* who have written more fully on roofs.


658.—Comparison of Roof Trusses.—Designs for roof trusses, illustrating various principles of roof construction, are herewith presented.

The designs at Figs. 98 to 102 are distinguished from those at Figs. 103 to 106, by having a horizontal tie-beam. In the latter group, and in all designs similarly destitute of the horizontal tie at the foot of the rafters, the strains are much greater than in those having the tie, unless the truss be protected by exterior resistance, such as may be afforded by competent buttresses.

To the uninitiated it may appear preferable, in Fig. 103, to extend the inclined ties to the rafters, as shown by the dotted lines. But this would not be beneficial: on the con-

^{*} Tredgold's Carpentry. Bow's Economics of Construction


trary, it would be injurious. The point of the rafter where the tie would be attached is near the middle of its length, and consequently is a point the least capable of resisting transverse strains. The weight of the roofing itself tends to bend the rafter; and the inclined tie, were it attached to the rafter, would, by its tension, have a tendency to increase this bending. As a necessary consequence, the feet of the rafters would separate, and the ridge descend.



In Fig. 104 the inclined ties are extended to the rafters; but here the horizontal strut or straining beam, located at the points of contact between the ties and rafters, counteracts the bending tendency of the rafters and renders these points stable. In this design, therefore, and only in such designs, is it permissible to extend the ties through to the rafters. Even here it is not advisable to do so, because of the increased strain produced. (See Figs. 118 and 120.) The design in Fig. 103, 105 or 106 is to be preferred to that in Fig. 104.

comparison of the force diagrams hereinafter given, of each of the foregoing designs, we may see that the strains in the trusses without horizontal tie-beams at the feet of the rafters are greatly in excess of those having the tie. In constructing these diagrams, the first step is to ascertain the reaction of, or load carried by, each of the supports at the ends of the truss. In symmetrically loaded trusses, the weight upon each support is always just one half of the whole load.


660.—Force Diagram for Truss in Fig. 98.—To obtain the force diagram appropriate to the design in Fig. 98, first letter the figure as directed in Art. 619, and as in Fig. 107. Then



draw a vertical line, EF (Fig. 108), equal to the weight W at the apex of the roof; or (which is the same thing in effect) equal to the sum of the two loads of the roof, one extending on each side of W half-way to the foot of the rafter. Divide EF into two equal parts at G. Make GC and GD each equal to one half of the weight N. Now, since EG is equal to one half of the upper load, and GD to one half of the lower load, therefore their sum, EG + GD = ED, is equal to one half of the total load, or to the reaction of each support, E or F. From D draw DA parallel with DA of Fig. 107, and from E draw EA parallel with EA of Fig. 107. The three lines of the triangle AED rep-

resent the strains, respectively, in the three lines converging at the point ADE of Fig. 107. Draw the other lines of the diagram parallel with the lines of Fig. 107, and as directed in Arts. 619 and 620. The various lines of Fig. 108 will represent the forces in the corresponding lines of Fig. 107; bearing in mind (Art. 619) that while a line in the force diagram is designated in the usual manner by the letters at the two ends of it, a line of the frame diagram is designated by the two letters between which it passes. Thus, the horizontal lines AD, the vertical lines AB, and the inclined lines AE have these letters at their ends in Fig. 108, while they pass between these letters in Fig. 107.

661.—Force Diagram for Truss in Fig. 99.—For this truss we have, in Fig. 109, a like design, repeated and lettered as



required. We here have one load on the tie-beam and three loads above the truss; one on each rafter and one at the ridge. In the force diagram, Fig. 110, make GH, $H\mathcal{F}$ and $\mathcal{F}K$, by any convenient scale, equal, respectively, to the weights GH, $H\mathcal{F}$ and $\mathcal{F}K$ of Fig. 109. Divide GK into two equal parts at L. Make LE and LF each equal to one half the weight EF (Fig. 109). Then GF is equal to one half the total load, or to the load upon the support G (Art. 660). Complete the diagram by drawing its several lines parallel with the lines of Fig. 109, as indicated by the letters (see Art. 660), commencing with GF, the load on

support G (Fig. 109). Draw from F and G the two is FA and GA, parallel with these lines in Fig. 109. Fir point of intersection defines the point A. From this several points B, C and D are developed, and the ire completed. Then the lines in Fig. 110 will represent forces in the corresponding lines of Fig. 109, as indicated the lettering. (See Art. 619.)

662.—Force Diagram for Truss in Fig. 100.—For this use we have, in Fig. 111, a similar design, properly prepared





Fig. 112.

y weights and lettering; and in Fig. 112 the force diagram propriate to it.

In the construction of this diagram, proceed as directed in the previous example, by first constructing NS, the vertical line of weights; in which line NO, OP, PQ, QR and RS are made respectively equal to the several weights above the truss in Fig. 111. Then divide NS into two



equal parts at T. Make TK and TL each equal to the half of the weight KL. Make $\mathcal{F}K$ and LM equal to the weights $\mathcal{F}K$ and LM of Fig. 111. Now, since MN is equal to one half of the weights above the truss, plus one half of the weights below the truss, or half of the whole weight, it is therefore the weight upon the support N (Fig.

and represents the reaction of that support. A horizonline drawn from M will meet the inclined line drawn N, parallel with the rafter AN (Fig. 111), in the M and the three sides of the triangle MN (Fig.

will give the strains in the three corresponding lines

ting at the point MN (Fig. 111). The sides of the tri-MN (Fig. 112) give likewise the strains in the three

esponding lines meeting at the point MS (Fig. 111).


tinuing the construction, draw all the other lines of the

diagram parallel with the corresponding lines of Fig.

and as directed in Art. 619. The completed diagram

measure the strains in all the lines of Fig. 111.

63.—Force Diagram for Truss in Fig. 101.—For the roof s at Fig. 101 we have, in Fig. 113, a repetition of it, and in 114 its force diagram.



The dimensions on the vertical line *HL* (Fig. 114) are made respectively equal to the weights in Fig. 113, as indicated by the lettering. With *GH* equal to half the whole weight on the truss (Art. 660), the triangle AGH is constructed, giving the strains in the three lines concentrating at the point AGH (Fig. 113). Then, drawing the other lines parallel with the corresponding lines of Fig. 113, the completed diagram gives the strains in the several lines of that figure, as indicated by the lettering. (See Art. 619.)

664.—Force Diagram for Truss in Fig. 102.—The roof truss indicated at Fig. 102 is repeated in Fig. 115, with the addition of the lettering required for the construction of the force diagram, Fig. 116.

In this case, there are seven weights, or loads, above the truss, and three below. Divide the vertical line OV at W, into two equal parts, and place the lower loads in two equal parts on each side of W. Owing to the middle one of these loads not being on the tie-beam with the other two, but on the upper tie-beam, the line GH, its representative in the force diagram, has to be removed to the vertical BJ, and the letter M is duplicated. The line NO equals half the whole weight of the truss, or 3½ of the upper loads, plus one of the lower loads, plus half of the load at the upper tiebeam. It is therefore the true reaction of the support NO, and AN is the horizontal strain in the beam there. be observed also, that while HM and GM (Fig. 116), which are equal lines, show the strain in the lower tie-beam at the middle of the truss, the lines CH and FG, also equal but considerably shorter lines, show the strains in the upper tie-beam. Ordinarily in a truss of this design, the strain in the upper beam would be equal to that in the lower one, which becomes true when the rafters and braces above

the upper beam are omitted. In the present case, the thrusts of the upper rafters produce tension in the upper beam




Fig. 116.

equal to CM or FM of Fig. 116, and thus, by counteracting the compression in the beam, reduce it to CH or FC, of the force diagram, as shown.

665.—Force Diagram for Truss in Fig. 103.—The force diagram for the roof truss at Fig. 103 is given in Fig. 114, while Fig. 117 is the truss reproduced, with the lettering requisite for the construction of Fig. 118.




Fig. 117.





Fig. 118.

The vertical EF (Fig. 118) represents the load at the ridge. Divide this equally at W, and place half the lower weight each side of W, so that CD equals the lower weight. Then ED is equal to half the whole load, and equal to the reaction of the support E (Fig. 117). The lines in the triangle ADE give the strains in the corresponding lines converging at the point ADE of Fig. 117. The other lines, according to the lettering, give the strains in the corresponding lines of the truss. (See Art. 619.)

666.—Force Diagram for Truss in Fig. 104.—This truss is reproduced in Fig. 119, with the letters proper for use in the force diagram, Fig. 120.

Here the vertical GK, containing the three upper loads GH, $H\mathcal{F}$ and $\mathcal{F}K$, is divided equally at W, and the lower load EF is placed half on each side of W, and extends from E to F. Then FG represents one half of the whole load of the truss, and therefore the reaction of the support G (Fig. 119). Drawing the several lines of Fig. 120 parallel with the corresponding lines of Fig. 119, the force

diagram is complete, and the strains in the several lines of 119 are measured by the corresponding lines of 120. (See Art. 619.)



A comparison of the force diagram of the truss in Fig. 117 with that of the truss in Fig. 119 shows much greater strains in the latter, and we thus see that Fig. 117, or 103, is the more economical form.

667.—Force Diagram for Truss in Fig. 105.—This truss is reproduced and prepared by proper lettering in Fig. 121, and its force diagram is given in Fig. 122.

Here the vertical $\mathcal{J}M$ contains the three upper loads $\mathcal{J}K$, KL and LM. Divide $\mathcal{J}M$ into two equal parts at

is, and make FG and GH respectively equal to the two hads FG and GH of Fig. 121. Then $H\mathcal{F}$ represents on half of the whole weight of the truss, and therefore the reation of the support \mathcal{F} . From H and \mathcal{F} draw lines parallel with AH and $A\mathcal{F}$ of Fig. 121, and the sides of the \Box





Fig. 121.



angle AHF will give the strains in the three lines concertrating in the point AHF (Fig. 121). The other lines of Fig. 122, are all drawn parallel with their corresponding lines Fig. 121, as indicated by the lettering. (See Art. 619.)




Fig. 123.




Fig. 124.

668.—Force Diagram for Truss in Fig. 106.—This truss is reproduced in Fig. 123 with the lettering proper for its force diagram, as given in Fig. 124. The five external weights of Fig. 123 make up the line LQ, and the two internal weights are set, one on each side of \mathcal{F} , the middle point of LQ, extending to H and K. KL equals one half the weight of the whole truss, and equals the reaction of the point of support L (Fig. 123). The sides of the triangle AKL, therefore, give the respective strains in the three lines converging at the point AKL of Fig. 123. The other lines of Fig. 124 are found in the usual manner. (See Art. 619.)

669.—Strains in Horizontal and Inclined Ties Compared. —A comparison between a truss with a horizontal tie at the




Fig. 125.

feet of the rafters, and one without such tie will now be given. The truss without a horizontal tie shown in Fig. 103 is one of the simplest in construction, and is suitable for the comparison. Repeating it in Fig. 125, and adding the dotted lines, we have likewise the form of a truss with a horizontal tie. From Art. 608 we have, in formula (293.), for the horizontal strain,

$$H_{i} = W_{i}^{h}$$

in which W_i equals the total weight of the truss and its load (Fig. 125), h equals half the span, equals AD, and ϵ

equals twice the height, equals 2DE. By putting $P = \frac{W}{2}$ equals the reaction of one of the supports A or B, and putting d for DE, we have

$$H = 2P\frac{h}{2d} = P\frac{h}{d}$$

or, from Fig. 125,

$$d: h: P: H = P\frac{h}{d}$$

that is to say, when the vertical DE represents half the weight of the truss, then AD may be put to represent the horizontal strain. Draw CF horizontal, and by similar triangles we have

$$DE : AD :: CE : CF$$
 or $CE : CF :: P : H = P\frac{CF}{CE}$

or, with *CE* put to represent one half the weight of the whole truss, then *CF*, by the same scale, will measure the horizontal strain.

Under these conditions, CF measures the *horizontal* strain in either truss, whether with or without a tie-beam. If the truss have a horizontal tie AB, then CF measures the tension in this tie. If it be without the tie AB, having instead thereof the raised tie ACB, then still CF measures the *horizontal* strain at A or B, but *not* the strain in the raised tie AC.

The strain in this inclined tie is measured by the line AC, for the three sides of the triangle ACE are in proportion as the strains in these lines respectively (see Art. 619). therefore the strains in the *ties* of the two trusses are compable by the two lines CF and AC.

The compressive strain in the rafter is also correspondingly increased; for just in proportion as AE exceeds EF, so does the compressive strain in the rafter of a trus with an inclined tie exceed that of one with a horizontal tie.

670.—Vertical Strain in Truss with Inclined Tie.—In Fig. 125, if the inclined tie were lowered, so that the point C,




Fig. 125.

descending, should reach the point D; or, if the inclined tie become the horizontal tie AB; then the vertical rod DE would be subject to no strain from the weight of the rafters and the load upon them. In the absence of the horizontal tie, or when the inclined tie is depended upon to resist the spreading of the rafters, the vertical rod CE is strained directly in proportion to CD, the elevation of the tie, and inversely as the height CE. This relation may be shown as follows:

Let P be put for DE (Fig. 125) and represent one half the weight of the truss. Then AD will represent the horizontal strain at A; or, representing the span AB by the symbol s, then $\frac{s}{2}$ equals AD equals the horizontal strain. Putting a for CD and d for DE we have the proportion

or
$$d : \frac{s}{2} :: P : H = P \frac{s}{2d}$$

and also,
$$AD : CD :: H : V$$

$$\frac{s}{2} : a :: H : V = H \frac{2a}{s} = P \frac{a}{d}$$

by substitution, or

$$d : a :: P : V = P \frac{a}{d}$$

This gives the vertical strain in CE, due to the raising of the tie from D to C, but it is not the whole of the strain; it is only so much of the vertical strain as is due to the weight of the roof. The tension thus found in CE is sustained at E by the two rafters, and, passing through them to A and B, creates horizontal and vertical thrusts precisely as did the original weight. The vertical tension thus brought to CE again acts as a weight at E, and, passing down the rafters and through the tie back to C, again adds a load at C. This in turn passes around and returns to C, adding to the load; and so on in an endless round to infinity. But the successive strains thus generated are in a decreasing series, and they may therefore be summed up and defined. Thus, as has just been shown, the vertical effect from the weight of the roof is

$$V = P \frac{a}{d}$$

The vertical effect of this latter is

$$d:a::V:V'=V\frac{a}{d}=P\left(\frac{a}{d}\right)^{2}$$

The vertical effect of this is

$$d:a::V':V''=V'\frac{a}{d}=P\left(\frac{a}{d}\right)^{s}$$

The next term in the series will be

$$V''' = P\left(\frac{a}{d}\right)^4$$

and the sum of all the terms will be

$$V = P\left[\frac{a}{d} + \left(\frac{a}{d}\right)^2 + \left(\frac{a}{d}\right)^2 + \text{etc.}\right]$$

showing that the several values of the fraction by which the weight P is multiplied constitute a geometrical series, with $\frac{a}{d}$ for the first term and $\frac{a}{d}$ for the ratio. Since $\frac{a}{d}$ is less than unity, we have a geometrically decreasing infinite series, the sum of which is equal to the first term divided by one minus the ratio,* or

$$S = \frac{\frac{a}{d}}{1 - \frac{a}{d}} = \frac{a}{d - a}$$

and, since d-a=b of Fig. 125,

$$S = \frac{a}{h}$$

We have, therefore, as the total vertical effect due to the elevation of the middle of the tie from D to C,

$$V = P \frac{a}{b}$$

^{*} Ray's Algebra, Part Second, Art. 299.

or the vertical effect is directly in proportion to CD, the elevation of the tie, and inversely in proportion to CE, the length of the vertical tie-rod.

671.—Illustrations.—To illustrate the effect of the elevation of the tie-rod, upon the vertical strain in the suspension-rod, let the point C, Fig. 125, be elevated $\frac{1}{2}$ of the verti-




Fig. 125.

cal height of the truss above the horizontal line AB. Here

t = 1 and b = 4, and $\frac{a}{b} = \frac{1}{4}$; or

$$V = P \frac{a}{b} = \frac{1}{2}P$$

When the elevation equals 1 of the entire height, then

$$V = \frac{1}{8}P$$

When the elevation equals \frac{1}{8} of the entire height, then

$$V = \frac{1}{2}P$$

When the elevation equals 1 of the whole height, then

$$V = \frac{1}{1}P = P$$

Thus it is seen, in this last case, that the effect due to

elevation of the tie-beam is equal to that of doubling the whole weight of the roof, and this increase affects not only the vertical suspension rod at the middle, but also the rafters and inclined ties, as was shown at Art. 669.

When, therefore, in order to gain a small additional height to the interior of a building, it is proposed to raise the middle point of the tie-rod, it would seem advisable to consider whether this small additional height be an adequate compensation for the increased strains thereby induced, and the consequent enhanced cost for material necessary to resist these strains; and also, whether it be not more advisable to raise the walls of the building, rather than the ties of the trusses.

672.—Planning a Roof.—In designing a roof for a building, the first point requiring attention is the location of the trusses. These should be so placed as to secure solid bearings upon the walls; care being taken not to place either of the trusses over an opening, such as those for windows or doors, in the wall below. Ordinarily, trusses are placed so as to be centrally over the piers between the windows; the number of windows consequently ruling in determining the number of trusses and their distances from centres. This distance should be from ten to twenty feet; fifteen feet apart being a suitable medium distance. The farther apart the trusses are placed, the more they will have to carry; not only in having a larger surface to support, but also in that the roof timbers will be heavier; for the size and weight of the roof beams will increase with the span over which they have to reach.

In the roof-covering, itself, the roof-planking may be laid upon jack-rafters, carried by purlins supported by the trusses; or upon roof beams laid directly upon the back of the principal rafters in the trusses. In either case, proper struts should be provided, and set at proper intervals to resist the bending of the rafter. In case purlins are used, one of these struts should be placed at the location of each purlin.

Ξ

The number of these points of support rules largely in determining the design for the truss, thus:

For a short span, where the rafter will not require support at an intermediate point, Fig. 98 or 103 will be proper.

For a span in which the rafter requires supporting at one intermediate point, take Fig. 99, 104 or 105.

For a span with two intermediate points of support for the rafter, take Fig. 100 or 106.

For a span with three intermediate points, take Fig. 102.

Generally, it is found convenient to locate these points of support at nine to twelve feet apart. They should be sufficiently close to make it certain that the rafter will not be subject to the possibility of bending.

diagram for any truss, it is requisite to determine the points of the truss which are to serve as points of support (see Figs. 109, 111, etc.), and to ascertain the amount of strain, or loading, which will occur at every such point.

The points of support along the rafters will be required to sustain the roofing timbers, the planking, the slating, the snow, and the force of the wind. The points along the tiebeam will have to sustain the weight of the ceiling and the flooring of a loft within the roof, if there be one, together with the loading upon this floor. The weight of the truss itself must be added to the weight of roof and ceiling.

674.—Load on Roof per Foot Horizontal.—In any important work, each of the items in Art. 673 should be carefully estimated, in making up the load to be carried. For ordinary roofs, the weights may be taken per foot superficial, as follows:

Slate,	about	7.0	pounds.
Roof plank,	46	2.7	66
Roof beams, or jack-rafter	s, "	2.3	66
In all,		12	pounds.

This is for the superficial foot of the inclined roof. For the foot horizontal, the augmentation of load due to the angle of the roof will be in proportion to its steepness. In ordinary cases, the twelve pounds of the inclined surface will not be far from fifteen pounds upon the horizontal foot.

For the roof load we may take as follows:

Roofing,	about	15	pounds.
Roof truss,	"	5	"
Snow,	"	20	66
Wind,	• 6	10	46
Total on	roof	<u> </u>	pounds

per square foot horizontal.

This estimate is for a roof of moderate inclination, say one in which the height does not exceed $\frac{1}{4}$ of the span. Upon a steeper roof, the snow would not gather so heavily, but the wind, on the contrary, would exert a greater force. Again, the wind acting on one side of a roof may drift the snow from that side, and perhaps add it to that already lodged upon the opposite side. These two, the wind and the snow, are compensating forces. The action of the snow is vertical: that of the wind is horizontal, or nearly so. The power of the wind in this latitude is not more than thirty

pounds upon a superficial foot of a vertical surface; except, perhaps, on elevated places, as mountain tops for example, where it should be taken as high as fifty pounds per foot of vertical surface.

- beam must of course be estimated according to the requirements of each case. If the timber is to be exposed to view, the load to be carried will be that only of the tie-beam and the timber struts resting upon it. If there is to be a ceiling attached to the tie-beam, the weight to be added will be in accordance with the material composing the ceiling. If of wood, it need not weigh more than two or three pounds per foot. If of lath and plaster, it will weigh about nine pounds; and if of iron, from ten to fifteen pounds, according to the thickness of the metal. Again, if there is to be a loft in the roof, the requisite flooring may be taken at five pounds, and the load upon the floor at from twenty-five to seventy pounds, according to the purpose for which it is to be used.
- 676.—Selection of Besign for Roof Truss.—As an example in designing a roof truss: Let it be required to provide trusses for a building measuring 60×90 feet to the centre of thickness of the walls, with seven windows upon each side, and with a roof having its height equal to one third of the span. The roofing is to be of plank and slate, the ceiling is to be finished with plastering, and the space within the roof is to be used for the storage of light articles, not to exceed twenty-five pounds to the square foot.

Here, in the first place, we have to determine the number of trusses. As there are seven windows on a side, there should be six trusses, one upon each pier between the windows. The six trusses and the two end walls will afford

eight lines of support for the roofing. There will thus be seven bays of roofing of $\frac{9}{7} = 124$ feet each, and this is the width of roofing to be carried by each truss.

In the next place, the points of support in the truss are to be ascertained. If these are provided at every ten feet horizontally, they will divide the half truss into three spaces, and there will be two intermediate points of support. For this arrangement, such a roof truss as is shown in Fig. 100 will be appropriate, but if the space in the roof is required to be quite unobstructed with timber at the middle, then a modification of this design may be used, as in the form shown in Fig. 126; each rafter being still divided into three equal parts.

677.—Load on Each Supported Point in Truss.—The horizontal measurement, then, of the roofing to be carried by each supported point in the truss, will be 10 feet along the line of the truss and 12\frac{1}{2} feet across the truss (this latter being the width of each bay as above found); or $10 \times 12\frac{1}{7} = 128\frac{1}{2}$ feet. With a weight per foot of 50 pounds, as estimated in Art. 674, we have, for the load upon each supported point of the truss,

$$1284 \times 50 = 64284$$

or, say 6500 pounds.

The tie-beam having two points of support, we have $\frac{60}{8} = 20$ feet for the length of the surface to be carried. This, multiplied by the width between trusses, gives $20 \times 12\frac{9}{7} = 257\frac{1}{7}$ feet area of surface to be carried by each point of support. We will estimate the weight per foot in this present case as follows:

Load upon the floor, 25 pounds. Flooring, with timber, 5 "
Plastering, 9 "
Tie-beam, etc., 1 pound.

Total at tie-beam, 40 pounds.

This gives

$$257\frac{1}{7} \times 40 = 10285\frac{5}{7}$$

or, say 10,300 pounds upon each supported point.


Therefore, the two balls GH and $H\mathcal{F}$, suspended from the tie-beam of Fig. 126, are to be taken as weighing 10,300 pounds each, while the five balls located above the rafters are to be understood as weighing 6500 pounds each (Art. 677).

679.—Constructing the Force Diagram.—We may now proceed to construct the force diagram, Fig. 127, as follows:

Upon the vertical line KP lay off in equal parts KL, LM, MN, NO and OP, according to any convenient scale, each equal to 6500 pounds—the weight of the balls above the rafters (Art. 677). If a scale of 100 parts to the inch be selected for the force diagram, and each part be understood as representing 100 pounds, then $\frac{6500}{100} = 65$, equals the number of parts to assign to each of the distances KL, LM, etc., and each will be $\frac{65}{100}$ of an inch in length. Dividing KP at H into two equal parts, lay off on each side of H the distances GH and $H\mathcal{F}$, each equal, by the scale, to 10,300 pounds. This distance is found by dividing 10,300 by 100; the quotient 103 is the number of parts, and the distances will each be $\frac{103}{100}$, or one inch and $\frac{3}{100}$ of an inch in length.*

^{*} The scale here selected, although sufficient for the purposes of illustration,

HK now represents one half the weight upon the rafters, and $H\mathcal{F}$ one half the load upon the tie-beam, and their sum, $\mathcal{F}K$, equals one half the total load of the truss, equals the load upon the point of support K.



From \mathcal{F} , H and G draw the horizontal lines $\mathcal{F}A$, HD and GF. From K, L, M, N, O and P draw

would be too small for a working drawing. For the latter, a scale should be selected as large as can be conveniently used, such as 10 parts to the inch, and 100 pounds to each part. This would give 1000 pounds to the inch, and each of the distances KL, LM, etc., would measure 61 inches.

It must also be remembered that the accuracy of the force diagram depends upon the care with which the distances upon the vertical line are laid off and the lines drawn. The drawing implements should be examined to know that they are true, and each line should be drawn carefully parallel with the corresponding line of the truss. Unless this care is exercised, the results may differ considerably from the truth.

lines, as shown, carefully parallel with the rafters. From F and A draw the lines FE and AB, parallel with the two braces. Connect B and E by the vertical line BE, and then the force diagram is complete.

680.—Measuring the Force Diagram.—After drawing the lines of the diagram as above directed, they should all be carefully traced to know that the required conditions are fulfilled, or that each set of lines, drawn parallel, in the diagram of forces, to the lines converging to a point in the truss, forms a closed polygon. (See Arts. 618, 619 and 620.)

The diagram, by this test, having been found correct, the force in each line of the truss may be measured by applying the scale to the corresponding line of the diagram.


For example, take the strains in one of the rafters. At its lower end, or the part AK, its corresponding line AK of Fig. 127 measures 478 parts, by the same scale with which the weights on the vertical line KP were laid off. This, at 100 pounds to the part, gives 47,800 pounds as the strain in the foot of the rafter. The next section of the rafter is designated by the letters BL, and the line BL (Fig. 127) measures 420, and indicates a strain in this part of the rafter of 42,000 pounds. The third or upper portion of the rafter is designated by the letters CM, and the corresponding line in Fig. 127 measures 58 parts, indicating 5800 pounds as the strain in the upper end of the rafter.

For the brace AB we have the line AB (Fig. 127), measuring 58 parts of the scale, and indicating 5800 pounds as the strain in the brace.

For the vertical *BD* we have the line *BD* (Fig. 127) measuring 135 parts of the scale, and indicating 13,500 pounds as the strain in the vertical.

For the horizontal strains, we have for CD, the corresponding line in Fig. 127, which measures 301 parts, and

HK now represents one half rafters, and $H\mathcal{F}$ one half the load their sum, $\mathcal{F}K$, equals one half equals the load upon the point of





From \mathcal{F} , H ... HD and GF. F

would be too small for selected as large as and 100 pounds to and each of the dista

It must also be reupon the care with the lines drawn. I they are true, and a sponding line of the considerably from a

the middle

neasures 350,

ior AJ, or

measures 398

- unling parts of the

Instead of deis if the lines in the :=etically. The size 5 is carefully drawn.: purposes; but i == the implements for . tund, and in all case - realts obtained by the -= 1: the correct results served that the triangle ... nate to the triangles - ters of Fig. 126 with the in the inclined lines of ___ aevation; and that the ... en mes with the vertical J. 187748

experience reception—namely, as 20

regat in each case, which its proportion obtain the recondicular, the length of its synthesis 47th of 1st book—

potheruse equals the square root of the
of the base and perpendicular. If the
triangle be computed by this method,
taince the triangles are homologous) may
more simple method of proportion.

and 14, we find, by the above rule, that its quals 1.802776 nearly. The hypothenuses of angles, therefore, may be found by the proportion:

$$1 : 1.802776 :: p : h$$
$$h = 1.802776p$$

the base we have

$$1:1\cdot5::p:b$$

$$b=1\cdot5p$$

these formulas, the lines in Fig. 127 have been computed.

strains in the proposed truss (Fig. 126), by both methods,

been found to be as follows:

	BY SCALE.			BY COMPUTATION.		
AK	=	47,800	pounds;	47,864	pounds.	
BL	=	42,000	41	42,005	14	
CM	=	5,800	46	5,859	16	
AB	=	5,800	44	5,859	44	
CD	=	30,100	44	30,075	64	
DH	=	35,000	46	34,950	44	
AF	=	39,800	"	39,825	**	
BD	=	13,500	14	13,550	66	

682.—Dimensions of Parts Subject to Tension.—With these forces, and the appropriate rules hereinbefore given, the dimensions of the several parts of the truss may now be determined.

Commencing with the tie-beam, KP, it may be observed, preparatory to computing its dimensions, that while this piece, in resisting the thrust of the rafters, is subjected to a tensile strain, it is also subject to a transverse strain from the weight of the ceiling and floor which it has to carry. These two strains, however, are of such a nature that in their effect upon the beam they do not conflict; for the tensile strain from the thrust of the rafters, acting, as it will usually, in the upper half of the beam, serves to counteract the compression produced by the transverse strain in this part of the beam, and the fibres near the middle of the beam, owing to their proximity to the neutral line, being strained very little by the transverse strain, have a large reserve of strength available to assist in resisting the tensile strain. It will be sufficient, therefore, to provide a piece of timber for the tie-beam of sufficient size to resist only one of the two strains; not necessarily that strain, however, which is the greater, but that one which requires the larger piece of timber to resist it.

The computations of dimensions required to resist the two strains will now claim attention.

For the tensile strain we have, by formula (299.),

$$\frac{20 \times 39800}{16000} = 49.75$$

or say 50 inches area of cross-section, for Georgia pine. For white pine the area should be 65 inches.

The load producing transverse strain is (Art. 678) 10,300 pounds. The rule for determining the proper area of cross-section is to be found in formula (130), which may be modified for this case by substituting rl for θ , the symbol for deflection, and by putting for r the rate 0.04 of an inch. With these substitutions, we have

Fixing upon a proportion for b in terms of d, say, for example, $b = \frac{a}{2}d$, and substituting this value for b, we have

$$\frac{20 \frac{6}{8}Ul^2 = 0.04 \times \frac{2}{4}Fd^4}{F} = d^4$$

If the timber is to be of white pine, then F equals 2900 (Table XX.), and we have

$$d = \sqrt[4]{\frac{20\% \times 10300 \times 20^3}{2900}} = 13.116$$

or the depth will need to be $13\frac{1}{8}$ inches. Three quarters of this, or $9\frac{7}{8}$, will be the breadth. The tie-beam, of white pine, will need to be, therefore, say 10×13 inches. If of Georgia pine, instead of white pine, then 5900, the value of F for Georgia pine, must be substituted for 2900 in the formula, and the results, 8.237 and 10.982, will show, say $8\frac{1}{4} \times 11$ inches as the size of timber required.

The dimensions thus found, to resist the transverse strain, being in excess of those required to resist the tensile strain, are to be adopted as the dimensions of the required tiebeam.

The length of the tie-beam, 60 feet, being greater than can readily be obtained in one piece, it will have to be built up. In doing this, it is necessary that each piece be of the full height of the beam, or that the joints of the make-up be vertical and not horizontal. These vertical laminas should be in pieces of such lengths that no two heading joints occur within five feet of each other, and that these joints shall be as near as practicable to the two vertical suspending rods. The laminas need to be well secured together with proper iron bolts. The feet of the rafters should be provided with iron clamps of sufficient area to resist the horizontal strain there, and should be secured to the tie-beam with bolts of corresponding resistance.

If the iron in the bolts and clamps of the truss be of average good quality, it may be calculated on as resisting effectually 9000 pounds per square inch (see Art. 642). The vertical suspension rods BD and DE, Fig. 126, may also be calculated for a like strain.

490

683.—Dimensions of Parts Subject to Compression.— The rafters, straining beam and braces are all subject to compression, and their dimensions may now be obtained.

The areas of these pieces may be had by the use of formula (301.); or, as this in some cases is objectionable, for the reason that the ratio between the length and thickness has to be assumed in advance, we may find in formula (303.) a rule free from this objection, but encumbered with more intricate computations. Formula (301.), when used by those having experience in such work, is far preferable, on account of its greater simplicity.

Taking first the rafter, and the portion of it at the foot, where the strain is greatest, 47,800 pounds, we have for its length about 12 feet. If of Georgia pine, its thinnest dimension of cross-section will probably be about 8 inches.

Then $r = \frac{12l}{h} = \frac{12 \times 12}{8} = 18$ (see Art. 643). The value of C is 9,500 and the value of e is 0.00109, both by Table XX. Making the symbol for safety, a, equal 10 we have

$$A = \frac{10[1 + (\frac{3}{2} \times 0.00109 \times 18^{2})]47800}{9500} = 76.97$$

or the area of the rafter should be 77, say $8 \times 9\frac{3}{4}$ inches. If computed by formula (303.), putting $n = 1 \cdot 2$, the exact size will be found at $8 \cdot 006 \times 9 \cdot 607 = 76 \cdot 92$ inches area.

684.—Dimensions of Mid-Rafter.—In the rafter at BL the strain is 42,000 pounds. The length and ratio here will be the same as at AK, and the dimensions of AK and BL are therefore in proportion to the weights (form. 301.), or

$$47800:42000:76.92:A$$

$$A = \frac{42000 \times 76.92}{47800} = 67.587$$

so that 68 inches of sectional area, or $8 \times 8\frac{1}{2}$ inches, is the size required.

- 685.—Dimensions of Upper Rafter.—The upper end of the rafter has only the weight at the ridge, 5,800 pounds, to bear. The thickness of the rafter here will probably be but 4 inches. This gives a ratio of $\frac{144}{4} = 36$. With this ratio, with 5,800 for the weight, and with the other quantities as before, a computation by formula (301) will result in showing the required area to be 19.04, or, say 4×5 inches; but, in order to resist effectually the distributed load of the roofing, this part of the rafter should not be less than 4×8 inches.
- 686.—Dimensions of Brace.—The brace, AB, being of equal length and carrying an equal load with the upper end of the rafter, may be made of the size there found necessary, or, say 4×6 inches.
- 687.—Dimensions of Straining-Beam,—The straining-beam CD is compressed with a strain of 30,100 pounds,

and its length is 20 feet.

Assuming its thickness to be that of the rafter, we have $r = \frac{12 \times 20}{8} = 30$, and in formula (301.)

$$A = \frac{10[1 + (\frac{3}{2} \times 0.00109 \times 30^{3})]30100}{9500} = 78.29$$

or its area should be $78\frac{1}{4}$, or, say $8 \times 10 = 80$ inches.

With this result, the computation of the dimensions of all the pieces of the truss is completed; for the other rafter and brace are in like condition with those computed, and should therefore be of the same dimensions.

QUESTIONS FOR PRACTICE.

688.—In a roof truss similar to that shown in Fig. 109, of 42 feet span and 14 feet height, measuring from the axial lines: What will be the strains in the various pieces of the truss, with a load of 5,000 pounds at each of the three points above the rafters, and a load of 10,000 pounds suspended from the centre of the tie-beam?

Draw the appropriate force diagram, and give the strains from measurement.

689.—Draw a force diagram for a roof truss similar to the design in Fig. 111, with a span of 54 feet and a height

18 feet; the upper weights being taken at 6,000 > unds each, the central weight under the tie-beam at 500 pounds, and each of the two other weights at 7,000 > unds.

Show, from the diagram, the strain in each line of the russ.

- **690.**—In a truss similar to that in *Fig.* 121, show, by a price diagram, what would be the strains in each line, when the span is 40 feet and the height 20 feet. The weights of and GH are so located as to divide the span into three equal parts, the three loads above the rafters are each point $\mathcal{F}ABK$ is to be taken at the middle of the after, and the line AB is to be drawn at right angles with the rafter.
- 591.—In a roof with an elevated tie-beam, such as in Fig.

 ≥5, with a span of 40 feet and height of 20 feet, and

 ith the tie elevated at the middle 8 feet above the level

 if the feet of the rafters, compute the strain in the suspen
 ion-rod at the middle, due to the elevation of the tie; the

 ieight upon one half of the truss being 24,000 pounds.
- 692.—In a building 119 feet long, and 80 feet wide the centres of bearings, and having the side walls pierced or seven windows each, state how many roof trusses there should be.

Which of the designs given, having a tie horizontal from the feet of the rafters, would be appropriate for the case?

The roof is to be 25 feet high at middle, and to have the interior space along the middle free from timber. The

load upon the roof is to be taken at 50 pounds per horizontal, upon the tie-beam at 40 pounds to the and upon the straining beam at 5 pounds per foot.

Make a force diagram, and from it show the strain each piece.

Compute the dimensions of the several timbers, we are all to be of Georgia pine; the rafter being 9 in thick below the straining-beam and 6 inches above the iron work being subjected to a tensile strain of pounds per inch.

CHAPTER XXIV.

TABLES.

mining the required dimensions of the various timbers are included in previous chapters. These rules are illy reduced to the forms required in practice. In using it is only needed to substitute for the various algesymbols their proper numerical values, and to perform ithmetical processes indicated, in order to arrive at the desired.

do even this simple work, however, requires care and ice, and these the architect, owing to the multiplicity ail demanding time and attention in his professional ce, frequently finds it difficult to exercise. To relieve f this work, the first twenty-one of the following tables been carefully computed. Tables I. to XXI. afford the for ascertaining readily the dimensions of the beams rincipal timbers required in floors of dwellings and first-stores. Tables XVII., XVIII. and XIX. refer to of rolled-iron; the others to those of wood.

4.—Floor Beams of Wood and Iron (L. to XIX. and —In these tables will be found the dimensions of Floors and Headers, of Hemlock, White pine, Spruce and pine; for Dwellings and for First-class stores. Ibles XVIII. and XIX. exhibit the distances from centure to the Rolled-iron Beams are required to be placed

in Banks, Office Buildings and Assembly-Rooms, and in First-class Stores.

695.—Floor Beams of Wood (I. to VIII.).—In these tables the recorded distance from centres is in inches, and is for a beam one inch thick, or broad. The required distance from centres is to be obtained by multiplying the tabular distance by the breadth of the given beam.

For example: Let it be required to ascertain the distance from centres at which white pine 3×10 inch beams, 16 feet long in the clear of the bearings, should be placed in a dwelling.

By reference to Table II., "White Pine Floor Beams One Inch Thick, for Dwellings, Office Buildings, and Halls of Assembly," we find, vertically under 10, the depth, and opposite to 16, the length, the dimension 4.5. This is the distance from centres for a beam one inch broad. Then, since the given beam has a breadth of 3 inches,

$$3 \times 4 \cdot 5 = 13 \cdot 5$$

equals the required distance from centres for beams 3 inches broad. Therefore, 3×10 inch white pine beams with 16 feet clear bearing, should, in a dwelling, etc., be placed $13\frac{1}{2}$ inches from centres.

Tables I. to IV. were computed from formula (143.),

$$cl^s = ibd^s$$

which, with b = 1, and putting c in inches, becomes

$$c = \frac{12id^s}{l^s} \tag{306.}$$

les V. to VIII. were computed from formula (149.),

$$cl^* = kbd^*$$

with $\bullet b = 1$, and with c in inches, becomes

$$c = \frac{12kd^s}{l^s} \tag{307.}$$

-Headers of Wood (IX. to XVI.).—(See Art. 142.) sults recorded in these tables show the breadth of which carry tail beams one foot long. The tabular, if multiplied by the length in feet of the given tail vill give the breadth of the required header.

example: Let it be required to ascertain the breadth orgin pine header 20 feet long, 15 inches deep, rying tail beams 12 feet long, in the floor of a first-tore. By referring to Table XVI., "Georgia Pine's for First-class Stores," at the intersection of the column for 15 inches depth and the horizontal 20 feet length, we find the dimension 1.06. This preadth of the header for each foot in length of the ms. As the tail beams in this case are 12 feet long, the 12×1.06 = 12.72, equals the required breadth of der in inches.

first four (IX. to XII.) of these tables were computed rmula (156.),

$$b = \frac{5 fng^{\,\bullet}}{16Fr(d-1)^{\,\bullet}}$$

when reduced (putting r = 0.03, f = 90 and becomes

$$b = \frac{937.5g^{3}}{F(d-1)^{3}} \tag{308.}$$

The second four (XIII. to XVI.) of these tables were computed from the same formula, (156.), by putting r = 0.04, f = 275 and n = 1; which reduction gives

$$b = \frac{2148 \frac{7}{16}g^{3}}{F(d-1)^{3}} \tag{309.}$$

697.—Elements of Rolled-Iron Beams (XVII.).—Table XVII. contains the dimensions of cross-section and the values of *I*, the moment of inertia, for 119 of the rolled-iron beams of American manufacture in use. These values are required in using the rules in Chapter XIX., by which the capacities of the beams are ascertained. (See Arts. 479 to 482, 485 to 492, 501, 511, 512, 514, 517, 519, 521, 523, etc.)

The values of I were computed by formula (213.)

$$I = \frac{1}{12} \left(bd^3 - b_i d_i^3 \right)$$

698.—Rolled-Iron Beams for Office Buildings, etc. (XVIII.).—Table XVIII. contains the distances from centres, in feet, at which rolled-iron beams should be placed, in the floors of Dwellings, Banks, Office Buildings and Assembly Halls. (See Arts. 500 and 501.)

These distances were computed by formula (237.),

$$c = \frac{255 \cdot 0 ?I}{l^3} - \frac{y}{420}$$

Table XIX. contains the distances from centres, in feet, at which rolled-iron beams should be placed, in the floors of First-class Stores. (See Arts. 504 and 505.)

These distances were computed by formula (239.),

$$c = \frac{148 \cdot 8I}{l^3} - \frac{y}{960}$$

700.—Example.—As an example to show the uses of Tables XVIII. and XIX.: Let it be required to know the distances from centres at which 9 inch 84 pound Phœnix rolled-iron beams should be placed, on walls with a span or clear bearing of 18 feet, to form a floor to be used in an Office Building or Assembly Room.

In Table XVIII., the one suitable for this case, at the intersection of the vertical column for 18 feet, with the horizontal line for the given beam named above, we find 4.51, or $4\frac{1}{2}$ feet, the required distance from centres.

For a First-class Store (see Table XIX.), these beams, if of the length stated, should be placed 2.66, or 2 feet and 8 inches from centres.

701.—Constants for Use in the Rules (XX.).—Constants. for use in the rules in previous chapters are to be found in Table XX.

These constants, for the 13 American woods named and for mahogany, have been computed from experiments made by the author in 1874 and 1876 expressly for this work (Arts. 704 to 707). For the values of B and F, the lowest and highest of the two series of experiments are taken, and the average given for use in the rules.

The constants for the other woods named in the table have been computed for this work from experiments made by Barlow, and recorded in his work on the Strength of Materials.

The constant F, for American wrought-iron, was com-

puted by the author from six tests made by Major Anderson on rolled-iron beams at the Trenton Iron Works, and from two tests made at the works of the Phœnix Iron Co. of Philadelphia. The beams upon which these tests were made were from 6 to 15 inches deep and from 12 to 27 feet long.

The values of F for the other metals, and of B for all the metals, have been computed from tests made by trustworthy experimenters, such as Hodgkinson, Fairbairn, Kirkaldy, Major Wade and others. The average of these values may be used in the rules, for good ordinary metal. For any important work, however, constants should be derived from tests expressly made for the work, upon fair specimens of the particular kind of metal proposed to be used.

702.—Solid Timber Floors (XXI.).—The depths required for beams when placed close to each other, side by side, without spaces between them, may be found in Table XXI.

This is not an economical method of construction. More timber is required than in the ordinary plan of narrow, deep beams, set apart. But a solid floor has the important characteristic of resisting the action of fire nearly as long, if not quite, as a floor made with rolled-iron beams and brick arches.

A floor of timber as usually made, with spaces between the beams, resists a conflagration but a very short time. The beams laid up like kindling-wood, with spaces between afford little resistance to the flames; but, when laid close, they, by the solidity obtained, prevent the passage of the air. The fire, thus retarded and confined to the room in which it originated, may be there extinguished before doing

serious damage. Floors built solid should be plastered upon the underside. The plastering lath should be nailed to narrow furring strips, half an inch thick, and the plastering pressed between the lath so as to fill the half inch space with mortar. The mortar used should contain a large portion of plaster of Paris, and be finished smooth with it. Owing to the fire-proof quality of this material, it will protect the lath a long time. Thus constructed, a solid floor will possess great endurance in resisting a conflagration.

The timbers should be attached to each other by dowels. These will serve, like cross-bridging, to distribute the pressure from a concentrated weight to the contiguous beams.

The depths given in Table XXI. were computed by formulas (311.) and (312.). These were reduced from formula (130.), which is

$$\frac{5}{8}Ul^s = Fbd^s\delta$$

In this formula U = cfl, c and l being taken in feet. If c be taken in inches, then for c we have $\frac{c}{12}$, and $U = \frac{c}{12} fl$. Putting rl for δ (Art. 313) we have

$$\frac{5cfl^3}{8\times 12} = Fbd^3r$$

In a solid floor the breadth of the beams will equal the distances from centres, or b = c (c now being in inches). In the formula these cancel each other; or

$$\frac{5fl^3}{8\times 12} = Fd^3r \qquad \text{and}$$

$$d^{s} = \frac{fl^{s}}{10 \cdot 2Fr} \tag{310.}$$

For dwellings and halls of assembly, we have taken (Art. 115) f at 90, or 70 for the superincumbent load and 20 for the materials of construction. In a solid floor, however, the weight of the timbers differs too much to permit an average of it to be used as a constant in the formula. The weight of the plastering, furring and floor-plank is constant, and may be taken at 12 pounds. To this add 70 for the superincumbent load, and the sum, 82, plus the weight of the beam, will equal f, the total load.

The weight of the beam will equal the weight of a foot superficial, inch thick, of the timber, multiplied by the depth of the beam; or, putting y equal to the weight of one foot, inch thick, of the timber, we have its total weight equal to yd; or, f = 82 + yd. Substituting this value for f in formula (310.), and putting r = 0.03, then we have

$$d^{s} = \frac{(82 + yd)l^{s}}{19 \cdot 2 \times 0 \cdot 03F}$$
 or

$$d^{s} = \frac{(82 + yd)l^{s}}{\cdot 576F} \tag{311.}$$

This formula is general for floors of dwellings, office buildings, and halls of assembly. As the symbol for the depth is found on both sides of this equation, the depth for any given length can not be directly obtained by it; a modification is needed to make the formula practicable.

An inspection of the formula shows that the depth will be very nearly in direct proportion to the length. By a simple transformation of the symbols, a formula is obtained which will give the length for any given depth. By an application of this formula to the two extremes of depth and length for each kind of material, the relative values of d and l may be found. The results for the two extremes in each case will differ but little. An average may be used as a constant for all practical lengths, without appreciable

The values of d have been computed for the four amed below, and the average value found to be for

Georgia pine,	d = 0.314l
Spruce,	d = 0.365l
White pine,	d = 0.389l
Hemlock,	d = 0.39l

verage value of y, the weight per foot superficial, zk, may be taken as follows: for

Georgia pine,	y = 4
Spruce,	$y=2\frac{1}{2}$
White pine.	$y=2\frac{1}{8}$
Hemlock,	y = 2

these values of y and d, formula (311.) becomes ble, and will give the required depth for any given of floor beams, of the four woods named, for the pors of dwellings, office buildings, and halls of y.

the floors of first-class stores, taking 250 pounds iperincumbent load and 13 pounds as the weight plastering, flooring, etc., and putting r = 0.04 we formula (310.),

$$d^{3} = \frac{(263 + yd)l^{3}}{.768F}$$
 (312.)

mula is general for floors of first-class stores. The of d have been computed for the extremes of and an average found to be as follows: for

Georgia pine,	$d = \cdot 4l$
Spruce,	$d = \cdot 472l$
White pine,	$d = \cdot 502l$
Hemlock,	d = .506l

With these values of d, and the above values of y, formula (312.) will give the depths of solid floors for first-class stores.

The depths of solid floors in Table XXI., for dwellings, office-buildings and halls of assembly, were computed by formula (311.), and those for first-class stores by formula (312.)

703.—Weights of Building Materials (XXII.).—Table XXII. contains the weight per cubic foot of various building materials.

704.—Experiments on American Woods (XXIII. to XLVI.).—Tables XXIII. to XLVI., inclusive, contain the results of experiments upon six of our American woods such as are more commonly used as building material.

These experiments, as well as those of 1874 (Art. 701), were made upon a testing machine constructed for the author, and after his plan, by the Fairbanks Scale Co. It is a modification of the Fairbanks scale, a system of levers working on knife edges, and arranged with gearing and frame by which a very gradual pressure is brought to bear upon the piece tested, which pressure is sustained by the platform of the scale and thus measured.

By an application of clock-work, devised by Mr. R. F. Hatfield, son of the author, the poise upon the scale beam is kept in motion by the pressure upon the platform, and is arrested at the instant of rupture of the piece tested. For the moderate pressures (under 2000 pounds) required, this machine is found to work satisfactorily.

705.—Experiments by Transverse Strain (XXIII. to XXXV., XIII. and XIIII.).—Tables XXIII. to XXXV.

contain tests by Transverse Strain, upon six of the thirteen woods tested by the author for this work.

At intervals, as shown, the pressure was removed and the set, if any, measured. It was found that in many instances a decided set had occurred before the increments of deflection had ceased being equal for equal additions of weight. It was thus made plain that some modification of this rule for determining the limit of elasticity must be made. To fix this limit clearly inside of any doubtful line, 25 per cent of the deflection obtained, while the increments of deflection remained equal for equal additions of weight, was deducted, and the remainder taken as the deflection at the limit of elasticity.

-Ti

Bei

196

With this deflection, the values of the constants e and in Table XX. were computed (Art. 701).

The load upon a beam, determined by the rules with the constants restricted within this limit, will not, it is confidently believed, be subject to set; or if, as is claimed by Professor Hodgkinson, any deflection, however small, will produce a set, that this set will be so slight and of such a nature as not to be injurious, or worthy of consideration.

A résumé of the results of Tables XXIII. to XXXV. is given in Tables XLII. and XLIII.

The values of F and B, given in Table XX., were derived, not alone from the results given in these tables, but also from results of the other experiments made in 1874.

(Arc. 701.)

706. — Experiments by Tensile and Sliding Strains XXVI. to XXXIX., XLIV. and XLV.).—Tables XXXVI. and XXXVII. contain tests of the resistance to tensile strain of six of the more common American woods.

A résumé of the results is given in Table XLIV.

Tables XXXVIII. and XXXIX. give tests made to sho the resistance to sliding of the fibres in six of the more common American woods. These experiments were made to ascertain the power of the several woods to resist a force tending to separate the fibres by sliding, in the longitudinal direction of the fibres. The rafter of a roof, when stepped into an indent in the tie-beam, exerts a thrust tending to split off the upper part of the end of the tie-beam. A pin through a tenon, when subjected to strain, tends to split out the part of the tenon in front of it. These are instances in which rupture may occur by the sliding of the fibres longitudinally, and a knowledge of the power of the various woods to resist it, as shown in these tables, and as condensed in Table XLV., will be useful in apportioning parts subject to this strain. The symbol G, in Table XX., represents in pounds the sliding resistance to rupture per square inch superficial, and is equal to the average of the results of the experiments in Table XLV. A discussion to show the application of these results is omitted as being uncalled for in a work on the Transverse Strain. For its treatment, see "American House Carpenter," Arts. 301 to 303, where H, the value of each wood, is taken at 1 of the resistance to rupture.

707.—Experiments by Crushing Strain (XL., XLI. and XLVI.).—Tables XL. and XLI. contain tests of resistance to crushing, in the direction of the fibres, of six of the more common of our American woods. The pieces submitted to this test were from one to two diameters high.

A résumé of the results is given in Table XLVI.

TABLES.

TABLE I.

HEMLOCK FLOOR BEAMS ONE INCH THICK, FOR DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

DISTANCE FROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 695.

Length between			DE	ртн ог	Велм	(in inc	hes).		
Bearings (in feet).	6	7	8	9	10	11	19	18	14
7	11.3								
8	7.6	12.0							İ
9	5.3	8.4	12.6						
10	3.9	6·1	9.2	13.1					
11	2.9	4.6	6.9	9.8					
12		3.6	5.3	7.6	10.4				
18		2.8	4.2	5.9	8.2	10.9			
14		••	3.3	4.8	6.5	8-7	11.3		
15		••	2.7	3.9	5 · 3	7·I	9.2	11.7	
16	••	••	••	3.2	4.4	5.8	7.6	9.6	
17		• •	••	2.7	3.6	4.9	6.3	8·o	10.
18		• •	••	• •	3·I	4·1	5.3	6.7	8.
19		••	• •	• •	2.6	3.5	4.5	5.7	7.
20		••	••	••	••	3.0	3.9	4.9	6.
21		••	• •	• •	••	••	3.3	4.2	5.
22		••	• •	••	• •	• •	2.9	3.7	4.
28		••	• •	• •	• •	• •	••	3.2	4.
24	1		• •	• •	• •	••	••	2.8	3.

TABLE II.

WHITE PINE FLOOR BEAMS ONE INCH THICK, FOR DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

DISTANCE FROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 695.

Length between		·	DE	TH OF	Beam	(in inch	kes).		
Bearings (in feet).	6	7	8	9	10	11	12	18	14
7	11.7								
8	7.8	12.4							
9	5.5	8.7	13.0						
10	4.0	6.4	9.5						
11	3.0	4.8	7.1	10.2	•			•	
12	• •	3.7	5 · 5	7.8	10.7				
13	••	2.9	4.3	6.2	8.4	11.2			
14		••	3.5	4.9	6.8	9.0	11.7		
15		••	2.8	4.0	5.5	7·3	9.5		
16		••	••	3.3	4.5	6∙0	7.8	10.0	,
17	• •	••]	2.8	3.8	5.0	6.5	8.3	10.4
18			••	••	3.2	4.2	5.5	7.0	8.7
19		••		••	2.7	3.6	4.7	5.9	7.4
20		••			••	3.1	4.0	5.1	6.4
21		••			• •	2.7	3.5	4.4	5 · 5
22		••		••	••	••	3.0	3.8	4.8
23					••		••	3.4	4.2
24	1						••	2.9	3.

TABLE III.

SPRUCE FLOOR BEAMS ONE INCH THICK, FOR DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

DISTANCE FROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 696.

Length between			DEI	тн ог	Велм	(in inc	kes). •		
BEARINGS (in feet).	6	7	8	9	10	11	12	13	14
7	14.1								
8	9.4	·	! !						
8	6.6	10.5	<u> </u>						
10	4.8	7.7	11.5						
ii	3.6	5.8	8.6	12.3					
12	2.8	4.4	6.6	9.4		•			
18		3.5	5.2	7.4	10.2	,			
14		2.8	4.2	6∙0	8.2	10.9			
15		• •	3.4	4.8	6.6	8 · 8	11.5		
16		••	2.8	4.0	5.5	7.3	9.4		
17		••	••	3.3	4.6	6·1	7.9	10.0	
18			••	2.8	3⋅8	*5·I	6.6	8-4	10
19		••	••	••	3.3	4.3	5.6	7.2	9.
20		••	••	••	2.8	3.7	4.8	6.3	7.
21		••	••	• •	• •	3.2	4.2	5.3	6.
22		• •		• •	• •	2.8	3.6	4.6	5.
23		• •	• •	• •	• •	• •	3.2	4.0	5.
24				• •			2.8	3.6	4.

TABLE IV.

DRGIA PINE FLOOR BEAMS ONE INCH THICK, FOR DWELL-INGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

DISTANCE FROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 695.

Length between			DEF	тн ог	Beam	(in inc	hes).	,	
Bearings (in feet).	6	7	8	9	10	11	12	13	14
9	11.2								
10	8.2	13.0							
11	6.1	9·7							•
12	4.7	7.5	11.2						
18	3.7	5.9	8.8						
14	3.0	4.7	7.0	10.0					
15	••	3.8	5 · 7	8.2	11.2				
16		3.2	4.7	6.7	9.2				
17		2.6	3.9	5.6	7.7	10.2			II
18			3.3	4.7	6.5	8.6	11.2		
19			2.8	4.0	5.5	7.3	9.5		
20	••	••	••	3.4	4.7	6.3	8 • 2	10.4	
21		• •	••	3.0	4.1	5.4	7.0	9.0	11-2
22			••	••	3.5	4.7	6.1	7.8	9.7
23			••	••	3.1	4.1	5.4	6.8	8.5
24				<u> </u>	2.7	3.6	4.7	6.0	7.5

TABLE V.

HEMLOCK FLOOR BEAMS ONE INCH THICK, FOR FIRST-CI STORES.

DISTANCE FROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 695.

Length between		· · · · · · · · · · · · · · · · · · ·		DEPT	н ог	Велм	(in in	ches).			
Bearings (in feet).	8	8	10	11	12	13	14	15	16	17	
8	7.8										T
9	5.5	7.8			Ì			•	<u> </u>		
10	4.0	5.7	7.8								
11	3.0	4.3	5.9								
12	2.3	3.3	4.5	6.0		ļ					
13	1 · 8	2.6	3.6	4.7	6.2						
14		2 · I	2.8	3.8	4.9	6.3					
15		1.7	2 · 3	3 · I	4.0	5.1	6.4				
16		•	1.9	2.5	3.3	4.2	5 · 2	6.4			
17			••	2 · 1	2.8	3.5	4.4	5 · 4	6.5	•	
18				1.8	2.3	2.9	3.7	4.5	5.5	6.6	
19	••	••	! !	• •	2.0	2.5	3 · 1	3⋅8	4.7	5.6	1
20			 	••	••	2 · I	2.7	3 · 3	4.0	4.8	1
21			• .	• •	• •	1.9	2.3	2.8	3.5	4.1	
22					••		2.0	2.5	3.0	3.6	
23		••					••	2 · 2	2.6	3.2	1
24							••	1.9	2.3	2.8	
25		•••		•••	••	••	••		2.0	2.5	
26 ·						••				2.2	

TABLE VI.

IITE PINE FLOOR BEAMS ONE INCH, THICK, FOR FIRST-CLASS STORES.

DISTANCE FROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 695.

Length Between				DEPT	H OF	Веам	(in in	ches).			
Bearings (in feet).	8	9	10	11	12	13	14	15	16	17	18
8	8.1					-					
9	5.7	8·1									-
10	4.1	5.9									
11	3.1	4.4	6·1								
12	2.4	3.4	4.7	6.2							
13	1.9	2.7	3.7	4.9	6.4						
14		2 · 2	3.0	3.9	5.1	6.5					
15		1.7	2.4	3.2	4.1	5.3	6.6				
16			2.0	2.6	3.4	4.3	5.4	6.7			
17				2.2	2.8	3⋅6	4.5	5.6	6.8		
18				1.8	2.4	3.1	3.8	4.7	5.7	6.8	
19					2.0	2.6	3.2	4.0	4.8	5.8	6.9
20			••	• •		2 · 2	2.8	3.4	4.1	5.0	5.9
21						1.9	2.4	3.0	3.6	4.3	5·I
22	••		! ••				2.1	2.6	3.1	3.7	4.4
23							1.8	2.2	2.7	3.3	3.9
24							••	2.0	2.4	2.9	3.4
25									2.1	2.5	3.0
26			• • •						1.9	2.3	2.7

TABLE VII.

SPRUCE FLOOR BEAMS ONE INCH THICK, FOR FIRST-STORES.

DISTANCE PROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 696.

LENGTH BETWEEN	٠			DEPT	н ор	Веам	(in se	ches).		
Bearings (in feet).		9	10	11	12	18	14	15	16	17
	6-9									
10	5.0	7.1								İ
11	3.8	5-4	7.3							
19	29	4 I	5.7	7.5						
13	2.3	3.2	4.4	519						
14	1-8	2-6	36	4:7	6.2					
15	• • •	2 · 1	2.9	3.9	5.0	6-4				
16		1.7	2-4	3-2	4-1	5.2	6-5			
17			2-0	2.6	3.4	4:4	5.2	6-7		
18				2 2	2.9	3.7	4.6	5-7	6-9	
19				19	2.5	3.1	3.9	4-8	5.8	
20			* *		2-1	2-7	314	4-1	5.0	ģ.
21				* 4	1.8	2:3	2.9	3.6	4.3	5
22				,,		2.0	3-5	3-1	3.8	1.4
23				4.0			2.2	2.7	3.3	3
94	٠	١					119	2.4	2.9	, 3
25						1		2 · I	2.6	3
26						1		1.9	2.3	2

TABLE VIII.

>RGIA PINE FLOOR BEAMS ONE INCH THICK, FOR FIRST-CLASS STORES.

DISTANCE FROM CENTRES (in inches).

For Beams Thicker than One Inch, see Arts. 693 and 695.

Length Between				DEPT	H OF	Веам	(in i	nches)			
BEARINGS (in feet).	8	9	10	11	12	13	14	15	16	17	18
11	6.3										•
12	4.9	7.0									
13	3.8	5.2						•			
14	3.1	4.1	6.0								
15	2.5	3.6	4.9	6.5			•				
16	2.1	2.9	4.0	5.4	7.0						
17	1.7	2.1	3.4	4.5	5.8						
18		2·I	2.8	3.8	4.9	6.2					
19	••	1.8	2.4	3.2	4.2	5.3	6.6				
20		••	2 · I	2.7	3.6	4.2	5.7				
31			1.8	2 · 4	3 · 1	3.9	4.9	6.0			
22		••		2.1	2.7	3.4	4.2	5.2	6.3		
23		• •	••	r · 8	2.3	3.0	3.7	4.6	5.5	6.7	
24					2·1	2.6	3.3	4.0	4.9	5.9	
25			••		1.8	2.3	2.9	3.6	4.3	5.2	6.2
26						2 · 1	2.6	3.2	3.8	4.6	5.5

TABLE IX.

HEMLOCK HEADERS FOR DWELLINGS, OFFICE BUILDINGS, A HALLS OF ASSEMBLY.

THICKNESS OF HEADER (in inches) FOR TAIL BEAMS ONE FOOT LONG.

For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length • Between			DEP	тн ог	HEADE	R (in i	nches).		
Bearings (in feet).	6	7	8	9	10	11	12	18	
5	·33	-19	-12	-08					
6	-58	.33	-21	.14	•10	-07			
7	.92	·53	.33	-22	.16	-11	.09		
8	1.37	.79	.50	.33	.23	.17	.13	•10	¦
9	1.95	1.13	·71	·48	.33	.24	·18	-14	
10	2.68	1.55	-98	-65	-46	•33	.25	-19	
11	• •	2.06	1.30	.87	·61	•45	.33	-26	
12	• •	2.68	1.69	1.13	•79	-58	.43	.33	
13	• •		2.14	1.44	1.01	·73	.55	.43	
14	• •		2.68	1.79	1.26	-92	-69	·53	
15	- ••	••	••	2.21	1.55	1.13	-85	.65	
16	••		••	2.68	1.88	1.37	1.03	•79	
17	••			3.21	2.26	1.64	I · 24	.95	
18	• •				2.68	1.95	1-47	1.13	
19	••		••		3.15	2.80	1.72	1.33	
20	• •				3.67	2.68	2.01	1.55	

TABLE X.

WHITE PINE HEADERS FOR DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

THICKNESS OF HEADER (in inches) FOR TAIL BEAMS ONE FOOT LONG.

For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length between			DEP	TH OF	HEADE	R (in in	ches).	•	
Bearings (in feet).	6.	7	8	9	10	11	12	13	14
8	.32	.19	.12	.08	,				
6	.56	.32	• •20	.14	•10	.07			
7	.89	-51	.32	.22	.15	.11	-08		
8	1.32	·77	-48	.32	.23	•16	.12	•10	-07
9	1.88	1.09	-69	.46	.32	·24	18	-14	.11
10	2.59	1.50	·94	.63	·44	.32	.24	•19	.16
11		1.99	1.25	-84	.59	·43	.32	.25	· 2 0
12	• •	2.59	1.63	1.09	.77	∙56	·42	.32	-25
13	•••		2.07	1.39	·97	.71	·53	·4I	·32
14			2.59	1.73	1.22	-89	-67	.51	.40
15	••	••	3.18	2.13	1.50	1.09	-82	.63	.50
16				2.59	1.82	1.32	.99	-77	.60
17	••			3.10	2.18	1.59	1.19	.92	.72
18	• •				2.59	1.88	1.42	1.09	-86
19	••	••			3̄.04	2.22	1.67	1.28	1.01
20	• •				3.55	2.59	1.94	1.50	1.18

TABLE XI.

SPRUCE HEADERS FOR DWELLINGS, OFFICE BUILDINGS, A HALLS OF ASSEMBLY.

THICKNESS OF HEADER (in inches) FOR TAIL BRAMS ONE FOOT LONG.

For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length between			DEPT	TH OF	Header	(in in	ches).		
Bearings (in feet).	6	7	8	9	10	11	12	13	1
5	.27	.15	.10	•06					
6	.46	.27	.17	.11	.08				
7	•73	.42	.27	.18	.13	.09			
8	1.10	.63	•40	.27	•19	.14	.10	-08	
9	1.56	.90	∙57	∙3 8	.27	.19	.15	.11	•
10	2.14	1.24	.78	.52	·37	.27	.20	.15	
11		1.65	1.04	.70	•49	.36	.27	·2I	•
12		2.14	1.35	.90	.63	.46	∙35	.27	
13		2.72	1.72	1.15	-81	· 5 9	•44	·34] ;
14			2.14	1.43	1.01	·73	.55	-42	,
15	••		2.63	1.77	1.24	.90	·68	.52	
16			3.20	2.14	1.50	1.10	·82	-63	
17				2.57	1.80	1.32	.99	.76	
18				3.05	2.14	1.56	1.17	.90	
19					2.52	1.84	1.38	1.06	
20					2.94	2.14	1.61	1.24	

TABLE XII.

ORGIA PINE HEADERS FOR DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

THICKNESS OF HEADER (in inches) FOR TAIL BEAMS ONE FOOT LONG.

For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length between			DEP	TH OF	Hradei	R (in in	ches).		
Bearings (in feet).	6	7	8	9	10	11	12	18	14
5	•16	.09							
6	.27	•16	.10	.07					
7	•44	.25	•16	•11	.07				
8	-65	-38	•24	-16	•11	∙08			
9	· 9 3	•54	•34	.23	.16	.12	.09		
10	1.27	-73	.46	.31	.22	•16	.12	.09	
11	1.69	.98	-62	.41	-29	·2I	-16	.12	•10
12	2.20	1.27	.80	∙54	· 3 8	-27	·2I	∙16	•12
18	••	1.62	1.02	-68	·48	∙35	· 2 6	.20	•16
14		2.02	1.27	∙85	-60	•44	∙33	·25	· 2 0
15		2.48	1.56	1.05	·73	-54	•40	.31	.24
16			1.90	1.27	.89	.65	·49 .	-38	.30
17			2.28	1.52	1.07	.78	-59	·45	•35
18		••	2.70	1.81	1.27	·9 3	.70	·54	·42
19				2.13	1.49	1.09	.82	-63	-50
20				2.48	1.74	1.27	-95	·73	· 5 8

TABLE XIII.

HEMLOCK HEADERS FOR FIRST-CLASS STORES. THICKNESS OF HEADER (in inches) FOR TAIL BEAMS ONE FOOT LONG. For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length Between				Dертн	OF I	IRADEI	in i	nches).			
BEARINGS (in feet).	8	9	10	11	12	13	14	15	16	17	18
5	-28	.19	.13	-10	.07				İ		
6	· 4 8	.32	.23	.17	.12	.10	-07				
7	-77	.51	.36	-26	-20	.15	.12	.10	-08		
8	1-14	.77	.54	-39	-29	.23	.18	.14	-12	.10	.08
9	1.63	1.09	·77	.56	.42	.32	.25	.20	.17	.14	. 11
10	2.24	1.50	1.05	•77	-58	-44	∙35	· 2 8	.23	.19	.16
11	2.98	1.99	1.40	1.02	.77	.59	.46	•37	.30	.25	.21
12	• •	2.59	1.82	1.33	1.00	.77	·60	-48	.39	.32	.27
13	• •	3.29	2.31	1.69	1.27	.97	·77	.61	.50	.41	.34
14	• •	••	2.89	2.10	1-58	1.22	-96	-77	-62	-51	-43
15	••	••	3.55	2.59	1.95	1.50	1.18	-94	•77	.63	•53
16		• •	• •	3.14	2.36	1.82	1.43	1-14	-93	-77	-64
17		• •	• •	3.77	2.83	2.18	1.72	1.37	1.12	.92	.77
18	••	••	••	••	3.36	2.59	2.04	1.63	1.33	1.09	.91
19	••		• •	• •	3.95	3.05	2.39	1.92	1.56	1.28	1.07
20	••	••	• •	••	4.61	3.55	2.79	2.24	1.82	1.50	1.25

TABLE XIV.

WHITE PINE HEADERS FOR FIRST-CLASS STORES. THICKNESS OF HEADER (in inches) FOR TAIL BEAMS ONE FOOT LONG. For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length Between				ДЕРТН	of H	EADER	(in is	nches).		1	
BEARINGS (in feet).	8	9	10	11	12	13	14	15	16	17	18
5	-27	.18	.13	.09	.07						
6	-47	-31	.22	.16	.12	.09	.07				
7	·74	.50	-35	.25	.19	.15	·12	.09	.07		
8	1.11	-74	• .52	-38	· 28	.22	.17	-14	.11	.09	.08
9	1.57	1.05	.74	-54	.41	.31	.25	.20	.16	.13	.11
10	2.16	1.46	1.02	·74	· 5 6	·43	-34	.27	.22	-18	-15
11	2.87	1.93	1.35	.99	.74	-57	·45	.36	.29	· 2 4	.20
12	••	2.50	1.76	1.28	.96	.74	-58	-47	-38	-31	-26
18	• •	3-18	2.23	1.63	I.22	.94	•74	.59	-48	·40	· 3 3
14	• •		2.79	2.03	1.53	1.18	-92	·74	.60	.50	.41
15	••	••	3.43	2.50	1.88	1-45	1.14	.91	•74	·61	-51
16				3.03	2.28	1.76	1.38	1.11	.90	-74	.62
17				3.64	2.73	2.11	1.66	1.33	1.08	-89	.74
18				4.32	3.25	2.50	1.97	1.57	1.28	1.05	-88
19	• •		••		3.82	2.94	2.31	1.85	1.50	1.24	1.03
20	• •			• •	4.45	3.43	2.70	2.16	1.76	1.45	1.21

TABLE XV.

SPRUCE HEADERS FOR FIRST-CLASS STORES.

THICKNESS OF HEADER (in inches) FOR TAIL BRAMS ONE FOOT LONG.

For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length Between	- ;			DEPTH	of I	Iradei	R (in i	nches).			
BEARINGS (in feet).	8	9	10	11	19	13	14	15	16	17	18
5	.22	-15	•10	.08							
6	.39	· 2 6	·18	.13	·IO	.08					
7	·61	·4I	.29	·2I	.16	.12	•10	408			
8	.92	-61	•43	-31	.24	.18	·14	·rr	.09	.08	
9	1.30	-87	·61	•45	·34	· 2 6	· 2 0	-16	.13	·II	•09
10	1.79	1.20	-84	.61	.46	∙35	-28	-22	.18	.15	-12
11	2.38	1.60	1.12	·8 2	.61	·47	-37	· 3 0	.24	.20	-17
19	3.09	2.07	1.45	1.06	·8o	·61	·48	•39	.31	· 2 6	.22
13	• •	2.63	1.85	1.35	1.01	-78	·61	.49	-40	•33	.27
14	• •	3.29	2.31	1.68	1.26	·97	.77	.61	-50	.41	∙34
15	••	••	2.84	2.07	1.56	1.20	∙94	·75	.61	.51	.42
16	• •		3.45	2.51	1.89	1.45	1.14	.92	·74	.61	.51
17	• •			3.02	2.27	1.74	1.37	1.10	.89	·74	·61
18	• •	••		3.58	2.69	2.07	1.63	1.30	1.06	.87	.73
19	••			4.21	3.16	2.44	1.92	1.53	1.25	1.03	-86
80		. .			3.69	2.84	2.23	1.79	1.45	1.20	1.00

TABLE XVI.

GEORGIA PINE HEADERS FOR FIRST-CLASS STORES.

THICKNESS OF HEADER (in inches) FOR TAIL BEAMS ONE FOOT LONG.

For Tail Beams Longer than One Foot, see Arts. 693 and 696.

Length Between				DEPT	H OF	HEADE	R (in	inches).			
Bearings (in <i>feet</i>).	8	9	10	11	19	13	14	15	16	17	18
5	-13	.cg	.06								
6	-23	.15	.11	.08							
7	·36	-24	· 4 6	.12	•09	.07					
8	•54	-36	.25	•19	.14	.11	-08				
9	·77	.52	∙36	· 2 6	.20	.15	.12	.10	• o 8		
10	1.06	.71	.50	.36	.27	.21	.17	.13	•11	.09	
11	1-41	-95	-67	· 4 8	∙36	.28	.22	.18	-14	.12	.10
12	1.83	1.23	-86	-63	·47	-36	.29	.23	•19	.15	.13
13	2.33	1.56	1.10	.80	-60	-46	.36	.29	·24	.19	.1(
14	2.91	1.95	1.37	1.00	·75	· 5 8	•45	· 3 6	· 3 0	·24	.20
15	• •	2.40	1.69	1.23	.92	.71	.56	∙45	∙36	-30	•2
16	• •	2.91	2.05	1.49	1.12	∙86	-68	·54	•44	.36	.30
17	• •	3.49	2.45	1.79	1.34	1.03	·81	.65	.53	•44	.30
18	• •	••	2.91	2.12	1.59	1.23	·97	.77	-63	.52	.43
19	• •	••	3.43	2.50	1.88	1.44	1.14	.91	·74	·61	.51
80	•	••	••	2.91	2.19	1.69	1.33	1.06	.86	.71	-59

TABLE XVII.

ELEMENTS OF ROLLED-IRON BEAMS.

Name.	<i>d</i> = Dертн.	WEIGHT PER YARD.	b= Breadth.	AVERAGE THICKNESS OF FLANGE.	THICKNESS OF WEB.	ð,	ď,	$T_{15}^{I} (bd^{3} - b_{i}d_{i}^{2})$
Pittsburgh.	3	21 27	2.316	.359	.191	2.125	2.28t 2.28t	3.109
Pittsburgh. Phænix	`3	18	2.516 2.	· 359	.391 .2	2.125 1.8		3.559
Trenton	4	18	2.	. 278 . 29	.187	1.813	3.444	4·539 4. 62 3
Pottsville.	4	18	2.125	.271	.187	1.938	3.42 3.458	4.655
	7	-	5	,_	.107	1.930	3.430	4.033
Paterson	4	18	2.25	.281	. 156	2.094	3.438	4.909
Pittsburgh.	4	24	2.481	. 328	.231	2.25	3.344	6.221
Pittsburgh.	4	30	2.631	. 328	.381	2.25	3 · 344	7.021
Pottsville	4	30	2.25	•5	.25	2.	3.	7.5
Buffalo	4	30	2.75	•4	.25	2.5	3.2	7.840
Paterson	4	30	2.75	.4	.25	2.5	3.2	7.840
Phœnix	4	30	2.75	•4	.25	2.5	3.2	7.840
Trenton	4	30	2.75	•4	.25	2.5	3.2	7.840
Paterson	4	37	3.	.456	.312	2.688	3.088	9.404
Trenton	4	37	3.	.456	.312	2.688	3.088	9.404
Duffala		•			0.7		4.0	70.080
Buffalo Paterson	5	30	2.75	•35 .	.25	2.5	4.3	12.082 12.082
Phœnix	5	30	2.75	•35	.25	2.5	4.3	12.082
Trenton) 	30 30	2.75 2.75	· 35 · 35	.25	2.5	4·3 4·3	12.082
Pottsville.	5 5 5	30	3.062	.311	.25	2.812	4.378	12.232
2003	J]] 3.002	- 5-2	123	2.012	4.27.	:
Pittsburgh.	5	30	2.725	-375	. 225	2.5	4.25	12.393
Pittsburgh.	5	39	2.905	·375	.405	2.5	4.25	14.268
Phœnix	5 5	36	3.	. 389	• 3	2.7	4.222	14.317
Paterson	5	40	3.	.438	·333	2.667	4.125	15.650
Trenton	5	40	3.	·454	.312	2.688	4.092	15.902
Pottsville	5	40	3.125	-434	.312	2.813	4.132	16.015
Phœnix	5 6	40	2.75	.5	.25	2.5	5.	23.458
Buffalo	6	40	3.	.454	. 25	2.75	5.091	23.761
Paterson	6	40	3.	·454	.25	2.75	5.091	23.761
Trenton	6	40	3.	•454	.25	2.75	5.091	23.761
		<u> </u>	<u> </u>		<u> </u>	<u> </u>		

TABLE XVII.—(Continued.)

ELEMENTS OF ROLLED-IRON BEAMS.

								
Name.	d = DEPTH.	WEIGHT PER YARD.	b= Breadth.	AVERAGE THICKNESS OF FLANGE.	THICKNESS OF WEB.	8,	ď,	$\begin{vmatrix} I = I \\ \frac{1}{12} \left(bd^3 - b_i d_i^3 \right) \end{vmatrix}$
Pottsville Pittsburgh. Pittsburgh. Buffalo Pottsville	6 6 6 6	40 40 1 54 50 50	3·375 3·237 3·462 3·25 3·437	·4 ·437 ·437 ·532 ·500	.25 .237 .462 .312	3.125 3. 3. 2.938 3.125	5.2 5.125 5.125 4.935 5.080	24.133 24.613 28.663 29.074 29.314
Phœnix Paterson Trenton Phœnix Pottsville	6 6 7 7	50 50 50 55 55	3·5 3·5 3·5 3·5 3·562	.492 .5 .5 .484 .510	.3I .3 .3 .35 .312	3.19 3.2 3.2 3.15 3.25	5.016 5. 5. 6.032 5.980	29.451 29.667 29.667 42.430 43.897
Trenton Pittsburgh. Buffalo Paterson Phœnix	7 7 7 7	55 54 60 60 69	3.75 3.604 3.5 3.5 3.687	.493 .562 .54 .54	·3 ·229 ·375 ·375 ·56	3·45 3·375 3·125 3·125 3·127	6.014 5.875 5.92 5.92 6.048	44.652 45.983 46.012 46.012 47.739
Pottsville Paterson Trenton Pittsburgh. Buffalo	7 6 6 7 8	65 90 90 75 65	3.625 5. 5. 3.904 3.5	. 596 . 667 . 667 . 562 . 56	·375 ·5 ·5 ·529 ·375	3.25 4.5 4.5 3.375 3.125	5.808 4.667 4.667 5.875 6.880	50.553 51.881 51.881 54.558 64.526
Paterson Phœnix Trenton Pottsville . Paterson	6 8 6 8	120 65 120 65 65	5·5 4· 5·25 4· 4·	. 789 . 478 . 892 . 543 . 554	·75 ·38 ·625 ·312 ·3	4·75 3.62 4.625 3.688 3·7	4.422 7.044 4.216 6.914 6.892	64.773 65.232 65.618 69.089 69.729
Trenton Pittsburgh. Pottsville Phænix Buffalo	8 8 8 9	65 66 80 81 70	4. 3.806 4.187 4.125 3.5	•554 •593 •542 •556 •500	·3 ·306 ·5 ·51 ·437	3·7 3·5 3·687 3·615 3·663	6.892 6.813 6.916 6.888 8.000	69.729 70.153 77.007 77.552 81.937

TABLE XVII.—(Continued.)

ELEMENTS OF ROLLED-IRON BEAMS.

		a			1	Ī		
Name.	d = Depth.	WEIGHT PER YARD.	breadth.	AVERAGE THICKNESS OF FLANGE.	THICKNESS OF WEB.	8,	ď,	$I = I = I$ $I = (bd^3 - b, d^3)$
Trenton	8	80	4.5	.606	-375	4.125	6.788	84.485
Paterson	8	8o	4.5	.610	.37	4.13	6.780	84.735
Pottsville	9 8	70	4.125	.483	-375	3.75	8.034	88.545
Pittsburgh.		105	4.293	• 593	· 793	3.5	6.813	90.932
Phœnix	9	70	3.5	.660	.31	3.19	7.680	92.207
Paterson	9	70	3.5	.672	.3	3.2	7.656	92.958
Trenton	9	70	3.5	.672	.3_	3.2	7.656	92.958
Pittsburgh.	9	70 1	4.012	.625	.262	3.75	7.75	98.265
Pottsville	9	90 84	4.5	.501	.562	3.938	7.998	105.480
Phœnix	9	04	4.	.667	•4	3.6	7.667	107.793
Buffalo	9	90 85	4.	.643	.5	3.5	7.714	109.117
Paterson	9		4.	.697	. 384	3.616	7.605	110.461
Trenton	9	85	4.	. 707	-375	3.625	7.586	111.124
Pittsburgh. Pottsville	9 10]	99 90	4.329	.625	-579	3.75	7.75	117.523
1 Ottsvine	209	90	4.25	. 578	•437	3.813	9 • 344	150.763
Pittsburgh.	10	90	4.325	.718	. 325	4.	8.563	151.123
Buffalo	10}	90	4 · 437	.551	·437	4.	9.397	151.436
Trenton	9	125	4.5	• 937	·57	3.93		154.917
Pittsburgh.	9	135	4.931	.812	·744	4.187	7.375	159.597
Pittsburgh.	10}	941	4 • 534	.625	.409	4.125	9.25	165.327
Pottsville.	10]	105	4.562	-575	. 562	4.	9.350	167.624
Trenton	101	90	4.5	.683	.312	4.188	9.134	168.154
Pittsburgh.	9.	150	5.098	.812	.911	4.187	7 · 375	169.742
Buffalo	101	105	4.5	.656	·5	4.	9.187	175.645
Phœnix	10}	105	4.5	-724	•44	4.06	9.052	183.164
Pittsburgh.	10	135	4 - 775	.718	-7 75	4.	8.563	188.623
Phœnix	9	150	5 · 375	1.005	.6	4.775	6.99	190.630
Paterson	10½	105	4.5	-795	· 375	4.125		191.040
Trenton	IO	105	4.5	• 795	· 375	4.125	8.909	191.040
Phœnix	10}	135	4.875	.614	.81	4.065	9.272	200.263
					<u> </u>			l .

TABLE XVII.—(Continued.)

ELEMENTS OF ROLLED-IRON BEAMS.

Name.	d = Depth.	WEIGHT PER YARD.	<i>b</i> = Breadth.	AVERAGE THICKNESS OF FLANGE.	THICKNESS OF WEB.	b.	ď,	$I_{\xi}^{I}\left(bd^{3}-bd^{3}\right)$
Pittsburgh. Paterson Trenton Pottsville Pittsburgh.	101 101 101 12 12	135 135 135 125 126	4.920 5. 5. 4.562 4.638	.625 •945 •945 .800 .781	.795 .47 .47 .5	4.125 4.53 4.53 4.062 4.125	9.25 8.609 8.609 10.400 10.438	202.564 241.478 241.478 276.162 276.946
Phœnix Buffalo Paterson Trenton Pittsburgh.	12 12 12 12 12 12	125 125 125 125 180	4·75 4·5 4·79 4·79 5.088	·777 ·797 ·768 ·780 ·781	.49 .5 .48 .47 .963	4.26 4. 4.31 4.32 4.125	10.446 10.656 10.714 10.690 10.438	279.351 286.019 292.050 293.994 341.746
Pottsville Phœnix Paterson Trenton Buffalo	12 12 12 12 12 12 12	170 170 170 170 180	5.5 5.5 5.5 5.5 5.375	1.086 1.010 .985 .981 1.089	.625 .59 .6 .6	4·375 4·91 4·9 4·9	9.828 9.980 10.28 10.351 10.072	373.907 385.284 398.936 402.538 418.945
Buffalo Paterson Phœnix Pottsville Trenton	15136 15136 15 15	150 150 150 150 150	4.875 5. 4.75 5.062 5.	.761 .731 .882 .822	.562 .56 .5 .5	4.313 4.440 4.25 4.562 4.5	13.477 13.725 13.235 13.356 13.542	491.307 502.883 514.870 517.948 528.223
Pittsburgh. Pittsburgh. Pittsburgh. Phænix Buffalo	15 15 15 15	150 195 201 200 200	5.030 5.330 5.545 5.375 5.375	.875 .875 1.031 1.085 1.118	.468 .768 .670 .65 .625	4.562 4.562 4.875 4.725 4.75	12.938 12.830	530.343 614.718 679.710 680.146 688.775
Paterson Pottsville Trenton Pittsburgh .	15 1 15 15 1 15	200 200 200 240	5·5 5·687 5·75 5·805	1.048 1.049 1.060 1.031	.65 .625 .6 .930	4.85 5.062 5.15 4.875	12.902	692.166 693.503 714.205 752.835

TABLE XVIII.—(Continued.)

ROLLED-IRON BEAMS IN DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

DISTANCES FROM CENTRES (in feet).

See Arts. 694, 698 and 700.

9 19
21 12 13 8 22 12 13 8 23 13 13 13 13 13 13 13 13 13 13 13 13 13
86 5.62 86 5.63 76 5.95 75 5.35
03 5 56 15 6.63 30 6.73 65 7.03 18 9.17
23 9.23 41 9.33 74 9.52
0 0 0 0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
4.00

TABLE XVIII.—(Continued.)

ROLLED-IRON BEAMS IN DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

DISTANCES FROM CENTRES (in feet).

See Arts. 694, 698 and 70Q.

] 1	0	N H Q Q/Q	+00000	53 6 36 33	3 6 H 4 E	N44NW	₩ ₩ ► ★
	8(288	6 6 6 6 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	* 8 W W W	++++	5.94 5.94 5.94 6.95	6.03 6.27 7.54
	88	8 8 8 8 8 8	3.78	3.51 3.62 3.77 3.80 3.95	5.03 5.03 5.17	2. 6. 6. 6. 7. 7. 7. 7. 7. 7. 7. 7. 7. 7. 7. 7. 7.	2.00 2.00 2.00 2.00 2.00 2.00 3.00 3.00
	30 61	0 4 4 9 9 0 8 H 4	86552	\$28.22	₩ 0 ₩ 0 ₩ 0	83 44 53 53	N. N. W. H.
	-	9 8 8 8 9 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	414 419 813 813 813 813 813 813 813 813 813 813	\$ 255 8 8 4 4 4 4 4	01 16 16 33 33 35 49 55	52 50 50 60 33 7 45 7	787 787 1987
]	A	9 9 9 9 9	<u> </u>	44444	<u> </u>	<u> </u>	ထဲထဲထဲ တဲ
	976	2.62 3.18 3.18 3.71	3.85 3.85 3.94 4.53	5.02 5.19 5.44 5.65	7.9.7.	7.88 9.99 9.39 9.53	9.52 9.59 9.89 10.35
	38	88844	4.37 4.47 4.50 5.15	5.70 6.11 6.17	27.66 8.05 8.27	8 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	10.77
NG.	24	64444 41188883 12583	4.98 5.09 5.09 5.83	6.76 6.96 7.09 7.30	9.90.69	4.88 : : :	::::
Bearings	88	3.93 4.74 5.49 5.51	5.30 5.30 5.83 5.87 6.74	7.43 7.96 7.96 8.03 8.35	9.90 10.00 10.50 10.70		::::
BETWEEN	88	5.4.53 6.32 6.33	6.39 6.55 6.70 7.70	8.55 8.82 9.15 9.24	# : : : : : : : : : : : : : : : : : : :	:::::	::::
	21	6.33 6.33 7.31	7.40 7.58 7.75 7.80 8.98	9.89 10.21 10.58 10.68	:::::	:::::	::::
in See	08	4	8.82 9.01 9.05		:::::	:::::	::::
LRNGTH (in feef)	19	8.66 8.66 9.97 0.00	10.34	:::::	:::::	:::::	::::
LEN	18	8.54 10.24 11.78	:::::	:::::	:::::	:::::	::::
	11		:::::	:::::	:::::	:::::	::::
	16	:::::	:::::	:::::		:::::	::::
	1.5	:::::	:::::	:::::	:::::	:::::	::::
	14	:::::	:::::	:::::	:::::	:::::	::::
	13	:::::	:::::	:::::	:::::	:::::	::::
HT PER .CE.	WEIG	135	125 125 125 125 180	170 170 170 180	88888	150 195 201 200	8 8 8 3
.HT4	₽₽	200 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	22222	2 2 2 2 2 2 X	15 8 15 15 15 15 15 15 15 15 15 15 15 15 15	ស្តីស្តីស្ត	15.7 15 15.7 15.7
NAKE.		Pittsburgh Paterson Trenton Pottsville	Phœnix Buffalo Paterson Trenton Pittsburgh	Pottsville Phœnix Paterson Trenton	Buffalo Paterson Phœnix Pottsville.	Pittsburgh Pittsburgh Pittsburgh Phænix Buffalo	Paterson Pottsville Trenton

TABLE XIX.

EXALED-IRON BEAMS IN FIRST-CLASS STORES.

DISTANCES FROM CENTRES (in feet).

See Arts. 694, 697, 699 and 700.

Name	Mex	ASTA					LEN	STH (in fo	nt) as	sa Wa	жи Е	EARI	NGS.				
	Span	* Water	3		7	8	9	10	11	19	13	14	15	16	17	18	19	2(
Property of the Property of th		20 20 20 20 20 20 20 20 20 20 20 20 20 2	4 31 38	3, 63	1.95	1,30 1,30 1,33												
Maria aras An escriptor gras Ances aras Ances aras Ances aras Ances aras		10 10 10 10	5,62	3.36 4.26 4.84 5.14	2.11 2.67 3.01 3.22	1.41 1.78 2.01 2 15 2,23	E.84 E.40											
Margaret Present Newsons	*	10 10 10 10 10 10		5 37 5 37	1.37 1.37 4.04	2,25 2,25 2,69 2,69	1.57 1.57 1.88	1,14										
Mar haborer Marcher spread Marcher Sa Marcher Sa Marcher Salve	3 3	22222			5,31 5,21 5,71	3.48 3.48	3,43 3,43 2,43	1.77 1.77 1.77 1.77 1.79	t.32 t.32									
100 C		40 40 40 40 40			6 15 6 17	4 21 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	2.87 2.88	2 81, 2 09 2 09 2 29 2 32	1,55	1,20								
Tropy of	3 3	4444				6,66 77 6,86 6,86	1-75 1,8¢	3.49	2 58 2.61 2.61	2,00 2,00	1 - 57	1,22						

TABLE XVIII.—(Continued.)

ROLLED-IRON BEAMS IN DWELLINGS, OFFICE BUILDINGS, AND HALLS OF ASSEMBLY.

DISTANCES FROM CENTRES (in feet).

See Arts. 694, 698 and 70Q.

N.	THE	HET THE						1	Length (in fer) between	in fee	C SALT	WEEK	BEARDICE.	DIG.						
	DE	Water Y	85	7.	10	-	17	18	1.0	90	10	96	DE OR	4	40	8	64	30 64	0.00	8.0
Pittsburgh Paterson Pottsville	2222	25228	: . : . :	:::::	:::::	:::::	00,01	22,007	8,68 8,68 8,00,00	4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	7.33	* N N O O	3.93 4.74 5.46 5.51	44444	85578	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	200000	0 4 4 0 0 0 E	80 8 8 9 9	28844
Phoenix. Buffalo Paterson Trenton	22222	125 125 185 180 180	.:.::	.:::	:::::	:::::	: ' . : :	: .::	10,34 10,36 10,64	8.61 8.83 9.03 9.08	4 5 5 5 8 8	0.000 r	25887	* 4 + 2 × 2 × 2 × 2 × 2 × 2 × 2 × 2 × 2 × 2	4 + 4 + 3 4 + 4 + 3 5 + 5 7 +	3.95 3.94 4.53	400	3.00.00.00.00.00.00.00.00.00.00.00.00.00	2000.4	46568
Pottsville Phænix Paterson Trenton	22222	170 170 180	: :::	:::::	:::::	:::::	:::::	:::::	:::::	\$	9.80 10.58 10.58 11.11	8.55 8.85 9.15 9.01 9.01	47.78 B	6-70 6-96 7-94 7-34	5.52 6.11 6.41	20.00	400000	2.00 2.00 2.00 2.00 2.00 2.00 2.00 2.00	20 20 20	226 42
Buffalo	4 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	88888	:::::	:::.	.::::	: : : : :	: : :	.:::,	:::::	::::	:::::	T	\$0.000 \$0.000 \$0.000	88.7. 9.99.99	20 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	6.77 6.94 7.11 7.16	20000 20000	25.00.00	2. 6. 6. 6. E.	THE PROPERTY OF
Pritsburgh Pritsburgh Pritsburgh Phenix	(A) (A) (A) (A) (A)	\$55 g g	:::::	.::::	:::::	: :::	*::::	:::::	, , , , 4	::::	:::::	:::::	F:::::	0.01 4.01	8 30 10.63 10.63	#000000 000000000000000000000000000000	0 F-80 80 80	5.81 5.68 7.42 7.53 6	40000	24486
Paterson Fotisville Trenton	25.55.2 25.55.25.25.25.25.25.25.25.25.25.25.25.2	8883	1:::	::::	:::	::::	::::	::::;	::::	::::	. : : :	: ::	::::	::::	10.77 10.85 11.18	9.50	250000	2000 H	Med 90	8.8 4.4

TABLE XIX.—(Continued.)

ROLLED-IRON BEAMS IN FIRST-CLASS STORES.

DISTANCES FROM CENTRES (in feet).

See Arts. 694, 697, 699 and 700.

	30						
					·		
	#						
	Ru						
	65						1r3 4r5
	_ dt					,	12.00
	OR				2 240 2	82328	28886
,	OS			77.00	27.75	88877	F
BRARITICS	OR		0.00	# # # # # # # # # # # # # # # # # # #		W 0 11 12 12 12 12 12 12 12 12 12 12 12 12	P B S O O
Эвал	94				2.03 2.03 2.23	86666	4.4.4.4.6.6.6.6.6.6.6.6.6.6.6.6.6.6.6.6
	124	#12 PT #2 #2 PT #2 #4 PT #4	44.000	3,522,5	nanan nanan	20 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	8 5 8 8 8
BETWEEN	80	24.4.4.4.4.4.4.4.4.4.4.4.4.4.4.4.4.4.4.	1.66 1.75 1.92	10000	P P P P P P	10 8 5 8 5 8 5 8 5 8 5 8 5 8 5 8 5 8 5 8	5 5 4 4 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5
Seef)	19	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	46.2	4 4 4 6 M	00 00 00 00 00 00 00 00 00 00 00 00 00	22222	28.00
3	50	0 0 1 0 0	84428	2,00	3.76	7 6 7 7 7 7 7 9 7 9 9 9 9 9 9 9 9 9 9 9	44.44
MENGTH	1.5	4440 C	44.24 3.28 3.28 3.28	2.20	4 4 4 4 4	5.99 5.49 5.44 5.44	\$ 50 50 50 50 br>50 50 50 50 50 50 50 50 50 50 50 50 50 50 50 50 50 5
Н	16	90 00 00 00 00 00 00 00 00 00 00 00 00 0	5 0 0 4 m	10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	5 + 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	0.0000 0.0000	7.000 P
	1.5	######################################	28728	4 4 4 7 2 8 8 8 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	78.50 V	7.533	177770
	14	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	258.9%	8 3 5 5 8 8 3 5 5 8	0 0 0 00 00	800000 800000 8000000	50.00 50.00 50.00 50.00 50.00 50.00
	133	200000	5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	7.30	10, 14 20 16 10 36 10 36 11 10	11,24 11,29 11,79 12,30	: : : :
	120	7.35	25885 58885	9.40	* ; ; ;	1:111	:::::
	=	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	15,01		: '	: :	: . : : :
08A 08A	Wind	88625	22233	82588	88252	25 8 8 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	550 500 501 501 501 501
'HLA	D	20 00 00 00 00 00 00 00 00 00 00 00 00 0	27077	JOHN 3	52002	28 25	2222
NAME		Patervon Poterville Pitishargh.	Pateron Tront.on P tishurgh Pottsville, Phiffer x	Fiffalo Paterson Irenton Patesburgh, Potesvalle	Patsburgh . Raffalo . Irenton Patsburgh	Pottswile, Trenton Patsbargh, Buffalo	Pittsburgh Phæinx, Paterson, Trenton, Phænix

TABLE XIX .-- (Continued.)

ROLLED-IRON BEAMS IN FIRST-CLASS STORES.

DISTANCES FROM CENTRES (in feet).

See Arts. 694, 697, 599 and 700.

	at 2-25	57 90 1.68 90 1.08 11.96 1.7	23 1,98 1,76 29 2,01 1,80 34 2,03 1,86 35 2,09 1,86 71 2,40 2,13	992 65236 062742-43 202842-53 30298-65	20 3.56 3.75 20 3.74 3.33 23 3.76 3.35 33 3.64 3.43	3 3.8c 4 4 4 4 4 9 3 1.4c 5 4 9 3 1.4c 5 4 9 3 4 4 6 5 4 9 3 4 4 6 5 5 6 6 7 6 7 6 5 6 7 6 7 6 5 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	65,5,02 4,48 56,5,03 4 49 14 5,19 4,63
	10	0 0 0 15 0 0 0 15	2 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	46200	\$ 5 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	20 5.54 27 5.55 37 5.55	20 0 0 8 20 0 8
	-	0 4 400	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	30.00	120000000000000000000000000000000000000	440.00	7842
é	96	中国 あるで	200	4.75	200000000000000000000000000000000000000	88 10 7	927.79
Вжаниса	ct ot	S S S S S S S S S S S S S S S S S S S	W W W W W	24.4.4.4	7.082	**************************************	9.46
	24	44.24	* * * * * * * * * * * * * * * * * * *	6.50	F-00000	60 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	10.91
BETWEEN	90	**************************************	25.50 25.50	8.8.7. 8.8.4.4.9.7	8 8 7 4 6	P. P	1111
Seed	10	**************************************	2000 F	1-000000 000000000000000000000000000000	10.35 11.03 11.08 11.08	E : : : :	::::
# (/m	90	0,000 € € € € € € € €	27 7 7 90	445 5 5 5 5 6 5 6 6 6 6 6 6 6 6 6 6 6 6	::::	;;'	-:,
LENGTH (Ja	10	8 1 1 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	8.33	24.11	; : :	';.:.	
-4	16	2000 00 2000 00 2000 00	0 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	: .	:::	-:::	::::
	10	8.79 10.50 10.50 17.05	1 + + + +		• • ;	::	: : : :
	14	eg : :	: :	1.:	:::::	11111	. : : : :
	13	: ' : ' :	: :.	: :	:::::	: : :	*
	87	. : : : :	. ' : : :	: • • :	:::::	:.: :	::-
	1	1 : 1		: ::	.:::	: .	: `
SHT YER GRA	Wei	135	125 125 186 186	22228	33233	150 100 100 100 100 100 100 100 100 100	300 300 240 300 300
'HJJ471	a	2222	****	2222	TO AT THE AT	N 10 10 10 10	15% 15% 15% 15%
NAME.		Pittsburgh, Paterson Fenton Pottsville, . Pittsburgh	Phoenix Buffalo Paterton. I renton	Potraville Paterson Trenton Huffalo	Buffalo Paterson Piloguix Potraville Frenton	Pittsburgh, Pittsburgh, Pittsburgh, Pitenix	Paterson Pottsville Trenton, Putsburgh,

TABLE XIX.—(Continued.)

ROLLED-IRON BEAMS IN FIRST-CLASS STORES.

DISTANCES FROM CENTRES (in feet).

See Arts, 694, 697, 699 and 700.

	0 1						
	100.						
	- B						
	OR		_				
	91		_				
	4D 61						60
	10 01					9,0	111.86
	4				2,72,3	\$ 7 5 7 8 8 4 6 4 6	80000
g	50) O1			1.33	XXX 8	38837	F F B B B
Вканиса	gk ot		20,4	444	8 8 6 8 8	20 0 0 0 4 20 0 0 0 4 20 0 0 0 43	4 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
	ri or	E E E	44484	1.00	H 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	B0000	8,000
BETWEEN	9	4 4 6 6 4	202	75865	01 04 04 04 04 01 04 04 04 04	P. 28 5 W	10 E E E E
Sect	#1	E VERNO	40.44	2 4 6 4 W	E E E E	50 50 50 50 50 50 50 50 50 50 50 50 50 5	6 6 0 0 k
-5	18	0 0 1 7 7 7	87.258	\$ 100 m	3.93	4-17 4-17 4-17 4-17 4-55	52226
KISKE	17	8 4 4 4 6 G	F 8 2 7 8 2 7 8 2 7 8 2 7 8 9 9 7 8 9 9 7 8 9 9 7 9 9 7 9 9 9 9	MWWW.	44444	4 2 4 2 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	5.0000
ы	10	2 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Service Andrews	10 17 17 14 18 10 17 17 14 18 10 18 18 18 18	5 - 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	80000	6.83 6.83 7.13
	15	# m # m m	4 4 4 4 4 5 6 6 6 8	4.73	6.50 6.50 7.40 7.40	7.32	7.0000
	#	3 2 2 3 5	44000	2 4 5 7 8	0 00 00 00 00 0 0 0 0 00 0 0 0 0 0	80 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	10,000 10,18 10,35 10,72
	67 mi	28 800 5	21.00 K	7.37	41.00	11.34	h 1 4 h
	OR III	127.77	7.47 8.09 8.09 9.49	5 4 4 6 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	:::::	::::	: ' ' ' :
	= '	9. 9. 9. 9. 9. 9. 9. 9. 9. 9. 9. 9. 9. 9	10,37	+ 1 + 1	1 1	: : : :	:::::
SHA THE	X I	86 20 20 70 70 70	22235	82588	8822.24 34	288253	135
"HLLAT	D	00 00 com c	B 7 0 7 B	22443	25 250	0 8 0 0 0 26.24 26.24	20200
NAME		Trenton Paterson Pottsville Pittsburgh.	Paterson Trenton Patersule Patersule Pharoux	Baffalo Paternon Prephorgh Pottsville .	Pattsburgh H figh I tenton Pattsburgh	Pothyville Pitroburgh Buffalo	Pattsburgh Phtenix Paterson Trenton

TABLE XIX.—(Continued.)

ROLLED-IRON BEAMS IN FIRST-CLASS STORES.

DISTANCES FROM CENTRES (in feel).

Set Arts. 694, 697, 699 and 700.

NAME.	HEA	STA TH.						1	LENGTH	5	Soul	aetween		BEARINGS.	ಕ							
	α	X.	=	81	m	1.1	1.5	16	12	# 18	19	90	18	94 94	(d)	4 0	10	90	(R)	90 I	0 1	000
Pattsbargh. Paterson . Trenton . Potsville. Pattsborgh.	2222	135	:	. :	= : :	10.84	80000	8 6 6 3 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	0 1 1 0 B	6.03 6.03 6.03 6.03	4 m m m m	25.4 25.35 25.35 25.35	EEE + +	900000		0 + 4000	20000	28888	2288	4 14		
Phena Buffalo Pateron Treaton Pitusburgh	22222	125	. : : : :	: '	: ::	;	. :	10.00 10.48 10.55	8.33 8.77 6.77 6.00	7.00	5.93	5.30	4 4 4 4 4 5 6 5 5 5 6 5 6 6 6 6 6 6 6 6 6 6 6 6 6	F 6 6 6 5	2.65	800004	22222	19492	80 0 0 Q	C - 8 8 8 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	22528	2.
Pottsville Phonos Paterson Frenton	22222	170	:::::	:::::	1111	: .	:	;;:: '	11.15	9.36	F	6.78 7.28 7.28 7.28	2000 0 A	5.03 5.40 5.45 5.67	4.704	2 6 2 6 6	3.66.3	88 4 4 %	4 4 4 5 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	55 55 55 55 55 55 55 55 55 55 55 55 55	27887	20024
Buffalo Paterson Phopnx Pottaville Tretton.	5 2 2 2 5 4 5 2 5 5	22322	: :::	7::::	1.111	, :::	4 4:	: :	:: '	:::::	0,50 0,73 10,73	8 0 0 0 0	4 0 0 B	7.007	5.85.50 5.45.50 5.30 5.45.50 5.30 5.50 5.30 5.50	E S S T D	22726	000000	MAMMA M	F 2 C C C	25885	23862
Petrsburgh. 15 Petrsburgh. 15 Petrsburgh. 15 Petrsburgh. 15 Petrsburgh. 15 Buffalo 15	FORES	25228	::.	:::::	::::	= :		.::::	. ::	: . :	7 ::::	12.11	8 9 0 0 0 7 7 7 8 8	- 00 00 00 00 00 00 00 00 00 00 00 00 00	6.33 8.10 9.11 8.10 7.11 8.20 7.11	55	460000	20 4 20 0 20 4 4 4 5 5	4 4 4 60	######################################	82228	名ななの
Potaville Treaton Pitaburgh.	1534 1534 1534 1534	2 20 2 20 2 20 2 20 2 20 2 2 2 2 2 2 2	. : : :	:::	:::		::::	- 1 +	- :	:	::::	: :	10.93	9.46	8 m m m	4000	15 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	200 mg 2	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	20 2 4 K	20.00

. TABLE XX.

See Arts. 701, 705 and 706.

				_			
	See Table XLII.	See Table XLIII.			See Table XLIV.	See Table XLV.	Ser Table XLVI.
The larger figures give the average, for use in the	For- mula (10.)	For- mula (113.)	Formula (117.)	For- mula (118.)	TENSION, INCH. SEC-	Supike, Supike,	M TO IN.
pules,	212	17.75 14.75	Tale of the second	B 72Fe	ANCE T BY T IQ. INC	ANCE BY	NTAME NE, PE
	es.	GE,		II T	RESIDENT TURE PER 1	RESESTA TUME PARE SQ FICTAL,	CHUSH
	500	4807	1001000	1 3514	11671	713	1170
Georgia Pine	850	590 0	-001118 -00100d	1-8357 a-1013	21742	934	9500
Locust	958 1200 1406	5050 5650	-0015 -0015 -001764	# 3874 2 · 2002 1 9593	11487 24800 33882	1160 1389	1170 1170 239h
White Oak	460 650 B75	3100 4444	-000791 -00086	4.7400 3.3863 2.9405	12453 19500 31194	1076 1250 1474	6531 8000 9775
Spruce	417 550	3500	-000846 -00098	3 0324 2 · 2271	35719	463 540 647	7166 7850
White Pine	728 490 500	4819 2005 2000	-0014 -00104	1 8940 2-8350 1 - 7105	9786 12000	433 480	\$408 \$879 6650
Hemlock	543 aBo 450	3766 1660 2500	-0017QE -000037 -00005	2 3496 2 3496	13754 6164 8700	322 370	5213 5700
Whitewood	707 380 600	4000 3368 3450	0009375 -0009375	2 5382 2 5517 2 5161	9871	410	Çeğı
	700 448	3556 2300	0009896 0008844	2 7628 2 0146			
Chestnut.	180 320 860	2550 2824 3800	00103 001177 001042	2 5382 2 1728 3-0166			
Ash	950	4248	-00111 001177	2 8153 2 6667			
Maple	1057 1100 1157	5150 5333	0013854 0014 0014063	2 1558 2 · 1190 2 · 1612			
Hickory	1040 1050 1100	3850 4000	001108 -0013 -001406	2 9138 2 9138			
Cherry	616 650 746	2800 2850 2933	001563 001563	I 0540			
Black Walnut	715 750	3619 3900	+0100-	9 8105 2 5682			
Mahogany, St. Dom	507 050	3973 3600		2 4842 1 8773 2 · 1618			
" Bay Wood.	790 813 850	3894 4545 4750	-001177 -001042 -00109	2 3940 2 1843 2 2802			
Oak, English	920 394	2022	001146 0000014	3 0024			
***********	557	3350	-0007256	3 . 1826		ĺ	
" Dantzie	490 460	2697 2249	+0003014				
Oaks, Average of	475	2580	-000834	3.0660			
Oak, Canadian	589	4466	·000012	2 . 9930			

TABLE XX.—(Continued.)

See Arts. 701, 705 and 706.

	See Table XLII.	See Table XLIII.			See Table XLIV.	See Table XLV.	See Table XLVI.
The larger figures give the uperage, for use in the	For- mula (10.)	For muln (113)	(117.)	For- mula (118.)	Tension, Tension, INCH SEC REA, . T	9 20	R TO R SQ. IN. SHORT
rules	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Par Me	44	B		Y W	RESISTANCE USHING, PER EC. ARRA, S BLOCKE, =
	B =	4	•	4	RESISTANCE TURE BY FRE SQ. 11	RESISTANCE TURE SY FIEL SQ. 11 FICIAL, =	CRUSHING, PER S SEC. ARRA, SI BLOCKE, =
AshBeach	675	3810	.0007177 .000582	3 4285 3 9520			
Elm	338	1590	+0009552	3.0910			
Pitch Pine	54.1 447	2836 4259	+0006428 -0004279				
Fir, New England	367	3454	-0005277	2 7966	l 1		
" Riga.	369 350	3080 2293	0004932				
" Awerage of Riga	360	2686	10005868	3 1723			
" Mar Forest	381	1858	+0008174				
" Av'ge of Mar Forest	42I 408	2013	0007762				
Larch	284	1422	.0010686	2.5958			
14	277 376	2078 . 2437	0006265	2 9552			
" Average of	330	2093	-000744	2.9433			
Norway Spar	491	3375 41500	0006173	3.2732	20000		6
Cast-Iron, American	2500 3000	50000 58500			27000	4 + 4 4 7	1 20000 1 70000
" English	1600 2100 2600	27700 40000 53800	,		13000 17000 26000		80000 IOOQO 140000
Wrought-Iron, Amer .	2400 2000	55500 02000	0002		40000 00000	,	40000 70000
	2800 1800	53000			30000		40000
" English }	1900	62000			50000 65000		50000 65000
" Swedish		65000 65000 71500					
Steel Bars	3900 6000 7900	70000 70000 74000					
" Chrome	11	.,		,	115780 155500 190862		
Blue Stone Flagging.	128 200 251						
Sandstone	33 59 94		,				3000 6000
Brick, Common	33 43		4 7 7 7 8 4				2000 3000
" Pressed	37						4000
Marble, Eastchester	147		1 4444				20000

TABLE XXI.

SOLID TİMBER FLOORS.

DEPTH OF BEAM (in inches).

See Art. 702.

BETWEEN (in feet).	DWELLI	NGS AND	Assembly	Rooms.	F	rst-cla	ss Store	S.
LENGTH BET BEARINGS (in	GEORGIA Pine.	SPRUCE.	WHITE PINE.	HEMLOCK.	Georgia Pine.	SPRUCE.	WHITE PINE.	Немгоск.
8 9 10 11 12 13 14 15 16 17 18 19 20 21 22	2·40 2·72 3·03 3·35 3·67 3·99 4·32 4·64 4·97 5·31 5·64 5·98 6·32 6·66 7·00	2·83 3·20 3·56 3·93 4·30 4·68 5·05 5·43 5·81 6·19 6·58 6·97 7·35 7·75 8·14	3·01 3·40 3·79 4·18 4·58 4·98 5·38 5·78 6·19 6·59 7·00 7·41 7·83 8·24 8·66	3·04 3·43 3·82 4·21 4·61 5·01 5·41 5·81 6·21 6·62 7·03 7·44 7·85 8·27 8·68	3·15 3·55 3·55 3·95 4·35 4·76 5·16 5·57 5·98 6·39 6·80 7·21 7·63 8·05 8·46 8·88	3·73 4·20 4·68 5·15 5·63 6·10 6·58 7·06 7·55 8·03 8·51 9·00 9·48 9·97 10·46	3·97 4·47 4·98 5·48 5·99 6·50 7·01 7·52 8·03 8·55 9·06 9·58 10·10	4·01 4·52 5·03 5·54 6·05 6·56 7·07 7·59 8·10 8·62 9·14 9·66 10·18 10·70 11·22
23 24 25 26 27 28 29 30	7·35 7·70 8·05 8·40 8·76 9·11 9·47 9·83	8·53 8·93 9·33 9·73 10·14 10·54 10·95 11·36	9·08 9·51 9·93 10·36 10·79 11·22 11·65 12·09	9·10 9·52 9·94 10·37 10·79 11·22 11·65 12·08	9·30 9·72 10·15 10·57 11·00 11·42 11·85 12·28	10·95 11·44 11·94 12·43 12·92 13·42 13·92 14·42	11 · 66 12 · 18 12 · 71 13 · 23 13 · 76 14 · 29 14 · 82 15 · 35	11·74 12·27 12·79 13·32 13·85 14·38 14·91 15·44

TABLE XXII.

MATERIALS USED IN THE CONSTRUCTION OR LOADING OF BUILDINGS.

WEIGHTS PER CUBIC FOOT.

As per Barlow, Gallier, Haswell, Hurst, Rankine, Tredgold, Wood and the Author.

MATERIAL.	Увож	To	AVERAUE.	Material.	FROM	ů.	AVERAGE.
WOODS.	41 35 49 41 39 35 59 47 39 27 27 27 69	51 51 57 53 49 55 57 53 40 41 55 41		Mahogany, St Domingo Maple Mulberry Oak, Adrianc Black Bog Canadian Dantaic English Live Red White, Olive Orange Pear-tree Pine, Georgia (pitch) Mar Forest Memel and Riga Red Scotch White Yellow Plum Poplar. Quince Redwood Rosewood. Sassafras Satinwood. Spruce Sycamore Teak Tulip-tree Vine. Walnut, Black White	45 33 35 60 	65 49 55 66 70 77 54 57 44 58 35 35 40 40 40 40 40 40 40 40 40 40 40 40 40	0AY 544684748108498879688604840708100818
Hickory Lance-wood Larch Red. White Lignum-vitte Locust Logwood. Mahogany, Honduras	40 41 31 31 41 41	58 63 35 54 83 51	49 43 43 43 45 45 45 45 45 45 45 45 45 45 45 45 45	Whitewood Yew METALS. Biamuth, Cast Brass, Cast (Gun metal) Plate	25	575 534	97 50

TABLE XXII.—(Continued.)

MATERIALS USED IN THE CONSTRUCTION OR LOADING OF BUILDINGS.

WEIGHTS PER CUBIC FOOT.

As per Bortow, Gallier, Haswell, Hurst, Rankine, Tredgold, Wool and the Author.

Material.	From	To	AVERAGE	MATERIAL.	Pros	To	Avename
Copper, Cast	537 1	549	548	Brick-work	gó	22.0	10
" Hammered	454		550	dry	1		Ц
Plate	- 1.1	117	544	IN CONCOL	** 1	1	Ц
Gold		101	1200	on Mortar	lan	1.30	H
" Standard	411	4.4	500	Caen Stone Cemant, Portland	***	**	나
Gun-metal	475	487	481	Roman, Cast.			н
lron, Bar .,	434	474	454	" and Sand.		2.4	
" Malicable	494	474	475	equal parts			h
Wrought	474	456	480	Challe	146	174	
Lead, Cast			109	Clay	119	115	
" English Cast		4 +	717	" with Gravel			11
Milled			718	Coal, Anthracite		308	
Mercury at 32"		-	849	" Betuminous		30	
" 60"	1.1		887	" Cumberland	27	:01	1
Nickel, Cast			488	Coke	46	6.3	
Pearter.		٠,	453	Concrete, Cement	135	735	1
Pewter Platina, Crude		4 1 -	975	Coquina .		-24	.1
Pure Rolled			1845	Earth, Common	95	kuş	
" Rolled			1379	" Loamy			11
Plumbago		-	686	with Gravel,		1 .	Ц
Silver, Parisian Standard			655	Emery.	*-		
Pure Cast Hammered	**		658	Feldspar		**	H.
" Standard	l . '	,	644	Flant.		١.	ı,
Steel	486	492	489	Glass, Crown	255	165	'n
Tin, Cast.	456	468	462	" Fliat	191	105	13
Zine, Cast	429	449	489	16 Green	1.	1	1
				Plate	153	173	1
STONES, EARTHS, Exc.		1	1 1	" White		181	1
STUNES, EARTINS, AIC.				Granite.	158	172	H
Alabaster	165	180	173	" Aberdeen	1	+ 1.7	Н
Asphalt, Gritted	103	140	156	" Guernsey	-	١.	li
Asphaltum	57	303	80	" Quincy			1
Rarytes, Sulphate of .	250	304	277	Gravel	-00	1200	130
Basalt	135	187	171	Grandstone		١, ١	
Bath Stone	123	129	130	Gypsum	135	345	, 1
Beton Colgnet	174	134	158				hi
Blue Stone, Common , , Brick.	0.		160	Limestone Aubigné.	139	199	(1)
Fire-	85	110	138	" Limerick	' '		H
" N. R. common hard	1	***	107		261	278	1
** Salmon	1 '''		100		-	1,7	H
" Philadelphia Front			105				Ц

TABLE XXII .- (Continued.)

MATERIALS USED IN THE CONSTRUCTION OR LOADING OF BUILDINGS.

WEIGHTS PER CUBIC FOOT.

As per Barlow, Gallier, Haswell, Hurst, Rankine, Tredgold, Wood and the Author.

Material.	FROM	ů	AVERAGE	MATERIAL.	Екон	To	AVELAGE
Marble, Eastchester	167	378	173	Serpentine			185
Egyptum			167	" Chester, Pu		11	144
FTERCH	165	360	166 167	CHOCK	• • •	**	159 98
Mari	100	170	140	Shingle	111	18x	1 69
Manonry		140	125	" Common	, ,		167
Mica	* 4	1	175	" Cornwall			157
fillstone	·	-	155	" Welsh ,			180
Cortar	87	118	103	Stone, Artificial	280	150	135
" dry	ou	410	107	Stone-work.	130	160	140
" Hair, incl. Lath and				⊓ Неwп		* *	160
Nails, per foot sup.	7	2.2	. 9	Rubble			140
Hair, dry			86	Sulphur, Melted			124
" Sand 3 and Lime paste a	*		105	Tiles, Common plain Trap Rock	4		170
46 4 3 46 14 46 2		•	100	Tufa, Roman			76
well beat together			118				
eat, Hard			88	MISCELLANEOUS,			
etrified Wood	***	**	146	Ashes Wood			56
itch laster, Cast. orphyry, Green			80	Bark, Peruvian		* * * *	49
probyry, Green	- 1		180	Butter			58
ortland Stone			175	Camphor	4.		69
ortland blone	132		147	Charcoal.	-	34	26
umice-stone .			165	Cotton, baled	24	≥3	90 58
martz, Crystallized	4.4		165	Gunpowder		Ča	57
otten-stone			124	Gutta-percha			61
otten-stone and, Coarse			113	Hay, haled	10	24	17
" Common	ga	118	105	India Rubber,	3 6	66	61
" Dry	118	BEI	123	Isoglan.			114
Mortar	,	2.00	105	Plaster of Paris	.,		78
** Pit	-92	tot	97	Plaster of Paris Plumbago	4 1		181
Quartz .,,	147		172	Red Lead	- 11	-	559
muth Gravel	100	25B	126	Rock Crustel		1	171
Amherst, O	1.00	130	183	Rock Crystal	* ;		183
Belleville, N. J.,			142	Saltpetre	,		131
Berea, O	***		134	Snow	8	20	14
" Dorchester, N S. Little Falls, N. J.	4 * *		134	Water, Rain	ю	100	80
Marietta, Q.	111		162	Sea	,		64
" Middletown, Ct	111		150	Whalebone			81

TABLE XXIII.

TRANSVERSE STRAINS IN GEORGIA PINE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of	1	2	3	1	5	6	7	8	9
Experiment.				-			-		-
Depth } (in inches).	1.04	1.04	1.03	1.04	1.03	1 03	1.03	1.03	1 03
BRRADTH (in inches).	1.05	1.04	1.03	1.03	1.04	1.04	1-04	1.03	1.04
Pressure (in pounds).				DEFLEC	TION (is	inches).			
.0	·000	.000	•000	•000	.000	•000	.000	.000	.000
25	.030	015	.030	.012	.012	•020	.010	.030	.012
50 75	•040	030	•040 • 060	.030	.025	.035	.025	.040	.030
100	·055 ·070	040 •050	· 080	•045 •060	∙045 •065	•o5o •o65	•035 •050	·055 ·070	-045 -000
_									ļ
100	•000	.000	.000	•000	·000	•000	•000	.000	•000
100 125	·070 ·085	050	.080	•060	∙c65 •o8o	∙065 ∙080	.050	•070	•c6o
150	•100	065 080	·110	•075 . •090	100	•090	•070 ∙08 5	· 110	· 075 · 085
175	1115	•095	110	105	1115	•105	· 1co	130	.100
200	• 130	.110	.140	120	.130	120	-115	150	-115
•		_					-		
0	•000	1000	.000	•000	.000	•000	•000	.000	.000
200 22 5	•130	.110	·140 ·160	120	130	.120	-115	·150 ·170	.115
250	•145 •160	·120 ·135	175	·135 ·150	-145 -160	·135	·125 ·140	150	·130 •145
275	•175	· 150	-190	.165	. 180	·160	·160	.210	.160
300	•190	•160	.510	180	.195	.175	175	.225	-175
•									
300	•000	•000 •160	.000	· 180	•000	.000	.000	.000	.000
325	•210	175	·210	•200	·215	•175	· 175	·245	175
850	.225	190	.250	.215	•230	.210	.210	·265	.205
375	.340	.205	•265	•230	•245	.225	.225	-285	.330
400	.255	• 220	·28o	.245	•260	.240	• 245	.310	.235
0			.00#		•000		.005	.005	
400	·oco	·220	· 005 • 280	·coo -245	·260	·005 ·240	·005 ·240	·005 ·310	·005
425	·275	.235	.300	·265	· 280	·255	.255	.330	• 255
450	.290	•250	.320	· 280	295	•270	.270	.355	• 275
475	.310	•265	.340	.295	.315	- 285	.285	·385	.390
500	.330	· 28o	•380	·315	•335	∙3∞	∙3∞	.415	.302
0	•000	•010	•030	-000	•005	.005	-005	.030	.005
50Ŏ	.330	·28o	•380	.315	.340	.300	.300	.430	.305
525	· · 350	.295		.330	· 360	.315	• 320	.470	.325
550	.370	.310	• • • •	.350	·38o	.330	·33 5	• • • •	345
575	.390	•330	• • • •	•375	405	.350	·35 5	••••	.370
600	.415	.350	••••	•395	· 435	•375	•375	••••	.400
o	.020	•020	• • • •	-015	.025	.020	-025		.025
600	.420	.350	••••	·405	.440	∙380	·380		.410
625	·460	•370		•435	.475	.405	.405		.455
650	• 560	.400	• • •	.470	• 535	.430	·430		-
675	•••	•440		• • •	• • • •	·460	•475		•
700	• • • •	-48o				•			
Breaking Weight (in pounds).	674.	719.	518.	6(2.	652.	699.	68 ₅ .	536.	642-

TABLE XXIV.

TRANSVERSE STRAINS IN LOCUST.

LENGTH 1.6 FEET BETWEEN BEARINGS.

			- 					<u> </u>	1		 i
Number of Experiment.	10	11	12	13	14	15	16	17	18	19	20
DEPTH (in inches).	1.03	1.08	1.05	1.08	1.07	1.05	1.07	1.08	1.07	1.09	1.08
BREADTH (in inches).	1.02	1.05	1.08	1.02	1.09	1 · 08	1.08	1.04	1.08	1.08	1.03
Pressure (in pounds).				D	BFLECT	ion (in	inches).			
0	•000	•000	•000	•000	•000	.000	.000	•000	.000	•000	-000
25	·015	.015	.015	.015	.010	.015	•015	.015	.015	.015	1.015
50	.035	•030	•030	•030	.025	.030	.030	.035	•030	.030	•030
75	.055	•050	.045	.045	•035	-050	.045	.050	.045	-045	.045
100	•075	•065	∙060	•060	•050	•065	•060	.070	•060	•060	∙060
o	•000	-000	•000	•000	-000	•000	.000	•000	•000	.000	.000
100	.075	•065	•060	·060	· o 50	.065	·060	.070	•060	•060	-060
125	.095	•o8o	.075	.075	.065	·080	.075	-090	.075	.075	∙080
150	•110	•100	.090	•090	·080	.095	•090	.110	•090	.090	.095
175	•125	•115	• 105	•110	.090	115	• 105	•125	105	-100	110
200	•145	•130	•115	-125	• 105	•130	•120	•145	•120	•115	125
i O	•000	•000	•000	•000	•000	•000	.000	-000	•000	.000	•000
200	• 145	.130	-115	•125	• 105	•130	1	-145	•120	í	125
225	.165	•150	.130	•140	•120	• 145	.135	• 165	•130	4	. 140
250	· 180	•170	• 145	• 155	•135	. 165	• 150	.190	·145	•145	155
275	.200	185	• 160	•175	•145	· 180	· 165	.210	•160	.160	
800	•220	•200	• 175	• 190	• 160	•195	· 180	•230	•175	•175	•190
		227	222		000	222					
0	.000	.005	.000	•000	• 000	.000	•000	.010	•000	.000	-005
300	•220	• 205	• 175	• 190	• 160	• 195	180	•230	175	175	190
325	· 240 · 260	•220	190	.210	175	•210	195	•250	•190	185	205
350	1	·240 ·265	·205 ·220	• 225	· 190 • 205	•230	·210 ·220	·270 ·290	•205	•200	•220
875	.275	•205	•235	·240 ·255	•220	·245 ·265	.235		.220	•215	• 240
400	·295	290	-33	255		205	235	.315	•235	•230	•255
0	•005	.020	•005	•005	•000	•005	•005		.000	•005	.010
400	.295	.295	·235	.255	.220	•265	•235		.235	•230	.255
425	•335		.250	.275	.235	•280	.250		.250	• 245	.275
450			· 265	.295	.250	.295	· 265		.265	.260	.290
475			·280	·310	• 265	.315	•280		.280	.275	.310
500	· · · ·		•290	.325	·280	•335	•295	••••	.295	•290	•330
	!	<u> </u>	l					l 	l ————	! 	i

TABLE XXIV.—(Continued.)

TRANSVERSE STRAINS IN LOCUST.

LENGTH 1.6 FRET BETWEEN BEARINGS.

Number of) Experi- ment.	10	11	12	13	14	15	16	17	18	19	20
DEPTH (in inches).	1.03	1.08	1.05	1.08	1.07	1.05	1.07	1.08	1.07	1.09	1.0
Breadth (in inches).	1.02	1.05	1.08	1.02	1.09	1.08	1 · 08	1.04	1.08	1.08	τ.ο
Pressure (in pounds).		-		Γ	EFLECT	non (in	inches).			
0			·005	·005	•005	· O15	·005		-005	-005	•01
500			•290	.325	·280	•335	.295		.295	•290	•33
525			· 3Ó5	.345	.295	.355	.310		.310	. 305	•35
550			• 320	.365	.310	.375	.325	• • • •	.325	.320	.37
575			.335	•385	.325	.395	• 340		.340	.335	•39
600		••••	.350	•405	•345	.415	• 360	• • • •	•355	•350	•41
0			.010	.020	•010	.020	.015	• • • •	.010	.015	-02
600			.350	-405	• 345	•420	•360		•355	•355	.41
625			· 365	·430	.365	•455	•375	• • • •	•375	• 370	•44
850			• 385	•455	· 385	•490	•390	• • • •	•390	• 390	•46
675]	•400	·485	.405	525	.405		•405	-410	•48
700		••••	.415	.510	.425	.560	.420	••••	.425	•430	.51
0 '			.015	.035	.030	.040	.020		.025	-025	.05
700			.415	.515	·430	· 565	.420		.425	.435	• 52
725			·435	.540	•455	• 595	•440	• • • •	•445	•455	l
750			•455	•575	•475	·635	·460		•465	·480	
775			•475	·610	.505	• • • •	·480		•490	.500	
800	:	• • • •	•495	.640	•535	••••	.500		.515	.520	
0			·035	.075	·060		.035		.045	-045	
800			.505	·650	• 545		.505		.520	•530	
825			-530	-690	·580		.530		•545	·560	
850		 .	.555	· 725	.615		.550		.570	.585	
875	[.585		-645		.575		-600	.615	
900			.615	• • • •	-675		·605	• • • •	·630	·650	
0			065				.050	•••	.075		
900] !	.635		.·		.610		.640		
925			.665				.640		675		
950			.695				.670		10		
975			·735				.700		•		
1000				••••	••••	• • • •	•735				
Breaking) Weight (in) pounds).	449	425.	1046	956.	1001 ·	860.	1037	402.	937	1027	715

TABLE XXV.

TRANSVERSE STRAINS IN WHITE OAK.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of) Experi-	21	22	23	24	25	26	27	28	29	30
MENT.	~ -									
DEPTH * } (in inches). }	1.06	1.06	1.08	I·07	1.08	1.06	1.09	1.08	1.07	1.06
BREADTH (in inches).	1.08	1.08	1.06	1.06	1.06	1.08	1.07	1.07	1.06	1.08
Pressure (in pounds).		•		Der	LECTION	(in inc	kes).			
]	į						
0	.000	.000	.000	.000	•000	.000	.000	•000	-000	-000
25	.030	•040	.035	•040	.045	.015	.035	-040	.035	.015
50	•060	.075	.065	∙080	.090	.085	.075	·080	.070	085
75	•090	.115	.095	.115	135	.125	•115	.125	105	.125
100	• 120	•155	130	•150	• 180	•170	•155	• 165	.140	• 165
0	•000	.000	.000	.000	.000	.000	.000	.000	•000	.000
100	.120	• 155	•130	.150	-185	.170	.155	. 165	•140	.170
125	-150	195	.165	-190	.235	.215	.200	.215	-175	.215
150	• 180	.235	.195	.230	.295	.260	.245	·260	.210	. 260
175	.215	•280	.225	.275	.355	.310	·285	.310	.240	.310
200	.245	.325	.265	.315	.410	.355	.330	· 360	.275	• 365
200	-43	3-3				333	33		-75	3.3
0	•000	.020	.010	•020	.025	-020	.015	•020	•010	.025
200	·250	•330	· 2 65	.325	.410	• 365	•345	· 360	·28o	. 365
225	· 285	·380	•310	·380	·480	•420	• 395	.420	• 320	.420
250	• 320	•440	.350	•430	.555	·480	•450	-485	• 360	·480
275	- 360	•500	•390	•480	•635	• 545	.515	· 560	.405	• 545
800	•400	· 560	•440	•540	.715	•615	·58o	∙640	•450	-615
o	•030	·060	-040	·065	• 100	.075	·065	·080	.045	-080
800	.415	·580	•440	.560	. 735	.635	•595	·66o	•455	-640
325	•465	.650	.490	.620		.705	.665		.510	· 725
350	.515	.715	.545	·68o	• • • •				.565	7-3
875	.570		.605	. 760	• • • •				.625	
400	· 630	• • • •	·670	••••	• • • •	• • • •	••••		.690	
o			. 105	•						
400	• • • •	••••	· 105 · 690	••••		• • •	••••	• • • •	• 105	
425	••••	••••	. 760	••••			• • • •	••••	•710	
BREAKING) RIGHT (in Founds).	520.	404.	510.	475	368 ·	430.	426.	391.	504 ·	401 •

TABLE XXVI.

TRANSVERSE STRAINS IN SPRUCE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of) Experiment.	31	32	83	84	35	36	37	38	8
DEPTH (in inches).	1.09	1.05	1.08	1.04	1.07	1.04	1.03	1.07	1.
BREADTH (in inches).	1.04	1.08	1.03	1.07	1.04	1.08	1.07	1.04	1.0
PRESSURE (in pounds).				Der	LECTION	(in inc	kes).		
0	•000	•000	.000	•000	•000	.000	.000	.000	· 00
25	.020	.025	•040	.025	.025	.030	.025	.025	.02
50	•040	.045	.075	•050	-050	·060	•045	.045	0.
75	·060	•070	.110	•070	.075	.090	.065	.070	·ot
100	∙080	.090	• 145	095	·ICO	120	-085	.090	•08
0	.000	.000	.000	.000	.000	.000	.000	•000	 • 00
100	∙080	•090	145	.095	•100	120	-085	•090	•08
125	•100	115	· 180	.115	•125	•145	•110	•115	•10
150	•125	•135	.215	•135	•150	•175	•135	•140	• 12
175	•145	• 155	•250	•155	• 170	•200	• 155	·160	• 14
200	• 165	• 175	285	•175	·190	•230	•175	.180	• 16
0	.000	.000	.010	•000	.010	.005	•005	•000	•00
200	• 165	175	-285	· 180	•190	.230	•175	·180	• 17
225	• 185	.200	.325	•200	.215	•265	• 195	• 200	• 19
250	.210	.225	370	•220	•240	•295	•220	•225	•21
275	•230	•245	.415	•245	•260	•330	• 240	•250	•23
300	•250	·265	• 465	•270	·285	• 370	•260	•270	• 25
0	· o o5	∙∞5	.045	.005	.010	.025	.005	·005	•00
800	•250	.270	+75	·275	·285	•375	•260	·275	•25
325 3 50	•275	•295	•530	• 300	•310	.410	·285	•300	• 27
375	• 300	•320	·600 ·680	• 330	·335	.450	.310	.325	• 30
400	•330 •380	·350 ·390	• 760	·355 ·385	· 360 · 390	·495 ·540	·335 ·365	·355 ·395	· 32
0	·035	.030		·020	.020	·070	· 020	.025	.01
400	.390	·400		•395	.395	.570	.370	.410	• 35
425	·460	.440		.425	.430	.620	.100	.455	·38
450	• • • •	•495		.455	.460	·68o	.410		.14
475		• • • •		.505	• • • •		·485		• • •
500		••••	••••	.565	• • • •	• • • •	• • • •	• • • •	• • •
0			• • • •			• • • •			• • •
500	••••	• • • •	• • • •	••••	••••	• • • •		••••	•••
Breaking Weight (in pounds).	445.	487 -	400.	502 ·	470	465.	498.	441.	475

TABLE XXVII.

TRANSVERSE STRAINS IN SPRUCE.

LENGTH 1.6 FRET BETWEEN BEARINGS.

NUMBER OF EXPERIMENT.	41	42	43	44	45	46	47	48	49	50
DEPTH } (in inches).	1.52	1.55	1.56	1.56	1.56	1.55	1.55	1.56	1.55	1-57
Breadth (in inches).	1.09	1.10	1.06	1.10	1.10	1.09	1.08	1.10	1.10	1.09
Pressure (in pounds).	•			Def	LECTION	(in inc	kes).			
0	•000	•000	•000	•000	•000	.000	•000	.000	.000	•000
25	.010	•010	•010	•010	•010	•010	•010	.010	.005	•005
50	-020	•020	.020	.015	•020	.020	•020	.015	•010	•010
75	.025	•030	.025	.025	-030	.025	•030	.025	•020	.020
100	.035	•040	•035	.035	•035	·035	•035	•030	.025	.025
0	•000	•000	.000	.000	.000	.000	•000	.000	•000	.000
100	.035	.040	.035	•035	.035	.035	•035	•030	.025	.025
125	.045	•050	.045	•040	.045	.015	•010	.035	.030	.035
150	.050	•060	.055	· o 50	.055	.050	•050	•040	•040	•040
175	•060	•070	•065	·060	-065	•060	•055	.050	•045	.045
200	·065	•075	.070	•065	.070	-065	·065	.055	•055	.055
0	.000	.000	•000	•000	•000	-000	•000	•000	.000	.000
200	·065	.075	•070	•065	•070	·065	•065	.055	.055	.055
225	•070	·085	∙080	•075	·080	.070	.070	·065	• 060	•060
250	·080	•095	.090	·085	.090	·080	·080	•070	-065	.065
275	•090	•100	•100	•090	.095	·085	•090	.075	.075	.075
800	-100	-110	.110	.095	105	.090	•095	·085	·080	· 080
0	.000	•000	.000	.000	•000	•000	.000	•000	•000	•000
300	•100	•110	•110	.095	• 105	• 090	.095	·085	·080	•080
325	• 105	•115	• 120	• 105	-115	• 100	• 100	.090	·085	∙085
350	•115	•120	•130	•115	·125	• 105	•110	• 100	.000	•095
375	• 120	•130	.140	• 125	• 130	.110	•120	· 105	•100	•100
400	• 125	•140	•150	• 135	• 140	•120	·125	.110	- 105	-110
0	.000	•000	.005	•000	•000	.000	•000	.000	.000	.000
400	125	140	-150	-135	- 140	• 120	• 125	·110	• 105	•110
425	•135	150	. 160	•140	• 145	125	130	· 120	.110	· I 20
450	•145	·160	• 170	• 145	·155	•135	140	·125	• 120	· 125
475	• 150	165	• 180	• 155	- 165	• 140	•150	•130	•125	• 130
500	• 160	•175	•190	• 165	•175	• 150	•155	• 140	130	• 135
o	.005	.000	•010	.000	.000	.000	.000	.000	·000	.000
500	.160	•175	• 190	• 165	•175	-150	-155	• 140	•130	-135
525	170	· 180	· 205	• 170	185	.155	· 160	• 145	-140	• 145
550	175	•190	.215	· 180	• 195	•160	·170	150	145	• 155
575	185	•200	.225	· 185	· 2 05	170	· 180	· 160	150	· 160
	• 190	.210	.240	•195	.215	·180	185	170	• 160	· 170

TABLE XXVII.—(Continued.)

TRANSVERSE STRAINS IN SPRUCE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of) Experiment.	41	42	43	44	45	46	47	48	49	50
Depth { (in inches). }	1.52	1.55	1.56	1.56	1.56	1.55	1.55	1.56	1.55	1.5
BREADTH (in inches).	1.09	1 · 10	1.06	1.10	1.10	1.09	1.08	1 · 10	01.1	1.0
Pressure (in pounds).			,	Dry	LECTION	(in incl	ies).	•		
0	•005	.005	·015	-005	·005	•005	-005	·005	-000	.0
600	• 190	.210	.240	.195	.215	180	185	• 170	• 160	1 - 1
625	195	.215	.250	.205	.225	• 185	.195	.175	170	• 1
650	· 2 05	·225	· 2 65	.215	•235	•195	-200	- 185	•175	1.1
675	-215	•230	·275	•220	·245	•200	·210	190	· 180	1 .1
700	·225	•240	·290	•230	.255	·210	•220	• 200	190	.1
0	.005	.005	.025	•010	•010	.005	•005	.005	•005	.0
700	.225	.240	•290	•230	.255	•210	•220	.200	•190	1.1
725	.235	.250	.305	.240	. 265	.220	· 23 0	.210	• 200	.2
750	•245	· 260	•320	•245	·275	·230	•240	· 220	•210	1 .2
775	.255	· 2 65	•335	.255	•290	•240	·250	·230	• 220	.2
800	· 2 65	·275	.350	• 265	.305	·250	·255	.240	•230	.3
0	•010	·oio	.040	.010	.025	.010	.010	.015	· 0 10	.0
800	• 265	·275	.350	.275	.310	•250	·255	.240	.230	• 2
825	·275	· 2 \$5	• 370	.285	•330	•260	· 2 65	.250	.240	.2
850	·285	. 295	• 385	.295	345	.270	·275	· 2 60	.255	•2
875	• 300	.305	.405	.310	• 365	·28o	-285	.275	•270	1
900	.310	.315	+420	• 320	•405	•290	· 2 95	·290	- 290	.2
0	.020	.020	-060	.025		.025	.020	•030	-025	.0
900	.315	.320	.430	.325		. 295	.295	.295	.295	. 2
925	· 365	•330	·460	• 340		.310	•310	.310	.315	•2
950		345		•355		• 325	• 320	• 325	•340	1 - 3
975		• 360		.370	• • • ·	•340	•335	• 345	.470	
1000		• 370	••••	.385	• • • •	• 365	•350	• 365	••••	• 3
0		.030		.045		•050	.030	·c60		.0
1000		.380		395		375	.355	.400		. 3
1025		.390				.400	•375	.450		1.3
1050		.405				•430	.400			.3
1075				• • • •		••••	• • • •	• • • •		· • 1
Breaking Weight (in pounds).	950.	1074	926.	1001	900.	1067	1071 -	1028	977	10

TABLE XXVIII.

TRANSVERSE STRAINS IN SPRUCE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

DEPTH (in inches). } 2 Breadth (in inches). } I Pressure (in jounds).	51 2·01 1·08 000 015 025 035	2·00 1·08	1.99 1.08	I·99 I·08 DEF	2.02 1.08	1.99 1.06	1·98 1·08	2·01 1·09	2·01 1·07	60 2·02 I·09
(in inches). } Breadth (in inches). } Pressure (in founds).	000 015 025 035	·000	.000	I-08	1.08	1.06	1.08			
O 50 100	000 015 025 035	·000 ·015	.000	DEF				1.09	1.07	1.09
0 50	015 025 035	·015			LECTION	(in inc	kes).			
50 100	015 025 035	·015		000						
50 100	025		.010		•000	•000	•000	.000	•000	•000
100	035	·025		.010	•010	.010	•010	.010	.015	.005
150	1		.020	.015	•020	·020	.020	.020	.025	.015
	A 4 A . !	·035	-030	·025	.025	·025	.025	·025	.035	·020
200	040	.045	·035	•030	•035	030	.035	·035	.045	.030
0 1.	000	•000	.000	.000	.000	.000	.000	•000	.000	.000
-	040	.045	· 035	·030	· 035	.030	.035	.035	.045	.030
•	050	.055	.045	.040	045	.035	.040	.010	.055	.010
	060	.065	.050	.050	.055	.045	.050	.045	.070	.050
350	070	.075	·060	.055	•065	.050	.055	·055	· 080	.055
400	O75	∙085	.065	.065	.070	∙060	.065	·ofo	.090	•065
0 .	000	•000	.000	.000	.000	.000	.000	.000	.000	.000
	075	·085	•065	· o 65	070	∙060	·065	∙060	•090	.065
	080	.095	•070	.070	·080	-065	•070	•070	•100	•070
1	090	105	·080	·080	.090	.070	·080	.075	.110	-080
	100	-115	.090	·085	.100	·080	·085	·080	·120	.090
600	110	125	.095	.095	.110	·085	•095	.090	•130	.100
	000	-005	.000	.000	.000	•000	.000	.000	·005	.000
	110	125	.095	.095	.110	∙085	.095	•090	135	•100
	120	-135	105	100	•115	·090	· 100	.095	140	.110
700	130	•145	110	110	125	• 100	· 105	• 105	• 150	·115
	135	·155	• 120	115	• 135	105	.115	•110	· 160	·125
800	145	-165	· 125	125	-145	•115	125	• 120	· 175	-135
0	005	•010	.005	.000	.005	•000	∙∞5	-005	.010	· 0 05
i i	145	165	·125	125	•145	-115	125	120	175	•135
	155	• 175	• 135	• 130	•155	120	•130	125	185	•140
	165	• 185	• 140	140	• 165	•130	140	•130	195	• 150
_	175	•195	• 150	• 145	•175	• 135	• 145	.140	.210	• 160
1000	185	.210	160	• 155	· t85	• 145	• 155	• 145	·225	•170

TABLE XXVIII.—(Continued.)

TRANSVERSE STRAINS IN SPRUCE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of Experi-	51	52	58	54	55	56	57	58	59	60
DEPTH (in inches).	2.01	2.00	1.99	1.99	2.02	1.99	1.98	2.01	2.01	2.02
Breadth (in inches).	1.08	1.08	1.08	1.08	1.08	1.06	1.08	1.09	1.07	1.09
Pressure (in founds).				Der	LECTION	(in inc	kes).			
0	.010	.015	.005	.005	.010	.000	.010	.010	:015	.010
1000	- 190	.210	• 160	. 155	•190	•145	•155	•145	:225	170
1050	.200	.225	• 165	.160	200	·150	•160	150	-235	· 180
1100	·210	.240	175	170	·210	. 160	• 170	- 160	.250	• 195
1150	· 23 0	.255	• 185	· 180	· 220	• 165	175	•170	.270	-205
1200	· 2 45	· 270	195	.190	•235	•175	185	• 175	· 285	-215
0	.030	.025	.010	.010	.025	.010	.010	.010	.030	.020
1200	· 2 50	· 275	195	• 190	•240	180	• 185	175	1.28 5	-220
1250	270	· 29 0	· 2 05	•200	.255	.190	•195	· 185	•300	•230
1300	•295	· 305	.215	.210	.270	• 200	•205	•195	.320	.245
1350	.325	. 325	•230	.220	·285	.210	.215	•205	•345	·260
1400	· 36 0	• 355	•240	•235	• 305	•220	.225	·215	• 365	•275
0	070	060	•020	.020	.040	· 020	.020	.020	.055	.030
1400	• 375	.370	· 245	.235	310	.220	· 2 30	.215	•370	•280
1450	•415	·400	· 2 55	•250	• 330	·235	• 240	· 2 30	•390	•295
1500	· · · ·	430	· 270	·265	•355	•250	·255	.245	.412	• 320
1550			· 29 0	·280		·265	·275	•260	• • • •	•350
1600	••••		.315	• 305	••••	-285	· 2 95	·28o	••••	•380-
			.055	•040		•040	040	-040	••••	070-
1600			• 330	.310	• • • •	.290	· 300	•290		
1650		1	•375	•335		•310	• 325	•310		
1700				•375	••••	• • • •		•335		
1750	• • • •	••••		•••	• • • •	• • • •	• • • •	•370		
Breaking Weight (in pounds).	1472	1536	1675	1717.	1519.	1653.	168 6 ·	1800-	1545	1600

TABLE XXIX.

TRANSVERSE STRAINS IN WHITE PINE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of Experiment.	61	62	63	64	65	66	67	68	69
DEPTH (in inches).	1.02	.99	.99	1.03	1.02	-99	.99	1.00	-99
BREADTH (in inches).	1.00	I · 02	1.02	1.00	1.01	1.01	1.01	.99	1.0
Pressure (in pounds).				Deflect	mon (in	inches).			
0	.000	•000	-000	.000	.000	•000	• 000	-000	•000
25	•035	•030	-010	.030	:035	•040	•030	.035	•030
50	.070	∙060	.075	∙060	.070	·080	·065	.065	.06
75	.100	· 0 95	•115	•090	• 100	•115	•095	.095	.09
100	•130	•125	150	·120	•130	•150	•130	•125	• 125
0	.000	.000	•000	.000	.000	.000	000	•000	.000
100	•130	• 125	•150	120	•130	150	130	.125	.125
125	160	•155	• 185	•150	· 165	• 185	160	- 160	. 155
150	•190	- 185	•220	· 180	• 195	-220	•190	190	- 185
175	• 220	.215	• 260	.210	· 230	•250	•220	.225	.215
200	•250	·245	•295	• 240	· 2 60	·285	· 2 50	•255	•245
0	-005	•000	.005	.000	•000	.010	.000	•005	•000
200	•250	·250	· 2 95	•240	· 260	•290	·250	•255	•245
225	·280	•280	•335	.270	· 2 95	325	•285	.285	•280
250	•315	.310	• 380	· 300	•330	• 365	•320	• 320	• 310
275	•345	•345	. 425	•335	• 365	.410	•350	355	• 345
800	·380	•375	•470	• 365	•405	460	• 385	·385	•375
0	•010	.005		· o o5	•010	•030	.005	010	.010
800	.385	.380		•370	.410	·465	•385	•390	• 380
325	.430	.415		.405	·460	.520	•430	.425	.415
350	•485	.450		·440	•535	••••	• • • •	·465	•455
375	• • • •	.500	••••	• 540	• • • •	•••	••••	•535	•495
Breaking Weight (in pounds).	376.	385.	300.	382.	356.	350.	349	383.	399

TABLE XXX.

TRANSVERSE STRAINS IN WHITE PINE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of) Experiment.	70	71	72	73	74	75	76	77	78
Durth (in inches).	1.53	1.50	1.52	1.53	1.51	1.49	1.53	1.52	1.49
BRRADTH ((in inches).)	1.02	1.03	1.03	1.02	1.03	1.01	1.02	1.02	1.01
Pressure (in Amads).		•		Deflec	TION (in	inches).			
0	•000	.000	•000	.000	.000	.000	.000	•000	•000
25	·015	.010	•010	•015	•010	.015	010	.010	.010
40	.025	•020	· 02 0	.025	.020	.025	.020	.015	.020
75	.035	·0 3 0	·030	•035	·0 3 0	035	•030	.025	.030
100	-045	•035	.010	.045	•010	.045	010	.035	•040
•	•000	.000	.000	•000	•000	.000	•000	.000	.000
100	·045	.035	. 040	.045	-040	·045	•040	.035	.040
185	·055	.012	.050	.055	-050	.055	.045	.010	.050
130	· o 65	.050	•060	.065	.055	·c65	.055	-050	•060
173	.075	· o 6o	.070	· 0 75	∙065	.075	•065	•06 0	•070
300	·085	•070	·080	.090	.075	·085	•075	.070	·080
v	000	.000	.000	•000	.000	.000	.000	.000	•000
400	·085	070	• o 8o	090	•075	∙085	•075	•070	·080
995	.095	∙o8o	.090	.100	∙085	· 0 95	·080	·075	.090
440	• 105	•090	· 100	•110	· 0 95	-105	•090	∙085	·100
452	-115	•100	.110	120	105	-115	.100	.095	.110
300	125	· 105	· 120	• 130	.110	·125	• 105	105	125
•	•005	•000	•000	•000	•000	•000	.000	•000	.000
344	125	• 105	• 120	·130	•110	· 125	• 105	: 105	·125
257	135	.115	.130	.140	·120	· 135	.115	115	•135
370	.145	· 125	140	• 150	125	145	•125	·120	•145
337	155	135	•145	160	135	155	•135	•130	• 160
144	105	• 145	.155	· 170	· 145	· 165	•145	• 140	•170
•	.005	•005	∙∞5	·005	.000	.000	.000	.000	.000
144	105	• 145	•155	•170	·145	• 165	•145	•140	170
137	175	•150	. 165	•180	150	•175	•150	•145	·180
470	185	160	•175	190	.160	.185	•160	• 155	.130
417	. 102	•170	· 185	200	170	195	170	•165	•200
744	8/14	180	195	.210	·180	·205	•175	•175	·210

TABLE XXX.—(Continued.)

TRANSVERSE STRAINS IN WHITE PINE.

LENGTH 1.6 FRET BETWEEN BEARINGS.

MENT.)	70	71	72	73	74	75	76	77	78
DEPTH (in inches).	1.53	1.50	1.52	1.53	1.51	1.49	1.53	1.52	1.49
BREADTH (in inches).	I · 02	1.03	1.03	1.02	1.03	1.01	I · 02	1.02	1:01
PRESSURE (in pounds).				DEFLEC	TION (in	inches).			
0	·005	·005	•005	•005	.000	•005	.000	·005	.000
500	.205	• 180	•195	.215	· 180	.205	-175	175	•210
525	.215	•190	•205	•225	.190	•220	• 185	•185	.225
550	.225	•200	.215	•235	•200	•230	•195	•195	• 235
575 600	•235	•210	.225	•250	.210	•240	•205	• 205	• 250
60 0	• 245	•220	•235	•260	.220	.250	.215	•215	• 260
0	•005	.005	•010	•010	.005	-010	-005	-005	•005
600	·245	•220	•235	• 260	.225	.255	.215	•215	•260
625	· 26 0	·230	·245	.275	.235	.265	.225	.225	.270
650	.275	.240	.255	•290	.245	•280	.235	.235	·285
675	•290	.250	•265	.305	.255	- 295	.245	.245	.300
. 700	•305	· 260	· 2 75	·325	· 265	.310	•255	.255	• 320
o	•020	•010	•010	-025	•010	•020	.005	.005	·OTE
700	•315	·265	.275	•335	·265	.315	•260	·255	·320
725	•345	.275	.290		•275	•335	.275	·265	•340
750	•445	.290	.300		.285	.355	•285	.280	.365
775		•310	.315		.305	.375	.300	· 2 95	
800	• • •	•330	•335	••••	·325	• 395	• 320	.315	
o		.030	.020		.020	•040	·025	.025	
800		•340	•340		.335	·405	.325	.320	
825			•365		.355	•430	.355	•340	
850			.390		•380	•455	•390	•355	
875			•465			• • • •	• • • •	•375	•
900	••••	• • • • •	• • • •	• • • •	•••	• • • •	••••	•400	
o								•045	
900								·410	
925	• • • •	••••	••••	• • • •	••••	••••	••••	•450	
Breaking) Weight (in)	753	824 ·	877 ·	720	874 ·	854.	869 ·	947	773

TABLE XXXI.

TRANSVERSE STRAINS IN WHITE PINE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

									
Share	79	80	81	82	88	84	85	86	87
ibered !	2· 11	3.10	2.05	2.09	2.09	2.08	2.06	2.09	2 · I
Manager !	1.01	1.01	1 03	1.03	1.03	1.03	1 · 04	1.03	1.0
a noming.				DEFLEC	rion (in	inches).		· 	
48	.000	•000	•000	.000	•000	•000	•000	.000	-00
•	.010	.010	.015	.015	.010	.015	.010	•010•	.01
144	.020	.020	025	.025	.020	.030	•020	•020	.02
1 in	-030	•030	.010	•035	.030	•040	.030	·030	•03
***	. 433	•ထုံဝ	.050	.010	·035	•050	·oto	·oto	•01
•	.005	•000	.005	•005	· o o5	•005	.000	•000	•00
***	.033	·oto	· o 50	.010	•035	•050	•040	.010	•04
dus.	WS	·045	•060	•050	.045	•060	·045	•050	.05
·ww	.143	.055	.070	.055	.055	•070	·055	•060	.05
tion.	· UOU	•060	·080	∙065	· 060	·080	•065	•065	•06
***	.630	•070	.090	•075	•070	.090	•070	•075	•07
•	wo	.005	·010	•010	·010	.010	.005	.005	.01
***	474	·070	•090	•075	•070	•090	•070	.075	.07
414	. 45.4	•080	.100	∙080	·075	.100	·080	·080	·08
***	144	∙085	.110	•090	∙085	•110	.090	•090	•08
wheth	10%	·095	•120	.095	-090	· 120	• 100	• 100	.09
***	. 81.14	· 100	· 130	105	• 100	•130	•110	•110	•10
•	443	010	.015	.015	.015	•020	.010	.010	.01
***	. 104	.100	• 130	•105	•100	•130	•110	·110	• 10
444	1110	110	.140	115	•110	140	•120	•120	• I I
144	1141	.115	. 155	· 125	•120	•150	•130	• 130	• 11
M	114	125	• 165	•135	•130	•160	• 140	140	· J 2
144	. 1'64	•130	•175	• 145	• 135	•170	•150	• 150	• 13

TABLE XXXI.—(Continued.)

TRANSVERSE STRAINS IN WHITE PINE.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of) Experi- MENT.	79	80	81	82	83	84	85	86	87
DEPTH ((in inches).	2.11	2.10	2.05	2.09	2.09	2.08	2.06	2.09	2.11
Breadth (in inches).	1.04	1.04	1.03	1.03	1.03	1.03	1.01	1.03	1.03
Pressure (in pounds).				Deflect	TON (in	inches).			
0	•020	·015	•020	.020	.020	.030	.015	.015	.020
800	•135	• 130	• 175	•145	· 135	•170	• 150	.150	135
850	. 140	140	· 190	•150	•145	·180	• 160	·160	-140
900	· 150	• 145	•200	•160	•150	•195	• 170	170	•150
950	• 155	•155	.215	•170	· 160	·205	·180	· 180	• 155
1000	• 165	• 160	•230	· 185	•170	•220	•190	•190	•165
0	•025	.020	·035	.025	.025	·035	·020	•025	.025
1000	• 165	• 160	•235	-185	•170	•220	•190	•195	•165
1050	• 175	•170	•250	• 195	·180	•235	•200	•205	175
1100	· 180	·180	•275	•205	•190	•250	.215	•215	185
1150	•185	•190		•220	•200	•270	·235	•230	•195
1200	•195	•200	• • • •	.240	•210	•295	•255	•245	•205
0	•030	•025		.045	· o 30	·060	·035	•040	.035
1200	• 205	•200	• • • •	•245	·210	•310	· 265	•255	210
1250	•210	•210	• • • •	•270	•220	•340	•285	·275	•220
1300	· 220	•220	• • • •	· 30 5	•230	• • • •	.310	•335	•230
1350	·230	•230	• • • •	• 390	•245	• • • •	• • • •	• • • •	•245
1400	•240	•240	••••	• • • •	•260	••••	• • • •	••••	•260
0	•040	•030			-045			l	.055
1400	•245	•245			•270		• • • •		·265
1450	· 260	•260	• • • •		.300		• • • •		.290
1500	·285	· 280			••••		• • • •	• • • •	.315
1550	.315			• • • •	• • • •		••••		• 360
1600	•355								
Breaking) Weight (in) pounds).	1629.	1536.	1150.	i383·	1500	1280•	1349	1303.	1553

HITE PINE.

BEARINGS.

. 705.

		152	288		284	285	286
	•-	×2	· 503		.748	1 •746	747
	.•	:00	1.000		11070	11170	1.00
		ECTI		PRESSURE (in pounds).	Die (i)	FLECTI V inche	юн %),
		י ו ככי		.0	·0~0	~∞	·
			000	10 20	11.7	·(KK)	٠ د ۲
		•021 •032	·018 ·027	30	·014	1027	·014
	_	• 4-2	C-35	4ŏ	•02,	1027	•
,	- :	يرن. ا	-044	50	٠٠٤٠,	.042	
	•	0,5	053	60	***+3	•054	.045
•	٠.	072	0/.2	70 80	050		
:	<u>.</u> .	د ۱۰۰۰ ۱۳۰۵	·071	90	1. 57 1. 04	*(72	
•	• ; : 5	103	-028	100	1072	·(~1	- •024 : •04
	:4	-114	1000	110	•079	ر برد ۰۰	
•	. 3	.125	105	120	150+	+18	
•	1.0	•	114	130	"73		
· •	15	· 147 · 157	· 123 · 13 2	140 150	· 100	· 127 · 136	1.13
	: 15	1 - : 67	- 141	160	-114	-140	.11
	1 1145	173	150	170	121	155	127
	: 4	11/2	15)	180	·125	1/15	133
• •	1 13 172	•210) •11)	163 -176	190 200	135	·1-6	
	. : - : 1	· 221	- 185	210	145	. \$50	· 161
	-1,1	232	194	220	115%	.513	171
	•2 >>	244	- 203	230	174	. 2 -	. 151
i f	1:20	256 215	225	240 250	17)	-47	* I , 5
4	220	zės i	237	260	1.0		2 <u>: 3</u>
1	230	1204	250	270	- 1-74		
	1 244	, , ,	. 27.2	280 290	2.4		
4	•25% •26%	3.23	277	300	·2003		
4	2-3	3*4	317	310	-278		
•	288	•373		320 330	• 2 ; ,		
ŕ	20) 310	ı j	1	310	·251		
()	321			- - - - - - - - - -	- 3		
4	132	1					
•	344	·					
6	1357	:	ľ		,		
ö	-387	i					
		t	\		i i		
	-			<u>-</u>		. •	
	550						

TABLE XXXIII.

TRANSVERSE STRAINS IN HEMLOCK.

LENGTH 1.6 FEET BETWEEN BEARINGS.

NUMBER OF Experi-	88	89	90	91	92	93	94	95	96
MENT.									
Depth (in inches).	1.07	1 · 08	1 07	1.07	1.09	1.10	1.09	80 1	1.11
Breadth (in inches).	1.07	1 00	1.09	1.06	1 05	1.06	1.07	1.08	1.09
Pressure (in pounds).				DEFLEC	rion (<i>in</i>	inches).	•		
0	•000	.000	.000	.000	.000	•000	•000	•000	•000
25	•050	.050	.030	.025	•035	.025	•040	.035	•040
50	•000	· 085	- 060	050	.070	.050	•080	.065	.07
75	· 120	.125	.090	.075	. 100	.070	• 120	.095	•110
100	- 150	- 165	•115	. 105	• 135	•095	• 160	· 125	. 14
0	•010	.005	.005	000	.000	.005	.000	.000	.000
100	· 160	.165	· 120	· 105	.140	.095	• 160	• 125	• 14
125	. 190	:210	150	130	•170	•120	· 200	.155	• 18
150	.225	•250	• 185	· 160	• 200	• 140	•240	• 185	.220
175	265	•295	215	•190	•230	• 165	·285	• 220	•260
200	300	· 340	•245	• 220	- 260	· 190	•330	• 250	•30
0	010	.015	-005	.000	.005	.005	.010	.005	.016
200	- 305	.345	.250	.220	· 265	185	•330	.250	.30
225	•340	·400	· 285	-250	.305	.210	· 380	· 285	• 340
250	· 380	•455	.315	·280	• · • •	•235	•430	• • • •	•38
275	•420	.510	•350	.310	• • • •	• 260	·480		•430
300	•••		·395	345		•285	•540	• • • •	•47
0			025	005		•010	•045		•040
300			-400	-350		•285	•570		.49
325		• • • •	• • • •	- 390		•315	• • • •	• • • •	•54
350	• • • •	• • • •		•••		•350			
375			• • • •	•••		•385			
400			•••	• • • •	•••	•445			
0						•045			
400						•465			
425			••••			. 530			
Breaking Veight (in pounds).	292 ·	277 ·	324	350	234 ·	433	313.	238	348

TABLE XXXIV.

TRANSVERSE STRAINS IN HEMLOCK.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of Experi- ment.	97	98	99	100	101	102	103	104	105	
DEPTH (in inches).	1.56	1.60	1.60	1.59	1.56	1.60	1.54	1.54	1.58	
Breadth (in inches).	1.04	1.06	1.07	1.03	1.01	1.08	1.09	1.11	1.08	
Pressure (in pounds).				Defi	ECTION	(in inc)	tes).			
0	•000	.000	.000	.000	.000	.000	•000	.000	.000	
25	•QIO	·oro	.010	.015	.010	•015	.015	.015	.010	
50	•020	.025	.025	.030	-015	•030	•030	.030	.025	l
75	•030	.035	.035	.010	.025	.045	.045	•045	.040	l
100	.040	•050	•050	·055	·035	·060	•060	· 0 55	•055	
0	.000	.000	.000	.000	.000	•000	•000	•000	.000	
100	.010	·050	·050	•055	.035	∙060	•060	.055	-055	
195	.045	•06o	•060	.065	•045	.075	.075	.070	.070	l
150	.055	.075	.070	·080	.055	•090	•090	·085	·085	I
175	.065	· 085	080	.000	·065	. 105	105	.100	•100	١
900	.070	.095	•090	. 105	.075	•115	125	-115	•115	١
0	,000	•000	.000	.000	.000	.000	000	.000	•000	l
900	.070	.095	.090	. 105	.075	.115	125	.115	.115	I
995	·080	105	· 105	1115	.080	•130	• 140	• 130	•130	l
450	.085	.115	· I 20	130	•090	•145	.155	.145	140	I
475	·(x)5	•130	•130	.145	·095	•160	.170	•160	.155	ļ
300	- 100	•140	.140	- 160	105	•175	• 185	•175	•170	
•	1005	•000	.005	•000	.000	•005	·005	•000	•000	
300	100	•140	•145	.160	. 105	.175	.190	.175	.170	
345	.110	.155	·155	.175	1115	190	.205	.190	185	
950	120	•170	.170	190	.125	.210	.225	.205	.200	
375	. 125	•180	180	.205	.135	.225	.240	.220	.215	
100	135	•190	•190	.220	• 145	240	•260	.235	.230	

TABLE XXXIV.—(Continued.)

TRANSVERSE STRAINS IN HEMLOCK.

LENGTH 1.6 FEET BETWEEN BEARINGS.

									_	
Number of } Experiment.	97	98	99	100	101	102	108	104	105	106
DEPTH (in inches).	1 · 56	1.60	1.60	1.59	1.56	1.60	1.54	1.54	1.58	1.58
BREADTH (in inches).	1.04	1.06	1.07	1.03	1.01	1.08	1.09	1.11	1.08	1.09
PRESSURE (in jounds).				Dre	LECTION	(in inc	kes).	,		
0	·005	•000	.010	•005	•005	.015	.015	•010	.010	.000
400	•135	•190	•190	•220	• 145	·240	.265	·235	· 23 0	•200
425	•145	.205	·205	•240	.150	•255	.285	.255	•250	.215
450	•150	•220	•220	•255	.160	• 275	.305	•270	• 265	•230
475	•160	•230	·230	.270	170	·290 ·310	.325	·285	· 285	•240
500	-170	•240	•245	· 2 95	• 175	310	• 345	.305	• 305	•255
o	·005	.010	.015	.020	•010	.025	.030	.020	•020	.010
600	.170	·245	.245	•300	· 180	.315	.355	.310	.305	•255
525	· 180	· 260	•260	•340	• 190	.335	•380	•330	.325	· 27 0
5 50	·185	· 275	.275		.200	.355	.405	•350	•345	.285
575	195	• 300	•290		.210	· 380	•430	•370	. 365	• 300
€00	•205	••••	• 305	••••	•220	·400	·460	••••	-385	.315
0	•010		.025		.015	•045	•060	• • • •	•030	·0 20
600	•205	• • • •	.310	• • • •	.225	•405	•470	• • • •	• 390	• 320
625	.215	••••	.325	• • • •	•235	.435	•500	• • • •	•415	· 335
650	•225	••••	• 340	• • • •	• 245	•465	• • • •	• • • •	•435	•350
675	•240	• • • •	· 360	••••	• 265	• • • •	• • • •	• • • •	•460	.370
700	•260	• • • •	•380	• • • •	·290		• • • •	• • • •	••••	- 385
0	•020				.030			,		.035
700	•260				. 305					.390
725	·280				•345		• • • •		••••	.405
750	•295							• • • •		.425
775	·360	••••	••••			•••	••••	• • • •	••••	•450
BREAKING) WEIGHT (in Founds).	777	575·	700.	548.	727.	651.	650.	600.	687.	800 •

TABLE XXXV.

TRANSVERSE STRAINS IN HEMLOCK.

LENGTH 1.6 FEET BETWEEN BEARINGS.

Number of) Experi- MENT.	107	108	109	110	111	112	113	114	115
DEPTH } (in inches).	2.02	2.02	2.00	2.03	3.01	3.01	1.99	2.00	2.03
Breadth { (in inches). }	1.03	1.05	1.03	1.04	1.05	1.04	1.03	1.03	1.05
Pressure (in pounds).				DEFLEC	TION (is	inches).			
0	•000	.000	.000	•000	•000	.000	.000	.000	•000
50	.015	.010	.010	.010	.015	.015	.030	.010	-010
100	.025	.030	.020	.020	.025	.030	.030	.020	.025
150 200	·035 ·045	·035 ·045	·030 ·045	·050	·03 5 ·045	·045 ·05 5	·045 ·055	·035 ·045	.032
0	.000	.000	• • • • • • • • • • • • • • • • • • • •	.000	•000	.000	∙‱	.000	.000
200	.045	•045	.045	.050	.045	.055	·05 5	•045	.042
250	•055	000	.055	-065	.055	•065	·065	·055	.055
300 350	·065	•070 •035	·005	.075	·070 ·085	·075 ·085	· 075 · 090	·065 ·075	- 065
400	·075 ·085	.035	·075 ·085	.100	.002	.005	100	.090	·075 ·085
400	.005	.000	.005	.005	.005	•005	•000	.000	.000
400 450	· 085	.005	·085	100	.095	·095	·100	·090 ·100	·085
500	•095 • 105	· 105 · 120	095 • 105	·115 ·130	· 105 · 120	·105 ·115	.120	110	1100
550	115	.130	.115	.145	. 135	125	130	•120	120
600	.125	145	125	155	145	.135	140	.130	-130
0	.005	.005	•∞5	-∞5	•∞5	· o o5	· o o5	•005	-005
600	.125	.145	.125	.122	145	• 135	-140	. 130	· 130
650	• 135	•160	.135	170	• 160	.145	•150	140	140
700 750	·145 ·160	·170 ·185	·150 ·165	· 185 · 200	•170	·155	· 165	·155 ·165	· 150
800	170	.200	.175	220	· 185 · 205	· 165 · 175	·175 ·190	· 180	-180
0	•010	.005	.005	.010	-005	•010	.010	.005	•010
800	170	.200	175	•220	. 205	175	.190	• 180	•180
850 900	· 185 · 200	·215 ·230	.185	·240 ·260	.225	· 185 · 195	·200 ·215	• 190 • 205	· 195 · 210
950	.215	•250	·195	.285	·245 ·265	.210	.235	.215	.225
1000	.330	· 2 75	. 220		.305	.330	.300	••••	.320
1000	.025	.025	.010		.025	.015	.025	••••	.020
1000 1050	·240	·280 ·315	.235	••••	.310	·220 ·235	.270	••••	·255 ·280
1100	·255 ·280	• 370	·240 ·260		• • • •	-33	••••		
1150	.320		.290						
Breaking)		<u> </u>	' <u></u>	<u>' </u>					
WEIGHT (in >	1154.	1111.	1181.	991.	1049	1099	1036.	985.	1075

TABLE XXXVI.

TENSILE STRAINS IN GEORGIA PINE.

See Arts. 704 and 706.

Number of Experiment.	116	117	118	119	120	121	122	123	124
DIAMETER (in inches).	.355	·355	.350	•355	•355	•345	•345	.355	·365
Breaking) Weight (in) Jounds).	2005	Less than 1600.	Less than 1300	2152.	1400.	1924 ·	1091	1306	1268 •

TENSILE STRAINS IN LOCUST.

Number of) Experiment.	125	126	127	128	129	130	181	132	133
DIAMETER (in inches).	•355	·345	.305	.305	•300	• 300	· 300	· 300	.300
Breaking) Weight (in) pounds).	1137-	2265 ·	More than 2400 ·	1592	2074	1561 -	2131.	1799	2395

TENSILE STRAINS IN WHITE OAK.

Number of Experiment.	134	135	136	137	138	139	140	141	142
DIAMETER } (in inches).	•355	.365	•345	•355	. 305	· 300	.305	• 300	•300
Breaking) Weight (in) pounds).	1908	1303	1182.	2375·	1700	1442•	1003	1319.	2205

TABLE XXXVII.

TENSILE STRAINS IN SPRUCE.

See Arts. 704 and 706.

Number of Experiment.	143	144	145	146	147	148	149	150	151
DIAMETER (in inches).	•305	.305	-300	•305	.305	• 305	•355	-365	•360
Breaking) Weight (in) pounds).	1573.	1402 ·	1560-	1368	1385 ·	1533	1882•	2078	1600•

TENSILE STRAINS IN WHITE PINE.

Number of Experiment.	152	153	154	155	156	157	158	159	16
DIAMETER (in inches).	.395	·365	•365	· 360	·365	355	.350	• 365	• 36
Breaking) Weight (in) pounds).	1363.	1157.	1127.	1316	1431 ·	1487.	1192.	1024	1400

TENSILE STRAINS IN HEMLOCK.

Number of Experiment.	161	162	163	164	165	166	167	168	168
Diameter \ (in inches).	•365	•355	•345	•360	•355	•355	.350	•335	·35
Breaking) Weight (in) pounds).	645 ·	897 ·	864.	999.	863.	726.	895.	809.	977 —

TABLE XXXVIII.

SLIDING STRAINS IN GEORGIA PINE.

See Arts. 704 and 706.

Number of Experi- ment.	170	171	172	173	174	175	176	177	178
Diameter (in inches).	} .525	.520	•530	•530	•520	•520	·525	.520	.530
LENGTH (in inches).	1 .065	Broke in two.	1.020	1.010	Broke in two.	1.040	1.020	1.015	1 .050
Breaking Weight (in pounds).	1546.	1295	1411.	1571 ·	1281 ·	1347	1520	1401 -	1247

SLIDING STRAINS IN LOCUST.

Number of Experiment.	179	180	181	182	183	184	185	186	187
DIAMETER (in inches).	•530	•530	•535	.525	• 525	.530	•535	•525	. 525
LENGTH (in inches).	735	•730	-715	•745	Broke in two.	· 760	·730	-715	• 760
Breaking Weight (in founds).	1490•	1236.	1533.	1192	1492 ·	1758-	1403.	1331.	1483

SLIDING STRAINS IN WHITE OAK.

Number of Experi- ment.	}	188	189	190	191	192	193	194	195	196
DIAMETER (in inches).	}	•530	•525	•535	.540	•535	.530	•530	•535	•530
LENGTH (in inches).	}	•730	•755	•740	•750	•750	•740	.725	•725	•730
Breaking Weight (in pounds).	}	1308	1801 -	1834 ·	1502	1701 ·	1359.	1667.	1321 •	1399

. TABLE XXXIX.

SLIDING STRAINS IN SPRUCE.

See Arts. 704 and 706.

NUMBER OF EXPERI-	197	198	199	KOO	201	202	208	204	205
Diameter i (in inches).	.565	-535	·550	-525	-550	-550	-545	-550	-550
Lungth i (in inches).	1.010	-990	1.010	1.010	1.030	I-020	1-005	1.010	1990
BREAKING WRIGHT (in founds).	988.	770-	t130+	882-	927 ·	976•	1043-	838-	902-

SLIDING STRAINS IN WHITE PINE.

NUMBER OF EXPERI- MENT,	206	207	208	209	210	211	BXW	918	214
Diameter (in inches).	-540	-545	-555	-545	•545	1545	-550	-545	-54
Langth (in inches).	-995	1.000	-990	1.010	1.025	1.005	1.010	1-040	-99
BREAKING WEIGHT (in founds).	730-	907	792.	803.	842+	8co-	881 -	852-	585

SLIDING STRAINS IN HEMLOCK.

	-		_	-					
NUMBER OF EXPERI-	215	218	917	KXX	219	330	221	222	223
Diameter }	-540	-540	-545	-540	•530	•540	-540	- 535	-536
Length) (in inches).	1995	1.010	1995	Broke ia two.	1.025	1.015	-995	1-010	-990
BREAKING } WRIGHT (fin founds). }	607	702.	620-	796-	700-	674-	556-	627-	530-

TABLE XL.

CRUSHING STRAINS IN GEORGIA PINE.

See Arts. 704 and 707.

Number of Experi- ment.	}	224	225	226	227	228	229	230	231	232
DIAMETER (in inches).	}	-515	.515	•520	.520	.505	.515	.510	.500	.515
LENGTH (in inches).	}	1.035	1.025	1.040	1.035	1.035	• 505	•515	•505	-510
Breaking Weight (in pounds).	}	2010-	1878 ·	2061 ·	1735	2304	2002	1845 •	1705.	2141

CRUSHING STRAINS IN LOCUST.

Number of Experi- ment.	283	234	235	236	237	238	239	240	241
DIAMETER (in inches).	} .520	.520	.520	.525	.530	.520	.525	.515	• 520
Length (in inches).	1.055	1.020	1.035	1.045	-490	.515	∙5∞	•490	•495
Breaking Weight (in pounds).	2338	2391 ·	2547	2539.	2695 ·	2500	2495	2374	2672

CRUSHING STRAINS IN WHITE OAK.

Number of Experi- ment.	242	243	244	245	246	247	248	249	250
DIAMETER (in inches).	.525	-530	•520	-530	• 525	.520	-525	•520	.515
LENGTH (in inches).	1.035	1.035	1.035	1.030	1.035	.505	-500	•485	.515
Breaking Weight (in pounds).	1546	1978•	1992 ·	1455	1989 ·	1650.	2116.	1387	1376.

TABLE XLI.

CRUSHING STRAINS IN SPRUCE.

See Arts. 704 and 707.

Number of Experiment.	251	252	253	254	255	256	257	258	259
DIAMETER (in inches).	•535	•535	•535	•535	•535	-530	•540	.530	- 530
LENGTH (in inches)}	1.035	1.025	1.040	1.030	•490	·480	·485	•495	•490
Breaking Weight (in founds).	1692 ·	1715.	1611•	1633.	1871 -	1818.	1812.	1855.	1832

CRUSHING STRAINS IN WHITE PINE.

Number of Experi- ment.	} 2	260	261	262	263	264	265	266	267	268
Diameter (in inches).	} .	540	.525	•535	.515	·530	•535	.525	.510	• 540
Length (in inches).	}	035	1.035	1.040	1.040	1.030	•495	•490	.505	•49
Breaking Weight (in pounds).	}	154·	1536.	1473	1322 ·	1297 ·	1503 ·	1624	1353.	1540

CRUSHING STRAINS IN HEMLOCK.

Number of Experi- ment.	}	269	270	271	272	273	274	275	276	277
DIAMETER (in inches).	}	-520	•520	•525	·530	·530	.520	•520	•525	•520
Length (in inches).	}	1.035	1.030	1.030	1.030	·48o	.525	• 520	•495	•490
Breaking Weight (in pounds).	}	1137.	1178	1130-	1156	1150.	1334 ·	1290	1317.	1320

TABLE XLII.

TRANSVERSE STRAINS.

Breaking Weights (in pounds) per Unit of Material = B.

See Arts. 704 and 706.

GEORGIA PINE.	Locust.	WHITE OAK, I" x I".	SPRUCE.	SPRUCE.	SPRUCE.	WHITE PINE.	WHITE PINE.	WHITE PINE.	HEMLOCK. I" × I".	Немлоск, г" х тф".	HEMLOCK.
950-	664	686-	576.	604-	540-	578.	504.	563.	381 -	491.	439
1023-	555	533-	654.	650-	569.	616-	569+	536.	358.	339	415
758-	1406-	660-	533	574-	627.	480-	590+	425	415	409+	459
951.	1286-	626-	694+	598-	642-	576 -	482.	492-	461.	337	370-
9451	1283	476+	632-	538-	552.	542 ·	5951	533	300-	4731	396
1014 -	1156.	567-	637-	652-	630+	566+	609-	460	540+	377	418.
993+	1342-	536-	702-	66a-	637	564-	582.	489.	394	402	410
785.	530-	501-	593	614.	654	g10.	643-	463+	302	365.	383-
9491	1213	664	627 -	592.	572-	639	552-	542+	415.	408 -	398.
	1281 -	529.	723-	642	576-					470-	
	952-										
		A	VERAG	e Bre	AKING	Wate	HT9, :	= <i>B</i> .			
930-	1061-	578.	637-	612.	600-	576 -	570-	500.	396	407-	410-

TABLE XLIII.

DEFLECTION.

VALUES OF CONSTANT, F.

See Arts. 704 and 706.

1			= _)		1
GRORGIA PINE.	Locust. I"xI".	WRITE OAK.	SPRUCE.	SPRUCE, I"x I\".	SPRUCE.	WHITE PINE, I"X I".	WHITE PINE.	WHITE PINE,	HEMLOCK. I" × I".	HEMLOCK. 1"× 14".	HEMLOCK, I' x 2".
5155.	4983	2599	3649	3329.	2577	3088	2746	2484 -	2083	3112-	2316-
6302	4645.	2033.	3640+	2909-	2299	3378 -	3191 -	2658+	1859.	1986.	1958 -
5199+	5616-	2360+	2215.	2679+	2962-	2806	2891	2130-	2667	2077	2386-
5555	5000-	2057	3867	2965	3105-	3124	2624-	2489+	286 8 ·	2940	1822 -
5498-	5442	1704.	3384.	2766	2539	2940-	3176-	2581 -	2259 -	3052-	1988 -
6007-	4998	1837-	2932	3291 -	3382-	2850-	2932	2040+	3056-	1606-	2190-
6007.	5239	1907-	4004	3302+	3127	3257-	3101	2371	1847-	1000-	2184-
4807	4312	1842-	3572	3344	3191.	3267 -	3225 ·	2323	2441 ·	1725	2294
6336 -	5239	2253-	3678 -	3714.	2176	3338-	2919	2509 -	1895 -	1683 -	2152-
	5033+	1930-	3967	3387-	2682					1864-	
	4952										
			Aver	AGE V	ALUES	оғ Со	NSTAN	т, F.			
5652	5042	2052	349 t	3169-	3804	3116-	2978	2398 -	2331-	2170-	2143-

TABLE XLIV.

TENSILE STRAINS.

Breaking Weights (in pounds) per Square Inch of Sectional Area, = T.

See Arts. 704 and 706.

Georgia Pine.	Locust.	WHITE OAK.	Spruce.	WHITE PINE.	HEMLOCK.
20257	11487-	19277 ·	21530	11123.	6164.
• • • •	24229 ·	12453•	19189	11057	9062
• • • •	• • • •	12644 •	22069•	10771 ·	9242
21742•	21790	23995•	18724 ·	12929	9815.
14144.	29341 ·	23268 ·	18957	13676 ·	8719.
20582	22084 ·	20400	20982	15023	7335·
11671 •	30147	13728 ·	19014.	12389 ·	9302
13195	25451 ·	18660.	19860	9786 ·	9178.
12118	33882 ·	31194.	15719.	13754	9871 ·
	Average W	EIGHTS PRO	DUCING RUP	TURE, = 7.	
16244 ·	24801 ·	19513.	19560•	12279•	8743

TABLE XLV.

SLIDING STRAINS.

Breaking Weights (in pounds) per Square Inch of Sliding Surface, =

See Arts. 704 and 706.

Georgia Pine.	Locust.	WHITE OAK.	Spruce.	WHITE PINE.	HEMLOCI
880-	1218-	1076-	551.	433-	360-
• • • •	1017.	1447.	463.	530-	410-
831.	1275.	1474	64.7	459-	364.
934.	970-	1181.	530-	464.	
• • • • •	• • • •	1349.	521.	480-	410-
793·	1389·	1103.	554·	465.	392.
904.	1143.	1381.	606.	505.	329
845.	1129.	1084.	480-	479	369-
713.	1183-	1151.	527·	. 520-	322.
Aver	AGE RESISTA	NCE TO RUI	TURE PER S	QUARE INCH,	= G.
843.	1165.	1250	542.	482.	369-

564

TABLE XLVI.

CRUSHING STRAINS.

Crushing Weights (in pounds) per Square Inch of Sectional Area, = C.

See Arts. 704 and 707.

Georgia Pine.	Locust.	WHITE OAK.	Spruce.	White Pine.	HEMLOCK.
9649 •	11009	7142.	7527	6349 ·	5354
9015•	11259.	8966 ·	7629 ·	7095 ·	5547·
9705 ·	11993 ·	9380+	7166•	6552•	5220
8170-	11729 ·	6595 ·	7264•	6346•	5240
11503 -	12216	≠ 9188 ·	8323 ·	5879 ·	5213.
9611.	11772 ·	7769.	8240	6686 •	6281 ·
9032•	11525 ·	9775 ·	7912.	7502 ·	6074
8683 •	11396	6531	8408•	6623.	6084
10278 •	12582 ·	6606	8304 ·	6724 •	6216
Aver	GE RESISTA	NCE TO CRU	shing per S	QUARE INCH	$r_{i} = C$.
9516.	11720	7995	7864	6640	5692•

DIRECTORY,

UR

DIGEST OF THE PRINCIPAL RULES.

Below may be found the numbers of such formulas, cles, figures and tables as are particularly applicable in given problem.

By reference to these, the rules heeded in any ce case, occurring in practice, may be more readily found by either the index or table of contents.

LEVERS-WOOD.

1		Strain at wall,
	ure.	" " any point, . Figs. 27, 28, 33, (42.),
_	Rupture	Size when at the point of rupture, (
end.	1	" to resist rupture safely, (19.), (
Load at		Weight,
	့	Length, $(1^{\frac{1}{2}})$
	exui	Breadth,
	Fl	Depth,
		Deflection,

Load uniformly distributed.	Rupture.	Strain at wall,
Load unif	Flexure.	Weight,
Loaded promiscuously.	Rupture.	Strain at wall,
		• LEVERS—-ROLLED-IRON.
Load at	end.	Flexure. Weight,
Load u	niforml ••	y distributed. Flexure. Weight, (230.) " " Size, (229.)

SINGLE BEAMS—WOOD.

	ſ	Strain at middle,	. (9 .)
		" " any point,	Fig. 29
		Size when at the point of rupture, (9.), (11.), (12.)	?.),(14.)
		" to resist rupture safely,	. (21.)
	1 5.	" at any point to resist rupture safely,	. (37.)
_	Rupture.	{ Weight,	. (13.)
ldle,	R	Length,	. (14.)
at middle.	}	Breadth,	.(11.)
]	Depth,	. (12.)
Load		Constant B ,	. (10.)
		Pressure on each support,	(3.), (4.)
		Weight,	(122.)
	<u>5</u>	Length,	. (124.)
	Flexure.	{ Breadth,	(125 .)
	巨	Depth,	. (1 2 6.)
	l	Deflection,	(120.)
			,,,,
nt.		Strain at middle,	(44.)
, poi	, e	•	(15)
at any point.	Rupture.	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
	Ru	Size when at the point of rupture,	
Load		" to resist rupture safely, (23.), (46.), (47.)	
	L	(<i>49</i>)	.), (50.)
	(Strain at middle, Art. 59	9, (72.)
		" " any point, Fig. 42	2, (71.)
ted.	Rupture.	Size when at the point of rupture,	
ribu	tupt	" to resist rupture safely,	•
dist	124	Shape of beam,	. 43, 4
uniformly distributed.		Pressure on each support,	
forr	ſ		(131.)
-	ا نه		(132.)
Load	Flexure	Breadth,	(133.)
-	E		(134)
		_	(135.)
•	-		- 1

3 loads. 2 loads.	Parista A	Siz Str	" " le to resirain at a	ocations ist rupti ny poin ocations	s of weig ure safely nt, <i>Fig</i> . 38	hts, <i>A</i> y, (<i>30</i> . s, (<i>61</i> .) ghts,	rt.49), (3. , (62 (58	53, (5 1.), (5 2.), (6 3.), (5	4.), (55.) (1.), (52.) (6.), (57.) (3.), (64.) (9.), (60.) (6.), (67.)
Loaded promiscuously.	Ru	pture. pture.			point,	(82.)	, (91	.), (9	(98.)
Load	ded (Rupture	. Stra	ins, <i>Fi</i>	gs. 39, 40 ,	, 41, <i>A</i>	l <i>rts</i> .	196	to 203 ,
rica	ily.								210, 211
	•		SINGLE	BEAMS	ROLLE	D-IROI	N.		·
	•	Gener	SINGLE	BEAMS	-ROLLE	D-IROI	N.	•	•
	•	Gener Weigl	SINGLE ral rule,	BEAMS	-ROLLE	D-IRO1 •	N. •	•	•
	•	Gener Weigl	SINGLE ral rule, ht, .	BEAMS .	-ROLLE	D-IRO1 • •	N.		·
	•	Gener Weigl Lengt	SINGLE ral rule, ht, . ht, . ction,	BEAMS	-ROLLE	D-IROI	N.	•	·
	•	Gener Weigl Lengt Deflect	SINGLE ral rule, ht, h, ction, ent of in	BEAMS	-ROLLE	D-IRO1	N	•	210, 211 . (216.) (217.) . (218.) (219.) . (220.)
Load at middle.	Flexure.		ral rule, ht, . h, . etion, ent of in	· · · · · · · · · · · · · · · · · · ·	-ROLLE	•	•		.(216.) (217.) .(218.) (219.) .(220.)
Load at middle.	Flexure.	ny point.	ral rule, ht, . h, . ction, ent of in	· · · · · · · · · · · · · · · · · · ·	• •		•	(221	.(216.) (217.) .(218.) (219.) .(220.) (223.) .), (222.)

FLOOR TIMBERS-WOOD.

	R'pt're	General rule,
	-	General rule,
		(General rule (160) (169)
.S.		Distance from centres, . I. to IV., (144.), (306.)
		Distance from centres, I. to IV., (144.), (306.) Length,
eam		Breadth,
Floor beams.	ure.	Depth,
Fic	Flexure.	gi General rule, (148.), (149.)
		Distance from centres, V. to VIII., (150.), (307.)
		Second Length,
		[로 Depth,
į		Solid floors of wood, XXI., (310.), (311.), (312.)
1	Pun	ture. General rule,
	_	
Headers	xur	Dwellings, etc IX. to XII., 382 (308)
H	Fle	General rule, (156.) Dwellings, etc., . IX. to XII., 382, (308.) First-class stores, . XIII. to XVI., 383, (309.)
`	`	
	re.	With one header, (29.)
	Rupture.	" two headers, (32.), (33.), (34.), (35.), (92.), (93.)
j	ھ (" three " (97.), (106.) General rule, (157.), (161.) Dwellings, etc., (158.), (162.) First-class stores (159.) (163.)
		General rule, (157.), (161.)
		Dwellings, etc., (158.), (162.)
ns.		. (100.), (100.)
beams.		General rule, (164.), (167.), (170.), (174),
Carriage	aš l	(179.), (183.), (186.)
arri	XII \	Dwellings, etc., (165.), (168.), (175.), (180.), (184.), (187.)
	Flexure.	(184.), (187.)
		Thst-class stores, (166.), (169.), (176.), (181.),
		(185.), (188.)
		General rule, Figs. 55, 56,(190), (194) Dwellings, etc., (191.), (195.) First-class stores, (192.), (196.)
		E de Dwellings, etc., (191.), (195.)
_ \		
Gire	ders	Rupture. General rule, Art. 137

FLOOR BEAMS-ROLLED-IRON.

	Flexure.	Dwell	ral rule, . lings, etc class stor	•, •				•	•	•
Ì			ral rule,		•	•		•	•	(247.)
4	exure.	Dwell	lings, asso	embly	roon	as, et	tc., .	•	•	(248.)
į	E	First-	class stor	es,	•	•	•	• .	•	(249.)
ſ	•	[Genera	l rule,	•	•	•	•	•	(250.)
İ		With	Dwellin	ıgs, as	semb	ly ro	oms,	etc.,	•	(251.)
		P ğ	First-cl							(252.)
;		. 1	Genera	l rule,	•	•	•	•	•	(253 .)
	re.	With	Dwellin					etc.,		•
1	Flexure	he. ∀	1					(2	<i>56</i> .),	, (258.)
	豆	~	First-cl	ass sto	res,	•	(25	5.), (2	57.),	(259.)
3			Genera	l rule,			•	•	. A	lrt. 531
		ith	Dwellin	igs, as	ssemb	oly re	ooms	, etc.,	•	(2 60.),
		With								(262.)
		[m	First-cl	ass sto	ores,	•	•	. (2	<i>(61.</i>)	, (263.)

FRAMED GIRDERS.

Proportionate depth,	•	•		•	•	•		•	(294.)
Number of bays, .	•	•	•	•	•		•	•	(295.)
Strains in a framed gir	rder,	•		•	•	•		Figs.	93, 94
" " diagonals,	•	•	•	•	•		•	•	(296.)
Tensions in lower cho	rd, .	•		•	•	•		•	(297.)
Areas of cross-section	in lo	wer o	chor	rd,	•		•	•	(299.)
66 66 66	" up	per	44		•	•	(3	01.),	(303.)
Unsymmetrical load, o	divide	ed be	twe	en t	he t	wo	sup	port	ts,
-				Fig.	s. 96	, 97	, (3	04.),	<i>(305.)</i>

DIRECTORY.

TUBULAR IRON GIRDERS.

200				
Load at middle.			(264.)	(265-)
" " any point.	66 66		• •	(26==.)
_ ਨੂੰ General rule,				(267 .)
हिंहिं Banks and asse	embly room	ms. Area o	of flange,	(274.)
General rule, Banks and asserting First-class store	es,	46	44	(275===.)
Thickness of web to re	sist sheari	ng, .		(268==3.)
Weight of girder,			(270.),	(271)
Economical depth of g	irder, .	• •	. (276.),	, (<i>277</i> ·)
CA	S T-IRO N G	IRDERS.		
Load at middle. Breaking	weight.		٠.	(278==.)
· · · · · · · · · · · · · · · · · · ·		· · · ·		(279)
" " any point. Breaki			•	(281 -)
• •	ea of flang			(282)
Two concentrated loads. Sa	•		(285.),	(286 -)
ਚੂਂ Sase area of flang		•		(280)
bute " " "	-			\
depth at any	-	•		` \
Arch girder, safe	_			•
" " safe Brick arch, "				
Brick arch, "			•	
	ROOF TRU	SSES.		, ,
Comparison of designs	i		. A	rt. 658
Strains derived graphi				
Horizontal and incline	_			
Designing a roof, .				
Load upon a roof,				
Load upon each suppo				
		" the tie-b		
Measuring the strains,				
Arithmetical computat		_		rt. 681
Dimensions of parts su		•		rt. 682
	•	mpressive :		
		_	-	to 687

FLOOR-ARCHES—TIE-RODS.

Uniformly distributed load, area of rod, (241.) Load per superficial foot, " " " , (242.) Banks, assembly rooms, etc., " " " (243.) " " " Diameter of rod, (245.) First-class stores, " " " (246.)
" " area of rod, (244.) SHEARING.
With compound load on lever,
PROMISCUOUS.
Bridle irons, for headers,

												FAGI
American House Carpenter, sliding strains,												500
" manufacture of rolled-iron beams,		•	•	•	•	•	•	•	•	•	•	313
" woods, constants for,	•	•	•	•	•	•	•	•	•	•	•	499
" experiments on,	•	•	•	•	•	•	•	•	•	•	•	504
" wrought-iron, constant for,	•	•	•	•	•	•	•	•	•	•	•	499
" elasticity of,	•	•	•		•	•	•	•	•	•	•	232
Anderson, experiments made by Major.	•	•	•	•	•	•	•	•	•	•	•	500
Angle irons in plate beam,												
Approximate formulas discussed,												
" value of resistances,												
Arch, area of cross-section of tie-rod of floor												
Arches and concrete floors, weights of, .												
" for floors, general considerations, .												
" tie-rods for brick												
" where to place tie-rods in brick .												348
Arched girder of cast-iron, and tie-rod, .												_
" substitute for iron,												398
Architect, his liability to err,												28
" tables save time of the,												
" too busy to compute by rules, .												495
Architect's knowledge of construction,												-
Area of cross-section, resistance,												
" " " of tie-rod of floor arch,												
Arithmetical computation of strains in truss,												486
" progression, the sum,												
" series,												
" coefficients form an,												226
Arithmetically computed strains,												
Ash resistance of		•	•	•	•	•	•	•	•	•		190

														Page
Assemb	oly halls,	formula for												502
	4.	rolled-iron	beams fo	r,	•	• •	•	•		•	•	•	• •	498
••	room	s, strains in,	the sam	e as	in d	wel	lings	3,		•	•	•		88
44	64	and banks	, load on	ooft p	rs c	f, .	•	•	•		•	•	340,	341
• •	• 6	load on flo	ors of,	• •	•	•		•	•		•	•		88
4	4	" " tu	bular gi	rders	for	Γ, .	•	•	•		•	•		380
64	44	rolled-iron	beams f	or,	•	• •	•	•		•	•	•		495
64	• •		"	" Ta	ble	XV	III.,	,	•		•	•	526,	527
4	44	46 44	carriage	bear	ms v	with	two	he	ade	rs a	ind (one	set	
		of tail	beams,	for,	•		•	•		••	•	•		358
4	44	rolled-iron	carriage	e bea	ms	with	two	he	ade	rs a	nd t	wo	sets	
		of tail	beams, i	or,	•			•	•		•	•	354,	356
44	af	rolled-iron	carriage	e bea	ıms	wit	h th	ree	hea	ade	rs, fo	or,	360,	362
44	44	rolled-iron												
"	44	rule for flo												
"	64		bular gir											380
44	64	tie-rods fo	•											347
Auxilia	ary formu	la for carria												193
		of Beams,												•
46	"		• (,						
•6	formula	for posts,												
•6		ression of m												
Banks.	-	for solid flo												
**		tubular gird	-											•
46		on beams fo												_
44	66 6		Table										-	_
46	• 6 • 6	' carriage												J-1
		•	ns, for,											258
66	66	' carriage			,									33 0
		_	ns, for,											256
u	4.6	carriage												-
"		headers											_	_
66	tie-rods	for floor arc												-
• 6		tubular gird												
									,					
		floors of,												
432TIOW		nts for use i								•				
44	_	ments on wo												
" D •		sion for elas												
		i truss, num												
Beam a	ind lever	compared,		•	•	• •	•	•	• •	•	•	•	• •	244

	PAGE
Beam and lever compared, deflection in,	237
" " their symbols compared,	49
" device for increasing the strength of,	402
" distributed load on rolled-iron	337
" ends shaped to fit bearings,	122
" load for a given deflection in a,	245
" of economic form,	163
" equal strength,	163
" rules for dimensions of deflected	248
" shaped as a parabola,	124
" values of U , l , b , d and d in a ,	253
" " W, I, b, d " & " "	248
" with load distributed, rules for size of,	253
Beams, formula for deflection of,	229
" general rule for strength of,	92
" of dwellings, general rule for strength of,	89
" " wood, their weight,	79
" warehouses to resist rupture,	260
" comparison of rolled-iron, plate and tubular,	3 67
" should not only be, but also appear safe,	-
" strains in, graphically expressed,	
Bearing surface,	_
" " of beams on walls,	121
Bearings, beams shaped to fit,	
Bending, a beam is to resist	
" and appearing dangerous, beam safe, yet	
" in good floors far within the elastic limit,	
" its effects on the fibres,	
" moment of inertia, resistance to,	
" rafter to be protected from,	-
" resistance to,	
Bent lever, equilibrium in,	
Bow-string iron girder,	
" " " substitute for,	
" " " unworthy of confidence,	
Bow, Economics of Construction,	
" has written on roofs,	
Braces in truss, dimensions of,	
•	68
" load of unit of material,	

### Pireaking load, the portion to be trusted,	Ti Real	ing load, the nortion to be trusted				PAGI
" compared with safe weight,		•				•
" index of, " per inch sectional area, tensile, Table XLIV., 562 " " " surface, sliding, Table XLV., 564 " " unit of material, transverse, Table XLII., 561 " " unit of material, transverse, Table XLII., 561 " in first-class stores, 265, 266 " its relation to depth and distance from centres, 265, 266 " its relation to depth, 333 " of beam, rule for, 248, 249 " " in dwellings, 262, 263 " " with distributed load, rule for, 254 " " header, rule for, 250, 256, 257 " proportioned to depth, rule for, 338 " " for floor, rate of rise, 346 " " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " " for floors, general considerations, 345 " " tie-rods for, 346 " " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance due to, 310 " measure of resistance due to, 304 " increased resistance due to, 304 " useful to sustain concentrated loads, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " " load upon a, 98 " " rule for a, 98, 99 " " rule for a, 98, 99	44					-
" per inch sectional area, tensile, Table XLIV., 563 " " unit of material, transverse. Table XLII., 564 " " unit of material, transverse. Table XLII., 564 " in first-class stores, 265, 266 " its relation to depth, 333 " of beam, rule for, 248, 249 " " in dwellings, 262, 263 " " with distributed load, rule for, 224 " " header, rule for, 271 " lever " 250, 256, 257 " proportioned to depth, rule for, 398 " " for floor, rate of rise, 346 " " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " " for floors, general considerations, 345 " " tie-rods for, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridged beam, resistance of a, 304 Bridged beam, resistance of a, 304 Bridged beam, resistance of a, 304 Bridged beam, resistance of a, 304 Bridger causes lateral thrust, 303 " in floor beams, 304 " increased resistance due to, 304 " measure of resistance by, 304 " useful to sustain concentrated loads, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " " load upon a, 98, 99 " " rule for a, 98, 99 " " rule for a, 98, 99						
" " surface, sliding, Table XLV						•
## " unit of material, transverse, Table XLII., 561 Streadth from given depth and distance from centres, 92 in first-class stores, 265, 266, 266, 266, 266, 266, 266, 266						
## in first-class stores,		_				
" in first-class stores, 265, 266 " its relation to depth, 33 " of beam, rule for, 248, 249 " " " in dwellings, 262, 263 " " with distributed load, rule for, 254 " " header, rule for, 271 " " lever " " 250, 256, 257 " proportioned to depth, rule for, 73 Brick arch a substitute for iron arch girder, 398 " " for floor, rate of rise, 346 " " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " " tie-rods for, 346 " " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " increased resistance due to, 310 " measure of resistance by, 304 " number of beams resisting by, 304 " principles of resistance by, 304 " useful to sustain conce						•
" its relation to depth, 33 " of beam, rule for, 248, 249 " " " in dwellings, 262, 263 " " with distributed load, rule for, 254 " " header, rule for, 271 " " lever " " 250, 256, 257 " proportioned to depth, rule for, 73 Brick arch a substitute for iron arch girder, 398 " " for floor, rate of rise, 346 " " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " " for floors, general considerations, 345 " " tie-rods for, 346 " " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " floor beams, 302 " increased resistance due to, 310 " increased resistance of, 304 " number of beams resisting by, 304 " useful to sustain concentrated loads, 304 " useful to sustain concentrated loads, 304						
## of beam, rule for,					•	
""" with distributed load, rule for, 254 """ header, rule for, 271 "" lever 250, 256, 257 " proportioned to depth, rule for, 73 Brick arch a substitute for iron arch girder, 398 "" for floor, rate of rise, 346 "" less costly than cast-iron arch, 399 "arches and concrete filling, 345 "" for floors, general considerations, 345 "" where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " increased resistance due to, 310 " measure of resistance of, 304 " useful to sustain concentrated loads, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " load upon a, 98, 99 " to be broad, 99						
""" with distributed load, rule for, 254 ""header, rule for, 271 ""lever"" 250, 256, 257 "proportioned to depth, rule for, 73 Brick arch a substitute for iron arch girder, 398 "for floor, rate of rise, 346 "less costly than cast-iron arch, 399 "arches and concrete filling, 345 "tofor floors, general considerations, 345 "where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 "for concentrated loads, 88 "floor beams, 302 "infloors tested, 303 "increased resistance due to, 310 "measure of resistance by, 304 "principles of resistance by, 304 "useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 "color total carriage beam, 98, 99 "to be broad, 99		· · · · · · · · · · · · · · · · · · ·				
" " header, rule for, 271 " " lever " " 250, 256, 257 " proportioned to depth, rule for, 73 Brick arch a substitute for iron arch girder, 398 " " for floor, rate of rise, 346 " " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " " for floors, general considerations, 345 " " tie-rods for, 346 " " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " infloors tested, 303 " increased resistance due to, 310 " measure of resistance by, 304 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98 " rule for a, 98 " rule for a, 98 " to be broad, 99 </td <td></td> <td>-</td> <td></td> <td></td> <td></td> <td>•</td>		-				•
" lever 250, 256, 257 " proportioned to depth, rule for, 73 Brick arch a substitute for iron arch girder, 398 " for floor, rate of rise, 346 " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " arches and concrete filling, 345 " " for floors, general considerations, 345 " " tie-rods for, 346 " " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance by, 304 " useful to sustain concentrated loads, 309 " useful to sustain concentrated loads, 309 " " rule for a, 98, 99 " " to be broad, 99						
" proportioned to depth, rule for, 73 Brick arch a substitute for iron arch girder, 398 " " for floor, rate of rise, 346 " " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " " for floors, general considerations, 345 " " tie-rods for, 346 " " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " " rule for a, 98, 99 " " to be broad, 99	"					-
### Brick arch a substitute for iron arch girder,	44					
" " for floor, rate of rise, 346 " " less costly than cast-iron arch, 399 " arches and concrete filling, 345 " " for floors, general considerations, 345 " " tie-rods for, 346 " " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance of, 304 " number of beams resisting by, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " " load upon a, 98, 99 " " to be broad, 99	_					73
" arches and concrete filling, 399 " arches and concrete filling, 345 " for floors, general considerations, 345 " tie-rods for, 346 " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance of, 304 " number of beams resisting by, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " " load upon a, 98, 99 " " rule for a, 98, 99 " " to be broad, 99	Brick	arch a substitute for iron arch girder,	•		•	398
" arches and concrete filling, 345 " "for floors, general considerations, 345 " "tie-rods for, 346 " "where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance of, 304 " number of beams resisting by, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " "load upon a, 98, 99 " "tule for a, 98, 99 " "to be broad, 99	66	" for floor, rate of rise,	•		•	346
" " for floors, general considerations, 345 " tie-rods for, 346 " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance of, 304 " number of beams resisting by, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " " load upon a, 98, 99 " " rule for a, 98, 99 " " to be broad, 99	44	" less costly than cast-iron arch,	•		•	399
" tie-rods for, 346 " where to place tie-rods in, 348 Bridge, greatest load on, 80 Bridges, Conway and Menai Straits tubular, 367, 368, 378 Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance of, 304 " number of beams resisting by, 309 " principles of resistance by, 304 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " " load upon a, 98 " " rule for a, 98, 99 " " to be broad, 99	••	arches and concrete filling,	•		•	345
## Where to place tie-rods in,	44					
Bridge, greatest load on,	44	" tie-rods for,	•		•	346
Bridges, Conway and Menai Straits tubular,	es	" where to place tie-rods in,	•		•	348
Bridged beam, resistance of a, 304 Bridging causes lateral thrust, 303 " for concentrated loads, 88 " floor beams, 302 " in floors tested, 303 " increased resistance due to, 310 " measure of resistance of, 304 " number of beams resisting by, 309 " principles of resistance by, 309 " useful to sustain concentrated loads, 309 Bridle iron and carriage beam, 98, 195 " load upon a, 98 " rule for a, 98, 99 " to be broad, 99	Bridge	, greatest load on,	•		•	80
Bridging causes lateral thrust,	Bridge	s, Conway and Menai Straits tubular,	•	367,	368,	378
for concentrated loads,	Bridge	d beam, resistance of a,	•		•	304
" floor beams,	Bridgi	ng causes lateral thrust,	•		•	303
in floors tested,	4	for concentrated loads,	•		•	88
"increased resistance due to,	66	floor beams,	•		•	302
measure of resistance of,	•6	in floors tested,			•	303
measure of resistance of,	44	increased resistance due to,	•			310
reprinciples of resistance by,	"					
" useful to sustain concentrated loads,	••	number of beams resisting by,	•		•	309
Bridle iron and carriage beam,	**	principles of resistance by,	•		•	304
" " load upon a,	**	useful to sustain concentrated loads,	•		•	309
" " load upon a,	Bridle					•
" rule for a,	*	_			•	• -
" " to be broad,	•6	-				•
	"					
	Britan					

							•										-	AGE
Buckling	or co	ontorti	on of	a tu	bulaı	gir	der,	•	•	•	• (•	•	•	•	•	377
Building	mate	rial s, v	veigh	ts of,	Tab	le X	XII	• •	•	•			•	•	533	3, !	534.	535
Buildings	s requ	aire st	abilit	y,	• • •	•		•	•	•	•		•	•	•	•	•	27
4.6	requ	isites	for s	tabili	ty in	,		•	•					•	•		•	28
Burbach,	large	rolled	l-iror	bea	ms fr	om,	•	•	•		•		•	•	•	•	•	313
Buttresse								•										
Calculus	and a	arithm	etic c	ompa	ared,			••	•	•	• .		•		31	B ,	32 0,	321
66		scale o																
46		īed, re																
		cient (
		ı by di																
46	**		ed by															
44	strair	ns in l	-															
Cape's M																		
44	44			ences														
Carriage	beam	and b																
46	"		eade															94
"	44	auxil													•			193
46	46	defini	•											•	•	•	•	-
"	44	for d																•
•	• •		st-cla															
44	44	form				_										_		
• •	46	load				•												_
44	46		ual c														•	
46	"	•	se ru															
44	••	"	•		h le			3										
44	4.6	spec	ial ru															
46	66	_	one l								•							99
	44	"	"	"			iron											
44	46	44	"	44			semi											
**	4.	4.	• •	4.6			nks,	•										
••	••	• •	••	44			velli:										_	
	• •	• •	• •	••	•		•••	g.,				on			•			
4.6	••		••	4.	•		st-cla				٠							
4.6	• •	• •	4.	• •	• (,, ,,			led						
44	64	4.6		h a a all a													•	352
44	44	44	two i	neau	•		· ·								•	_	•	101
44	64	44	44				welli											292
46	44	••		،، مسنط									SC					
44	44	••	(equid	istar 	it de	adei	_				•	-	_	SA 1			
		- •		•	-			11	ur O		1117	105	ות		EA T	m L	per .	ZOU.

INDEX. . 579

			PAG	æ
Carriage	beam,	with	two equidistant headers, for first-class stores, precise	
			rule,	19
••	4.6	6.6	" headers and one set of tail beams,	ک د
44	4.4	4.6	" " precise rule, . 28	33
66	• 6	• •	" equidistant headers and one set of tail beams,	
			precise rule,)0
• 4	4.6	4.6	" headers and one set of tail beams, for dwellings, 27	77
• 6	• •	44	16 61 16 16 11 11 11 11	
			rolled-iron	58
44	4.4	••	" headers and one set of tail beams, for first-class	
			stores,	78
**	44	"	" headers and one set of tail beams, for first-class	•
		•	stores, rolled-iron	59
44	••	4.6	" headers and two sets of tail beams, . 104, 192, 19	
44	44	"		79
	• 6	44		53
44	44	4.4		75
• 6	44	••	11 11 11 11 11 11 11 11 11	, ,
			precise rule,	82
66	4.6	66	" headers and two sets of tail beams, for dwellings,	
			rolled-iron	56
• •	4.6	4.6	"headers and two sets of tail beams, for first-class	
,	•		stores,	76
46	44	44	" headers and two sets of tail beams, for first-class	
			stores, rolled-iron	57
"	**	4.6	three headers,	
44	4.6	4.6	" for dwellings, rolled iron 360, 3	
**	••	• •	" " first class stores, rolled-iron 361, 3	64
4.6	4.6	• •	" the greatest strain at middle header, . 2	97
"	**	66		94
44	4.	•	" " " middle "	•
•			for dwellings,	98
44	• •	44	" headers, the greatest strain at outside header,	
			. 1 111	95
44	44	**	" headers, the greatest strain at middle header, for	,,
				99
44	••	4.6	" headers, the greatest strain at outside header, for	, ,
			first-class stores,	Q5
4.6	44	4.6		-
Cast-iro	n. con	npres	sion and tension in,	•

PAG
Cast iron resists compression more than tension,
" superseded by wrought-iron,
" " beam, load at middle, Hodgkinson,
" " arched girder with tie-rod,
" " " tie-rod for,
" " form of web of,
" " for brick wall with three windows, 39
" " " load at any point of, rupture,
" " " " middle of,
" " " proportion of flanges of,
" " safe distributed load, effect at any point on, 39
" " safe load at any point on,
" " two concentrated weights on,
" " girders, chapter on,
Ceiling of room plastered,
" to be carried by roof truss, weight of,
" weight of,
Cement grout for brick arches of floors,
Centennial Exposition, rolled-iron beams at,
Centre of gravity, load concentrated at the,
Centres, distance from,
Cherry, resistance of,
Chestnut, "
Chord, framed girder with loads on each
" of framed girder, allowance for joints, etc., in,
" " " area of <i>uncut</i> part of,
" " " strains in lower
" " " " upper
" and struts of framed girder, upper
. " " " " compression in upper 445
Chords and diagonals, gradation of strains in,
" of framed girders usually of wood,
Civil Engineer and Architects' Journal,
Clark, moment of inertia, by Edwin
Clark's formula only an approximation,
" useful in certain cases,
Clay has but little elasticity,
Coefficient of strength for tubular girder,
Coefficients in rule for floors of dwellings,
" " " " " first-class stores,

TATE	7777
	IM. K

							•					•					
Com																	PAGE
_		oad on floor												•	•	•	339
COTT DORE	ia ioza,	assigning t										•	•	•	•	•	187
44	44	dimensions													•		187
•4	46	general rul															199
41	44	greatest sti															182
41	46	maximum															
44	44	strain analy															478
46	4.6	strains and													•		171
46	44	on floors,				•			•						•		339
46		" lever, th															174
Co	strain ii:di:	s graphicall	y expi	essea,	•	•	•	•	•	•	•	•	•	•	•	•	177
Compress	donity (of fibres, .	• •	• •	•	•	•	•	•	•	. •	•	•	•	•	•	37
· ·		ances exten												•	•	•	45
44		nensions of	-	•										•	•	•	490
44		phically sho								•		•	•	•	•	•	115
44		istance to,								•	•		•	•	•	•	45
44	and	d extension			_										•	•	35
44			summ														228
44	11	tension, fil															
44	44		cast-i														
44			pture														313
•		ibres at top															42
46	44	struts, rule f															_
44	•	- -	cation														• • •
4.		struts and cl	•														445
44		nkine, Bake															446
Compressi		dgold and l tensile strai	•														446
oompress:		n in rafter i															408
Computati		n in raitet i ogarithms, e															474 311
oomputati.	•	ogarithms, coment of ir	-														315
44		ns in frame															416
44		neck graphic		•													132
Concave si		eam, fibres															•
		half of distr	_														
ooncentrat		bridging us									•	_					
64	"	resistance of				_									•	•	308
44	46	location of															•
44		s, a series of															
44	1044	11		oxima													155
			~PF.		- -	•				*	~~	- ,			•	•	-33

				•									PAGE
Concentr	ated and d	istributed	loads										
4.6	4.6	6.6	44	comi	pared,	•	•	• •	•	•	61, 6	52, 63	, 161
4.6	"	• •	46	grapl	hically	ex	pre	ssed	•	•	• •	• •	177
• •	6.6	• •	4.6	on be	eam,	• .	•		•	•		• •	252
• •	• •	• •	66	size (of bea	m,	•	• •	•	•	•	182	, 191
"	64	44	4.6	on le	ver,	•	•	• •	•	•	. 171	, 174	, 255
ė.	loads,	a distrib	uted a	and tw	, o	•	•	• •	•	•	184	, 187	, 191
. 46	44	**	44	thre	e .	•	•	195,	197	7, 19	8, 199	, 2 03	, 292
4.6	**	middle l	oad of	distr	ib ute d	an	d th	ree	•	•			296
Concrete	and brick	arches, w	reight	of, .		•	•		•	•			340
• •	filling ove	r floor ar	ches,			•	•	• •	•	•			345
Conflagra	tions resist	ed by so	lid floo	ors, .	• •	•			•	•	•		500
Constant	F for de	eflection,	values	of, T	able I	KLI	II.,	•	•	•			562
Constants	for tubula	r girders	9 • •		·	•	•		•	•			•
4.6		the rules											• •
44		6.6			,								, 531
"	from expe	riments											
••	how deriv												
44	precaution												-
Convergin	g forces re												
	de of beam												
	nd Brit a nn												_
	ion define										_	_	
"		old an au											
**	_	of the m											
46		s of mate										•	
"		of, weigh											
Cross-brid	ging,												
	''_ assist												•
		ls act as,											_
Cross-furri													_
Cross-sect													_
Crush, brid													_
Crushing s													-
46		Georgia p											
		pruce, w								•			-
	weights per												_
Curve and												- •	
	quilibrium											. 4	
"	4.6	stable an	d uns	table,	• •	• •	•	•	•	•	• •	. 4	πq

INDEX. ' 583

							:	PAGE
Dangerou	s, beam though safe may bend and appear	•	•	•			•	235
Deflected	lever, rules for size of,	•	•	•			•	2 56
Deflecting	energy,	•	•	•			•	211
66	" of weight on lever,	•	•	•			•	229
44	energies in beam and lever,	•	•	•			•	251
46	power of concentrated and distributed loa	ds,	•	•			•	252
Deflection	and rupture compared,	•	•	•			•	211
"	excessive under rules for strength,	•		•			•	77
**	resistance to,	•		•			•	221
66	by distributed load, rule for,	•					•	255
44	directly as the weight,							304
44	" " extension,							
"	" " " length,							
**	" " force and length,							
44	total, directly as the cube of the length,.							
•"	" " " weight and cube of le							219
44	values of constant F , Table XLIII., .							562
46	of beam, effect at bearing,							121
**	" " formula for,							
"	" " load for given,							
**	" " with load at middle,							
**	in floors, rate of,							
"	not to be excessive,							
44	to the limit of elasticity,							
44	within elastic limit,							
44	of beams not to be perceptible,							
44	per lineal foot, rate of,							
	injurious to plastering, perceptible							
44	in good floors far within the elastic limit,							
44							- •	-
44	of beam with distributed load,						•	_
66	rule for dimensions of beam,							
66	of bridged beams tested,							
	" rolled-iron beams, load at middle, .							
16	" lever and beam compared,							
• • • • • • • • • • • • • • • • • • • •	" " amount of,							
44	" test of,							•
46	" load for a given,							
44	" by distributed load,							
66	" to limit of elasticity,							
•6	" " rule for,	•	•	•	229,	244,	256,	258

							21	
Deflect	ion, dimensions of lever,							
4.6	" " rules for,	•		•	•	•	. :	250
4.4	is as the leverage, the power to resist	•		•	•	•	. 2	223
Demor	stration of scale of strains,	•		•	•	•	. 1	134
Depth,	its value, test by experience,	•		•	•	•	•	33
* *	and length, ratio between,	•		•	•	•	. :	240
6.4	relation to weight and fibres,	•		•	•	•	•	3 6
44	in proportion to weight,	•		•	•	•	•	44
44	defined for compound load,	•		•	•	•	. :	178
44	relation to breadth,			•	•	•	•	33
44	proportional to breadth, rule,	•		•		•	•	73
44	from given breadth and distance from centres,							
"	of simple beams necessarily small,							
64	in a beam, the importance of,							
44	of beam proportioned to load, square of,							
"	" " rule for,							
**	" " with load distributed, rule for,						-	
44	" " in dwellings,							
4.6	" " first-class stores,							
**	" lever, uniform load,							
"	" " promiscuous load,							
44	" " rule for,							
**	" framed girder, rule for,							
**	in " objectionable,							
4.	and length of framed girder,							
4.4	to length in tubular girders, ratio of,							
Depths	analytically defined, varying							
	expressions for varying,							
4.6	demonstrated, rule for varying,							
4.4	compound load on lever, scale of,							
Design	for a roof truss, selecting a,							
_	ctive energy,							
	' ' its measure,							
	" symbol of safety,							
	" and resistance,							
	' load at any point,							
,	" from two weights,							
	" " several weights,							
	on lever,							
	power of weight and resistance of material,							
	power or weight and registance or material,	•	•	•	•	•	'	

															PAGE
Diagona	ls, grada	ation of str	ains in c	hords	and	l, .	•	•	•	•	•	•	•	432	, 435
• •	of fra	med girder	, s trains	in the	••		•	•	•	•	•	•	•	• •	436
4.4	• • •	• • •	top che	ord and	d,		•	•	•	•	•	•	•		448
Diagram	of force	s describe	d,		•	• •	•		•	•	•	•	418	, 419	, 421
4.6	**	order of	develop	ment o	of,	• •	•	•	•	•	•	•	•		421
4.6	46 44	gradatio	n of stra	ins in,	•		•	•	•	•	•	•	•	• •	433
• •	46 46	in frame	d girder		•		•	•	•	•	•	•	•	• •	429
Diagram	s and fr	ames, recij	orocal,		•		•	•	•	•	•	•	•	• •	418
• •	corres	pondence	of lines	in fran	ies	and,	. •	•	•	•	•	•	•		462
Differen	tial calcı	ılus,		• •	•		•	•	•	•	•	•	•		158
••	• (comp	ıtation b	у, .	•		•	•	•	•	•	•	•		228
64	•	strain	defined	by, .	•		•	•	•		•	•	•	180	184
44		strain	s in leve	er, .	•		• •	•	•		•	•	•		168
66	of va	triable, mo	ment of	inertia	a,		•	•	•	•		•	318	, 319,	322
Digest o	r directo	ory of this	work, .		•		•	•	•			•	•		566
Dimensi	ons of b	eam for co	mpound	load,	•		•		•		•	•	182	, 187	, 189
• •	4.6	" at give	en point	, for co	mp	oun	d la	oad.	•	•		•	•		189
4.4	••	" load a	t any po	int, .			•	•	•	•	•		•		129
••	••	" when	h equ	als n	, ,		•	•	•	•	•	•	•		190
• •	• •	••	h exc												191
Director	y or dige	est of this													566
		entres of b													0, 91
44	• •		irders,												94
44	••		olled-iro											342,	
**	••		wellings												•
• •	• •	••	"	rolled											343
44	• •	" fi	rst-class												265
**	• •	44 44	•• ••												344
Distribu	ted load	, strain by	the calc	ul us ,							-				157
••	• •	effect at a													161
44	• •	equal in	-												162
4.6	• •	on floors													77
4.6	. ••	" beam,													75
44	••	deflection													251
**	"	shape of													162
44	44	on lever,													74
4.6	••	deflection													255
46	• •	shape of		-											170
44	• •	on rolled													337
	"	" cast-ir													389
			_												_ /

			1	PAGE
Distribute	l load on tubular girder,		•	368
66	" " " size at any point,		•	372
**	and concentrated loads compared, 61,62			
"	" on beam compared,			
64	" " lever "			•
.4	" one concentrated load, 179,			• •
4.6	" graphic representation, .		_	• •
44	" " size of beam,			
44	" " on lever,			
46	" two " loads, 184,			
4.6	" size,		•	191
44	" three " 195, 197, 198,			
4.6	" " middle load,			296
Drury, tes	timony on loading,			82
•	load on floors of,			
"	floor beams and headers for			495
"	rule for floors in		•	261
44	" " headers in,		•	271
44	values of c , l , b and d in floors of,		•	-
4.6	rule for solid floors of,			502
4.6	hemlock beams, Table I.,			508
66	" headers, Table IX			516
4.6	Georgia pine beams, Table IV.,			511
**	" headers, Table XII.,			519
44	spruce beams, Table III.,			510
46	" headers, Table XI.,			518
44	white pine beams, Table II.,			509
4.6	" " headers, Table X.,			- •
44	carriage beam, precise rule,	•		517 282
44	" with one header,			
44	" " two headers, precise rule,			272
"	" " equidistant headers, precise ru			292
	" " headers and one set of tail bea			289
4.6	" " " " two sets " "		•	277
66	two sets		41.	275
••	three the greatest strain at			~ - 0
	header,			298
4.6	the greatest strain at			
	header,			
"	rolled-iron beams for,			- •
4.6	" " " Table XVIII	_	£20	527

", DACIIII	igs, rolled															343
			oor arc	_												347
44			eaders i													349
4.0	**	" ca	arriage	beams	with	n t	wo	he								0
			•	"	••						-			• •		358
4.6	4.6	• •	••	••	44		••	h						sets		
							•							•		
44		46		11							_			•		
44			lar gird													_
	rule fo													• •		
Econor	nical depth															
			oular													
			m, .										•			
• •	44		ed-iron													
	"	_	f truss,													
	curve defi	•														_
66	limit, ben														_	
44			ned be	•												
• •	_		to kno													
			ion of f													
•• .	3911		safety													- •
6.6	power of															
"	substance															
	ity are exc		_													
• •			s of,													
44			ron, m													
4.6			ing bod													
**	_	-	all ma													
	nts of rolle															
-	c curve for															
Elonga	ation of fib															
•			aphical													•
Englis	h rolled-ir															
44	wrought															_
Equal	weights eq															
44	_		results,													
44			first w	•												
44			second													
"	44	46 44	any we	eight,	•	•	•	•	•	•		•	•	•	• •	150
E1	lv distribu	red safe	load	rule for	•				_	_		-				70

							•						•				7	AGE
First-c	las s s t	ores,	rolled-i	ron	headers,	•	•	•	•	•	• •	•	•	•	•	•	,	350
44	4.6	• 6	44	• •	carriage	beams	w	ith	one	e ho	ead	er,	•			,	•	352
46	••	44	44	46	44	4.		4 4	two	o h	ead	ers	an	ıd	one	e s	et	
			•							of	tail	be	am	s,	•	•	•	359
6.	• •	••	••	44	• •	16	(4 4	tw	o h	ead	егя	s an	d	two	50	:ts	
										of	tail	be	am	s,	•	•	•	357
44	••	44	**	"	"	• •		44	th	ree	hea	ade	ers,	•	•	3	61,	364
"	44	"	tie-rod	s in	floor arcl	ies,	•	•	•	•	•	•	•	•	•	•	•	348
"	••	••	values	of a	r, <i>l</i> , <i>b</i> a	nd d,		•	•	•	•	•	•	•	•	•	•	265
Five e	qual w	eight	s, grapl	aic s	trains, .		•	•	•	•	•	•	•	•	•	•	•	141
Flange	s an e	leme	nt of st	reng	th,		•	•	•	•	•	•	•	•	•	•		313
• •	and	web,	propor	tion	s between	n, .	•	•	•	•	•	•	•	•	•	•		313
• •	44	4.6	in cast	-iron	girders,	relatio	n	of,	•	•	•	•	•	•	•	•	•	387
4.6	• •	• •	mome	nt of	inertia f	or, .	•	•	•	•	•	•	•	•	•	•	•	327
4.6	in c	ast-ir	on gird	ers,	proporti	on of,	•	•	•	•	•	•	•	•	•	•	•	387
"	equa	al, to	p and b	otto	m		•	•	•	•	•	•	•	•	•	•		314
"	of c	ast-ir	on gird	ers,	proporti	on of,		•	•	•	•	•	•		•		•	336
4.	" t	ubula	r girde	rs, co	nstructio	on of		•	•	•	•	•	•		•	•	•	374
4.	• •	4.6	44	e	qual, top	and be	ott	om	l	•	•	•	•	•	•			371
• •	4.6	**	• •	te	nsion in	lower,	•	•	•	•	•	•	•	•	•	•		370
• •	41	• •	• •	fo	r floors,	area o	f,	•		•	•	•	•	•	•	•		377
"	••	4.6	4.	m	inimum	area o	f,	•	•	•	•	•	•	•	•			, 383
••	"	4.6	4.6	tì	ickness	of, .	,	•	•	•	•	•	•	•		•	1	. 373
4.6	to	predo	minate		r the web							•						
Flexu	re and	rupt	ure com	pare	ed,	• • •		•	•	,	•	•	•	•	•		,	. 267
64	4.4	44	•		mpared,													
"	4.6	• •	wei	ghts	producii	ng con	pa	rec	d,		•	•		•	•	•	,	. 237
• •	floo	r bea			based or	-	_											
• •																		
4.					esistance													
• •					tance to,													
4.																		
46		46			or,						_							
4.6	valu	ie of			nbol of r													
Floors				-	or streng													
4.4					eam, .													
4.4			s stron			• •			t	•	•	•	•	_	-		•	2
4.4		-		_	e XXI.,		•	•	•	•	•	_	•		•		•	. 53
•					ries and			•	•	•	•	_	•	_			•	. 7
4.			•		load on,	•	•	•	•	•	•	•	•	•	•		•	361
	-	•									-	-	_	_				

																	PAGE
		tance to,															
		oad on, .															, 79
		riments,															500
		Co., testii															504
		e force exe															
		stance in s															
		s of,															
Fibres,	, crushed	on wall,		• •	•	•	•	•	•	•	•	•	•	•	•	•	121
46	crushing	in direction	on of, .	• •	•	•	•	•	•	•	•	•	•	•	•	•	506
• •	elongated	d to elastic	c limit,		•	•	•	•	•	•	•	•	•	•	•	•	236
4.6	end and	side pre s s	ure on,		•	•	•	•	•	•	•		•	•	•	•	120
44	extended	or compr	essed,		•	•	. •	•	•	•			•	•	:	212,	214
4.6	extension	of, graph	ically s	hown,	•	•	•	•		•	•	•	•	•	•	•	222
• •	in a tie-b	eam, cons	id <mark>er</mark> atio	n of,	•	•	•	•	•	•	•	•	•		•		488
• •	load shou	ald not inj	ure the	,	•	•	•	•	•	•		•	•	•	•	•	69
••	measurin	g extensio	on of th	е, .	•	•	•	•	•	•	•	•	. •	•	•	•	221
• •	power of	resistance	e as the	depth	, .	•	•	•	•	•	•	•	•			•	46
4.4	resistance	e as the de	epth of	beam,	•	•	•	•	•	•	•	•	•	•	•	•	43
• •	"	" " le	everage,		•	•	•		•	•	•	•	•	•	•	•	223
€¢	**	directly	as the o	depth,	•	•	•	•	•	•		•			•	•	36
• •	• •	to chang	e of lei	ngth,	•	•	•	•	•			•			•	•	46
••	"	" exten	sion,		•	•	•	•		•	•		•	•	•	•	222
• •	46	" horizo	ontal st	rain,	•	•	•		•	•	•	•	•	•	•	•	43
• •	66	" side p	ressure	·,	•	•	•				•	•	•		•	•	120
€€	resisting	compréssi	ion and	tensio	n,	•	•		•		•	•	•	. •	•	•	403
44	strained	beyond ela	astic lin	nit, .	•	•				•			•		•	•	235
4.6	strength	due to the	ir cohe	renc e ,	•	•	•	•	•	•	•	•	•	•	•	•	35
Fire, re	esisted by	solid timb	er floor	s, .	•	•	•	•	•		•	•	•	•		•	500
		ıms liable															
Firepla	ices, frami	ng for, .			•	•	•	•	•	•	•	•	•	•		•	95
_		, carriage															
44	**	floor bea	ms, .			•	•	•	•	•	•	•	•	•		•	264
64	44	460 6	' and	heade	ers,	•	•	•	•	•	•	•	•	•	•	•	495
**	**	rule for l															
**	••	formula	for soli	d floor	s,	•	•	•			•		•	•		•	503
**	• • • • • • • • • • • • • • • • • • • •	load on	floors,		•	•	•	•	•		•	•	•	•		339,	341
14		44 44															
44	66 66	rule for		•													
**	44	rolled-ir		_													
44	16 66			dista													311

592 · INDEX.

•					PAGE
Forces sh	nown	by a closed polygon,	•	•	418
Force dia	ıgram,	, example of constructing a,	•	•	483
4.6	44	for a roof truss,	3, 4	69,	472
••	44	form a closed polygon, lines in a,			485
• 6	• •	line of weights for a,	- 4	64,	466
	• •	of a roof, measuring the,	•	•	485
6.	4.6	of an unsymmetrically loaded girder,	•	•	455
4.6	4.6	scale of weights in a,	•	•	483
" dia	igrams	s, strains in trusses compared by,	•	•	469
Form of	beam	for distributed load,		•	162
** **	lever		•	•	171
44 44	44	" compound "		•	173
	iron b	beam, economical	•	•	312
Formula,	comp	parison of F with E of common,	•	•	232
• •	for re	esistance to flexure,		•	232
• "	" se	olid floors,	•	•	502
44	4.4	" reduction,	•	•	501
44	mana	agement of a,		_	, 90
4.6	pract	tical application,	•	•	•
		ights, graphic strains,			
-		agrams, reciprocal,			
		, allowance for joints, etc., in chord,			•
"	16	area of uncut part of chord,			
4.6	• •	bearings of metal for struts,			
"	••	compression in chord and struts,			
44	• •	compromise of objections,			
4.6	44	cost inversely as the depth,			
4.6	• •	diagram of forces in,			
4.6	4.6	economical depth,			
4.4	4.6	forces in,			
44	6.6	horizontal thrust in,			
44		irregularly loaded,			
		its relation to a beam,			
4.6	44	liable to sag from shrinkage,			
"	• •	minimum of strains in,			
44	"	number of bays or panels,			_
44	"	peculiarity in strains of,			
44	46	proportions of,			
44	"	resistance to tension in,			
"	66	rule for depth,			
**	"	series of triangles in,			

•		•
	INDEX.	593

•											PAGE
Framed girder, strains in diagonals of,	•	•	•	•	•		•	•	•	•	436
" " lower chord of,	•	•	•	•	•	•	•	•	•	•	439
" " upper " ".	•	•	•	•	•	•		•	•	•	440
" system of trussing in,			•	•	•	•	•	•	•	•	425
" top chord and diagonals of, .			•	•	•	•	•	•	•	•	448
" tracing the strains in,	•		•	•	•			•	•	•	437
" trussing in,	•	•	•	•		•	•	•	. 4	117,	42 5
" unequal reactions of supports o	f,	•		•	•	•	•	•	•	•	451
" with loads on each chord,	•	•		•	•		•	•	•	•	433
" " wrought-iron ties in,	•	•		•	•	•	•	•	•	•	443
" girders, chapter on,	•	•	•	•	•	•	•	•	•	•	402
" compression in, rule for,	•		•	•	•	•	•	•	•	•	447
" usually of wood, chords of .	•	•	•	•		•	•		•	•	444
truss, reaction of supports of,											415
France, testing bridges in,											82
Francis on compression of materials,											446
Funicular or string polygon,											408
Furniture reduces standing room,										•	88
Galileo's theory of the transverse strain,	•	•	•	•		•				•	36
Geometrical approximation to moment of inerti											
" series of values of strains,											
Georgia pine, resistance of,											•
" beams, their weight,	•		•	•	•			•			79
" floor beams and headers,											
" coefficient of in rule,	•	•	•	•	•	•				261,	265
German rolled-iron beams, large,		•	•	•							313
Girder defined, rule,	•	•	•			•		•			94
" history of tubular iron,											_
" plate and rolled-iron, compared with tul	bul	ar,		•						•	367
Girders, distance between,		•					•	•	•	•	94
" headers and carriage beams,											_
Graphic representation of strains,		•	•		•	•	•	•		•	127
" strains checked by computations, .	•	•	•	•	•	•	•			•	132
" " from two weights,											
" " three "											
" " equal weights,											_
" " four " "											143
Graphical representations,											
" of compound loads,											
of moment of inertia,											
	-	-	-	-	-	,		-	-	•	J

L.

ZZZZ.

												1	PAGE
		•	•	•	•	•	•	•	•	•	•	•	127
••		•	•	•	•	•	•	•	•	•	•	•	114
. ***		•	•	•	•	•	•	•	•	•	•	•	113
_ ====		•	•	•	•	•	•	•	•	•	•	•	406
		•		•	•	•	•	•	•	•	•	•	223
		•		•	•	•	•	•	•	•	•	•	27
· · · · · · · · · · · · · · · · · · ·	-	•	•	•	•	•	•	•	•	•	•	•	60
	•	•	•	•	•	•	•	•	•	•	•	•	80
	-	•	•	•	•	•	•	•	•	•	•	•	504
	•	•	•	•	•	•	•	•	•	•	•	•	95
	•	•	•	•	•	•	•	•	•	•	•	96,	196
	•	•	•	•	•	•	•	•		•	•	•	97
	•	•	•	•	•	•	•	•	•	•	•	96	97
.>		•	•	•	•	•	•	•	•	•	•	•	497
		•	•	•	•	•	•	•	•	•	•	•	27 0
		•	•	•	•	•	•	•	•	•	•	•	2 66
		•	•	•	•	•	•	•	•	•	•	•	495
	•	•	•	•	•	•	•	•		•	•	•	349
Sent. Y	wyms	5,	•	•	•	•	•	•	•	•	•	•	271
		rol	led	-ir	on	•	•	•	•	•	•	•	349
	. •	•	•	•	•	•	•	•	•	•	•	•	271
, commente	:a .	•	•	•	•	•	•	•	•	•	•	•	350
· Carrier	. •	•	•	•	•	•	•	•	•	•	•	•	94
• • • • • • • • • • • • • • • • • • • •	. •	•	•	•	•	•	•	•	•	•	•	•	101
was the Section	•	•	•	•	•	•	•	•	•	•	•	•	100
~ a tet		•	•	•	•	•	•	•	•	•	•	•	20 0
.~	•	•	•	•	•	•	•	•	•	•	•	•	497
•	Table				•	•	•	•	•	•	•	•	519
1 4 miles 20			able	e X	VI	••	•	•	•	•	•	•	523
	e IX	••	•	•	•	•	•	,	•	•	•	•	516
~ . The 47.4	K Ta	ble	X	II.	•	•	•	•	•	•	•	•	520
The Three	XI,	•	-	•	•	•	•	•	•	•	•	•	518
ं अन्य स्थाप्ता	Table	e X	V.,	•	•	•	•	•	•	•	•	. •	522
To me with the	ble?	ζ.,			•	•	•	•	•	•	•	•	517
24-1-120 201	res, T	abl	e N	X I V	••	•	•	•	•	•	•	•	521
" October 3 mile Co	. •	•	•	•	•	•	•	•	•	•		261,	_
			•	•	•	•	•	•	•	•		120,	
Course to a sellage	• •	•	•	•	•	•	•	•	•	•	•	•	79
in the second se		•	•	•	•	•	•	•	•	•	•	•	495
On the Carte of th		•	•	•	•	•	•	•	•	•	•	•	120

INDEX.		595
•	ì	PAGE
History of the rolled-iron beam,	•	313
" " tubular iron girder,	•	367
Hodgkinson on compression of materials,	•	446
Hodgkinson's edition of Tredgold on Cast-iron,	•	386
" experiments,	•	500
" rule for cast-iron, load at middle,	•	388
" "set" in testing,	•	505
" value of elasticity of iron,	•	232
Hoes' foundry, weight of men at,	•	85
Homologous triangles, proportions by	•	487
Hooke's contribution to the science,	•	37
Horizontal and inclined ties compared, strains in	•	472
" strain in roof truss,	173.	474
" resisted by iron clamps,	•	489
" strains in framed girders,	14 1,	443
" measured arithmetically,	•	412
" " shown by bent lever,	•	42
" " graphically,	•	406
" thrust in a framed girder,	•	403
" tie, raise wall of building to get,	•	478
Hypothenuse of right-angled triangle,	•	486
Important work should be tested, materials in	•	244
Inclined tie-rod of truss, enhanced strain,	•	477
Increased strains in roof truss from inclined tie,	174,	478
Index of strength for unit of material,	•	48
India-rubber, experiment on,	•	212
" largely elastic,	•	211
Infantry, space required for,	•	83
Infinite series, sum of an,	•	476
" value of coefficient,	•	227
Infinitesimally small, differential is	318,	319
Insurance offices, load on floor of,	340,	341
Integral of moment of inertia,	•	319
" calculus, maximum ordinate,	180,	184
Integration, computation by,	•	228
" rule for strain in lever by,	•	169
" strain by,	•	150

312

489

" load upon wrought,

" bolts and clamps for tie-beam,

•	•												PAGE
Iron be	eam, load at middle upon,	•	•	•	•	•		•	•	331	I, 3	32 ,	333
46	" progressive development of,	•	•	•	•	•		•	•	•	•	•	312
Jackso	n's foundry, weight of men at, .	•	•	•	•	•		•	•	•	•	•	85
Kirkal	dy's experiments,	•	•	•	•	•		•	•	•	•	•	500
Lamina	ated and solid beams compared,	•	•	•	•	•		•	•	•	•	•	34
Lateral	l thrust by cross-bridging,	•	•	•	•	•		•	•	•	•	•	303
Lead h	as but little elasticity,	•	•	•	•	•	• •	•	•	•	•	•	211
Leibnit	tz's theory of transverse strains, .	•	•	•	•	•		•	•	•	•	•	37
Length	and weight, relation between, .	•	•	•	•	•	•	•	•	•	•	•	65
44	" depth, ratio " .	•	•	•	•	•	•	•	•	•	•	•	240
4.6	of beam, rule for,	•	•	•	•		•	•	•	•	2	4 8,	249
"	" with load distributed,	rule	for	•	•	•	•	•	•	•	•	•	253
"	" " in dwellings,	•	•	•	•		•	•	•	•	2	62,	263
**	" " first-class stores, .	•	•	•	•		•	•	•	•	2	65,	2 66
**	" rolled-iron beam, load at midd	ile,	•	•	•	•	•	•	•	•	3	31,	332
£ 6	" lever, rule for,	•	•	•	•	•	•	•	•	250	, 2	56,	257
4.6	and depth of framed girder,	•	•	•	•		•	•	•	•	•	•	422
"	to depth in tubular girder, ratio	of,	•	•	•		•	•	•	•	•	•	382
Lever a	and beam compared,	•	•	•	•	•	•	•	•	•	•	•	244
66	" deflection in	•	•	•	•	•	•	•	•	•	•	•	237
4.6	" strength "	•	•	•	•		•	•	•	•	•	•	55
4.4	" " symbols "	•	•	•	•		•	•	•	•	•	•	49
"	arms in inverse proportion as the	wei	ght	s,	•		•	•	•		•	•	39
"	at limit of elasticity, load on	•	•	•	•		•	•	•		•	•	248
**	by distributed load, deflection of	•	•	•	•	•	•	•	•	•	•	•	255
** (deflection in a,	•	•	•	•		•	•	•		•	•	213
" (destructive energy in a	•	•	•	•	•	•	•	•	•	•	55.	III
" (dimensions of a deflected,	•	•	•	•		•	•	•	•	•	•	251
" (distributed load on rolled-iron,.	•	•	•	•		•	•	•	•	•	•	338
**	effect of weight at end of,	•	•	•	•		•	•	•	•	•	•	47
" 1	formula for deflection in a,	•	•	•	•	• •	•	•	•	•	•	•	229
4.4	" modified to apply to a, .	•	•	•	•	• •	•	•	•	•	•	•	54
** 8	graphical strains in a double, .	•	•	•	•	• •	•	•	•	•	•		113
" 1	load at end of rolled-iron,	•	•	•	•		•	•	•	•	•	•	336
" 1	principle in transverse strains, .	•	•	•	•	• •	•	•	•	•	•	•	38
4.6	" demonstration,	•	•	•	•	• •	•	•	•	•	•	•	3 9
4.4	" effect of several weights,		•	•	•		•	•	•	•	•	•	62
**	" unequal weights,	•	•	•	•		•	•	•	•	•	•	39
"]	promiscuously loaded,	•	•	•	•	•	•	•	•	•	•	•	175
"	" depth of												IΧ

505

181

..

tests of the.

Limited application of formula for value of h in carriage beam, . . .

PAGE
Lines and forces in proportion,
Live load, measurement of a,
" " weight of people,
Load and strain, various conditions,
" at limit of elasticity in a beam
" " any point, effect on beam,
"""""test of rule,
" " " rule for strength,
" " " safe rule,
" " " " strain at any point,
" " " to rupture a cast-iron girder,
Load at any point on tubular girder,
" " end of rolled-iron lever,
" " middle, pressures,
""""of beam,
" · · · · · deflection,
""" safe rule,
" " cast-iron girder,
" " rolled-iron beam,
" analyzed, compound
" strains and sizes, compound
" deflection of beam with distributed
" " lever "
" distributed, rules for size of beam with
" safe rule,
" equally distributed, effect,
" " at middle, 60
" for given deflection in a lever,
" not at middle, effect at middle,
" " " pressure on supports, 40, 41
" on beam, at middle and distributed,
" " rule for distributed
" " lever, distributed and concentrated,
" " bridge, Tredgold's 80
" " floor, components of
" " Tredgold's remarks, 80
" " estimate, 81
" " the greatest 80
" " per superficial foot,
'' '' heam its nature

INDEX. 599.

																PAGE
Load on floor	r-beam, 1	rule, .	• •	•	•	•	•	•	•	•	•	•	• •	•	• •	78
" " rolle	ed-iron fl	loor bea	m, .	•	•	•	•	•	•	•	•	•		•	• •	340
" " head	ier	• . •		•	•	•	•	•	•	•	•	•		•	• •	196
" " carr	iage bear	m,	•	•	•	•	•	•	•	•	•	•		•	105,	107
4 4 4	• ••	with	one h	ead	er,	•	•	•	•	•	•	•		•		99
" roof	per foot	horizo	ntal,		•	•				•	•	•		•		480
** ** **	" inc	lined fo	ot su	perf	icia	1,	•	•	•	•	•	•		•		480
" " supj	ports ari	thmetic	ally c	omj	pute	ed,	•	•	•	•	•	•		•		456
44 (4	, pro	portion	of, .	•	•	•	•	•	•	•	•	•		•		119
** 44 6	' fro	m weigi	ht not	t at	mid	ldle	€,	•	•	•		•		•		56
· " " each	suppor	t from (ınsyn	nme	tric	al l	oac	din	g,		•	•	• •			451
" per soot	on floor	, for pe	ople.			•		•	•	•	•	•		•		83
** ** **		66 po	unds,		•	•	•	•	•	•	•			•		87
•• •• ••	superfic	cial of f	loor.	70 p	oui	nds	,	•	•	•	•	•	• •	•	88,	264
" on leve	r, promi	scuous		•	•	•	•	•	•	•		•		•		175
" proport	ioned to	square	of de	pth	of t	oea	m,	•	•	•	,	•		• ,		123
" upon a	header,			•		•			•	•	•	•		•		96
** ** **	bridle i	ron, .	• •	•			•		•	•	•	•				98
	carriage	beam,		•	•	•		•		•					•	98
	roof tru															
- 4	ch supp															
" " tic	e-beam o	of a roof	· .		•				•	•	•	•	• •		481,	483
Loads between	n the su	pports,	divid	ling	un	syn	am	etr	ica	1		•			•	453
" compa	red, con	centrate	ed and	d di	stri	but	ed			•	•			•	•	61
Loaded, fram	ed girde	r irregu	larly		•				•	•	•			•		451
	heavily,															
Locust. coeffi																
" resis	stance of				•	•	•	•	•	•	•	•		•		120
Logarithms, o	example	of com	putat	ion	bу,		•	•	•	•	•	•			•	311
Mahan's editi	ion of M	oseley's	s wor	k,	•	•	•	•	•	•	•	•		• •	•	251
Mahogany, re	esistance	of, .		•	•	•	• (•	•	•	•	•			•	120
Males, weigh																
Maple, resist																
Mariotte's the	eory of t	ransver	se str	ains	5,	•	•	•		•	•	•			•	37
Material, kno	wledge	of elast	ic pov	wer	of a	any	•	•	•	•	•				•	244
· defi	ned, uni	t of, .		•	•	•		•	•	•	•	•			•	29
Materials for	importa	nt 'work	to be	e tes	sted	•	•	•	•	•	•	•		- •	•	244
" wei	ights of	building	g.			•	•		•	•	•	•		• .	•	504
••	• • • • • • • • • • • • • • • • • • • •	**													534,	
• • of •	construc	tion, we														

.600 INDEX.

· PAGI
Materials of construction of floors,
" " in a roof, weight of,
Maximum moment defined,
" ordinate by the calculus,
" strain analytically defined
" graphically shown,
" compound load
" location analytically defined,
" three concentrated loads,
" on middle one of three headers,
" " outside " " "
" of three loads on carriage beam,
Maxwell, reciprocal frames and diagrams by Prof 418
Measure of extension of fibres,
" forces in equilibrium
" symbol for safety tested
" resistance of cross-bridging,
" strains in truss with inclined tie, 475
" symbol for safety,
Measured arithmetically, strains
" horizontal strains
Measuring strains in roof truss,
Men, actual weight of,
" effect of when marching,
" space required for standing room,
Menai Straits and Conway tubular bridges,
" " weight of bridge over,
Merrill's Iron Truss Bridges,
Methods of solving a problem, various
Military, estimate of space required by,
" weight of,
" step. the effect of,
Mill floor, load on
Minimum of strains in framed girder,
" area of tubular girder,
Model of a floor of seven beams,
" iron tubes experimented on,
Modulus of elasticity for wrought-iron,
" "rupture by Prof. Rankine,
Moment of inertia defined.

••	•	_	_																PAGI
Momen	t of in																•	• •	320
••	••	••		metic															314
"	44	••		netrica															315
"	••	4.		e calc															_
•				of par															322
44	••	4.6		n gra															
44	4.	• • •	_	outed,															
44	••	••		ral ru															
**	44	4.6	•	pariso														_	
**	66	66		ortion															314
"	66	• • • • • • • • • • • • • • • • • • • •		tance														_	
11	4.6	66		olled-i			as.										•		
"	44	"	• •	•	**	44					_						•		
"	4.6	44	61	"	"	• • • • • • • • • • • • • • • • • • • •			ble		•				•				498
44	4.6	4.6		ange													,		327
44	44	44		olled.											•	•	•	•	349
44	6.6	_	ht de	fined.	•	• •	•	٠	•	•	•	•	•	•	•	•	•	•	47
"	"	66		leve	•			•				•			•	•	• •	•	111
44	4.6	46		m of l											•	•			
46		66		midd															•
Momen		-		_															188
• •	cap	pacity	of tul	bular	gird	er b	y.	•	•	•	,	•	•	•	•	•		•	3 69
44	loa	id at n	niddle	e, tub	ular	gird	er t	y,	•	•	•	•	•	•	•	•	'• •	•	370
Momen	•																		87
Mortisu	ng. th	e wea	kenir	ng effe	ect of	f, .	•		•	•	•	•	•	•	•	•		•	195
••		ımagiı	_																97
••		rriage																	•
Mosele					-														_
46		ulus	_	•	-														50
**	sym	bol fo	r stre	ngth	4.6	4.6	•		•	•	•	•	•	•	•	•		•	49
Mosele	•																		
Movem	ent of	f men	, effe	ct of,	•	•	•	•	•	•	•	•	•			•.		•	86
Negativ	•			_															
Neutral	axis,	dista	nce fr	om,	. •	•	•		•	•	•	•	•	•	31	5,	318,	319,	324
44	4.	in a f	frame	d gird	er.		•	•	•	•	•	•	•	•	•	•		•	402
44	4.6	flange	e to b	e dist	ant f	rom,	,	•	•	•	•	•	•	•	•	•	•	313,	314
44	line,	•				•	•	•	•	•	•	•	•	•	•	•	• •	•	45
4.	• 6	defin	ed,			•	•	•	•	•	•	•	•	•	•	•		•	37
4.6	4.	dista	nce o	f fibre	s fro	m,	•	•	•	•	•	•	•	•	•	•		•	222
44	44	at mi	iddle	of de	pth.				•	•	•	•	•	•	•			•	45

PAG
Neutral axis at any depth, effect,
" in a deflected lever,
" " tie-beam, fibres near
New England fir, experiment on
Oak, coefficient in rule for,
" live, resistance of,
Office buildings, formula for solid floors of,
" rolled-iron beams for,
" " " Table XVIII., 526, 52
Openings in floors, framing for,
Ordinate, location of longest, compound load,
Ordinates measure strains, 128, 130, 134, 136, 139, 140, 167, 168, 172, 173, 177
179, 181, 183, 184, 197, 198. 201, 20
Ordinates measure strains in lever,
Panels in a framed truss, number of,
Parabola, a polygonal figure
" the curve of equilibrium is a
" expression for the curve,
" form of scale of strains,
" side of beam from a
" " lever "
" defines strains in lever,
" form of web of cast-iron girder is a
Parabolic curve, moment of inertia,
" " limits the strains,
" form of floor arches,
Parallelogram of forces in framed girders,
People as a live load, weight of,
" to weigh them,
" floors covered with,
" " required for a crowd of,
" on floor, crowd of,
" " their weight,
" " " per foot,
"their weight, authorities,
Philadelphia, iron beams at Exposition at,
Phœnix Iron Co., beams tested by,
Planning a roof, general considerations,
" " an example in
Plaster of Paris, fire-proof quality of,

																			PAGE
Plaster	ed ce	iling	of a re	oom, .		•	•		•	•	•	•	•	•		•	•	•	303
Plaster	ing, v	veigh	nt of,			•	•			•			•	•	•	•	•	•	7 9
4.0	F	erce	ptible (deflectio	n inji	ıriou	s t	0,	•	•	•	•	•	•		•	•	•	26 0
Plate b	eam i	forme	ed with	angle i	rons,	•			•	•		•	•	•		•	•	•	312
" g	irder	or be	eam,		• ,	•	•	•		•		•	•		•	•	•	•	367
" a	nd tu	bulaı	girde	rs compa	ired.		•		•	•	•	•	•	•	•				377
" ov	rer a 1	tubul	lar gird	ler, adva	ntage	s of	a		•	•	•	•	•	•	•	•		•	377
Polygo	n, for	ces	shown	by a clos	sed.	•			•	•	•	•	•	•	•	•	•	•	418
• •	fui	nicul	ar or st	tring .				•	•	•	•	•	•	•	•	•		•	408
• •	lin	es in	force	diagram	form	a cl	ose	ed	•	•	•	•	•	•	•	•			485
Polygo	nal fi	gure,	, parab	ola, .	•	•	•	•	•	•	•	•	•	•	•				161
Pores o	of wo	od, s	size of,			•	•	•			•	•	•	•	•			•	120
Positio	n of v	veigt	nt on a	beam, .		•	•	•	•	•	•	•	•	٠	•	•		•	54
Positiv	e qua	ntity	, dedu	cting a r	egati	ve e	qu	als	ad	din	g	•	•	•	•	•		•	428
Post, r	ule fo	r thi	ckness	of a, .		•	•	•	•	•	•	•	•	•	•	•		147,	449
Posts,	Bake	r's fo	rmula	for,		,•	•	•	•	•	•	•	•	•	•	•		•	446
Precau	tions	in re	gard to	o consta	nts, .		•	•	•	•	•	•	•	•	•			•	243
Precise	rule	for c	carriage	e beams,	for d	lwell	lin	gs,		•	•	•		•	•	273	, 2	282,	285
••	4.4	• •	4.6	••	fi	rst c	las	ss s	tor	es.		•	•	•	•	275	, :	282,	286
66	4.6	• •	"	• •	with	two	ec	luic	dis	tant	h	ead	ers	,	•				287
46	• •	• 6	• •	• ••	**	4.6	he	ead	ers	, fo	r	dwei	lliı	ngs	,			•	292
44	••	• •	••	••	**	• •		"	1	• •	í	irst-	cla	\\$ S	sto	res	,	•	292
4.6	46	4.6	4.6	••	• •	• •		• •	•	a	nd	one	e t	ail	be	am,		•	283
4.6	4.6	• •	• •	• •	• •	• •	ec	quie	dis	tant	t	hea	de	rs	an	d	on	e	
								tai	l b	ean	n,	•	•	•	•	•		•	290
6.6	• •	• •	• •	••	• •	• •	h	ead	ers	an	d	two	ta	il t	ea	ms,	•		279
Pressu	re, co	nditi	ions in	loaded	beam,	, .	•	•	•	•	•	•		•				•	39
44	or	sup	port fr	om load	not a	t mic	ldl	c,		•	•	•	•	•				40	, 41
Proble	m, va	rious	s metho	ods of so	olving	ga,	•	•		•	•	•	•						72
Promis	scuou	s loa	d, scal	e of stra	ins, .	•	•	•	•	•	•	•	•	•	•	•			175
6.0	•	• 0	on l	ever, .		•	•	•	•		•	•	•	•		•	•	•	167
Propor	tion 1	betwe	een flar	nges and	web,	••		•	•		•	•		•		•	•		313
Propor	rtions	of a	frame	d girder,		•	•	•	•		•	•		•		•	•	•	422
Quetel	et on	weig	ght of 1	people,		•		•	•			•		•	•				83
Rafters	, dim	ensi	ons of,		•		•			•		•		•	•	•	4	4 9 0,	491
4.4	inc	rease	d, com	pressive	strai	n in	•		•		•	•	•		•	•		•	474
4.	to b	e avo	oided,	transver	se str	ains	in	•		•			•	•	•	•		•	460
**				from be															479
Rankii				on of ma															
••				g forces,															

PAG	E
Rankine on modulus of rupture,	jO
" moment of inertia,	18
Rate of deflection per foot lineal,	2
""" in floors,	0
" rise in brick arch in floor,	6
Ratio of depth to length in tubular girders,	}2
Ray's Algebra referred to,	16
Reaction of fibres on removal of force,	? 2
" from points of support,	13
" of supports equal to load,	19
" " " " shearing strain,	9
" " from unsymmetrical loading,	, I
" " of framed truss,	5
Reciprocal figures explained,	!2
" frames and diagrams,	8
" lettering of lines and angles,	
Resistance of materials,	
" " " to destructive energy,	8
" its measure,	3
" directly as the breadth,	3
" increases more rapidly than the depth, . :) 4
" as the area of cross-section,	,2
" not as the area of cross-section,	
" to compression,	15
" " extension,	5
" " and compression	
" " " equal,	15
" " or to deflection,	22
" summed up,	25
" "flexure,	35
" " rules for,	12
" value of F , the symbol of,	3 C
" " of floor beams,	Ю
" of a lever, rule for,	ŧ8
" to rupture,	56
	16
	47
" of fibres to change of length,	46
" " as the depth of beam	
	36

INDEX.	•	605

				PA	\G E
Resi	stance	of fibres to extension and compression,	•	• •	35
	••	" " expression for,	•	2	24
	4.6	to extension as the number of fibres,	. •	2	22
	64	as the distance of fibres from neutral line,	•	2	22
	"	of cross-bridging, principles of,	•	3	04
	44	increased by cross bridging,	•	305, 3	10
	4.6	of a bridged beam,	•	3	04
	4.6	in cross-bridging, number of beams giving	•	3	109
Rise	of brie	ck arch in floor, rate of,	•	3	46
Rive	t holes	s in iron girders, allowance for	•	• • 3	68
Rolle	ed-iror	n beams, chapter on,	•	• • 3	12
• •	••	beam, history of the,	•	3	13
4.4	••	beams preserable to cast-iron,	•	3	99
• •	• •	" means of manufacture,	•	3	86
• •	4.6	" have superseded cast-iron,	•	3	86
64	• •	" to be had in great variety,	•	3	13
44	• •	" distance from centres,	•	3	42
44	44	beam, moment of inertia for,	•	326, 3	28
"	4.4	" weight of,		· · 3	40
"	6.6	" plate beam and tubular girder,	•	3	67
"	**	" load at any point,	•	333, 3	34
"	6.6	" " " Table XVII.,	•	3	35
4.1	4.	" " " middle,	•	3	31
"	44	" " distributed,			37
• •	4.6	beams for dwellings, etc.,	•	4	98
• •	44	" distance from centres,	•	3	43
"	**	" first class stores,	•	4	98
• 6	4.4	" " distance from centres, .	•	3	44
4.6	4.6	" Table of elements of,	•	4	.98
• •	6.6	" elements of, Table XVII.,	•	5 24. 5	25
• •	4.4	" Tables of,	•	4	95
• •	4.6	" for dwellings, Table XVIII.,	•	52 6, 5	27
	* *	" first-class stores, Table XIX.,	•	528 , 5	29
4.	4.6	lever, load at end	•	3	36
••	4.6	" distributed,	•	3	38
• •	4.4	headers for dwellings,	•	3	49
• 6	4.6	" " first-class stores,		3	50
• •	••	carriage beam with one header, for dwellings,		3	5 I
	44	" " " " first-class stores,		3	52

too6 INDEX.

Rolle	ed-iron	carriage	beam	with													
				١													35 ·
**	44	• •	"	66											ams,		
																• •	359
44	4.6	4.	44	4.6	two	hea	ade	rs a	nd 1	two	se	ts of	ftail	be	ams,	for	
					d	wel	ling	rs, e	etc.,	•	•	•	• •	•	•	354,	3 5
44	4.6	4.4	4.6	4.6	two	hea	ade	rs a	nd 1	wo	set	ts of	tail	bea	ams,	for	
					fi	rst	clas	s st	ore	S,	•	•		•	• •		35
4.	• ••	4.6	64	4.6	thre	ee h	ead	ers,	for	r dv	rell	ling	s, .	•	•	360,	36
• •	••	4.6	44	. ••		•	••		••	firs	t-c	lass	sto	res,	•	361,	36.
Roof,	gener	al consid	deratio	ns in	pla	nnir	ng a	•	•	•	•	•		•		•	47
• •	an ex	ample in	plann	ing a	a, .	•		•	•	•	•	•		•		, •	48
• •	beam	s, increas	se in w	eigh	t of,			•	•	•	•					. •	47
4.		es, chapte															
• •	••		arison														
••	••		ing a c														
4.4	• •		dered a														
••	• •		and wit														
4.4	truss,	force di															
4.6	• •	horizon	tal stra	in in	١, .			•	•	•	•	•		•			473
4.6	• •	support															
Rule	for flo	or beams															89
		ipture. v															•
		e base of															
• •		sistance															
		6.6	" the													_	
• •		44	" ele														
• •	m	odulus c								•							
4.6		quilibriu															
4.		y compre															
4.6	•	cross s															
66	ie																
6.6		s resistar nd flexur															
4.6		iu nexuit															
44	•	. 44	rules													_	_
			comp														
		isues fro															
••		eams of v															
••		sistance		_											• •	•	100
• •	of	cast iro	n girde				-								• •		390
• •	• •	• •	• •	rc	latio	n of	fla	nge	s,	•	•	•		•		•	387

																			1	PAGE
Sase	load	at an	y point	on ca	st-iro1	n gir	der	•	•	•	•	•	•	•	•	•	•	•	•	391
• •	distri	bute	l load,	effect	of at a	ny j	poin	it c	n c	as	t-ir	on	gir	der	•	•	•	•	•	391
• •	and 1	break	ing loa	ds com	parec	i	•	•	•	•	•	•	•	•	•	•	•	•	•	68
• •	load,	valu	e of a,	the sy	mbol	for	a,	•	•	•	•	•	•	•	•	•	•	•	•	235
• •	loads	s, rule	es for st	rength	١,	•	•	•	•	•	•	•	•	•	•	•	•	•	•	70
44	by ru	iles fo	or stren	gth ye	t too	smal	ll, b	ea	m	•	•	•	•	• ·	•	•	•	•	•	77
• 6	beam	shou	ıld app	ear as	well	as b	e,	•	•	•	•	•	•		•	•	•	•	•	235
• •	load	on tu	bular g	irder,		•	•	•	•	•	•	•	•	•	•	•	•	•	•	36 9
Safet	y in 1	floors				•	•	•	•	•	•	•	•	•	•	•	•	•	•	28
••	pre	cauti	ons to	en sure			•	•	•	•	•	•	•	•	•	•	•	•	•	2 44
••	me	asure	of sym	bol for	·,	•	•	•	•	•	•	•	•	•	,	•	•	•	•	239
• •	<i>a</i> ,	in ter	ms of	B and	F,	sym	bol	fo	r,	•	•	•	•	•	•	•	•	•	•	2 68
••	cau	tions	in rega	ird to	symbo	ol fo	r,	•	•	•	•	•	•	•	•	•	•	•	•	71
Sagg	ing o	f fran	ned gir	der fro	m sh	rink	age,	•	•	•	•	•	•	•	•	•	•	•		450
Scale	e, stra	ains n	neasure	d by,		•	•	•	•	•	•	•	•	•	•	•	•	•	•	111
• •	of c	lepth	s, comp	ound	load o	on le	ever	•	•	•	•	•	•	•	•	•	. 1	•	•	172
• •	" s	train	s and th	ie calc	ulus,	•	•	•	•	•	•	•	•	•	•	•	•	•	•	161
44	4.4	44	demo	nstrate	d, .	•	•	•	•	•	•	•	•	•	•	•	•	•	•	134
"	••	••	applie	d prac	ticall	y, .	•	•	•	•	•	•	•	•	•	,			411,	414
"	6.6	"	to be	careful	lly dra	awn,		•	•	•	•	•	•	•	•			•	•	412
"	460	4.6	for de	pths, .			•	•	•	•	•	•	•	•	•	•	•	•	•	132
46	. 44	44	made	from g	iven '	weig	thts.	,	•		•	•	•	•	•	•	•	•		409
44	4.	4.6	load a	t any j	point,	•	•	•	•		•	•	•	•		•	•			128
• •	• •	••	promi	scuous	load	, .	•		•	•	•	•	•	•		•	•	,	167,	175
••	••	• 6	for tw	o weig	hts,		•	•		•	•	•	•	•		•	•			133
••	44	4.4	distrib	outed a	and o	ne c	onc	ent	rate	ed	loa	d,	•	•	•			•		179
• 4	6.6	4.6	4.0	1	" tv	vo		• •			loa	ds,)	•		•			184,	187
• •	44	44	compo	und lo	ad or	be:	am,	•	•	•	•	•	•	•	•	•	•		•	177
••	"	4.4	• •																172,	
	4.6	4.6	carriag	ge bear	n witl	h thi	ree	hea	ıde	rs,		•	. :	197,	Iç	8,	201	•	202,	208
• •	** 5	veigh	ts for a																	
Scien			rican qu																	302
			y strair																	505
			elliptic																	164
44			of beam																	162
4.4	• •		4 44	from																163
66				graph																•
44	•• 1	lever	a triang	-	_															170
Shea			ransver	'																116
			equals																	119
			-			•	_	-												-

																				PM	32
Shear	ing s	train	gra	phically	showi	1,	•	•	•		•	•	•	•	•	•	•	•		I	15
44		• •	pro	vided fo	r, .	•	•	•	•	•	٠.	•	•	•	•	•	•	•		. 12	23
4.6		• •	at e	end of b	eam,	•	• •	•	•	•	•	•	•	•	•	•	•	•.		I	81
••		••	in t	ubular g	girder,		•	•	•	•	•		•	•	•	•	•	•	37	4, 3	75
Shrin	kage	of ti	mbe	rs, dera	ngeme	nt	fro	m,	•	•	•	•	•	•	•	•	•	•		4!	50
Side o	of bea	m g	raph	ically sl	hown,	sh	ape	of	•	•	•	•	•	•	•	•	•	•		12	12
** 1	pressi	ure,	resi	stance t	0, .	•	•	•	•	•	•	•	•	•	•	•	•	•		. 11	19
Size a	ınd st	reng	gth,	relation	of, .	•	•	•		•	•	•	•	•	•	•	•	•		. 3	ļI
Skew	-back	of t	orick	arch in	floor,		•	•	•	•	•	•	•	•	•	•	•	•		34	15
••	4.	brio	ck a	rch foot	ed on,	•	•	•	•	•	•	•	•	•	•	•	•	•		39	ŝ
••	• •	tie	rod	to hold	arch o	n,	•		•	•	•	•	•	•	•	•		•		39	S
Slate,	brick	c arc	ches	keyed	with,	•	•	•	•	•	•	•	•	•	•	•	•	•		34	15
4.4	on r	oof,	wei	ght of,		•	•		•	•	•	•	•	•	•	•	•	•		49	0
Slidir	ng str	ains,	, ex	p erimen	ts on,	•	•	•	•	•	•	•	•	•	•	•	•	•	50	5, 50	6
4.	•	•	in	Georgia	pine,	lo	cus	t a	nd	wł	iite	oa	k,	Ta	ble	X	XX	V	III.,	55	7
••	•	•	• •	spruce,	white	pir	ne a	and	l he	em	loc	k,		4 (•	X	XX	IX.		55	3
64	sui	rface	, br	eaking v	veight	рe	r s	qua	are	in	ch,			• •		ΧI	.V.,	•		56	4
Snow	on ro	oof,	weig	tht of,			•	•	•	•	•	•	•	•	•	•		•		43	0
Soldi	er s or	a fi	loor,	weight	of, .	•	•	•	•	•	•	•		•	•	•	•	•		8	3
Solid	and 1	lami	nate	d beams	s comp	ar	ed,	•	•	•			•	•	•	•	•	•		3-	‡
64	timbe	er flo	ors	not so	liable t	o l	bur	n,		•		•	•	•	•	•	•	•	. • .	500)
44	66		44	reducti	on of f	or	mµ	la i	for,	•		•			•	•		•	501	, 502	ļ.
46	44		64	should	be pla	ste	erec	i,	•		•	•	•	•	•	•		•		501	
u	44		44	Table f	or,	•		•	•		•	•	•	•	•	•		•		504	
44	64		44	thickne	ess of,	•				•	•	•	•	•	•	•		•	500	, 501	
**	66		44	Table 2	XXI.,	•				•		•		•	•	•	•	•		532	
Space	on a	floo	r oc	cupied l	by men	,		•		•	•	•		•	•	•	•	•		85	
4.4	44 44	"	re	quired b	у реор	le	,	•	•	•			•		•	•	•			83	
• •	44 44	4.		4.6	' men	w	hei	a n	nov	/in	g,	•	•	•	•	•	•	•		86	
4.4	44 44	••	red	uced by	furnit	ure	e,	•	•		•	•	•	•	•	•	•	•		83	1
Sprud	e, co	effici	ent	in rule f	or, .	•	•		•		•	•	•	•	•	•	•		2 61,	265	ł
••	res	sista	nce	of, .		•				•	•	•	•	•	•	•	•	•	120,	12 I	ı
4.	b e	ams,	, we	ight of,	• •	•		•	•	•	•	•	•	•	•	•	•	•		79	
4.6	flo	or b	eam	s and he	eaders,	•	•	•	•	•	•	•	•	•	•	•	•			495	I
Squar				for stre																	i
-				l perpen	•															_	
				red in b					_												
	-			equilib	_	_														,	
				on carr														•	. 19	_	
Stairs													•	•	•	•		•	. 9	Ď	

	PAGE
Stairway opening in floor,	. 201
" openings, carriage beams,	95, 196
Step, effect of military	. 86
Stiffness and strength compared,	67, 268
" resolvable, rules for,	. 270
" differ from rules for strength, rules for	. 235
" requisite in floor beams,	. 260
Stores for light goods same as dwellings,	. 264
" floor beams for first-class	. 264
" headers for first class	. 271
" carriage beams for first-class, precise rule for 275, 28	32, 286
" " with one header, for first-class	. 273
" " " two headers, " " precise rule,	. 292
" " equidistant headers, for first-class, pre	•
cise rule,	. 289
" " headers and one tail beam, for first-class	•
" " headers and two tail beams, for first-class	s. 276
" " three headers, the greatest strain being a	•
middle header,	. 299
" " three headers, the greatest strain being a	
outside header,	. 295
" load on tubular girders for first-class	. 380
" tie-rods of floor arches of first-class	. 348
" Georgia pine beams for first class, Table VIII.,	. 515
" " headers " " XVI.,	. 523
" hemlock beams " " " V.,	. 512
" " headers " " " XIII.,	. 520
" spruce beams " " VII.,	. 514
" headers " " XV	. 522
" white pine beams " " " VI.,	. 513
" " headers " " " XIV	. 521
	8, 529
Straight line, equation to a,	. 171
Strains useful, knowledge of gradation of	. 433
by movement, increase of,	. 84
" analytically defined,	. 137
	8, 415
" graphically represented,	
" checked by computations, graphical	_
" graphically shown, shearing	. 115

										PAGI
	Strain	is measured by ordinates,		128,	130,	167,	168,	177,	201,	20
	6.6	" " lines,	•	•	• •	•	• •		•	40
	4.6	proportioned by triangles,	•		• •	•	• ,•		•	48
•	Strain	analytically defined, maximum	•	•	• •	•	• •	•	181.	18.
	• •	graphically "	•	•	• •	•			•	17
	4.6	analytically. " location of,	•	•		•	• •	•	179.	18.
	••	at any given point graphically shown,	•	•		•	• •		•	12
	• •	" point from a distributed load, .	•	•		•	• •		•	16
	Strain	s demonstrated, scale of,	•	•		•	• •		•	13
	4.4	from given weights, to construct scale	of,	•		•			•	40
	• •	" promiscuous load,	•	•		•		• •	•	16
	• •	" distributed load, by the calculus.	•	•		•	• •		•	15
	• •	" two weights,	•	•		•			•	10
	4.6	"""graphic	•	•		•			•	13
	**	of compound load analyzed,	•	•	• •	•	• •		•	17
	• 1	" maximum	•	•	• •	•	• •	•	186,	18
	• •	" " greatest at concentra	ate	d lo	ad,	•	• •		•	18
	4.	and dimensions, compound load,	•	•		•			•	17
	Strain	at first weight, with equal weights	•	•		•	• •		•	14
	• •	" second weight, with equal weights,	•	•		•			•	14
	• •	" any " " " "	•	•		•			•	15
	Strains	s in a beam, graphical	•	•		•			•	11.
	Strain	"" " loaded at any point,	•	•		•			•	12
	Strain	s "beam and lever compared,	•	•	• •	•			•	33
	4.4	"lever measured by scale,		•		•			•	11
	4.4	" computed calculus,	•	•	• •	•			•	16
	4.4	"levers, graphical	•	•	• •	•	• •			16
	• •	"double lever, graphical	•	•	• •	•				11
	4.6	" lever with unequal arms,	•	•	• •	•	• •		•	12
	4.4	" " promiscuously loaded	•	•	• •	•			•	17
	••	" " uniformly "	•	•	• •	•	• •		•	169
	4.6	like two weights at ends of lever,	•	•	• •	•	• •		•	4
	44	from three headers								19
	"	in framed girder arithmetically compute	d,	•		•	• •		•	43
	44	" peculiarity in,	•	•		•	• •		•	43
	4.4	" " tracing the,				•	• •	• •	•	43
	• •	" diagonals of framed girder,				•	•	• •	•	436
	••	"lower chord of framed girder,	•	•		•	• •		•	439
	• •	"upper " " "						• •	•	440
	• •	"chords and diagonals, gradation of			_				400	491

														PAGE
Strains	in roof truss comp	ared,			•	•	• •	•	•	•	•	•	•	469
4.6	" truss, arithmetic	al comp	utation	of,	• ,	•		•	•	•	•		•	486
44	" equilibrated tru	ss,			•	•		•	•	•	•	•	•	408
4.6	" tie-beam of trus	s, two			•			•	•	•		•		488
	"horizontal and i	nclined	ties con	pare	d,			•		•		•	•	472
4.6	" truss with inclin	ed tie m	ay be n	ieasu	red,			•	•	•		•		475
4.6	" " an infinite													
••	" " without tie	e increas	ed, .		•	•		•	•		•	•	•	461
4.6	from raising the tie													
46 .	in rafters increased													
44	"Georgia pine, ti													
**	" hemlock,		Tables											
44	" locust,	••	Table											
	" spruce,	4.4	Tables											
44	" white pine,	4.6	••	XX										
	•								•					550
44	" white oak,	• 6	Table	XXV	7.,	•		•					•	
44	"Georgia pine, lo	cust and												
44	" spruce, white pi		hemlo		46	•	66				711.			556
44	"Georgia pine, lo		white o	•	slidi	ng.	44		ХX	ΧV	711	[.,	•	557
44	" spruce, white pi		hemloc	•	• •	,	46				X.,	•		558
44	"Georgia pine, lo		white	•	crus	hin	g. ''							559
44	" spruce, white pi		hemlo			•	"		XL		•		•	560
	ng beam in a roof t			-					•	•	•		•	460
••	" dimension								•		•	4		491
Strengt	th, test of specimen							•		•	•			29
"	as the area of cr							•	•	•		•	•	46
44	not as the area of						•	•		•		•	•	33
44	directly as the b							•	•			•	•	33
4.6	increases more							•	•	•			•	34
••	in more commo	_							•	•	•	•		235
4.	and stiffness co								•	•		2	67.	268
• •	differ from those	_												235
**	more simple tha								•			•		235
"	and stiffness res								•					27 0
44	" size, relation						• •					•	•	31
44	of beams, rule f				•			•		•				49
44		al rule fo						_		•	•	•	•	92
46		or load a												58
"	" beam increas		• •										•	402
	A INCICAS	Ju Dy a	40 · 100,	• •	•	•	-	•	•	•	•	•	•	~~~

											PACE
Strength of floor, by experiment,		•	•	•	•	•	•	•	•		7
" " beams. rule for,	•		•	•	•	•	•	•	•		7
" beam and lever compared,	•		•		•	•	•	•	•		5=
" " lever, rule for,											
" square timber, rule for											
" wood, unit of material,								•			
String polygon, funicular or											
Strongest form for a floor beam,		•	•	•	•	•	. •	•	•		
Struts of timber under pressure							•				
" formula for compression of											
" " thickness of,											449
" of framed girder, compression in,											445
" or straining beams in trusses, .											
" and ties form triangles in a girder.											-
" in trusses prevent bending of rafter											
Superficial foot, load per											88
" " on floors per											261
" " 200 pounds per,											264
" " 250 " "											•
" " on roofs per inclined											
" weight of people,											
" " tubular girder p											
Superimposed load on floor		•	•	•	•	•	•	•	•	310	. <i>319</i> 8 80
" " tubular girder											
Superincumbent load on floor											
Support in a roof truss, points of											
" "framed girder, points of,											
" of a truss, weight upon											
Supports " " division of load upon,											
" unvielding											-
" reaction from											_
equal to load, reaction of,					-						
of framed truss.											
" portions of load on											
											119
menting mentile of any reaction of											•
Surfaces of confact, resistance of,											-
Suspension bridge at Vienna.			•	•	•	•	•	•	•	•	82
" iolo dass straits in			•	•	•	•	•	•	• •	•	477
			•	•	•	•	•	•	•	•	490
Mandred and the second of the					•	•	•	•	• •	•	207
	_										

	•								PAGI
Symb	ol of safety, value of a, the	•		•	•	69,	235	, 239	, 26
••	" ' cautions in regard to,	•		•	•	•	•		7
4.6	" unit of materials, the,	•		•	•	•	•		49
Symb	ols, assigning the,	•		•	•	•	•	• • •	101
6.6	compound load, assigning the	•		•	•	•	•		18;
44	for two weights, ""	•		•	•	•	•		105
44	" " headers, " "	•		•	•	•	•		108
4+	" three " "	•			•	•	201	204,	206
• •	" beam and lever compared,		•	•	•	•	•		49
Symbo	olic expression, moment of inertia,		•	•	•	•	•		314
System	n of trussing a framed girder,		•	•	•	•	•		425
Table	s, chapter on the,		•	•	•	•	•		495
••	of beams for dwellings, etc.,	•	•	•	•	•			495
66	" " of wood,			•	•	•			495
44	" " for first-class stores,		•	•	•	•	•		495
"	"rolled-iron beams	•	•	•	•	•	•		495
4.	save time of architect,	•	•	•	•	•			495
Tables	s,	•	•	•	•	•	•	• •	507
Table	I., hemlock beams for dwellings	, ,	•	•	•	•	•		508
44	II., white pine beams for dwellings,	•	•	•	•	•	•		509
"	III., spruce " "		•	. •	•	•	•	• •	510
"	IV., Georgia pine " "			•		•	•		511
46	V., hemlock " " first-class stores.			•	•	•	•		512
66	VI., white pine " " " " "		•	•	•	•	•	• •	513
46	VII., spruce " " " " " .	•	•	•	•	•	•		514
44	VIII., Georgia pine beams for first-class store	es,	•	•	•	•	•		515
66	IX., hemlock headers for dwellings,		•	•	•		•		516
46	X., white pine " "		•	•	•	•	•		517
46	XI., spruce " "		•	•	•	•	•		518
**	XII., Georgia pine headers for dwellings, .		•	•	•	•	•		519
44	XIII., hemlock headers for first-class stores.	•	•	•	•	•	•		520
44	XIV., white pine " " " "		•	•	•	•	•		521
"	XV., spruce " " " "	•	•	•	•	•	•		522
4.6	XVI, Georgia pine headers for first-class sto	res	S				•		523
	XVII., elements of rolled-iron beams,		-				•	. 524,	
	XVIII., rolled-iron beams for dwellings,			•	•	•		526,	
66	XIX., " " first-class stor							. 52 8,	•
66	XX., constants for use in the rules,							_	- •
	XXI., solid timber floors,								
	XXII weights of building materials								

	PA
ble	XXIII., transverse strains in Georgia pine,
1.6	XXIV., " " locust,
4.4	XXV., " " white oak,
••	XXVI., " " spruce,
44	XXVII., " " "
• •	XXVIII., " " "
4.6	XXIX., " " white pine,
4.6	XXX., " " "
**	XXXI., " " "
• •	XXXII., ". " " "
4.	XXXIII., " " hemlock,
4.6	XXXIV., " " "
4.	XXXV., " " "
44	XXXVI., tensile "Georgia pine, locust and white oak, . 559
••	XXXVII., " " spruce, white pine and hemlock 556
44	XXXVIII., sliding " " Georgia pine, locust and white oak 55;
44	XXXIX., " " spruce, white pine and hemlock, 550
44	XL., crushing "Georgia pine, locust and white oak, . 550
4.6	XLI., " spruce, white pine and hemlock, 560
• •	XLII., transverse breaking weight per unit of material,
••	XLIII., deflection, values of constant, F
4.	XLIV., tensile breaking weight per square inch area,
••	XLV., sliding " " " surface, 56.
• •	XLVI crushing weight per square inch sectional area
Tail b	peams, definition of,
••	" two headers and one set of,
4.4	" sets of,
44	" three headers and two sets of,
Tange	ent defined, point of contact with 179, 184, 19
	le and compressive strains
••	strains, experiments on,
• •	" in Georgia pine, locust and white oak, Table XXXVI., . 55
6.4	" spruce, white pine and hemlock, Table XXXVII., 550
• •	breaking weight per square inch area, Table XLIV.,
••	strength of wrought-iron,
Tensi	on measures rupture,
• •	graphically shown,
• •	in a framed girder, resistance to,
• •	dimensions of parts subject to
••	and compression, rupture by.

				_	
Tens	sion and compression in cast-iron,				287
• •					117
• •					370
44					
44					117
Testi	ing machine,				504
	of deflection in a lever,				245
_	s of the materials used desirable,				
"	should be made for any special work,				
46	of value of symbol of safety,				
Thre	e headers, the greatest strain at middle one				
"	" " " outside "				
"	equal weights on beam				141
••	weights, graphic strains from,				•
Ties	compared, strains in horizontal and inclined				•
	in trusses extended through to rafters,				460
	peam, importance of a,				404
"	" tensile and transverse strains in a,		•		488
	" of roof, load upon the,			481,	483
• •	" " " truss, strains in,		•		488
66	" truss, built up				
64	" " manner of building,				489
Tie-r	od, effect of elevating the				477
4.	" of brick arch, area of cross-section,				347
66	" " where to place,				348
4.6	" " in floor,	•	•		346
64	" " on skew-back,	•	•		398
44	" cast-iron arched girder with,	•	•		396
44	" of iron arched girder	•	•	396,	397
Timb	per, experiments on,	•	•		30
44	floors, thickness of solid,	•	•		500
Tran	sverse breaking weights per unit of material, Table XLII.	, .	•		561
•	force, test,	•	•		2 9
•	strain, the philosophy of,	•	•		312
•	experiments by,	•	•	• •	504
•	resistance to,	•	•	• •	47
,	by rupture or deflection,	•	•		211
•	lever principle,	•	•		38
•	'' in a tie-beam,	•	•		
	14 14 222 : 222				

							PAGI
Transverse strains, the object of this work,	•	•	• •	•	•	• •	25
" in framed girders,	• •	•		•	•		402
" shearing and		•		•	•		116, 118
" in Georgia pine, Table ?	XXII	Ι.,		•	•		536
" " locust, Table XXIV.		•		•	•	• •	537, 53 ⁹
" " white oak, Table XX	.V.,	•		•	•	• •	539
" " spruce, Tables XXV	I. to	XX	VIII	•••	•	•	540 to 544
white pine, Tables X	XIX	. to	XX	XII.,	545	5, 546	, 547, 548,
							549, 550
" " hemlock, Tables XX	XIII	. to	XX.	XV.	, .	•	551 to 554
" strength of beams, rule for, .		•		•	• •		48
Tredgold an authority on construction, .		•		•	•		81
" on compression of materials, .		•		•	•		446
· " cast-iron		•		•	• (. 380	5, 387, 396
" has written on roofs,	. •			•	• (- 459
Tredgold's "Carpentry,"		•		•		• •	417
" estimate of load on floor	• .	•		•	•		81
" rate of deflection,		•		•	•		240
remarks on load on floor,		•		•	•		80
" value of elasticity of iron	• .	•		•	• (• į•	232
Trenton Iron Works, beams tested by		•		•	•		500
Triangle, measure of extension,		•		•	•		221
" showing elongation of fibres, .		•		•	•		236
" resistance of fibres as area of, .		•	•	•	,		222, 223
" distributed load, side of lever a,		•		•		•	170
" of forces in framed girders,		•		•	• (404
Triangles " Professor Rankine,		•	: .	•	• (418
" strains,		•	. •	•		128	3, 16S, 413
" in proportion to strains,	• .			•	• (486
" framed girder, series of,	• .			•		•	425
Trimmers, definition of,		•		•			96
" and headers,				•			. 266
" " bridle irons,				•	• •	. •	95
Truss, arithmetical computation of strains in	ı a,	•		•		•	436
" graphically shown, forces in a,		•		•		•	417
" should have solid bearings for suppo	rt, .	•		•		•	473
" with inclined tie, vertical strain in,		•				•	474
" without tie, increased strains in, .		•		•		•	. 461
" load upon each supported point in a,							
" " support of a							466, 470

					P	AGE
Trusses	s for ro	ofs, .		•		459
"	load v	ipon r	oof	•	479,	483
46	points	of su	pport in roof	•		1 79
"	divisi	on of	load upon supports of roof	•		461
64	distan	ce ap	art for placing roof	•	4	478
44	requir	ed, n	umber of roof	•		481
**	dimen	sions	of rafters, braces, etc., in	•	490, 4	49 I
Trussin	g a frai	med g	irder,	•	417,	425
Tubula	r iron g	girder,	history of,	•	:	367
••	44	4.4	useful for floors of large halls,	•	;	367
44	4.	4.4	coefficient of strength,	•	:	3 68
46	44	4.	constants,	•	:	369
44	44	••	by leverage,	•	:	369
66	46	46	" principle of moments,	•	• • ;	369
44	44	44	" moments, load at middle,	•	• • ;	370
44	44	**	allowance for rivet holes,	•	• • ;	3 68
44	e (44	shearing strain in,		374,	375
"	66	4.6	buckling of sides of	•	• •	377
"	44	64	uprights of T iron in sides of,	•	• • .	377
44	46	4.6	economical depth,	•		382
"	"	6.6	ratio of depth to length,	•	• • •	382
44	44	44	approximated, weight of,	•		378
**	64	4.6	per superficial foot, weight of,	•	378,	37 9
"	66	4.	minimum area of,	•	382,	383
44	44	44	tension in lower flange of	•		370
44	66	44	top and bottom flanges equal,	•		371
"	"	"	construction of flanges of,			374
44	44	44	thickness of flanges of,	•		373
			strain in web of,			374
"	"	4.4	construction of web of,			376
46	"	4.6	thickness of web of,	•		375
• •	"	44	" " plates of,	•		382
46	44	44	load at middle,	•		367
4.	44	44	" " common rule, ,			368
**	44	44	" " any point,	•	368,	37
44	"	44	" uniformly distributed,	•	368,	372
44	44	44	" " size at any point,	•		37
66	4.6	44	weight of load on floor,	•		37
16	66	46	for floors, rule for,			
45	66	66	" dwellings etc. load on.			

					•	.,	<i>J</i>												
		•															7	A	G.B.
Tubu	ılar iror	gird	er, for	dwelli	ngs, c	etc.,	rule	e fo	r,	•	•			. •	•	•	•	3	30
"	"	"	CO	mpared	with	plat	le g	ird	er,	•	•				•	•	•	37	
4.		• 6	ad	vantage	es of j	plate	gir	dei	OV	er,		• ,		•	•	•	•	37=	
• •	• •	gird	ers, cl	napter o	on,		•	•	•	•	•			•	•	•	•	367	- 207
Two	loads,	graph	ic stra	ins, .			•	•	•	•	•			•	•	•	•	1332	= 8 3
Two	weights	, thei	r effec	t at loc	ation	of c	ne	of	the	m,		•		•	•	•	•	103	E 3
Unio	n Iron	Co. o	f Buffa	alo, lar	ge be	ams,		•		•	•	•		•	•	•	•	313	E 3
Unit	of mate	erial,	symbo	ol of, .	•		•	•	•	•			•	•	•	•	•	49	9
• •	• •		Mosel	ey's sy	mbol	of, .	•	•	•	•	•	•	•		•	•	•	49	2 9
• •	44		index	of stre	ngth,	•	•	٠	•	•	•			•	•	•	•	50	
4.6	• • • • • • • • • • • • • • • • • • • •		measu	re of s	treng	th,	•	•	•	•	•	•		•	•	•	•	30	
••	44 44		streng	th and	size c	of, .	•	•	•	•	•	•		•	•	•	•	46	Ø
• •	• • • • • • • • • • • • • • • • • • • •		size ar	bitrary	, .			•	•	•	•	•		•	•	•	•	32	3
••		•	dimen	sions a	idopte	ed,	•	•	•	•	•	•		•	•	•	•	53	1
••	• • •		4.	•	and w	eigh	it,	•	•	•	•	• ,		•	•	•	•	53	
66	• • •		harmo	ony nec	essar	y bet	wee	en j	pie	ce (ake	n a	ınd		•	•	•	54	
4.	"	•	break	ing loa	d of,	•	•		•	•			•	•	•	•	•	69	
6.4	44 6	•	resista	ance of	•		•	•	•	•	•	•		•	•	•	•	53	
Unk	nown q	uantit	i e s, el	iminati	ng,		•	•	•		•	•		•	•	•	•	90	
Unst	able an	d stab	ole equ	illibriu	m,		•	•	•	•	•		•	•	•	•	•	416	
Unsy	rmmetri	cal lo	ading,	reaction	on of	sup	port	s f	rom	1,	•	, ,		•	•	•	•	451	
Unsy	mmetri	cally	loade	d girde	r, for	e di	agra	am	of,			•	•	•	-	•	•	455	
Unyi	elding	suppo	rts for	load, .	•		•	•	•	•	•		•	•	•	•	•	119	
	e of h																		
Vers	ed sine	of br	ick ard	ch; .	•		•	•	•	•	•	•	•	•	•	•	•	346	
Verti	ical effe																		
• •				with in															
Vien	na susp	ensio	n brid	ge,	•		•	•	•		•		•	•	•	•	•	82	
	Mitis, t		•			_													
	e's expo																		
	s, tubu		_														-	_	
	cer, Jan			•		•													
Wall	s, beari	_																	
• •	of bu	ilding	g rais ç	d to pe	rmit	horiz	zont	al	tie,		•	•	•	•	•	•	•	478	
• •	• •	4.6	-	ned out															
	iut, resi																		
	ehouse l			_															- 1
				rs of, .															- 1
	, mome							•	•	•	•	•	•	•	•	•	•		1
66	and fl	nges	nron	ortion	hetwe	en												212	4

	•										1	PAGE
Web	to connect flanges and resist shearing,	•	•	•	•	•	•	•	•	•		314
4.6	usually larger than needed,	•	•	•	•	•	•	•	•			314
44	and flanges in cast-iron, relation of,	•	•	•	•	•	•	•	•			387
46	of cast-iron girder, form of,	•		•	•	•	•	•	•	•	•	392
44	" tubular girder, strain in,	•	•	•	•	•	•	•	•	•		374
44	" construction of,.	•	•	•	•	•	•	•	•	•	•	376
46	" thickness of,	•		•	•	•	•	•	•		•	375
44	" " area of,	•	•	•	•	•	•	•	•		382,	383
Weigh	ht and depth of beam, relation,	•	•	•	•	•		•	•	•		36
44	in proportion to depth,	•	•	•	•	•	•	•	•	•		44
66	its effect and position,	•	•	•	•	•	•	•	•	•		53
6.6	" " at end of lever,	•	• •		•	•	•	•	•	•		58
60	on a lever, rule for,			•		•	•	•	•			2 56
44	" " beam, its position,	•	•	•	•	•	•	•	•	•		54
44	not at middle, effect on supports,	•	•		•	•		•	•	•		56
44	at middle of rolled-iron beam, .		•	•	•	•	•	•	•		331,	332
• •	on each support of a truss,	•	•	•	•	•	•	•	•	464,	466,	470
44	of military,	•	•	•	•	•	•	•	•	•		85
4.6	" people, live load,			•	•	•	•			•		84
44	" beams per superficial foot,		•	•	•	•	•	•	•	•		79
4.6	" floors in dwellings,			•	•	•		•	•	•		80
44	" timber in solid floors,	•	•	•	•	•	•	•	•			502
"	" materials of construction in a ro	of,	•	•	•	•		•			480,	483
44	"rolled-iron beams,	•	•	•	•	•	•	•	•	•	339.	340
Weig	hts of building materials,	•	•	•	•	•	•		•	•		504
••	assigning the symbols for,	•	•	•	•	•	•	•	•	• •	101,	105
4.4	and deflections in proportion, .	•	•	•	•	•	•	•	•	•		304
**	" lengths, relation between, .	•	•	•	•	•	•	•	•	•	65, 66	5, 67
4.6	" pressures, equilibrium,	•	•	•	•	•	•	•	•	•		38
• 6	" strains put in proportion, .	•	•	•	•	•		•	•	•		409
• 6	in proportion as arms of levers, .	•	•	•	•	•	•	•	•			3 9
••	at location of one, effect of two.	•	•	•	•	•	•	•	•	•		101
44	for force diagram, line of,	•	•	•		•	•	•	•	•	464,	466
4.	producing rupture and flexure cor	npa	irec	l,	•	•			•	•		237
• •	of building materials, Table XXI	I.,	•	•	•	•	•	•		533	, 534	535
Whal	ebone largely elastic,	•	•	•	•	•	•	•	•			211
White	e pine, coefficient in rule for,	•	•	•	•	•	•	•	•	•	261,	265
4.	" resistance of,	•	•	•	•	•	•	•	•	•		
••	" experiment on units of,	•	•	•	•	•	•	•	•	•		
••	" beams, weight of,	•	•	•	•	•	•	•	•	•		

																	PAGE
White p	oine flo	oor beams and h	neaders	3, .	•	•	•	•	•	•	•	•	•	•	•	•	495
Whitew	ood, r	esistance of, .			•	•	•	•	•	•	•	•	•	•	I	2 0,	121
Wind, i	ts e ffe	ct on a roof, .			•	•	•	•	•	•	•	•	•	•	•	•	480
" s	tronge	er on elevated p	laces.		•	•	•	•	•	•	•	•	•	•	•	•	431
Wood,	iron a	substitute for,			•	•	•	•	•	•	•	•	•	•	•	•	312
Woods,	expe	iments on Ame	erican		•	•	•	•	•	•	•	•	•	•	•	•	504
Wooder	n bean	ns liable to dest	ructio	n by	fire			•	•	•	•	•	•	•	•	•	312
••	• •	weight of			•		•	•	•	•	•	•	•	•	•	•	79
4.	floor	s, when solid n	ot so l	iable	e to	bu:	rn,	•	•	•	•	•		•	•	•	500
Work a	ccomp	lished in deflec	ting a	leve	r,	•	•	:	•	•	•	•	•	•	•	•	229
** to	be te	sted, materials	in imp	ortai	nt .	•	•	•	•	•		•	•	•	-	•	211
Wrough	ıt-iron	, modulus of el	asticit	y of,	•	•	•	•	•	•	•	•	•	•	•		232
4.6	64	tension,			•	•	•		•	•	•	•	•	•	•	•	116
• •	• •	tensile strengt	h of,			•	•	•	•	•	•	•	•	•	•	•	347
4.6	4.6	for ties in fran															
Varman	h fal	l of bridge et															

ANSWERS TO QUESTIONS.

37.—Transverse.

- 38.—In proportion directly as the breadth.
- 39.—In proportion directly as the square of the depth.
- 40.—The elements are the strength of the unit of material, the area of cross-section and the depth.

The expression is $R = Bbd^n$.

- 41.—The amount is equal to the total load.
- 42.—One half.
- 43.—The sum is equal to the total load.
- 44.—The portion of the weight borne at either point is equal to the product of the weight into its distance from the other support, divided by the length between the two supports.

$$45. - R = W \frac{n}{l}$$

46.—
$$P = W \frac{m}{l}$$

47.—10000 pounds.

5000 pounds.

48.—The moment, or the product of half the weight into half the length of the beam.

49.—
$$117 = Bbd^{2}$$
.

51.—As many times as the breadth is contained in the depth.

84.—Depth, 6.6 inches; breadth, 3.3 inches.

86.—
$$6.93$$
 inches.

126.—2 feet
$$10\frac{8}{4}$$
 inches.

127.—2 feet
$$4\frac{1}{2}$$
 inches.

128.—2 feet
$$7\frac{5}{8}$$
 inches.

134.—1 foot
$$9\frac{8}{4}$$
 inches.

160.—Breadth, 6.78 inches; depth, 12.34 inches.

- 162.—2.86 inches.
- 163.—0.291% inches.
- 164.—1.763 inches.
- 165.—I.244 inches.
- 166.—3·111 inches.
- 179.—36720 foot-pounds.
- 180.—36.72 inches.
- For 5 st., 18·36 18360 foot-pounds.

 " 6 " 22·032 22032 " "

 " 7 " 25·704 25704 " "

 " 8 " 29·376 29376 " "

 " 9 " 33·048 33048 " "
- 182.—10.733, 10.182 and 9.6 inches respectively.
- 183.—6.245, 8.062, 9.539 and 10.198 inches respectively.
 - Weight, 652.218 pounds.

 Shearing strain at wall, 733.783 pounds.

 " " 5 ft. from wall, 699.798 pounds.
 - 185.—302·222 pounds.
 - 186.—Shearing strain, 4973‡ pounds. Height, 0.93‡ inches.
 - 187.—1.46 inches.
 - 204.—10666²/₈ pounds.
 - **205.**— $2666\frac{2}{8}$, $5333\frac{1}{8}$ and 8000 pounds.
 - **206.**—Strain at A, 17142 $\frac{1}{4}$; at B, 22285 $\frac{1}{4}$.

- 207.—85713, 74284 and 21000 pounds respectively.
- 208.—12750, 22750, 19000, 8500, 9500, 20500 and 21500 pounds respectively.
 - 209.—3920 pounds.
 - 217.—A parabolic curve.
 - 218.—800, 1050 and 1200 pounds.
 - 219.—5·1087 inches.
 - 220.—Elliptical.
 - 228.—0, 300, 600, 900 and 1700 pounds.
 At the wall 2500 pounds.
 - 229.—A parabolic curve.
 - 230.—1250 pounds.
 - 231.—Triangular.
 - 232.—3450, 6250 and 9450 pounds.
 - 233.—200, 1600, 6150 and 11050 pounds.
- 269.—19200 pounds; located at the concentrated weight.
 - **270.**—7.01 inches.
 - 287.—Resistance to flexure.
 - 288.—To any amount within the limits of elasticity.
 - 289.—The extensions are directly as the forces.
 - 290.—The deflections are directly as the extensions.
- 291.—The deflections are as the weights into the cube of the lengths.
 - 307.—By the power of reaction.

308.—To the number of fibres, to the distance they are extended, and to the leverage with which they act.

$$309. \quad Wl^3 = Fbd^3\delta.$$

310.—0.266 of an inch.

315.—The rules for strength are the more simple.

$$316.-\delta=\frac{72el^2}{d}$$

$$317.-\epsilon=\frac{d\delta}{72l^2}$$

318.—
$$a = \frac{B}{72Fe}$$

$$319.-r = \frac{72cl}{d}$$

354.—Formulas (122.), (124.), (125.), (126.) and (120.).

355.—Formulas (123.), (127.), (128.), (129.) and (121.).

356.—Formulas (131.), (132.), (133.), (134.) and (135.).

357.—Formulas (136.), (137.), (138.), (139.) and (140.).

437.—12·345 inches.

438.—4·176 inches.

439.—7·700 inches.

440.—8.417 inches.

441.—10.779 inches.

442.—9.530 inches.

537.— $\frac{1}{12}bd^3$ (form. 205.).

538. $-\frac{1}{12}(bd^3-b_id_i^3)$ (form. 213.).

539.—The Buffalo 121 inch 180 pound beam.

540.—9475.58 pounds.

541.—2004·52 pounds.

542.—The Pottsville 10½ inch 90 pound beam.

543.—Two 12 inch 170 pound beams.

544.—It should be a 15 inch 200 pound beam.

545.—A Paterson or Trenton 10½ inch 135 pound bea

574.—41² inches.

575.—35 inches.

576.—At 5 feet from the end of girder, 15 inches ear

" IO 268 " I5 " 35 46 46 46 46 40 " 25 " or at middle, 6. 418

577.—At end of girder, 0.38 inch;

5 feet from end of girder, 0.30 " 10 0.23 15 " " 0.15 46 46 46 20 0.08 25 " or at middle, 66

578.—At 5 feet from end of girder, 8.95 inches:

" IO " " " " " " 15.34 15 66 " 19.18 20.46 or at middle, " 20

0.0

579.—4.2155 feet.

597.—Bottom flange, 16 × 2·195 inches;

 $5\frac{1}{8} \times 1.646$ Top Web, thick. I · 372

ANSWERS TO QUESTIONS. '

```
598.—Bottom flange, 16 \times 1.646 inches;
                   5\frac{1}{8} \times 1.234
      Top
      Web,
                           I · 029 "
                                          thick.
599.—Bottom flange, 16 \times 2.49 inches;
                " 5<del>1</del> × 1 · 867
      Top
                           1.556 "
                                         thick.
      Web,
600.—32.99 inches.
601. —At the location of the 25000 pounds;
        The bottom flange, 16 \times 1.663 inches;
         " top
                        5\frac{1}{8} \times 1.247
         " web,
                                1.039 "
                                             thick
      At the location of the 30000 'pounds;
        The bottom flange, 16 \times 1.588 inches;
         " top
                           5<del>8</del> × 1 · 191
                               0.992 "
         " web,
                                              thic
602.—3.68 inches.
651.—The strain in AB is 3550 pounds;
                " BC " 10280
         " " EA " 10740
         " " AF " 15240
         " " BG " 10130
                                     "
652.—7.8125 feet.
653.—Six.
654.—The strain in
                    DE
                             3600 pounds;
                         is
                    CD
                             5425
                    BC
        "
                             12700
                    AB
                             14500
                    KA
                             21725
```

AU

CT

15700

35275

```
The strain in ES is
                              41800 pounds;
                     BL
                              26125
                     DM
                              39200
                                        "
655.—The strain in
                     DE
                          is
                               3614 pounds;
        66.
                     CD
                               5420
                     BC
                              12647
        66
                                         "
                     AB
              "
                              14454
                     KA
                              21681
                     AU
                          " 15655
                     CT
        "
             "
                              35223
                                        "
                      ES
                              41746
        "
                     BL
                              26091
        "
                     DM
                              39137
                                        66 .
656.—The area at AU should be 16.103 inches;
                                   36.180
                    CT
                                   42.872
                   ES
            "
       The size of
                   BL
                                    6.626 \times 7.951 inches
                   DM
                                    7.715 \times 9.258
                                    3.004 × 3.605
        "
                   DE
                   BC
                                    4.612 \times 5.534
                                    5.651×6.781
                   KA
            "
                                    0.603 inches;
       The area of CD
                                    1.611
                   AB
688.—The computed strain in AG is
                                        22535 pounds;
                               BH
                                        18028
                               AB
                                         4507
        "
                                AF
                                        18750
                       "
        "
                "
                                BC
                                        15000
                "
                       "
        "
                               AG
                                        22500
           measured
                            "
                       "
        "
                            "
                               BH
                                        18000
                "
                       "
        "
                               AB
                                         4500
                       "
                            "
                "
        "
                                AF
                                        18750
                                                  "
                            "
        "
                "
                       "
                                BC
                            "
                                        15000
                                                  "
                       "
        "
                "
```

```
689.—The strain in AN is 44200 pounds;
                 BO
                       38720
                DP
                        29160
                AB
                     " 5400
                CD "
                        13300
                AM " 36760
          "
                CL
                     " 32240
                BC "
                       10000
                DE
                     " 26320
```

```
690.—The strain in A\mathcal{F} is 41000 pounds; "" " BK " 36150 " " " AB " 4950 "
```

" " " *AH* " 32400 "

" " BC " 24700 "
" " CG " 14500 "

691.—The strain is 16000 pounds.

692.—Six.

That shown in Fig. 115.

```
The strain in AO is 96200 pounds;
             BP "
                     88200
             CH
                     53000
              CQ
                  "
                     25700
                               "
             DR
                      17600
                               "
             AB
                       8000
             CD
      "
                       8000
                               "
             AN
                      81600
      "
                               "
             HM
                      74800
                               "
             DE
                      10200
             BH
                      24700
                              . 66
```

AO should be 9 × 15.80
$$BP$$
 " " 9 × 14.49 BP " 9 × 13.41, or 9 × 14 CH " 6 × 8.61 BP " 6 × 5.89 BP 6 × 9 tapered to 6 × 6 BP " 4 × 6.41, or 4 × 7 BP " 4 × 6.41 " 4 × 7 BP " 8.83 × 11.77 " 9 × 12 BP " 14.85 × 19.80 " 15 × 20 BP " 1.133 area, or 1½ diameter. BP " 2.744 " " 2 "

			·	
			•	
		•		
	•	·		
			•	
	•		•	
		•		
			•	
•		-		

		•			
	•				
				•	
•		•			
•					
		•			
					•
					•



THE NEW YORK PUBLIC LIBRARY REFERENCE DEPARTMENT

This book is under no circumstances to be taken from the Building

